# Programmer's Guide EMI Receiver Series

HP 8542E/HP 8546A EMI Receiver HP 85422E/HP 85462A Receiver RF Section



HP Part No. 5962-5083 Printed in USA August 1994

#### Notice.

The information contained in this document is subject to change without notice.

Hewlett-Packard makes no warranty of any kind with regard to this material, including but not limited to, the implied warranties of merchantability and fitness for a particular purpose. Hewlett-Packard shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

© Copyright Hewlett-Packard Company 1994 All Rights Reserved. Reproduction, adaptation, or translation without prior written permission is prohibited, except as allowed under the copyright laws. 1400 Fountaingrove Parkway, Santa Rosa CA, 95403-1799, USA

#### Certification

Hewlett-Packard Company certifies that this product met its published specifications at the time of shipment from the factory. Hewlett-Packard further certifies that its calibration measurements are traceable to the United States National Institute of Standards and Technology, to the extent allowed by the Institute's calibration facility, and to the calibration facilities of other International Standards Organization members.

#### **Regulatory Information**

Regulatory information is located in the *EMI Receiver Series Reference* at the end of Chapter 1, "Specifications and Characteristics."

### Warranty

This Hewlett-Packard instrument product is warranted against defects in material and workmanship for a period of one year from date of shipment. During the warranty period, Hewlett-Packard Company will, at its option, either repair or replace products which prove to be defective.

For warranty service or repair, this product must be returned to a service facility designated by Hewlett-Packard. Buyer shall prepay shipping charges to Hewlett-Packard and Hewlett-Packard shall pay shipping charges to return the product to Buyer. However, Buyer shall pay all shipping charges, duties, and taxes for products returned to Hewlett-Packard from another country.

Hewlett-Packard warrants that its software and firmware designated by Hewlett-Packard for use with an instrument will execute its programming instructions when properly installed on that instrument. Hewlett-Packard does not warrant that the operation of the instrument, or software, or firmware will be uninterrupted or error-free.

#### LIMITATION OF WARRANTY

The foregoing warranty shall not apply to defects resulting from improper or inadequate maintenance by Buyer, Buyer-supplied software or interfacing, unauthorized modification or misuse, operation outside of the environmental specifications for the product, or improper site preparation or maintenance.

NO OTHER WARRANTY IS EXPRESSED OR IMPLIED. HEWLETT-PACKARD SPECIFICALLY DISCLAIMS THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE.

#### EXCLUSIVE REMEDIES

THE REMEDIES PROVIDED HEREIN ARE BUYER'S SOLE AND EXCLUSIVE REMEDIES. HEWLETT-PACKARD SHALL NOT BE LIABLE FOR ANY DIRECT, INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES, WHETHER BASED ON CONTRACT, TORT, OR ANY OTHER LEGAL THEORY.

### Assistance

Product maintenance agreements and other customer assistance agreements are available for Hewlett-Packard products. For any assistance, contact your nearest Hewlett-Packard Sales and Service Office.

# Compliance

This instrument has been designed and tested in accordance with IEC Publication 348, Safety Requirements for Electronic Measuring Apparatus, and has been supplied in a safe condition. The instruction documentation contains information and warnings which must be followed by the user to ensure safe operation and to maintain the instrument in a safe condition.

# **Safety Notes**

The following safety notes are used throughout this manual. Familiarize yourself with each of the notes and its meaning before operating this instrument.

#### WARNING

Warning denotes a hazard. It calls attention to a procedure which, if not correctly performed or adhered to, could result in injury or loss of life. Do *not* proceed beyond a warning note until the indicated conditions are fully understood and met.

#### **CAUTION**

Caution denotes a hazard. It calls attention to a procedure that, if not correctly performed or adhered to, would result in damage to or destruction of the instrument. Do *not* proceed beyond a caution sign until the indicated conditions are fully understood and met.

# **General Safety Considerations**

#### WARNING

- No operator serviceable parts inside. Refer servicing to qualified personnel. To prevent electrical shock, do not remove covers.
- If this instrument is used in a manner not specified by Hewlett-Packard Company, the protection provided by the instrument may be impaired.
- For continued protection against fire hazard, replace line fuse only with same type and rating ([F 5A/250V]). The use of other fuses or material is prohibited.

#### **CAUTION**

- Before switching on this instrument, make sure that the line voltage selector switch is set to the voltage of the power supply and the correct fuse is installed.
- Always use the three-prong ac power cord supplied with this instrument. Failure to ensure adequate earth grounding by not using this cord may cause instrument damage.



The instruction documentation symbol. The product is marked with this symbol when it is necessary for the user to refer to the instructions in the documentation.

CE

The CE mark is a registered trademark of the European Community. (If accompanied by a year, it is when the design was proven.)

ISM1-A

This is a symbol of an Industrial Scientific and Medical Group 1 Class A product.

CSA

The CSA mark is a registered trademark of the Canadian Standards Association.

## **Manual Conventions**

Front-Panel Key

This represents a key physically located on the instrument.

Softkey

This indicates a "softkey," a key whose label is determined by the firmware of the instrument.

Screen Text

This indicates text displayed on the instrument's screen.

# **EMI Receiver Series Documentation Description**

The following documents are provided with either the HP 8542E/HP 8546A EMI receiver or the HP 85422E/HP 85462A receiver RF section.

- Installation and Verification provides information for installing your instrument, verifying instrument operation, and customer support.
- *User's Guide* describes instrument features and how to make measurements with your EMI receiver or receiver RF section.
- Reference provides specifications and characteristics, menu maps, error messages, and key descriptions.
- Programmer's Guide provides information on remote control instrument configuration, creating programs, and parameters for each of the programming commands available.

# Contents

1.	Preparing for Use	
	What You'll Learn in This Chapter	1
	Connecting Your Instrument to a Computer	. 1
	Configuring Your Computer System	-1
	Connecting the Computer to the Instrument	
	For the HP-IB Interface	-
	For the RS-232 Interface	
	The Test Program	
	HP-IB Connections for the HP 9000 Series 200 Technical Computers 1-	
	Equipment	
	Interconnection Instructions	
	Test Program	
	HP-IB Connections for the HP 9000 Series 300 Technical Computers 1-	
	Equipment	
	Interconnection Instructions	_
	Test Program	
	HP-IB Connections for the HP Vectra Personal Computer	
		-
	•	
		_
		_
	Interconnection Instructions	
	Test Program	
	RS-232 Connections for the IBM PC/AT and Compatible Computers 1-1	-
	Equipment	
	Interconnection Instructions	
	Test Program	
	Printing or Plotting	-
	Printer with an HP-IB Interface	_
	Equipment	-
	Interconnection and Printing Instructions	
	Plotter with an HP-IB Interface	
	Equipment	
	Interconnection and Plotting Instructions	
	Printer with an RS-232 Interface	
	Equipment	5
	Interconnection and Printing Instructions	_
	Plotter with an RS-232 Interface	6
	Equipment	6
	Interconnection and Plotting Instructions	6
	Printing after Plotting or Plotting after Printing	7
	If There is a Droblem	n

2.	Writing a Program	
		2-:
		2-
	Composing the Program	2-
	Program Example for the HP-IB Interface	2-2
	Modifying the Program	2
	Program Example for the HP-IB Interface	2-
	Enhancing the Program with Variables	2-:
	Program Example for the HP-IB Interface	2-
	Getting Information from the Instrument	2-(
		2-
	Programming Guidelines	2-8
3.	Programming Topics	
		3-1
		3-2
		3-2
		3-2
		3-3
		3-4
		3-4
	Saving and Recalling Instrument States	3-8
	Saving the Instrument's State	3-5
		3-:
	Returning the Instrument to its Former State	3-7
	Program Example for the HP-IB Interface	3-7
	Different Formats for Trace Data Transfers	3-8
	P Format	3-8
		3-8
	B Format	3-8
		3-8
	A-Block Format	-10
		11
		-1
		-1]
	M Format	-12
		-14
	mample of ossigned in tornation	1.
4.	Programming Commands	
	What You'll Learn in This Chapter	1-1
		<b>1</b> -2
		25
		27
	AMB Trace A Minus Trace B	-
	AMBPL Trace A Minus Trace B Plus Display Line	
		34
	AMPLEN Amplitude Correction Length	37
		.38
	APB Trace A Plus Trace B	
		-3ε -4(
	AT Attenuation	- `
	ATINITS Amplitude Unite	41 41
		45 47
		41

AUTOQPD Quasi-Peak Detector	4-49
AVBW Average Video Bandwidth	4-50
AVG Average	4-52
AXB Exchange Trace A and Trace B	4-54
BAUDRATE Baud Rate of Instrument	4-55
BIT Bit	4-57
BITF Bit Flag	4-59
BLANK Blank Trace	4-61
BML Trace B Minus Display Line	4-62
BTC Transfer Trace B to Trace C	4-63
BXC Trace B Exchange Trace C	4-64
BYPASS Bypass Path	4-65
CAL Calibration	4-66
CALCHECK Calibration Check	4-69
CALSW Calibration Switch	4-70
CALTIME Calibration Time	4-71
CAT Catalog	4-72
CF Contar Programmy	4-76
CF Center Frequency	4-70
CLRAVG Clear Average	_
CLRW Clear Write	4-79
CLS Clear Status Byte	4-80
CNTLA Auxiliary Interface Control Line A	4-81
CNTLB Auxiliary Interface Control Line B	4-82
CNTLC Auxiliary Interface Control Line C	4-83
CNTLD Auxiliary Interface Control Line D	4-84
CNTLI Auxiliary Interface Control Line Input	4-85
COMPRESS Compress Trace	4-86
CONCAT Concatenate	4-88
CONTS Continuous Sweep	4-90
CORREK Correction Factors On	4-91
COUPLE Couple	4-92
CTA Convert to Absolute Units	4-93
CTM Convert to Measurement Units	4-95
DATEMODE Date Mode	4-96
DEMOD Demodulation	4-97
DET Detection Mode	4-98
DISPOSE Dispose	4-100
DIV Divide	4-101
DL Display Line	4-103
DN Down	4-105
DONE Done	$\frac{4}{100}$
EDITANNOT Edit Annotation	4-108
EK Enable Knob	4-109
EP Enter Parameter Function	4-109
ERASE Erase	4-111
EXITANNOT Exit Annotation	4-112
EXP Exponent	4-113
FA Start Frequency	4-116
FASTMRKR Fast Marker	4-118
FB Stop Frequency	4-119
FCALDATE Last Calibration Date	4-121
FFT Fast Fourier Transform	4-122
FMGAIN FM Gain	4-126
FOFFSET Frequency Offset	4-127
FORMAT Format Disk	4190

FS Full Span	4-130
FSER RF Filter Section Serial Number	
OD An Continuing	4-131
GRAT Graticule	4-132
HAVE Have	4-133
HD Hold Data Entry	4-135
HN Harmonic Number	4-136
HNLOCK Harmonic Number Lock	4-137
HNUNLK Unlock Harmonic Number	4-139
IB Input B	4-140
ID Identify	4-141
IFBW Intermediate Frequency Bandwidth	4-142
INT Integer	4-144
INZ Input Impedance	4-146
IP Instrument Preset	4-147
LASTKEYMENU Last Key Menu	4-150
LF Base Band Instrument Preset	4-150
I. C. Logorithmic Cools	
LG Logarithmic Scale	4-152
LIMIAMPSCL Limit-Line Amplitude Scale	4-153
LIMIDEL Delete Limit-Line Table	4-154
LIMIDISP Limit Line Display	4-155
LIMIFAIL Limits Failed	4-157
LIMIFRQSCL Limit-Line Frequency Scale	4-159
LIMIFT Select Frequency or Time Limit Line	4-160
LIMIHI Upper Limit	4-161
LIMILINE Limit Lines	4-163
LIMILINESTA Limit-Line State	4-166
LIMILO Lower Limit	4-168
LIMIMARGAMP Limit Margin Amplitude	4-169
LIMIMARGSTA Limit-Margin State	4-170
LIMIMIRROR Mirror Limit Line	4-172
LIMIMODE Limit-Line Entry Mode	4-174
I I I I I I I I I I I I I I I I I I I	
LIMINUM Limit-Line Number	4-176
LIMIREL Relative Limit Lines	4-177
LIMISEG Enter Limit-Line Segment for Frequency	4-179
LIMISEGT Enter Limit-Line Segment for Sweep Time	4-182
LIMITEST Enable Limit-Line Testing	4-185
LINCHK Linearity Check	4-187
LINFILL Linear	4-188
LN Linear Scale	4-190
LOAD Load	4-191
LOG Logarithm	4-193
LSPAN Last Span	4-196
LOGSWEEPSPD Log Sweep Speed	4-197
M4 Marker Zoom	4-198
MDS Measurement Data Size	4-200
MDU Measurement Data Units	4-200
MEAN Trace Mean	-
MEAN Trace Mean	4-204
MEANTH Trace Mean Above Threshold	4-206
MEASALLSIGS Measure All Signals	4-208
MEASAVG Measure Average	4-209
MEASFREQ Measure Frequency	4-210
MEASPEAK Measure Peak	4-211
MEASQPD Measure Quasi-Peak Detector	4-212
	4-213
MEASSIG Measure Signal	4-215

MEASTIMEAVG Measure Time Average	4-216
MEASTIMEPK Measure Time Peak	4-217
MEASTIMEQPD Measure Time Quasi-Peak Detector	4-218
MEASURE Measure Mode	4-219
MEASWITHPP Measure With Preselector Peak	4-221
MERGE Merge Two Traces	4-222
MF Marker Frequency Output	4-224
MIN Minimum	4-226
MINH Minimum Hold	4-228
MINIT MINIMUM HOLD	4-229
MINPOS Minimum Position	-
MIRROR Mirror Image	4-231
MKA Marker Amplitude	4-233
MKACT Activate Marker	4-235
MKACTV Marker As the Active Function	4-236
MKBW Marker Bandwidth	4-237
MKCF Marker to Center Frequency	4-238
MKCONT Marker Continue	4-239
MKD Marker Delta	4-240
MKF Marker Frequency	4-242
MKFC Marker Counter	4-244
MICHOD Marker Counter Danieles	
MKFCR Marker Counter Resolution	4-245
MKMIN Marker Minimum	4-247
MKN Marker Normal	4-248
MKNOISE Marker Noise	4-250
MKOFF Marker Off	4-252
MKP Marker Position	4-253
MKPAUSE Marker Pause	4-255
MKPK Marker Peak	4-257
MKPX Marker Peak Excursion	4-258
MKREAD Marker Readout	4-260
MKRL Marker to Reference Level	4-262
MKSP Marker to Span	4-263
MKSS Marker to Step Size	4-264
MICOTOD Marker Cton	4-266
MKSTOP Marker Stop	4-267
MKTRACE Marker Trace	
MKTRACK Marker Track	4-268
MKTYPE Marker Type	4-269
ML Mixer Level	4-270
MOD Modulo	4-272
MOV Move	4-274
MPY Multiply	4-276
MSI Mass Storage Is	4-278
MXM Maximum	4-279
MXMH Maximum Hold	4-281
NRL Normalized Reference Level	4-282
OA Output Active Function Value	4-284
OLY D. Oversland	4-285
OVLD Overload	4-286
PDA Probability Distribution of Amplitude	4-288
PEAKS Peaks	4-290
PLOT Plot	4-293
POWERON Power-On State	4-295
PP Preselector Peak	4-296
PREAMP Preamplifier	4-297
PREAMPG External Preamplifier Gain	4-299

PREFX Prefix	4-300
PRINT Print	4-301
PRNTADRS Print Address	4-302
PRNTPPG Prints Per Page	4-303
PRNTRES Print Resolution	4-304
PRNTTYPE Printer Type	4-305
PROTECT Protect	4-307
PSTATE Protect State	4-308
PURGE Purge File	4-309
PWRBW Power Bandwidth	4-310
DWDHDTME Damer Un Time	4-310 4-312
PWRUPTIME Power Up Time	
QPGAIN Quasi-Peak Gain	4-313
RANGE Range	4-314
RB Resolution Bandwidth	4-315
RCLC Recall Colors	4-317
RCLS Recall State	4-318
RCLT Recall Trace	4-319
RCVRMRKR Receiver Marker Position	4-321
REMEASSIG Remeasure Signal	4-323
REPEAT UNTIL Repeat Until	4-324
RESETRL Reset Reference Level	4-326
REV Revision	4-327
RFIN RF Input Signal	4-328
RFINLK RF Input Lock	4-330
RL Reference Level	4-331
RLPOS Reference-Level Position	4-333
DMC Doot Moon Square Volus	4-334
RMS Root Mean Square Value	
ROFFSET Reference Level Offset	4-335
RPTDEF Report Definition	4-336
RQS Service Request Mask	4-337
SAVEC Save Colors	4-339
SAVES Save State	4-340
SAVET Save Trace	4-341
SEGDEL Segment Delete	4-343
SENTER Segment Entry for Frequency Limit Lines	4-345
SENTERT Segment Entry for Sweep Time Limit Lines	4-348
SER Serial Number	4-351
SETC Set Colors	4-352
SETDATE Set Date	4-354
SETTIME Set Time	4-355
SHOWSETUP Show Set Up	4-356
SIGADD Signal Add	4-357
SIGDEL Signal Delete	4-358
SIGDLTAVIEW Signal Delta View	4-359
SIGCDADH Signal Craph	
SIGGRAPH Signal Graph	4-361
SIGLEN Signal List Length	4-362
SIGLIST Signal List	4-363
SIGMARK Signal Mark	4-364
SIGPOS Signal Position	4-365
SIGRESULT Signal Result	4-366
SIGSORT Signal Sort	4-367
SIGUNMARK Signal Unmark	4-369
SMOOTH Smooth Trace	4-370
SNGLS Single Sweep	4-372
SP Span	4-373

SPEAKER Speaker	4 - 375
	4-376 4-376
	4-377
	4-378
	4-380
	4-381
	4-383
	4-384
	4-386
	4-388
SRCTK Source Tracking	4-390
	$\frac{1}{4}$ -392
SRQ Force Service Request	4-393
CC Conton Tracularias Cton Circ	<del>1</del> -396
*	4-398
	4-400
	4-401
	4-404
SUM Sum of Trace Amplitudes	4-406
SUMSQR Sum of Squared Trace Amplitudes	4-408
	4-409
	4-410
TA Transfer A	4-412
TB Transfer B	1-414 4-414
	1-415
	4-416
	4-421
	4-423
	4-424
	4-425
TM Trigger Mode	4-426
	4-428
	4-430
TRDEF Trace Define	4-431
	4-433
	1-434
	1-435
TROTAL Have Status	<del>*-4</del> 35 4-436
· · · · · · · · · · · · · · · · · · ·	
	4-437
+	4-438
•	4-439
	4-440
	<b>1-44</b> 1
VARDEF Variable Definition	1-442
VARIANCE Variance of Trace Amplitudes	1-444
VAVG Video Average	<del>1-44</del> 6
	1-447
	1-449
	4-450
	4-451
	4-452
	4-453
	4-454
	4-456
XCH Exchange	4-457

	XUNITS Transducer Conversion Units	4-459
	ZMKCNTR Zone Marker at Center Frequency	4-460
	ZMKPKNL Zone Marker for Next Left Peak	4-462
	ZMKPKNR Zone Marker for Next Right Peak	4-463
	ZMKSPAN Zone Marker Span	4-464
5.	Error Messages	
	Nonrecoverable System Errors	5-12
Α.	нр-ів	
В.	RS-232 Option 023	
	What You'll Learn in This Appendix	B-1
	Introducing the RS-232 Interface	B-1
	The RS-232 Data Lines	B-1
	The RS-232 Handshaking Lines	B-1
	Baud Rate	B-2
	Protocol	B-2
	Connecting a ThinkJet Printer	B-3
	ThinkJet Printer Mode Switches:	B-4
	Connecting a Modem	B-4
	System Settings	B-5
	Connecting an HP-GL Plotter	B-5
	Switch Settings	B-5
	Setting the Instrument Baud Rate	B-5

Index

# **Figures**

1-1,	Connecting the HP 9000 Series 200 Computer to the Instrument .	٠	٠			1-3
	Connecting the HP 9000 Series 300 Computer to the Instrument .					1-5
	Connecting the HP Vectra Personal Computer to the Instrument .					1-7
	Connecting the HP Vectra Personal Computer to the Instrument					1-9
	Connecting an IBM PC/AT Compatible Computer to the Instrument					1-11
	Measurement Unit Range and Trace Amplitudes					3-13
	Command Syntax Figure					4-2
	Hanning Filter Window					4-124
	Uniform Filter Window					4-125
	Flat Top Filter Window					4-125
A-1.	HP-IB Connector		٠	 		A-1
	RS-232 Connector					B-1
B-2.	Full Handshaking Connection					B-3
	3-Wire Connection					B-3
B-4.	ThinkJet Printer Connection					B-3
	Modem Connection					B-4
B-6.	HP-GL Plotter Connection		۰	 		B-5
[ab]	les					
	Measurement Units		•		•	3-13
	Summary of the Trace Data Formats					3-14
	Syntax Elements					4-3
	Characters and Secondary Keywords (Reserved Words)					4-
	Summary of Compatible Commands					4-9
	Functional Index					4-11
	LIF or DOS File Types					4-74
	LIF or DOS Data Types					4-192
4-7.	Instrument Status Byte					4-394
4-8.	LIF or DOS Data Types		٠	 		4-403
	Programming Commands That Exit The Windows Display Mode					4-455
	Setting of Thinkjet Printer Mode Switches					B-4
B-2.	Setting of RS-232 Switches					B-4
B-3.	Setting the Baud Rate					B-4

# **Preparing for Use**

# What You'll Learn in This Chapter

This chapter tells you how to connect a computer to your instrument via the Hewlett-Packard Interface Bus (HP-IB) or the RS-232 Interface and how to connect a printer or a plotter. The remainder of the chapter covers procedures to follow if a problem is encountered.

#### Connecting Your Instrument to a Computer

The instrument works with many popular computers. However, the steps required to connect your instrument to a specific computer depend on the computer you are using. Before turning to the interconnection instructions for your computer, please read the following general information.

#### **Configuring Your Computer System**

Every computer system has a specific configuration. Your system configuration might include a printer, external disk drive, or plotter. Whenever you add another piece of equipment, you may need to reconfigure your computer system so that the computer knows where and how to send information to the newly added device.

Some computers do not require configuring when an instrument is connected; others require a simple modification. The most common modification is changing the configuration information stored on the computer's operating system disk. A few computers require the insertion of an add-on board, or "card." Refer to your computer documentation if your system needs these modifications.

All of the test programs for HP-IB and RS-232 interfaces are written using the BASIC language of the computer under consideration. If you have never entered or run a BASIC program, refer to your computer documentation.

### Connecting the Computer to the Instrument

#### For the HP-IB Interface

Appendix A contains instructions for connecting the instrument's or to an HP Vectra PC equipped with an HP 82300B BASIC Language Processor. If your computer is not listed, but it supports an HP-IB interface, there is a good possibility that it can be connected to the instrument. Consult your computer documentation to determine how to connect external devices on the bus.

#### For the RS-232 Interface

Appendix B contains instructions for connecting the instrument's RS-232 interface to an HP Vectra PC or IBM PC/AT or compatible computers. If your computer is not listed, but it supports a standard RS-232 interface, there is a good possibility that the instrument may be connected to the computer. Consult your computer documentation to determine how to connect external devices to your computer's RS-232 connector.

There are two types of RS-232 devices: data terminal equipment (DTE) and data communication equipment (DCE). Types of DTE devices include display terminals. DCE equipment includes modems and, generally, other computer RS-232 devices. The instrument RS-232 port is the DTE-type. Connections from the computer (DCE) to the instrument (DTE) are shown in Figure 1-4.

## The Test Program

To test the system configuration, a simple test program is provided for each computer listed. After you have connected your computer and instrument, you should enter and run the test program on your computer to make sure the computer is sending instructions to the instrument through the interface cable. If the interface is working and the program is entered correctly, a statement is displayed on the computer screen.

Note	The listed computer and instrument equipment includes the minimum components necessary to establish communication between your instrument and computer. If you are using application software, check with your software supplier for specific computer hardware and memory requirements.		
Note	Using an interface cable other than the one listed with your computer's interconnection instructions may prevent proper communication between the instrument and computer.		

Pressing CONFIG removes the instrument from remote mode and enables front-panel control.

# HP-IB Connections for the HP 9000 Series 200 Technical **Computers**

#### **Equipment**

- HP 9816, 9826, or 9836 Series 200 technical computer
- HP 8542E/HP 8546A EMI receiver
- HP 10833 (or equivalent) HP-IB cable

#### **Interconnection Instructions**

Connect the instrument to the computer using the HP-IB cable. Figure 1-1 shows an HP 9836 computer connected to the instrument.




Figure 1-1. Connecting the HP 9000 Series 200 Computer to the Instrument

#### **Test Program**

To test the connection between the computer and the instrument, turn on your instrument and follow the instructions below.

- 1. Your HP 9000 Series 200 computer may have either a soft-loaded or built-in language system. If your language system is built-in, remove any disks from the drives and turn on the computer.
- 2. If your language is soft-loaded, install the BASIC language disk into the proper drive. Turn the computer power on. After a few seconds, the BASIC READY message appears; the computer is now ready for use.
  - For further information on loading BASIC on your system, consult your BASIC manual.
- 3. Check the HP-IB address of the instrument: press [CONFIG], More 1 of 3, RECEIVER ADDRESS. The usual address for the instrument is 18. If necessary, reset the

- address of the instrument: press CONFIG, More 1 of 3, RECEIVER ADDRESS, 18, (Hz) (or enter the appropriate address).
- 4. Enter the following program, then press (RUN) on the computer. If you need help entering and running the program, refer to your computer and software documentation.

The program shows that the computer is able to send instructions to, and read information from, the instrument.

```
10 PRINTER IS 1
20 Instrument=718
30 CLEAR Instrument
40 OUTPUT Instrument; "IP; SNGLS;"
50 OUTPUT Instrument; "CF 300MZ; TS;"
60 OUTPUT Instrument; "CF?;"
70 ENTER Instrument; A
80 PRINT "CENTER FREQUENCY = "; A; "Hz";
90 END
```

The program tells the instrument to perform an instrument preset and enter single-sweep mode. Next, the program sets the center frequency to 300 MHz and takes a sweep.

The program then queries the center frequency value and tells the computer to display CENTER FREQUENCY = 3.0E+8 Hz.

If the computer does not display the center frequency, refer to "If There is a Problem" at the end of this chapter.

# HP-IB Connections for the HP 9000 Series 300 Technical Computers

#### **Equipment**

- HP 98580A, 98581A, 98582A, or 98583A Series 300 technical computer
- HP 8542E/HP 8546A EMI receiver
- HP 10833 (or equivalent) HP-IB cable

#### **Interconnection Instructions**

Connect the instrument to the computer using the HP-IB cable as shown in Figure 1-2.




Figure 1-2. Connecting the HP 9000 Series 300 Computer to the Instrument

#### Test Program

To test the connection between the computer and the instrument, turn on your instrument and follow the instructions below.

- 1. Your HP 9000 Series 300 computer may have either a soft-loaded or built-in language system. If your language system is built-in, remove any disks from the drives and turn on the computer.
- 2. If your language is soft-loaded, install the BASIC language disk into the proper drive. Turn the computer power on. After a few seconds, the BASIC READY message appears; the computer is now ready for use.
  - For further information on loading BASIC on your system, consult your BASIC manual.
- 3. Check the HP-IB address of the instrument: press (CONFIG), More 1 of 3, RECEIVER ADDRESS. The usual address for the instrument is 18. If necessary, reset the address of the instrument: press (CONFIG), More 1 of 3, RECEIVER ADDRESS, 18, (Hz) (or enter the appropriate address).
- 4. Enter the following program, then press (RUN) on the computer. If you need help entering and running the program, refer to your computer and software documentation.

The program shows that the computer is able to send instructions to, and read information from, the instrument.

```
10 PRINTER IS 1
20 Instrument=718
30 CLEAR Instrument
40 OUTPUT Instrument: "IP: SNGLS;"
50 OUTPUT Instrument; "CF 300MZ; TS;"
60 OUTPUT Instrument; "CF?;"
70 ENTER Instrument; A
80 PRINT "CENTER FREQUENCY = ";A;"Hz";
90 END
```

The program tells the instrument to perform an instrument preset and enter single-sweep mode. Next, the program sets the center frequency to 300 MHz and takes a sweep.

The program then queries the center frequency value and tells the computer to display CENTER FREQUENCY = 3.0E+8 Hz.

If the computer does not display the center frequency, refer to "If There is a Problem" at the end of this chapter.

# **HP-IB** Connections for the **HP** Vectra Personal Computer

#### **Equipment**

- HP Vectra personal computer, with option HP 82300B, the HP BASIC Language Processor
- HP 8542E/HP 8546A EMI receiver
- HP 10833 (or equivalent) HP-IB cable

#### **Interconnection Instructions**

Connect the instrument to the computer using the HP-IB cable as shown in Figure 1-3.




Figure 1-3. Connecting the HP Vectra Personal Computer to the Instrument

#### **Test Program**

To test the connection between the computer and the instrument, turn on your instrument and follow the instructions below.

- 1. Refer to the HP 82300 Language Processor documentation to install the language processor board in your computer and load the BASIC programming language into your computer.
- 2. Check the HP-IB address of the instrument: press CONFIG, More 1 of 3 RECEIVER ADDRESS. The usual address for the instrument is 18. If necessary, reset the address of the instrument: press CONFIG, More 1 of 3, RECEIVER ADDRESS, 18 (Hz) (or enter the appropriate address).

3. Enter the following program, then press F10 on the computer. If you need help entering and running the program, refer to your computer and software documentation.

The program shows that the computer is able to send instructions to, and read information from, the instrument.

```
10 PRINTER IS 1
20 Instrument=718
30 CLEAR Instrument
40 OUTPUT Instrument; "IP; SNGLS;"
50 OUTPUT Instrument; "CF 300MZ; TS;"
60 OUTPUT Instrument; "CF?;"
70 ENTER Instrument; A
80 PRINT "CENTER FREQUENCY = "; A; "Hz";
90 END
```

The program tells the instrument to perform an instrument preset and enter single-sweep mode. Next, the program sets the center frequency to 300 MHz and takes a sweep. The program then queries the center frequency value and tells the computer to display CENTER FREQUENCY = 3.0E+8 Hz.

If the computer does not display the center frequency, refer to "If There is a Problem" at the end of this chapter.

# RS-232 Connections for the HP Vectra Personal Computer

#### **Equipment**

- HP Vectra personal computer with RS-232 interface that has an 9-pin female port
- HP 8542E/HP 8546A EMI receiver
- HP 24542G RS-232 cable

#### Interconnection Instructions

1. Connect the instrument to the computer using the RS-232 cable as shown in Figure 1-4.




Figure 1-4. Connecting the HP Vectra Personal Computer to the Instrument

2. Turn on the instrument and the computer.

#### **Test Program**

The program shown below works with the following computers:

- HP Vectra PC using a version of BASIC (HP 45952A) for the Vectra PC. The MS BASIC Interpreter (HP 35190A) is compatible with the version of BASIC for the Vectra PC.
- IBM PC/AT and compatible computers using BASICA (version 2.0 or later) or GW BASIC.

To test the interconnection, first load the BASIC language for your computer and specify a communications buffer of 4096 bytes. Use the following command:

BASICA/C:4096

Set the instrument baud rate to 1200, to match the baud rate set up for the computer port in the test program. In line 20, the "1200" indicates 1200 baud for the computer port. Press the following keys to set the baud rate: (CONFIG), More 1 of 3, BAUD RATE, 1200, (Hz).

Enter the following test program. The program shows that the computer is able to send instructions to, and read information from, the instrument.

```
10 'File = TESTPGM
20 OPEN "COM1:1200,N,8,1" AS #1
30 PRINT #1,"IP;"
40 PRINT #1,"SNGLS;"
50 PRINT #1,"CF 300MZ;TS;"
60 PRINT #1,"CF?;"
70 INPUT #1,CENTER
80 PRINT,"CENTER FREQUENCY = ";CENTER;"Hz"
90 END
```

When you have entered the program, type:

```
SAVE "TESTPGM"
```

When you are ready to run the program, turn on the instrument and run your program.

The program tells the instrument to perform an instrument preset and enter single sweep mode. Next, the program sets the center frequency to 300 MHz and takes a sweep. The program then queries the center frequency value and tells the computer to display CENTER FREQUENCY = 3.0E+8 Hz.

If the computer does not display the center frequency, refer to "If There is a Problem" at the end of this chapter.

# RS-232 Connections for the IBM PC/AT and Compatible Computers

#### **Equipment**

- IBM PC/AT or compatible with RS-232 interface
- HP 8542E/HP 8546A EMI receiver
- HP 13242G RS-232 cable (DCE-DCE), 7 pins used (refer to Appendix Bfor wiring of this cable)

#### **Interconnection Instructions**

1. Connect the instrument to the computer with the RS-232 cable. (See Figure 1-5.) The instrument uses a female RS-232 connector; the IBM PC/AT computer usually uses a male RS-232 connector. Some compatibles use a female RS-232 connector.




Figure 1-5. Connecting an IBM PC/AT Compatible Computer to the Instrument

2. Turn on the instrument and the computer.

#### **Test Program**

The program shown below is written to work with BASICA (version 2.0 or later) or GW BASIC.

To test the interconnection, first load the BASIC language for your computer and specify a communications buffer of 4096 bytes. Use the following command:

BASICA/C:4096

Set the instrument baud rate to 1200, to match the baud rate set up for the computer port in the test program. In line 20, the "1200" indicates 1200 baud for the computer port. To set the baud rate to 1200 press (CONFIG), More 1 of 3, BAUD RATE, 1200 (Hz).

Enter the following test program.

The program shows that the computer is able to send instructions to, and read information from, the instrument.

```
10 'File = TESTPGM
20 OPEN "COM1:1200,N,8,1" AS #1
30 PRINT #1,"IP;"
40 PRINT #1,"SNGLS;"
50 PRINT #1,"CF 300MZ;TS;"
60 PRINT #1,"CF?;"
70 INPUT #1,CENTER
80 PRINT,"CENTER FREQUENCY= ";CENTER;"Hz"
90 END
```

When you have entered the program, type:

```
SAVE "TESTPGM"
```

When you are ready to run the program, turn on the instrument and run your program.

The program tells the instrument to perform an instrument preset and enter single-sweep mode. Next, the program sets the center frequency to 300 MHz and takes a sweep. The program then queries the center frequency value and tells the computer to display CENTER FREQUENCY = 3.0E+8 Hz.

If the computer does not display the center frequency, refer to "If There is a Problem" at the end of this chapter.

# **Printing or Plotting**

You may wish to obtain a permanent record of data displayed on the screen. This can be done using the (COPY) key of the instrument, and a printer or plotter.

Note

The HP 7470A plotter does not support 2 plots per page. If you use an HP 7470A plotter with an HP 8542E/HP 8546A EMI receiver, you can select one plot per page or four plots per page, but not 2 plots per page.

#### Printer with an HP-IB Interface

#### **Equipment**

- HP 8542E/HP 8546A EMI receiver
- HP 2225 ThinkJet printer or HP 3630A PaintJet color printer
- HP 10833 (or equivalent) HP-IB cable

#### **Interconnection and Printing Instructions**

- 1. Turn off the printer and the instrument.
- 2. Connect the printer to the instrument using the HP-IB cable.

Note	Because HP-IB cables can be connected together, more than one instrument can communicate on the HP-IB. This means that both a printer and a plotter can be connected to the instrument (using two HP-IB cables). Each device must have its own HP-IB address.			
Note	Because the instrument cannot print or plot with two controllers (the computer and the instrument) connected, the computer must be disconnected from the HP-IB.			

- 3. Turn on the instrument and printer.
- 4. On the instrument, press CONFIG, Print Config.
- 5. The printer usually resides at the first device address. To enter address 1 for the printer, press PRINTER ADDRESS, 1, (Hz).
- 6. If the instrument is connected to an HP PaintJet printer and you want a color printout, press, Printer Type, More 1 of 3, PAINTJET. If the instrument is connected to an HP PaintJet printer and you want a black and white printout press, Print Options, then press COLOR MONOCHRM until MONOCHRM is underlined.
- 7. If you want the softkey labels to be printed with the display printout, press PRT MENU ON OFF so that ON is underlined.
- 8. Press Previous Menu, Previous Menu, COPY DEV PRNT PLT (PRNT should be underlined), then (COPY).

#### Plotter with an HP-IB Interface

#### **Equipment**

- HP 8542E/HP 8546A EMI receiver
- HP 7440A ColorPro plotter
- HP 10833 (or equivalent) HP-IB cable

### **Interconnection and Plotting Instructions**

- 1. Turn off the plotter and the instrument.
- 2. Connect the plotter to the instrument using the HP-IB cable.

Note	Instrument can communicate on the HP-IB. This means that both a printer and a plotter can be connected to the instrument (using two HP-IB cables). Each device must have its own HP-IB address.
Note	Because the instrument cannot print or plot with two controllers (the computer and the instrument) connected, the computer must be disconnected from the HP-IB.

- 3. Turn on the instrument and the plotter.
- 4. On the instrument, press CONFIG, Plot Config.
- 5. The plotter usually resides at the fifth device address. To set the plotter address, press PLOTTER ADDRESS, 5, (Hz), to enter the address 5 for the plotter.
- 6. With PLTS/PG 1 2 4, you can choose a full-page, half-page, or quarter-page plot. Press PLTS/PG 1 2 4 to underline the number of plots per page desired.
- 7. If two or four plots per page are chosen, a function is displayed that allows you to select the location on the paper of the plotter output. If two plots per page are selected, then the PLT [] LOC \_ \_ is displayed. If four plots per page are selected, then the PLT [] LOC \_ \_ is displayed. Press the softkey until the rectangular marker is in the desired section of the softkey label. The upper and lower sections of the softkey label graphically represent where the plotter output will be located.

Note

For a multi-pen plotter, the pens of the plotter draw the different components of the screen as follows:

Pen Number	Description
1	Draws trace A, the active function, markers, display line, and softkeys.
2	Draws limit 2, status and error messages.
3	Draws limit 1 and the annotation.
4	Draws the graticule.
5	Draws trace C.
6	Draws trace B.

8. Press Previous Menu, COPY DEV PRNT PLT (PLT should be underlined), then COPY).

Note

Once the address of the printer and plotter have been entered, the instrument remembers these addresses even though the power is turned off. There is no need to reenter them when the instrument is turned off and on.

### Printer with an RS-232 Interface

#### **Equipment**

- HP 8542E/HP 8546A EMI receiver
- HP 2225 ThinkJet printer with an RS-232 interface, or HP 3630A PaintJet color printer with an RS-232 interface

Note

Refer to Appendix B of this manual for the appropriate RS-232 cable connectors.

#### **Interconnection and Printing Instructions**

1. Turn off the instrument and the printer.

Note

The RS-232 interface allows only one device (either the printer or the plotter) to be connected to the instrument.

- 2. Connect the printer using an RS-232 cable.
- 3. Turn on the instrument and printer.
- 4. Press (CONFIG), More 1 of 3.
- 5. To set the baud rate to 9600 baud, press BAUD RATE, 9600, (Hz). To set the baud rate to 1200 baud, press: BAUD RATE, 1200, (Hz).

Note

Some of the programs in this manual utilize 1200 baud. If your system uses the RS-232 handshake lines, you can use 9600 baud for all of the programs.

- Press CONFIG, Print Config.
- 7. If the instrument is connected to an HP PaintJet printer and you want a color printout, press Printer Type, More 1 of 3, PAINTJET. If the instrument is connected to an HP PaintJet printer and you want a black and white printout, press Print Options then COLOR MONOCHRM.
- 8. If you want the softkey labels to be printed with the display print out, press PRT MENU ON OFF so that ON is underlined.
- 9. Press Previous Menu, Previous Menu, COPY DEV PRNT PLT (PRNT should be underlined), then (COPY).

#### Plotter with an RS-232 Interface

#### **Equipment**

- HP 8542E/HP 8546A EMI receiver
- HP 7440A ColorPro plotter with an RS-232 interface

Note

Refer to Appendix B of this manual for the appropriate RS-232 cable connectors.

# Interconnection and Plotting Instructions

1. Turn off the instrument.

Note

The RS-232 interface allows only one device (either the printer or the plotter) to be connected to the instrument.

- 2. Connect the plotter using an RS-232 cable.
- 3. Turn on the instrument and the plotter.
- 4. Press CONFIG. More 1 of 3.
- 5. To set the baud rate to 9600 baud, press BAUD RATE, 9600, (Hz). To set the baud rate to 1200 baud, press: BAUD RATE, 1200, (Hz).

Note

Some of the programs in this manual utilize 1200 baud. If your system uses the RS-232 handshake lines, you can use 9600 baud for all of the programs.

6. Press CONFIG, Plot Config. You can choose a full-page, half-page, or quarter-page plot with the PLTS/PG 1 2 4 softkey. Press PLTS/PG 1 2 4 to underline the number of plots per page desired.

7. If two or four plots per page are chosen, a function is displayed that allows you to select the location on the paper of the plotter output. If two plots per page are selected, then the PLT [ ] LOC \_ \_ function is displayed. If four plots per page are selected, then the PLT [] \_LOC \_ \_ is displayed. Press the softkey until the rectangular marker is in the desired section of softkey label. The upper and lower sections of the softkey label graphically represent where the plotter output will be located.

Note

For a multi-pen plotter, the pens of the plotter draw the different components of the screen as follows:

Pen Number	Description
1	Draws the annotation and graticule.
2	Draws trace A.
3	Draws trace B.
4	Draws trace C and the display line.
5	Draws the lower-limit line.
6	Draws the upper-limit line.

8. Press Previous Menu, COPY DEV PRNT PLT (so that PLT is underlined), then (COPY).

# Printing after Plotting or Plotting after Printing

Pressing (COPY) without changing COPY DEV PRNT PLT produces the function last entered (a print or a plot).

- To print after doing a plot, press (CONFIG), COPY DEV PRNT PLT (so that PRNT is underlined), then (COPY).
- To plot after printing, press (CONFIG), COPY DEV PRNT PLT (so that PLT is underlined), and (COPY).

#### If There is a Problem

This section offers suggestions to help get your computer and instrument working as a system. The test programs provided in this chapter let you know if the connection between the computer and the instrument interconnection is working properly.

If the test program does not run, try the following suggestions:

- 1. You may need to modify the program syntax to work with your computer. Refer to your BASIC manual for correct syntax.
- 2. The program must be executed correctly. Refer to your computer manual for information about program execution.
- 3. Check your program for errors.

If the test program runs on the computer, but the instrument does not respond, try the following suggestions:

- 1. Make sure the instrument is turned on. If the instrument has power, the green indicator light located on the line switch is on.
- 2. Make sure the interface cable is connected securely. Check the interface cable for defects. Make sure the correct cable is used.
- 3. If you are using an HP-IB interface, the instrument must be set to the correct address setting. Press CONFIG, More 1 of 3, RECEIVER ADDRESS.
- 4. If you are using the RS-232 interface, check the instrument baud rate. Refer to Appendix B for information about setting the baud rate on the instrument.
- 5. If a program in user memory is suspected of causing problems, press CONFIG, More 1 of 3, Dispose User Mem, DISPOSE USER KEY, ERASE STATEALL, and ERASE TRACEALL this erases all user programs, variables, and user-defined traces that are in instrument memory.
- 6. If you wish to reset the instrument configuration to the state it was in when it was originally shipped from the factory, use DEFAULT CONFIG. To access DEFAULT CONFIG, press CONFIG, More 1 of 3, DEFAULT CONFIG, DEFAULT CONFIG. (DEFAULT CONFIG requires a double key press.)

If you suspect your computer is causing the problems, check it by running a program that you know works. If your system still has problems, contact your HP salesperson. Your salesperson will either be able to help solve the problem or refer you to someone who can.

# Writing a Program

# What You'll Learn in This Chapter

This chapter introduces instrument programming. The first section of this chapter, "Writing Your First Program," helps you write your first instrument program and introduces programming fundamentals. The second section, "Getting Information from the Instrument," shows how to get data out of the instrument. A summary at the end of this chapter reviews the programming guidelines introduced.

If the computer is not connected to the instrument, follow the instructions in Chapter 1.

A general knowledge of the BASIC programming language and the instrument is recommended before reading this chapter. Refer to your software documentation manuals for more information about BASIC. For reference, Chapter 4 provides instrument commands in alphabetical order.

Note

All programming examples in this chapter for the HP-IB interface are written in HP BASIC 4.0, using an HP 9000 Series 200 computer.

# Writing Your First Program

When the instrument has been connected to a computer via HP-IB interface, the computer can be used to send instructions to the instrument. These instructions tell the instrument such things as frequency span, intermediate frequency bandwidth, and sweep mode. If a properly selected sequence of instructions is sent to the instrument, a measurement is made. Sequences of coded instructions are called programs.

#### Composing the Program

Most programs contain several common statements, or "commands," that address the instrument, preset it, and select its sweep mode. As an example, we will write a short program that executes only these common commands.

The following programs are for the HP-IB interfaces. Note the quotation marks that contain instrument commands in each line. Also note the semicolons at the end of each line, inserted at the end of each set of commands within the quotation marks. Using semicolons makes programs easier to read, prevents command misinterpretation, and is recommended by IEEE Standard 728.

Note

In commands where quotation marks occur, the computer recognizes data as character data and not BASIC programming language commands.

## Program Example for the HP-IB Interface

- O5 !File: "IBPROG1"
- 10 Instrument=718
- 20 CLEAR Instrument
- 30 OUTPUT Instrument; "IP;"
- 40 OUTPUT Instrument; "SNGLS; TS;"
- 50 LOCAL 7
- 60 END

Line 10 of our program assigns a variable called "Instrument" to our instrument at address 718. This instruction is followed by the HP BASIC CLEAR command, which resets the instrument on the HP-IB. With these two program lines, we have set up a clear communication path between the computer and the instrument.

Line 30 introduces the instrument preset (IP) command, which corresponds to the PRESET key on the instrument. The IP command sets all of the analog parameters of the instrument to known values and provides a good starting point for every measurement.

### Note

Most softkey functions on the instrument have corresponding programming commands. As you continue programming, you will learn the command names that correspond to the front-panel keys and softkeys.

Line 40 activates the single-sweep mode. Most remotely controlled measurements require control of the sweep. Once SNGLS has activated the single-sweep mode, take sweep (TS) starts and completes one full sweep. TS maintains absolute control over the sweep, which is necessary for accurate computer data transfer and reduced program execution time.

Before we end the program, we return the instrument to front-panel control with line 50, LOCAL 7. The LOCAL command corresponds to the (CONFIG) (LOCAL) key on the front panel of the instrument. (LOCAL 7 commands everything on the bus to go to local mode.)

Finally, in line 60, we end the program with the END command. (If you forget to include the END command, the computer will give an error message.)

Enter the program lines, press (RUN) on the computer, and watch the display as it completes each instruction.

# Modifying the Program

Remote operation of the instrument is similar to manual operation. Remote measurements are executed by commands that correspond to front-panel keys and softkeys.

The first chapter in the instrument operating manual shows you how to make a simple measurement using the calibration signal. We can add instructions to our program so that it will make the same measurement. (Because the manual process closely resembles that of the program, you may want to review "Making a Measurement" in the *EMI Receiver Series User's Guide*.)

By inserting a few lines into the initial program, we can set functions such as the center frequency and span, and we can activate a marker to find a signal's frequency and amplitude.

### Program Example for the HP-IB Interface

First, we set the center frequency to 300 MHz. The CF command corresponds to the center frequency function, CENTER FREQ. (All instrument commands, such as CF, are described in Chapter 4.

Insert the following program line between lines 40 and 50:

```
41 OUTPUT Instrument; "CF 300MZ;"
```

Next, we set the span to 200 MHz with the SP command. Add the following program line:

```
42 OUTPUT Instrument; "SP 200MZ;"
```

Because we are controlling the sweep, we must update the display screen with the following program line:

```
43 OUTPUT Instrument; "TS;"
```

When the program is executed, the instrument takes one full sweep before executing line 41. Line 41 changes the center frequency to 300 MHz, and line 42 changes the span to 200 MHz.

Enter the following program line to place a marker at the highest peak on the trace with a MKPK HI command:

```
44 OUTPUT Instrument: "MKPK HI;"
```

The completed program is shown below:

```
05 !File: "IBPROG2"
10 Instrument=718
20 CLEAR Instrument
30 OUTPUT Instrument; "IP;"
40 OUTPUT Instrument; "SNGLS; TS;"
41 OUTPUT Instrument; "CF 300MZ;"
42 OUTPUT Instrument; "SP 200MZ;"
43 OUTPUT Instrument; "TS;"
44 OUTPUT Instrument; "MKPK HI;"
50 LOCAL 7
60 END
```

Run the program to make the measurement. Watch the display as it completes each instruction. Notice that the program executes the instructions faster than is possible from the front panel.

When a certain measurement is repeated often, a computer program can save time. In addition, the computer is less likely to make an error than an operator manually entering the same instructions from the front panel.

# Enhancing the Program with Variables

In the last program, specific center frequency and span values were set. By modifying the program, we can cause different values to be set each time the program is run.

### Program Example for the HP-IB Interface

In the following program, the exclamation point (!) allows the words that follow to be ignored by the computer. Thus, they serve as comments in the program.

```
10
     !FILE: "VAR10"
20 REAL C_freq,S_pan !define the variables
30 Instrument=718
40 CLEAR Instrument
50 OUTPUT Instrument; "IP; SNGLS; TS;"
    !ask for the desired center frequency:
70 INPUT "CENTER FREQUENCY(MHz)?",C_freq
80
    !ask for the desired span:
90 INPUT "SPAN(MHz)?", S_pan
100 !send the center frequency and span to the
110 !instrument and take a sweep to update the
120 !screen:
130 OUTPUT Instrument; "CF "; C_freq; "MZ;"
140 OUTPUT Instrument; "SP "; S_pan; "MZ;"
150 OUTPUT Instrument; "TS;"
160 !find the signal peak with peak search:
170 OUTPUT Instrument; "MKPK HI;"
180 LOCAL 7
190 END
```

Three modifications are made to the previous program so it includes center frequency and span variables. First, using the HP BASIC REAL command, we define two variables, C\_freq and S\_pan. The frequency and span parameters are stored in these variables. (Refer to line 20.)

Second, using the HP BASIC INPUT command, we prompt the user to enter the desired center frequency and span. The center frequency and span values are entered on the computer; because the measurement units will be entered by the program, the user does not enter them. (See lines 70 to 140.)

Third, we modify the output parameter statements so that the values stored in C\_freq and S\_pan are sent to the instrument. (See lines 130 to 140.)

A sweep is taken after the parameters are sent to the instrument, to ensure that the screen is updated before the marker is placed on the highest signal peak.

# Getting Information from the Instrument

The first part of this chapter demonstrated techniques for setting instrument parameters. This section demonstrates a technique for getting information out of the instrument.

For example, in the second program of this chapter, we placed a marker at the highest peak of a trace and the value of the marker could be read in the upper right-hand corner of the instrument display. In the following program, we will add some commands that will read the marker's frequency and amplitude value and return those values to the computer.

### Program Example for the HP-IB Interface

```
10 !FILE: "MKR"
20 REAL A_mpmarker,F_reqmarker !define variables
30 Instrument=718
40 OUTPUT Instrument; "IP;"
50 !set the output format of the instrument for
60 !real numbers:
70 OUTPUT Instrument; "TDF P;"
80 !set the instrument parameters:
90 OUTPUT Instrument; "SNGLS;"
100 OUTPUT Instrument; "CF 300MZ;"
110 OUTPUT Instrument; "SP 200MZ;"
120 OUTPUT Instrument; "TS;"
130 OUTPUT Instrument; "MKPK HI;"
140 !ask the instrument for the marker's
150 !amplitude value:
160 OUTPUT Instrument; "MKA?;"
170 !send the amplitude value to the computer:
180 ENTER Instrument; A_mpmarker
190 !ask the instrument for the marker's
200 !frequency value:
210 OUTPUT Instrument; "MKF?;"
220 !send the frequency value to the computer:
230 ENTER Instrument; F_reqmarker
240 !print the amplitude and frequency:
250 PRINT "THE SIGNAL PEAK IS "; A_mpmarker;
260 PRINT " dB\mu V AT ";F_reqmarker/1.E+6;" MHz"
270 !set the instrument to continuous sweep mode:
280 OUTPUT Instrument; "CONTS;"
290 LOCAL 7
300 END
```

First, using the HP BASIC REAL command, we define two variables, A\_mpmarker and F\_reqmarker. The amplitude and frequency values of the marker are stored in these variables. (See line 20.)

Second, we set the output format of the instrument for real numbers with the instrument's trace data format (TDF) command. (See line 70.) As in our original program, we set the center frequency and span values. A sweep is taken and the marker is placed on the trace.

Next, we ask the instrument for the amplitude value of the marker. We have the instrument send the marker amplitude value to the computer. Note that there can be only one instrument query per programming line. We also ask the instrument for the frequency value of the marker, and we have the instrument send the marker frequency value to the computer. (See lines 100 through 230.)

Finally, we print the values on the computer screen:

```
"THE SIGNAL PEAK IS ... dB\mu V AT ... MHz"
```

Before we end the program, we return the instrument to continuous-sweep mode and local control.

# **Programming Guidelines**

- 1. Perform the measurement manually, keeping track of the sequence of functions used.
- 2. In the written program, execute an instrument preset (IP) and set single-sweep mode (SNGLS) before setting other instrument functions.
- 3. Use variables for function values. List variables at the beginning of the program.
- 4. Activate instrument functions in logical order. Place quotation marks around instrument commands. Separate commands with semicolons.
- 5. After setting instrument functions, execute a take sweep (TS) command before reading data or activating markers.
- 6. The instrument can return only one value per programming line. Do not have more than one query per programming line.
- 7. Use the exclamation point (!) to include comment lines when using HP BASIC. Use the apostrophe (') or REM to create comment lines when using GW BASIC. (The use of the exclamation point and the apostrophe to create comment lines are dependent on the controller and the programming language [not interface-dependent] and may be different for your system.)

# **Programming Topics**

# What You'll Learn in This Chapter

This chapter contains the following advanced programming techniques and topics.

- An example of moving and saving trace data from the instrument into the computer.
- An example of how instrument states are saved with the computer, then returned to the instrument.
- An example of reading trace data from a computer disk.
- An example of saving and recalling instrument states.
- An example of returning the instrument to its former state.
- A summary of using different formats for trace data transfers.

Many of the programming suggestions discussed in Chapter 2 have been incorporated into the programs in this chapter.

Note

All programming examples for the HP-IB interface in this chapter are written in HP BASIC 4.0.

A general knowledge of the BASIC programming language is recommended before reading this chapter. (Refer to your software documentation manuals.) Chapter 4 defines instrument commands alphabetically.

# Controlling Trace Data with a Computer

Using sample programs, this section shows you how to read trace data and store the data with your computer.

### **Reading Trace Data**

The following program, which has been annotated with comments, reads a trace from the instrument and stores the trace data in a variable.

### Program Example for the HP-IB Interface

```
10 !FILE: "IBPROG5"
20 !create a 401 point trace array:
30 REAL Trace_a(1:401)
40 Instrument=718
50 OUTPUT Instrument; "IP;"
60 !set the output format of the instrument for
70 !real numbers:
80 OUTPUT Instrument; "TDF P;"
90 !set the instrument parameters:
100 OUTPUT Instrument; "SNGLS;"
110 OUTPUT Instrument; "CF 300MZ;"
120 OUTPUT Instrument; "SP 200MZ;"
130 OUTPUT Instrument; "TS;"
140 OUTPUT Instrument; "MKPK HI;"
150 !move peak to center of screen:
160 OUTPUT Instrument; "MKCF;"
170 OUTPUT Instrument; "TS;"
180 !ask the instrument for trace data:
190 OUTPUT Instrument; "TRA?;"
200 !send the trace data to the computer:
210 ENTER Instrument; Trace_a(*)
220 OUTPUT Instrument; "CONTS;"
230 LOCAL 7
240 END
```

Trace data can be read with the computer by making three changes to the program created in Chapter 2. First, we modify the program to create a 401-point trace array, called Trace\_a, in which the trace data will be stored. Second, the program uses the TRA command to request trace A data. (The MKA and MKF commands from the previous program have been deleted.) Third, the instrument sends trace A data to the variable, Trace\_a.

### Saving Trace Data

The trace data in the previous program can be stored on a computer disk by making three program modifications.

```
!FILE: "IBPROG6"
10
20 !create a 401 point trace array:
30 REAL Trace_a(1:401)
40 Instrument=718
50 OUTPUT Instrument: "IP:"
60 !set the output format of the instrument for
70 !real numbers:
80 OUTPUT Instrument; "TDF P;"
90 !set the instrument parameters:
100 OUTPUT Instrument; "SNGLS;"
110 OUTPUT Instrument; "CF 300MZ;"
120 OUTPUT Instrument; "SP 200MZ;"
130 OUTPUT Instrument; "TS;"
140 OUTPUT Instrument; "MKPK HI;"
150 !move peak to center of screen:
160 OUTPUT Instrument; "MKCF;"
170 OUTPUT Instrument; "TS;"
    !ask the instrument for trace data:
190 OUTPUT Instrument; "TRA?;"
    !send the trace data to the computer:
210 ENTER Instrument; Trace_a(*)
220
     !create file to store trace
230 !file is 13 records long:
240 CREATE BDAT "DATA_A",13
250
    !assign path for the file:
260 ASSIGN @File TO "DATA_A"
270 !send trace data to the file:
280 OUTPUT @File; Trace_a(*)
290 OUTPUT Instrument; "CONTS;"
300 LOCAL 7
310 !close file:
320 ASSIGN @File TO *
330 END
```

First, using the CREATE command, we create an empty file on the disk for storing the trace. The file is 13 records long. (To determine the number of records, the 401-point trace is multiplied by 8 bytes per point, the storage required for real numbers, then divided by 256 bytes per record. The result is rounded to the next largest integer.)

Next, we assign an input and an output path to the file DATA\_A. Then, we send the trace data to the file. (See lines 260 through 280.) Finally, in line 320, we close the file.

#### Note

If a program containing the CREATE command is run twice, the computer will report an error the second time because the file already exists. To prevent this error, place an exclamation mark before the CREATE command to "comment out" the line after the first run. (See line 240.)

# Reading Trace Data from a Computer Disk

If we want to return trace data to the instrument for later viewing, we must work the "saving" process in reverse. The following program reads a trace previously stored on a computer disk and stores the trace in an array variable.

# Program Example for the HP-IB Interface

```
10 !FILE: "IBPROG7"
20 !create a 401-point trace array:
30 REAL Trace_a(1:401)
40 !assign path to the file with the
50 !trace in it:
60 ASSIGN @File TO "DATA_A"
70 !enter trace into variable Trace_a:
80 ENTER @File;Trace_a(*)
90 !close file:
100 ASSIGN @File TO *
110 END
```

First, in line 30, the program creates a 401-point trace array. Then, in line 60, the program assigns a path to the trace file. Finally, in line 80, the program sends the trace data to the variable Trace\_a(\*).

## Saving and Recalling Instrument States

The instrument's control settings (or its "state") can be saved with a computer and retrieved later to streamline test sequences or repeat manual measurements. Control settings can be stored in one of eight state registers in the instrument, in computer memory, or on a computer disk.

The first program in this section demonstrates techniques for saving an instrument state, along with its current trace A data. The second program demonstrates how the state information and the trace data is read from the computer and returned to the instrument.

If you wish to save states in the instrument, see the descriptions of the save state (SAVES) and recall state (RCLS) commands in Chapter 4.

### Saving the Instrument's State

The following two programs read and store a trace from the instrument.

### Program Example for the HP-IB Interface

```
!FILE: "IBPROG8"
20 !define 202 character string:
30 DIM Learn_string$[202]
40 !create 401-point array to store trace:
50 INTEGER Trace_a(1:401)
60 Instrument=718
70 !set output format for two byte integers:
80 OUTPUT Instrument; "TDF B;"
90 !ask instrument for trace data:
100 OUTPUT Instrument; "TRA?;"
110 !send trace to the computer:
120 ENTER Instrument USING "#,W";Trace_a(*)
130 !get learnstring from instrument:
140 OUTPUT Instrument; "OL;"
150 ENTER Instrument USING "#,202A"; Learn_string$
160 !create file to store trace:
170 CREATE BDAT "STATE",4
180 !assign path to the file:
190 ASSIGN @File TO "STATE"
200 !send trace to the file:
210 OUTPUT @File; Learn_string$, Trace_a(*)
220 !return output format to default mode:
230 OUTPUT Instrument; "TDF P;"
240 !close file:
250 ASSIGN @File TO *
260 END
```

The program stores the trace in the variable called Trace\_a(\*). The state of the instrument is stored in the variable Learn\_string\$. These two variables are then saved in a file called STATE. Finally, the file is stored on a disk.

Using the data stored in STATE, the instrument settings can be reset according to the saved state. Then, using the stored trace data, trace data can be viewed on the display.

Line 30 gives the dimensions of the learn string using the HP BASIC DIM command. Learn strings for the instrument require 202 bytes of storage space. Also see the output learn string (OL) command.

Line 70 uses TDF B to format the output in binary. Binary provides the fastest data transfer and requires the least amount of memory to store data. Each data point is transferred in binary as two 8-bit bytes. The data points are in the internal representation of measurement data. (See "Different Formats for Trace Data Transfers" at the end of this chapter for more information about trace data formats.)

When the trace and state data are sent from the instrument to the computer, they must be formatted. Lines 120 and 150 format trace data with the HP BASIC USING command. In the formatting statement, "#" indicates that the statement is terminated when the last ENTER item is terminated. EOI (end-or-identify) and LF (line feed) are item terminators, and early termination will result in an inaccurate learn string. "W" specifies word format. "202A" indicates the size of the learn string.

Line 170 creates a file called STATE that is 4 records long. (To determine the number of records for the computer in our example, the 401-point trace is multiplied by 2 bytes per point and the 202-byte learn string is added to give 1004 bytes total. This total is divided by 256 bytes per record, resulting in 4 records.)

#### Note

If the program containing the CREATE command is run twice, the computer will report an error the second time because the file already exists. To prevent this, place an exclamation mark before the CREATE command to "comment out" line 170 after the program has been executed.

# Returning the Instrument to its Former State

The following programs read a trace stored in a file and load it into a variable.

### Program Example for the HP-IB Interface

```
10 !FILE: "IBPROG9"
20 !define 202 character string:
30 DIM Learn_string$[202]
40 !create 401 point array to store trace:
50 INTEGER Trace_a(1:401)
60 Instrument=718
70 !assign path to the file:
80 ASSIGN @File TO "STATE"
90 !get values for Learn_string$
100 !and Trace_a(*) from disk:
110 ENTER @File;Learn_string$,Trace_a(*)
120 !send learnstring to instrument:
130 OUTPUT Instrument; "IP DONE;"
140 ENTER Instrument
150 OUTPUT Instrument; Learn_string$
160 !set single sweep mode:
170 OUTPUT Instrument; "SNGLS;"
180 !prepare instrument for a trace from
190 !the computer:
200 OUTPUT Instrument; "TRA #A";
210 !send trace to the instrument
220 OUTPUT Instrument USING "#,W";802,Trace_a(*)
230 !view trace to see it was sent:
240 OUTPUT Instrument; "VIEW TRA;"
250 !close file:
260 ASSIGN @File TO *
270 END
```

The HP-IB program reads a trace stored in the file STATE, then loads it into the variable  $Trace_a(*)$ .

First, the settings of the instrument that were stored in the variable LEARN\$ are recalled. The instrument state is changed to the same state as when the trace was stored. Then previously stored trace data is returned to the instrument and the trace is viewed on the instrument screen. Finally, line 220 uses the HP BASIC USING command to format the trace data.

### Different Formats for Trace Data Transfers

Two different ways to format trace data using the TDF command were introduced earlier in this chapter (TDF P and TDF B). This section describes all the available trace data formats.

The EMI receiver or receiver RF section provides five formats for trace data transfers: real number (P) format, binary (B) format, A-block format, I-block format, and measurement units (M) format.

#### P Format

The P format allows you to receive or send trace data in a real-number format. This is the default format when the instrument is powered up. Numbers are in dBm, dBmV, dB $\mu$ V, volts, or watts. The AUNITS command can be used to specify the amplitude units. Real-number data may be an advantage if you wish to use the data later in a program. However, data transfers using P format tend to be slow and take up a lot of memory (compared to binary format, the P format can take up to four times the amount of memory). Data is transferred as ASCII type.

Although the instrument can send the trace data to the computer as real numbers, the trace data cannot be sent back to the instrument without changing the trace data to measurement units (integers). See the following example.

#### Example of Using the P Format

This example sends trace data to the computer and back to the instrument using P format.

Note

The instrument must be in the log amplitude scale to use the TDF P format.

```
1 REAL Trace_data(1:401)
```

10 OUTPUT 718; "IP; CF 300MHZ; SP 20MHZ; SNGLS; TS; "

20 OUTPUT 718; "TDF P; TRA?; "

30 ENTER 718; Trace\_data(\*)

40 OUTPUT 718; "VIEW TRA; MOV TRA,O;"

50 OUTPUT 718; "RL?;"

60 DISP "PRESS CONTINUE WHEN READY"

70 PAUSE

80 ENTER 718; Ref\_level

90 MAT Trace\_data=Trace\_data-(Ref\_level)

100 MAT Trace\_data=Trace\_data\*(100)

110 MAT Trace\_data=Trace\_data+(8000)

120 OUTPUT 718;"TRA ";

130 OUTPUT 718; Trace\_data(\*)

140 LOCAL 718

150 END

Declare an array for trace data. Take a measurement sweep. Activate the P format, output trace A data.

The computer receives trace A data from the instrument.

To verify that the trace data is transferred back to the instrument, set trace A to zeros.

Determine the amplitude of the reference level. The amplitude of the reference level is used to change the integers sent to the instrument into real numbers.

Get the reference level.

These lines change the real trace data (stored in Trace\_data) into integers (in measurement units).

Sends the trace data back to the instrument in measurement units.

The trace data is sent to the computer in parameter units. A parameter unit is a standard scientific unit. For the TDF P format, the parameter unit depends on the current amplitude units (dBm, dBmV, dB $\mu$ V, V, W). Use the AUNITS command to change the units.

For more detailed information about the P format, see the description for TDF in Chapter 4.

#### **B** Format

The B format allows you to receive or send trace data in a binary format. The B format provides the fastest data transfer and requires the least amount of memory to store data. Each data point is transferred in binary as two 8-bit bytes. The data points are in the internal representation of measurement units (0 to 8000). Unlike the A-block format, the B format does not send a header. An end-or-identify (EOI) is sent with the last byte of data.

#### Example of Using the B Format

This example sends trace data from the instrument in B format. The trace data format must be changed to A-block format to return the trace data to the instrument. See following example.

Note	It is not possible to return data to the instrument using binary format. You must use either A-block or I-block format to return the trace data to the instrument.		
10 INTE	GER Tra_binary(1:401)	Tra_binary stores the trace data.	
20 ASSI	GN @Sa TO 718; FORMAT OFF		
30 OUTP	OUT @Sa;"IP;CF 300MZ;SP 20MZ;SNGLS;TS;"	Takes a measurement sweep.	
40 OUTP	UT @Sa;"MDS W;TDF B;TRA?;"	Outputs trace A data.	
50 ENTE	R @Sa;Tra_binary(*)		
60 OUTP	UT @Sa;"TDF A;"	Changes the trace data format to Ablock format.	
70 OUTP	UT @Sa;"MOV TRA,O;"	To verify that the trace data is sent back to the instrument, move all zeros into trace A.	
80 DISP	"PRESS CONTINUE WHEN READY"		
90 PAUS	Œ		
100 OUT	PUT @Sa USING "#,K,W";"TRA#A",802	Prepares the instrument for the trace data.	
110 OUT	PUT @Sa;Tra_binary(*)	Transfers the trace data back to the instrument.	
120 OUT	PUT QSa;"VIEW TRA;"		
130 LOC	AL 718		
140 END	•		

The result is transmitted as binary information. The MDS command can be used to change the data format from two 8-bit bytes to one 8-bit byte. For more detailed information about the B format and the MDS command, see the descriptions for TDF and MDS in Chapter 4.

Binary data can be converted to dBm or volts. For example, use the following equation to change the trace data (in measurement units) to a real logarithmic number ( $dB_{\mu}V$ ):

$$dB\mu V = ((\text{trace data} - 8000) \times 0.01) + \text{reference level (in } dB\mu V)$$

To change the trace data (in measurement units) to linear data (volts):

volts = 
$$\left(\frac{\text{reference level}}{8000}\right) \times \text{trace data}$$

The following programming converts binary data to  $dB\mu V$ .

```
! 8546 binary data to real numbers
   20
         Rcvr=718
   30
         ASSIGN @Rcvr_bin TO Sa; FORMAT OFF
   40
         INTEGER Trace_a(1:401)
   50
         OUTPUT Rcvr; "AUNITS DBUV;"
   60
         OUTPUT Rcvr; "RL?;"
   70
         ENTER Rcvr; Ref_lev
   80
         PRINT Ref_lev
         OUTPUT Rcvr; "TDF B; TRA?;"
   90
   100
         ENTER @Rcvr_bin:Trace_a(*)
   110
         ! now the instrument has all the data
   120
         ! to determine the measured trace data
   130
         REAL Trace_a_real(1:401)
   140
           MAT Trace_a_real= Trace_a-(8000) ! Results in below ref
   150
           ! level
   160
           MAT Trace_a_real = Trace_a_real*(.01)! now in hundredths of db
   170
           ! below ref lev
   180
           MAT Trace_a_real= Trace_a_real+(Ref_lev)
   190
         FOR I=1 TO 401
   200
             PRINT Trace_a_real(I)
   210
             NEXT I
   220
         END
The following programming converts binary data to volts.
         ! 8546 binary data to real numbers (linear)
   20
         Rcvr=718
   30
         ASSIGN @Rcvr_bin TO Rcvr; FORMAT OFF
   40
         INTEGER Trace_a(1:401)
   50
         OUTPUT Rcvr; "LN; AUNITS V;"
   60
         OUTPUT Rcvr; "RL?;"
   70
         ENTER Rcvr; Ref_lev
   08
         Ref_lev_factor=Ref_lev/8000
   90
         OUTPUT Rcvr; "TDF B; TRA?;"
   100
         ENTER @Rcvr_bin:Trace_a(*)
         ! now the instrument has all the data
   110
   120
         ! to determine the measured trace data
   130
         REAL Trace_a_real(1:401)
   140
           MAT Trace_a_real= Trace_a*(Ref_lev_factor)
   150
         FOR I=1 TO 401
   160
             PRINT Trace_a_real(I)
   170
             NEXT I
   180
         END
```

#### **A-Block Format**

The A-block format is similar to binary format in that each data point is sent as two 8-bit bytes (this, too, is in the internal representation of measurement data). A-block format also transfers a four-byte header before the 401 points of trace data. These bytes are the ASCII character "#", "A", and two-byte number representing the length of the trace data, followed by the data bytes.

#### Example of Using the A-Block Format

This example sends trace data from the instrument to the computer and back to the instrument in A-block format.

```
10 INTEGER Tra_binary(1:401)
                                                                   Declare an array for trace
                                                                   data.
20 DIM Header$[4]
                                                                   Declare a string for the
                                                                   #, A, MSB length, and
                                                                   LSB length header.
30 OUTPUT 718; "IP; CF 300MZ; SP 20MZ; SNGLS; TS; "
                                                                   Take a measurement sweep.
40 OUTPUT 718; "MDS W; TDF A; TRA?; "
                                                                   Send trace A to the com-
                                                                   puter in A-block format.
50 ENTER 718 USING "#,4A,401(W)"; Header$, Tra_binary(*)
                                                                   The computer receives
                                                                   the header and the trace
                                                                   data.
60 PRINT "PRESS CONTINUE TO RETURN DATA TO THE INSTRUMENT"
70 PAUSE
80 OUTPUT 718; "IP; TS; VIEW TRA;"
                                                                   View trace A.
90 OUTPUT 718; "TDF A;"
100 OUTPUT 718 USING
                                                                   The instrument receives
"#,K,W,401(W)";"TRA#A",802,Tra_binary(*),";"
                                                                  the trace data from the
                                                                   computer.
110 END
```

The transferred trace data consists of #A, a two-byte number representing the most significant byte (MSB) length and the least significant byte (LSB) length, and the data bytes. Depending on the terminal you are using, the data bytes may appear as symbols instead of numbers. Consult your computer documentation to determine the numeric value of the data bytes.

For more detailed information about the A-block format and the MDS command, see the descriptions for TDF and MDS in Chapter 4.

#### **I-Block Format**

The I-block format transfers data points as two 8-bit bytes in the internal representation of measurement data. In addition to transferring trace data, I-block format also transfers the characters "#" and "I". These characters indicate that the trace data is in I-block format. The I-block format allows the instrument to accept up to 401 points of trace data when using I-block format. Fewer than 401 points of trace data can be specified, and the instrument will accept data until an EOI signal is sent to it. Therefore, returning the trace data to the instrument requires an important instruction, END. (See following example.)

### **Example of Using the I-Block Format**

This example sends trace data from the instrument to the computer and back to the instrument in I-block format.

```
10 INTEGER Tra_binary(1:401)

Declare an array for trace data.

20 DIM Header$[2]

Declare an array for #,

I header.

30 OUTPUT 718; "IP; CF 300MZ; SP 20MZ; SNGLS; TS;"

Take a measurement sweep.

Send trace A data in I-block format.
```

50 ENTER 718 USING "#,2A,401(W)"; Header\$, Tra\_binary(\*)

The computer receives the header and trace A data.

60 PRINT "PRESS CONTINUE TO RETURN DATA TO THE INSTRUMENT"

70 PAUSE

80 OUTPUT 718; "IP; TS; VIEW TRA;"

90 OUTPUT 718;"TDF I:"

100 OUTPUT 718 USING "#,K,W,401(W)";"TRA#I",

Tra\_binary(\*)END

110 END

View trace A.

The trace data is returned

to the instrument.

The END statement in line 100 sends the instrument the last data byte stored in the array and sets the HP-IB EOI line "true," as required by the I-block format.


The transferred trace data consists of #I, followed by data bytes until the EOI line is set true.

For more detailed information about the I-block format and the MDS command, see the descriptions for TDF and MDS in Chapter 4.

#### **M** Format

The M format is for sending trace data only. It formats the trace data in the internal format used by the instrument, also known as measurement units. Refer to Figure 3-1.

The displayed amplitude of each element falls on one of 8000 vertical points with 8000 equal to the reference level. For log scale data, each point is equal to 0.01 dB. The peak of the signal in Figure 3-1 is equal to 72 dB $\mu$ V for the EMI receiver (87 dB $\mu$ V for the RF filter section) or two divisions below the reference level. In measurement units, it is equal to 6000 (8000 - 2000 = 6000). In linear mode, each point has a resolution of [reference level in volts divided by 8000]. The range of internal data is -32,768 to +32,767. In practice however, the range limits can be reached during trace math operations only.



cu119e

Figure 3-1. Measurement Unit Range and Trace Amplitudes

Table 3-1. Measurement Units

Index Number	Description	
1	A number within the range of 8161 to 32,767 measurement units is clipped at upper limit.	
2	The area from 8000 (reference level) to 8160 (1.6 dB above reference level) represents the amount a trace element's amplitude can exceed the top graticule and still be displayed without clipping.	
3	The area from 0 to 8000 represents the displayed range for trace amplitude data. The range of 0 to 8000 varies according to the amplitude scale of the instrument as follows:	
	<ul> <li>In 10 dB/division, the range is from 0 to 8000.</li> <li>In 5 dB/div, the range is from 4000 to 8000.</li> <li>In 2 dB/div, the range is from 6000 to 8000.</li> <li>In 1 dB/div, the range is from 7000 to 8000.</li> </ul>	
4	A number within the range of 0 to $-32,768$ measurement units is clipped at lower limit.	

### Example of Using the M Format

This example sends trace data from the instrument to the computer in M format.

- 10 INTEGER A(1:401)
- 30 OUTPUT 718;"IP;CF 300MZ;SP 20MZ;SNGLS;TS;"
- 40 OUTPUT 718; "TDF M; TRA?;"
- 50 ENTER 718; A(\*)
- 60 PRINT A(\*)
- 70 END

Dimension array A.

Take a measurement sweep.

Send trace A data in M format.

The computer receives the trace data.

Print trace data.

Note

All trace math functions are done using measurement units. See Table 4-4 for a list of all trace math functions.

The result is in measurement units (-32768 to +32767).

Table 3-2 summarizes the different trace data formats.

Table 3-2. Summary of the Trace Data Formats

Trace Data Format	Description	Remarks
TDF P	Real Number Format	Instrument must be in log scale to use TDF P. To send the trace data back to the instrument, the data must be converted to measurement units.
TDF B	Binary Format	Fastest format for trace data transfers. Use the A-block format to send data back to the instrument.
TDF A	A-Block Data Format	Trace data preceded by "#," "A," and a two-byte number. To use the A-block format for sending data, you must provide the number of data bytes.
TDF I	I-Block Data Format	Trace data preceded by "#," and "I."
TDF M	Measurement Data Format	TDF M cannot be used to send trace data back to the instrument.

# **Programming Commands**

# What You'll Learn in This Chapter

This chapter is a reference for the EMI receiver and receiver RF section that lists all parameters for each of the programming commands available.


To find a programming command that performs a particular function, first refer to Table 4-4 where commands are categorized by function. Once the desired command is found in the functional index, refer to the description for the command in this chapter.

This chapter includes the reference tables listed below:

- Table 4-1, Syntax Elements
- Table 4-2, Characters and Secondary Keywords (reserved words)
- Table 4-3, Summary of Compatible Commands
- Table 4-4, Functional Index

# **Syntax Conventions**

Command syntax is represented pictorially.



cu114e

Figure 4-1. Command Syntax Figure

- Ovals enclose command mnemonics. The command mnemonic must be entered exactly as shown.
- Circles and ovals surround secondary keywords or special numbers and characters. The characters in circles and ovals are considered reserved words and must be entered exactly as shown. See Table 4-2.
- Rectangles contain the description of a syntax element defined in Figure 4-1.
- A loop above a syntax element indicates that the syntax element can be repeated.
- Solid lines represent the recommended path.
- Dotted lines indicate an optional path for bypassing secondary keywords or using alternate units.
- Arrows and curved intersections indicate command path direction.
- Semicolons are the recommended command terminators. Using semicolons makes programs easier to read, prevents command misinterpretation, and is recommended by IEEE Standard 728.

Note

Uppercase is recommended for entering all commands unless otherwise noted.

Syntax Elements are shown in the syntax diagrams as elements within rectangles.

Table 4-1. Syntax Elements

Syntax Component	Definition/Range	
instrument command	Any instrument command in this chapter, with required parameters and terminators.	
character	$S_P$ ! " # \$ % & '() + , /0123456789: ; A B C D E F G H I J K L M N O P Q R S T U V W X Y Z [\]? _ 'a b c d e f g h i j k l m n o p q r s t u v w x y z (Characters are a subset of data byte.)	
character & EOI	8-bit byte containing only character data and followed by end-or-identify (EOI) condition, where the EOI control line on HP-IB is asserted to indicate the end of the transmission. END signifies the EOI condition.	
data byte	8-bit byte containing numeric or character data.	
data byte & EOI	8-bit byte containing numeric or character data followed by end-or-identify (EOI) condition, where the EOI control line on HP-IB is asserted to indicate the end of the transmission. END signifies the EOI condition.	
delimiter	" \@ = /^\$ %;!':" & Matching characters that mark the beginning and end of a character string, or a list of user-defined functions or instrument commands. Choose delimiting characters that are not used within the string they delimit.	
digit	0 1 2 3 4 5 6 7 8 9	
lsb length	Represents the least significant byte of a two-byte word that describes the number of bytes returned or transmitted. See msb length.	
msb length	Represents the most significant byte of a two-byte word that describes the number of bytes returned or transmitted. See lsb length.	
number	Expressed as integer, decimal, or in exponential (E) form. Real Number Range: $\pm$ 1.797693134862315 $\times$ 10 <sup>308</sup> , including 0.	
	Up to 15 significant figures allowed. Numbers may be as small as $\pm$ 2.225073858507202 $\times$ 10 $^{-308}$	
	Integer Number Range: -32,768 through +32,767	
output termination	Carriage return ( $C_R$ ) and line feed ( $L_F$ ), with end-or-identify (EOI) condition. ASCII codes 13 (carriage return) and 10 (line feed) is sent via HP-IB, then the end-or-identify control line on HP-IB sets to indicate the end of the transmission.	
predefined function	BITF, CNTLI, CORREK, DONE, HN, LIMIFAIL, MEAN, MEANTH, MINPOS, MKBW, PEAKS, PKPOS, PWRBW, REV, RMS, SER, STB, SUM, SUMSQR, TRCMEM, VARIANCE.	
	A predefined function is an instrument command that returns a number that can be operated on by other instrument commands. Insert a predefined function into a command statement where predefined function appears in the command syntax chart.	
	If a predefined function takes a parameter (for example, PKPOS TRA), it can be used only as the last parameter of a instrument command that has two or more predefined functions as parameters. For example, MPY V_AR,PKPOS TRB,HAVE DISK; is illegal, but MPY V_AR,DONE,HAVE DISK; is not.	

Table 4-1. Syntax Elements (continued)

Syntax Component	Definition/Range		
predefined variable	The values of the following variables change depending on the current instrument settings. Each variable represents the value of the command function that has the same name as the variable.		
	AMB, AMBPL, ANNOT, AT, AVBW, BAUDRATE, CF, CNTLA, CNTLB, CNTLC, CNTLD, COUPLE, DATEMODE, DET, FA, FB, FMGAIN, FOFFSET, GR, GRAT, IFBW, INZ, LG, LIMIDISP, LIMIMODE, LIMIREL, LIMITEST, MEASURE, MF, MKA, MKACT, MKF, MKFCR, MKN, MKNOISE, MKP, MKPAUSE, MKPX, ML, MKTRACK, MSI, NRL, POWERON, PREAMPG, PRNTADRS, PSTATE, RB, RL, RLPOS, ROFFSET, SETDATE, SETTIME, SP, SQLCH, SRCALC, SRCAT, SRCNORM, SRCPOFS, SRCPSTP, SRCPSWP, SRCPWR, SRCTK, SS, ST, SWPCPL, TH, TIMEDATE, TIMEDSP, VB, VBR, WINZOOM, ZMKCNTR, ZMKSPAN.		
trace element	Value contained in one trace point. Notated as TRA[N] where N specifies the point position in the trace array. Values for N are 1 to 401 (for traces A, B, C) or 1 to 2047 (for traces specified by TRDEF). The same values apply to trace B (TRB[N]), trace C (TRC[N]), and user-defined traces (LABEL[N]).		
trace range	Values contained in trace segment. Multi-point segments are notated as TRA[N,M], where N and M are end points of a segment and specify point positions in trace array. Values for N or M are 1 to 401 (for traces A, B, C), or 1 to the length of a trace as specified by TRDEF. The same values apply to trace B (TRB[N,M]), trace C (TRC[N,M]), and user-defined traces (LABEL[N,M]). Single-point segments are notated the same as the trace element above.		
units	Represent standard scientific units.		
	Frequency Units:	GHZ or GZ, MHZ or MZ, KHZ or KZ, HZ	
	Amplitude Units: DB, DM, DBMV, DBPT, DBUA, DBUV, DBUAM, DBUVM, G, PT, V, MV, UAM, UV, UVM, W, MW, UW		
	Time Units: SC, MS, US		
	Current Units:	A, MA, UA	
	Impedance Units: OHM		
user-defined trace	A label 2 to 11 characters long that is defined by the TRDEF command. Choice of characters is A through Z and the underscore(_). The underscore should be used as the second character of the label. Omitting the underscore, or using the underscore as other than the second character in a label, is not recommended.		
user-defined variable	A label 2 to 11 characters long that is defined by the VARDEF command. Choice of characters is A through Z and the underscore(_). The underscore should used as be the second character of the label. Omitting the underscore, or using the underscore as other than the second character in a label, is not recommended.		

In the syntax diagrams, characters and secondary keywords are shown within circles or ovals. Characters and secondary keywords must be entered exactly as shown.

Table 4-2. Characters and Secondary Keywords (Reserved Words)

Element	Description		
A	Amp (unit) or A-block data field		
ABSHZ	Absolute Hz (unit)		
AC	Alternating current		
ALL	All		
AM	Amplitude modulation		
AMP	Amplitude		
AMPCOR	Amplitude correction		
AUTO	Auto couple or set to automatic		
AVG	Average		
В	8-bit byte or binary format		
вотн	Both odd and even frames trigger		
BW	Black and white		
c	Cable amplitude correction factors		
CNT	Counter-lock		
COLOR	Color		
CPL	Couple		
d	Downloadable programs		
DB	Decibel (unit)		
DBM	Absolute decibel milliwatt (unit)		
DBMV	Decibel millivolt (unit)		
DBUV	Decibel microvolt (unit)		
DC	Direct current		
DELTA	Delta		
DISP	Display		
DM	Absolute decibel milliwatt (unit)		
DMY	Day, month, year format		
DN	Decreases parameter one step size		
DUMP	Dump		
e	Setup file		
EDGE	Triggers on the edge of the trigger input		
EP	Pauses program for data entry from instrument front panel		
EQ	Equal to		
EVEN	Even video frame		
EXT	External trigger		
FADC	Fast analog-to-digital converter (ADC)		
FETCH	Fetch		
FFT	Fast Fourier transform		
FIXED	Fixed		
FLAT	Flat		
FLATTOP	Flat top filter window		
FMD	Frequency modulation demodulator		

Table 4-2. Characters and Secondary Keywords (Reserved Words) (continued)

Element	Description	
FM	Frequency modulation	
FMV	Frequency modulation detection	
FREE	Free run	
FREQ or FRQ	Frequency	
g	Signal list file	
G	Gauss	
GE	Greater than or equal to	
GHZ	Gigahertz (unit)	
GT	Greater than	
GZ	Gigahertz (unit)	
HANNING	Hanning filter window	
HI	Highest	
нрів	HP-IB	
HZ	Hertz (unit)	
I	I-block data field	
i	Display image file	
INIT	Initialize	
INT	Internal or integer	
IP	Instrument preset	
IST	Inverse sweep time	
K	Free field ASCII format with no terminator	
KC	Free field ASCII format with "CR" an "LF" terminator	
KHZ	Kilohertz (unit)	
KL	Free field ASCII format with "CR" an "END" terminator	
KZ	Kilohertz (unit)	
1	Limit line file	
LAST	Last state	
LE	Less than or equal to	
LEVEL	Level gating	
LIMILINE	Limit line	
LINE	Line trigger	
LOAD15	Loads the values for the horizontal and vertical position of the instrument	
LOWER	Lower limit line	
LT	Less than	
M	Measurement units	
MA	Milliamp (unit)	
MDY	Month, day, year format	
MHZ	Megahertz (unit)	
MS		
MTR	Millisecond (unit)	
MV	Meter	
MW	Millivolts (unit)	
	Milliwatt (unit)	
MZ	Megahertz (unit)	
n	Antenna amplitude correction factors	
NE	Not equal to	
NEG	Negative	
NH	Next highest peak	
NL	Next peak left	

Table 4-2. Characters and Secondary Keywords (Reserved Words) (continued)

Element	Description		
NONE	No units		
NR	Next peak right		
NRM or NORMAL	Normal		
0	Other amplitude correction factors		
OA.	Output amplitude		
ODD	Odd video frame trigger		
OFF	Turns off function		
ON	Turns on function		
P	Parameter units		
PER	Period		
PKAVG	Peak average		
PKPIT	Peak pit		
POINT	Point		
POS	Positive		
PSN	Position		
PT	pico Tesla		
RECALL	Recall operation		
RS232	RS-232 interface		
s	State file		
SA	Signal analysis		
SAVE	Save operation		
sc	Seconds (unit)		
SLOPE	Slope		
SMP	Sample detection mode		
SP	Space		
SR	Stimulus response		
STATE	State register		
STEP	Step key ability		
STORE	Store		
SWT	Sweep time		
t	Trace file		
TG	Tracking generator		
TRA	Trace A		
TRB	Trace B		
TRC	Trace C		
UA	Microamp (unit)		
UAM	Microamps per meter		
UNCPL	Uncouple		
UNIFORM	Uniform filter window		
UP	Increases the parameter one step size		
UPLOW	Upper and lower limit lines		
UPPER	Upper limit line		
US	Microseconds (unit)		
UV	Microvolts (unit)		
UVM	Microvolts per meter		
UW	Microwatt (unit)		
<u> </u>	parentum (mm)		

Table 4-2. Characters and Secondary Keywords (Reserved Words) (continued)

Element	Description	
v	Volts (unit)	
VERTICAL	Vertical triggering	
VID	Video trigger	
w	Watts or word (for MDS command)	
YTF	YIG-tuned filter	
XTAL	Crystal	
*	Asterisk (used as a wildcard)	
j	Semicolon (ASCII code 59)	
<b>,</b>	Comma (ASCII code 44)	
0	Off (command argument)	
1	On (command argument)	
50	50Ω	
75	75Ω	
?	Returns a query response containing the value or state of the associated parameter. The query response is followed by a carriage-return/line-feed.	

The alternate commands (listed in the left column of Table 4-3) provide compatibility with commands used by the HP 8566A/B, HP 8568A/B, and HP 70000 Series instruments. The equivalent commands for the HP 8542E/HP 8546A EMI receiver or HP 85422E/HP 85462A receiver RF section are listed in the right column.

Table 4-3. Summary of Compatible Commands

Alternate Commands	Description	HP 8546A/HP 8542E Command	
A1	Clear write trace A	CLRW TRA	
A2	Max hold trace A	MXMH TRA	
A3	Store and view trace A	VIEW TRA	
A4	Store and blank trace A	BLANK TRA	
Bl	Clear write trace B	CLRW TRB	
B2	Max hold trace B	MXMH TRB	
B3	Store and view trace B	VIEW TRB	
B4	Store and blank trace B	BLANK TRB	
C1	Trace A minus trace B off	AMB OFF	
C2	Trace A minus trace B on	AMB ON	
CA	Coupled input attenuation	AT AUTO	
CR	Coupled resolution bandwidth	IFBW AUTO	
cs	Coupled step size	SS AUTO	
CT	Coupled sweep time	ST AUTO	
CV	Coupled video bandwidth	AVBW AUTO	
E1	Peak search	мкрк ні	
E2	Enter marker into center frequency	MKCF	
E3	Enter marker delta into center frequency step size	MKSS	
E4	Enter marker amplitude into reference level	MKRL	
EX	Exchange trace A and B	AXB	
KSA	dBm amplitude units	AUNITS DBM	
KSB	dBmV amplitude units	AUNITS DBMV	
KSC	$dB\mu V$ amplitude units	AUNITS DBUV	
KSD	Volt amplitude units	AUNITS V	
KSE	Screen title	TITLE	
KSG	Video average on	VAVG ON	
KSH	Video average off	VAVG OFF	
KSM	Marker noise	MKNOISE	
KSO	Marker value to span	MKSP	
KSZ	Reference level offset	ROFFSET	
KSc	Trace A plus trace B into trace A	APB	
KSi	Exchange trace B and C	BXC	
KSI	Trace B into trace C	BTC	
KSm	Graticule off	GRAT OFF	
KSn	Graticule on	GRAT ON	
KSo	Annotation off	ANNOT OFF	
KSp	Annotation on	ANNOT ON	
LO	Display line off	DL OFF	

Table 4-3. Summary of Compatible Commands (continued)

Alternate Commands	Description	HP 8546A/HP 8542E Command
M1	Marker off	MKOFF
M2	Marker normal	MKN
мз	Marker delta	MKD
MA	Marker amplitude	MKA?
MC	Marker count	MKFC
MTO	Marker track off	MKTRACK OFF
MT1	Marker track on	MKTRACK ON
01	Output format, in real number format	TDF P
02	Output format, in binary format, two bytes (word) per element	TDF B;MDS W
03	Output format, in measurement data format	TDF M
04	Output format, in binary format, 1 byte per element	TDF B;MDS B
R1	Activates illegal command service request only	RQS 32
R2	Activates end-of-sweep, illegal command	RQS 36
R3	Activates broken hardware, illegal command	RQS 40
R4	Activates units-key pressed, illegal command	RQS 34
RC	Recall state	RCLS
S1	Sweep continuous	CONTS
S2	Sweep single	SNGLS
sv	Save state	SAVES
то	Threshold off	TH OFF
Т1	Trigger mode free run	TM FREE
<b>T2</b>	Trigger mode line	TM LINE
Т3	Trigger mode external	TM EXT
<b>T4</b>	Trigger mode video	TM VID

This functional index categorizes the programming commands by the type of function that the command performs. The functional index contains the following information: the programming command mnemonic, the softkey or front-panel key that corresponds to the command's function, and a brief definition of the command. Once the desired command is found, refer to the alphabetical listing of commands later in this chapter for more information about the command.

Table 4-4. Functional Index

Function Category	Command	Corresponding Key Function	Description
AMPLITUDE	ARNG	(AUTO RANGE)	Turns the autorange function on or off.
	AT	ATTEN AUTO MAN	Specifies RF input attenuation.
	AUNITS	Amptd Units	Specifies amplitude units for input, output, and display.
	COUPLE	CDUPLE AC DC	Selects direct-current (dc) coupling or alternating-current (ac) coupling.
	INZ	INPUT Z 50Ω 75Ω	Specifies the value of input impedance expected at the active input port.
	LG	SCALE EUG LIN (when LOG is underlined)	Specifies the vertical graticule divisions as logarithmic units, without changing the reference level.
	LN	SCALE LOG LIN (when LIN is underlined)	Specifies the vertical graticule divisions as linear units, without changing the reference level.
	ML	MAX MXR LVL	Specifies the maximum signal level that is applied to the input mixer for a signal that is equal to or below the reference level.
	NRL		Sets the normalized reference level.
	OVLD	OVLD ON OFF	Enables or disables overload detection.
	PREAMP	PREAMP ON OFF	Switches the system preamplifier in and out of the input path.
	PREAMPG	EXTERNAL PREAMPG	Subtracts a positive or negative preamplifier gain value from the displayed signal.
	PP1	PRESEL PEAK	Performs a preselector peak.
	RANGE		Puts highest signal on display close to the reference level.
	RESETRL	Assenta Automata Automata Automata Concentra co	Resets the reference level to its instrument preset level.
	RL	REF LVI	Specifies the amplitude value of the reference level.
	ROFFSET	REF LVL OFFSET	Offsets all amplitude readouts without affecting the trace.
	UNRANGE		Restores reference level to the value set prior to RANGE command.
	XUNITS	Edit Antenna functions	Selects the transducer conversion units for the AMPCOR correction factors.
AUTO COUPLING	AUTO	AUTO ALL	Couples the active functions automatically.

<sup>1</sup> For an HP 8546A/HP 85462A only.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
AUXILIARY CONTROL	BYPASS <sup>1</sup>	INPUT 2 BYPASS	Switches in and out of the bypass input path.
	CALSW	VIEW CAL ON OFF	Switches the 300 MHz calibrator signal.
	CNTLA <sup>2</sup>	CNTL A 0 1	Sets the control line A of the auxiliary interface high or low.
	CNTLB <sup>2</sup>	CNTL B O 1	Sets the control line B of the auxiliary interface high or low.
	CNTLC <sup>2</sup>	CNTL C 0-1	Sets the interface control line C of the auxiliary interface high or low.
	CNTLD <sup>2</sup>	CNTL D Ø 1	Sets the interface control line D of the auxiliary interface high or low.
	CNTLI	DISPLAY CNTL I	Returns a "1" when the interface control line I of the auxiliary interface is high, and "0" if the line is low.
	DEMOD	DEMODON OFF, DEMOD AM FM	Turns the demodulator on or off, and selects between AM, FM, or quasi-peak demodulation.
	FMGAIN	FM GAIN	Sets the total FM frequency deviation for full screen demodulation.
	MEASURE		Determines the type of measurement: signal analysis, stimulus response, or signal normalization.
•	NRL		Sets the normalized reference level.
	RFIN <sup>1</sup>	(INPUT)	Specifies signal path through the RF filter section.
	RFINLK <sup>1</sup>	INPT LCK ON OFF	Enables or disables tuning limits based on RF filter section input.
	RLPOS		Selects the position of reference level.
	SPEAKER	SPEAKER ON OFF	Turns on or off the internal speaker.
	SQLCH	SQUELCH	Sets the squelch level.
	SRCALC	ALC INT EXT	Selects internal or external leveling for the tracking generator.
	SRCAT	SRC ATN MAN AUTO	Attenuates the source output level.
	SRCNORM		Subtracts trace B from trace A, adds the display line, and sends the result to trace A.
	SRCPOFS	SRC PVR OFFSET	Offsets the source power level readout.
	SRCPSTP	SRC PWR STP SIZE	Selects the source-power step size.
	SRCPSWP	PWR SWP ON OFF	Selects sweep range of the source output.
	SRCPWR	SRC PWR ON OFF	Selects the source power level.
	SRCTK	MAN TRK ADJUST	Adjusts tracking of source output with instrument sweep.
	SRCTKPK	TRACKING PEAK	Adjusts tracking of source output with instrument sweep.
	SWPCPL	SWP CPLG SR RECV	Selects a stimulus-response (SR) or receiver (RCVR) auto-coupled sweep time.

<sup>1</sup> Accessible if the HP 85460A/HP 85420E RF filter section is present.

<sup>2</sup> Not accessable if the HP 85460A/HP 85420E RF filter section is present.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
BANDWIDTH	AVBW	AVG BW AUTO MAN	Specifies the video bandwidth.
	IFBW	IF BW AUTO MAN,	Specifies the resolution bandwidth.
		200 Hz EMI BW,	
		9 kHz ENL BW,	
		120 kHz EMI BW	
	VAVG	VID AVG ON OFF	Turns on or off video averaging.
	VBR	AV/IF BW RATIO	Specifies coupling ratio of video bandwidth to resolution bandwidth.
CALIBRATION	AMPCOR	Amp Cor functions	Applies amplitude corrections at specified frequencies.
	AMPLEN		Returns the number of frequency-amplitude correction factors that have been entered.
	CAL	(CALIBRATE) functions	Initiates self-calibration routines.
	CORREK		Returns a "1" if the correction factors are on, a "0" if they are off.
COMMAND TRIGGER	WAIT		Suspends all instrument operation for the specified time duration.
CONFIGURATION	BAUDRATE	BAUD RATE	Specifies the baud rate of a instrument.
	CAT	Catalog Internal, CATALOG DISK	Returns the catalog information of either internal memory or the floppy disk.
	DATEMODE	DATEMODE MDY DMY	Allows you to set the format for displaying the real-time clock.
	DISPOSE	DISPOSE USER KEY	Frees instrument memory that was previously allocated for user-defined operands.
	FORMAT	FORMAT DOS DISK, FORMAT LIF DISK	Formats the floppy disk.
	LINCHK	(LINEARITY CHECK)	Determines whether a measured signal is undergoing compression.
	POWERON	POWER ON IP LAST	Selects the instrument's power on state.
	PREFX	Change Prefix	Specifies or changes the prefix used in save and recall operations.
	SETDATE	SET DATE	Sets the date of the real-time clock.
	SETTIME	SET TIME	Sets the time of the real-time clock.
	TIMEDATE	Time Date	Sets the time and date of the real-time clock.
	TIMEDSP	TIMEDATE ON OFF	Turns on or off the display of the real-time clock.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
DISPLAY	ANNOT	ANNOTATN ON OFF	Turns on or off the screen annotation.
	GRAT	GRAT ON OFF	Turns on or off the graticule.
	HD	HOLD	Disables data entry via the instrument numeric keypad, knob, or step keys.  The active function readout is blanked, and any active function is deactivated.
	LASTKEYMENU	LAST HRD KEY MENU	Changes the menu to the last hardkey menu that was active.
	PREFX	Change Prefix	Specifies the prefix.
	RCLC	RECALL COLORS	Recalls previously displayed colors.
	SAVEC	SAVE COLORS	Saves currently displayed colors.
	SETC	Adjust Color functions	Displays the sub-systems color editor.
	ТН	THRESHLD ON OFF	Clips signal responses below the threshold level.
	SHOWSETUP	SHOW SETUP	Shows the setup on the display.
	TITLE	Change Title	Activates the screen title mode.
	UDKDEFINE	DEFINE USER KEY	Redefines a user-defined key.
	UDKSET	DEFINE USER KEY	Changes the definition of the user-defined key.
EMI MEASUREMENTS	AUTOAVG	DETECTOR PK QP AV	Turns on and off the automatic measuring of the average detector.
	AUTOQPD	DETECTOR PK QP AV	Turns on and off the automatic measuring of the quasi-peak detector.
	MEASALLSIGS	AUTU-MEASURE	Finds all signals on or above the display, then makes an EMI measurement.
	MEASAVG		Makes a measurement with peak and average detectors.
	MEASFREQ		Makes a measurement at the specified frequency.
	MEASPEAK		Makes a measurement using the peak detector.
	MEASQPD		Makes a measurement using the quasi-peak detector.
	MEASRESULT		Sends the results of the last EMI measurement to the controller.
	MEASSIG	MEASURE AT MKR	Makes a measurement using specified detectors.
	MEASTIMEAVG	AV DWELL TIME	Sets the average detector measurement time.
	MEASTIMEPK	PK DWELL TIME	Sets the peak detector measurement time.
	MEASTIMEQPD	QP DWELL TIME	Sets the quasi-peak detector measurement time.
	MEASWITHPP		Automatically peaks the preselector before making an EMI measurement.
	REMEASSIG	Re-measure functions	Remeasures one or more signals in the signal list.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
EMI OUTPUT	RPTDEF	Define Report	Specifies which report elements are output to a printer or plotter.
	TBLDEF	Define List functions	Specifies which elements of a table are output to the printer.
FREQUENCY	CF	CENTER FREQ	Specifies center frequency.
	FA	START FREQ	Specifies the start frequency.
	FB	STOP FREQ	Specifies the stop frequency.
	FOFFSET	FREQ OFFSET	Specifies the frequency offset for all absolute frequency readouts such as center frequency.
	LOGSWEEPSPD	LOGF SPD STD FAST	Optimizes the frequency accuracy (standard) or minimizes the scan time (fast) when the LOG frequency sweep type is activated.
	SS	CF STEP AUTO MAN	Specifies center-frequency step size.
	SWEEPTYPE	SWEEP LOG LIN	Selects either logarithmic or linear frequency axis.
GRAPHICS	PRINT	COPY to a printer	Prints screen data.
	PRNTADRS	PRINTER ADDRESS	Allows you to set the HP-IB address of the printer.
	PRNTPPG	PRN/PG 1 2	Specifies number of prints per page for printing.
	PRNTRES	RESOLUTA LOW HIGH	Sets the resolution of subsequent prints.
	PRNTTYPE	Printer Type	Specifies which printer is connected to the output port.
INFORMATION	BIT		Places the state of a bit in the destination.
	BITF		Returns the state of a bit.
	CLS		Clears all status bits.
	FCALDATE		Returns the date of the last calibration performed on the system.
	FSER		Returns the serial number of the RF filter section.
	HAVE	SHOW INST CONFIG	Returns a "0" if a device or option is not installed.
	ID	SHOW INST CONFIG	Returns the instrument model number.
	MDU		Returns values for the instrument's baseline and reference level.
	PWRUPTIME		Returns the number of milliseconds that have elapsed since the instrument was turned on.
	REV	SHOW INST CONFIG	Returns the date code of the firmware revision number in YYMMDD format.
	RQS	To the large to trademont advert order and recommendate trademont to the large to t	Sets a bit mask for service requests.
	SER	SHOW INST CONFIG	Returns the serial number suffix of the instrument.
	SRQ		Used by an external controller to simulate interrupts from the instrument.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
INPUT and OUTPUT	EK		Allows data entry with the front-panel knob when the instrument is under remote control.
	EP		Sends values entered on the instrument number keyboard to the present active function value.
	OA		Returns the value of the active function
	OL		Transmits information to the controller that describes the state of the instrument when the OL command is executed.
	TA		Returns trace A amplitude values from the instrument to the controller.
	TB		Transfers trace B amplitude values from the instrument to the controller.
	TDF		Formats trace information for return to the controller.
	TRA TRB TRC		Controls trace data input or output.
LIMIT LINES	LIMIAMPSCL	AMPL SCL LOG LIN	Specifies the limit-line amplitude definition as logarithmic or linear.
***	LIMIDEL	DELETE LIMIT PURGE LIMITS 1	Deletes all segments in the current limit-line table.
	LIMIDISP	LMT DISP Y N ADTO <sup>1</sup>	Controls when the limit line (or limit lines) are displayed.
	LIMIFAIL	LMT TEST ON OFF	Returns a "0" if the last measurement sweep of trace A is equal to or within the limit-line bounds.
	LIMIFRQSCL	FREQ SCL LOG LIN	Specifies the limit-line frequency axis definition as logarithmic or linear.
	LIMIFT	LIMITS FRQ TIME.1	Selects how the limit-line segments are placed on the display: according to frequency, or according to the sweep time setting of the instrument.
	LIMIHI		Allows you to specify a fixed trace as the upper limit line.
	LIMILINE		Outputs the current limit-line table definitions.
	LIMILINESTA	LIMIT 1 ON OFF, LIMIT 2 ON OFF	Displays the selected limit line.
	LIMILO		Allows you to specify a fixed trace as the lower limit line.
	LIMIMARGAMP	MARGIN 1 ON OFF, MARGIN 2 ON OFF	Sets the amplitude in negative dB for the limit margin.
	LIMIMARGSTA	MARGIN 1 ON DFF, MARGIN 2 ON OFF	Displays the selected limit margin.
	LIMIMIRROR		Reflects the current definition about the amplitude axis at the largest frequency or the largest sweep time in the definition.

<sup>1</sup> Signal analysis mode only.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
LIMIT LINES (continued)	LIMIMODE	Edit Upper 1, Edit Lower 1, Edit Up/Low 1, Edit Mid/Delt 1	Determines whether the limit-line entries are treated as upper amplitude values, lower amplitude values, upper and lower amplitude values, or mid-amplitude and delta values.
	LIMINUM	CIMIT 1, LIMIT 2	Selects limit-line number 1 or 2 and its corresponding margin.
	LIMIREL	LIMITS FIX REL <sup>1</sup>	Specifies the current limit lines as fixed or relative.
	LIMISEG	Edit Upper, Edit Lower	Adds new segments to the current frequency limit line in either the upper limit line or the lower limit line.
	LIMISEGT	Edit Upper <sup>1</sup> , Edit Lower <sup>1</sup>	Adds new segments to the current sweep time limit line in either the upper limit line or the lower limit line.
	LIMITEST	LMT TEST ON OFF	Compares trace A with the current limit-line data.
	SEGDEL	DELETE SEGMENT	Deletes the specified segment from the limit-line tables.
	SENTER	Edit Up/Low 1, Edit Mid/Delt 1	Enters the limit-line data in either the upper and lower limit-line tables or the mid and delta table for limit lines based on frequency.
	SENTERT	Edit Up/Low 1, Edit Mid/Delt 1	Enters the limit-line data in either the upper and lower limit-line table or the mid and delta table for limit lines based on sweep time.
MARKER	FASTMRKR	MARKER SLO FAST	Increases the range of the marker functionality.
	MDS		Specifies measurement data size as byte or word.
	MF		Returns the frequency (or time) of the on-screen active marker.
	MKA	MARKER AMPTO	Specifies amplitude of the active marker.
	MKACT	SELECT 1 2 3 4	Specifies the active marker.
	MKACTV	MARKER 1 ON OFF	Makes the current active marker the active function.
	MKBW		Returns the bandwidth at the specified power level relative to an on-screen marker (if present) or the signal peak (if no on-screen marker is present).
	MKCF	MARKER -> CF	Sets the center frequency equal to the marker frequency and moves the marker to the center of the screen.
	MKCONT		Resumes the sweep after execution of a MKSTOP command.
	MKD	MARKER A	Activates the delta marker.
	MKDLMODE		Selects if the marker amplitude values are shown as relative to the reference level or relative to the display line.
	MKF		Specifies the frequency value of the active marker.

<sup>1</sup> Signal analysis mode only.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
MARKER (continued)	MKFC	MK COUNT ON OFF	Turns on or off marker frequency counter.
	MKFCR	CNT RES AUTO MAN	Sets the resolution of the marker frequency counter.
	MKMIN	MARKER -> MINIMUM	Moves active marker to minimum signal detected.
	MKN	MARKER NORMAL	Activates and moves the marker to the specified frequency.
	MKNOISE	MK NOISE ON OFF	Displays the average noise level at the marker.
	MKOFF	MARKER ALL OFF	Turns off either the active marker or all the markers.
	МКР		Places the active marker at the given x-coordinate.
	MKPAUSE	MK PAUSE ON OFF	Pauses the sweep at the active marker for the duration of the delay period.
	MKPK	(PEAK SEARCH), NEXT PEAK	Positions the active marker on a signal peak.
		NEXT PK RIGHT,	
		NEXT PK LEFT, MARKER ->PK-PK	
	МКРХ	PEAK EXCURSN	Specifies the minimum signal excursion for the instrument's internal peak-identification routine.
	MKREAD	MK READ F T I P	Selects the type of active trace information displayed by the instrument marker readout.
	MKRL	MARKER -> REF LVL	Sets the reference level to the amplitude value of the active marker.
	MKSP	MARKER A SPAN	Sets the start and stop frequencies to the values of the delta markers.
	MKSS	MARKER -> CF STEP	Sets the center-frequency step-size to the marker frequency.
	MKSTOP		Stops the sweep at the active marker.
	MKTRACE	MK TRACE AUTO ABC	Moves the active marker to a corresponding position in trace A, trace B, or trace C.
	MKTRACK	MK TRACK ON OFF	Moves the signal with an active marker to the center of the display and keeps the signal peak at center screen.
	MKTYPE		Changes the type of the current active marker.
	M4		Activates a single marker on the trace and enables the knob to change the position of the marker. The active function is then set to span.
	RCVRMRKR	MARKER TUNE SPN	Modifies the behavior of the instrument's marker functionality.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
MATH (see also Trace Math)	ABS		Places the absolute value of the source values in the destination.
	ADD		Adds the sources and sends the sum to the destination.
	AVG		Averages the source and the destination
	BIT		Returns the state of a bit.
	CTA	,	Converts the source values from measurement units to the current absolute amplitude units and stores the result in the destination.
	CTM		Converts the source values to measurement units and places the result in the destination.
	DIV		Divides source 1 by source 2 and places the result in the destination.
***	EXP		Places the exponential of the source in the destination.
	INT		Places the greatest integer that is less than or equal to the source value into the destination.
	LOG		Takes the logarithm (base 10) of the source, multiplies the result by the scaling factor, then stores it in the destination.
	MEAN		Returns the mean value of the given trace in measurement units.
	MEANTH		Returns the mean value of the given trace above the threshold, in measurement units.
	MIN		Compares source 1 and 2, point by point, and stores the lesser of the two in the destination.
	MINPOS		Returns a value, which is the x-axis position (in display units) of the minimum amplitude value in trace A, trace B, trace C, or user-defined trace.
	MOD		Stores the remainder from the division of source 1 by source 2 in the destination.
	MPY		Multiplies the sources, point by point, and places the results in the destination.
	MXM		Compares source 1 and source 2, point by point, sending the greater value of each comparison to the destination.
	PDA		Sums the probability distribution of amplitude in the destination trace with the amplitude distribution function of the source trace.
	RMS		Returns root mean square value of trace in measurement units.
	SQR		Places the square root of the source into the destination.
	SUB		Subtracts source 2 from source 1, point by point, and sends the difference to the destination.
	VARIANCE		Returns the amplitude variance of the specified trace, in measurement units.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
MEASURE/USER	FFT		Performs a discrete fast Fourier transform on the source trace array and stores the result in the destination array.
OPERATOR ENTRY	DN	₩	Reduces the active function by the applicable step size.
	EK		Enables front-panel knob control.
	EP		Enter parameter from front panel.
	HD	HOLD	Holds or disables entry and blanks active function readout.
	UP	<u></u>	Increases the active function by the applicable step size.
PLOTTER	PLOT	COPY (to a plotter)	Initiates output of the instrument display to a plotter.
PRESET	IP	(PRESET)	Performs an instrument preset.
	LF		Performs an instrument preset to the base band (band 0).
	POWERON	POWER ON IP LAST	Selects the state the instrument will be in when it is turned on: IP (instrument preset) or LAST state.
	RESETRL		Resets the reference level to instrument preset value.
PRINTER	PRINT	COPY (to a printer)	Initiates output of the display to a printer.
	PRNTADRS	PRINTER ADDRESS	Sets the HP-IB address of the printer.
	PRNTPPG	PRN/PG 1 2	Specifies number of prints per page for printing.
•	PRNTRES	RESOLUTN LOW HIGH	Sets the resolution of subsequent prints.
	PRNTTYPE	Printer Type	Specifies which printer is connected to the output port.
PROGRAM FLOW	IF		IF/THEN/ELSE/ENDIF forms a decision and branching construct.
	REPEAT		REPEAT/UNTIL forms a looping construct.
	WAIT		Suspends all instrument operation for the specified time duration.
RECALL or SAVE	CAT	Catalog Internal, CATALOG DISK	Displays directory information from either the specified or the current mass storage device.
	LOAD	LOAD FILE	Loads a file from the disk.
	MSI		Allows you to specify the current mass storage device as the internal memory or a disk.
	PREFX	Change Prefix	Specifies the prefix.
	PROTECT	PROTECT ON OFF	Prevents overwriting an existing file.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
RECALL or SAVE	PSTATE	SAV LOCK ON OFF	Protects all of the instrument user state and trace registers from being changed.
	PURGE	DELETE FILE	Deletes the specified file from the current mass storage device.
	RCLS	INTERNAL -> STATE	Recalls instrument state data from one of the nine state registers in internal memory.
	RCLT	Internal -> Trace functions	Recalls previously saved trace data, amplitude factors, or limit-line data from the trace registers in internal memory.
	SAVES	STATE -> INTRNL	Saves the currently displayed instrument state in internal memory.
	SAVET	Trace -> Intrn1 functions	Saves the selected trace data and state information, amplitude correction factors, or a save or recall operation.
	STOR	Save -> Disk functions	Stores data on a floppy disk.
SIGNAL LIST	EDITANNOT	EDIT ANNOTATN	Enters the annotation editor.
	EXITANNOT	EAST EDIT	Exits the annotation editor.
	REMEASSIG	Re-measure functions	Remeasures one or more signals in the signal list.
	SIGADD	ADD TO LIST	Adds a signal to internal signal list.
	SIGDEL	Delete Signals functions	Deletes one or more signals from the signal list.
	SIGDLTVIEW	VIEW A OFF functions	Selects which delta is viewed on the display signal list.
	SIGGRAPH	SAVE LOG GRAPH, SAVE LIN GRAPH	Draws an EMI report graph on display.
	SIGLEN		Queries current number of signals in the signal list.
	SIGLIST	SIG LIST ON OFF	Turns on or off signal list viewing and editing functions.
	SIGMARK	Signal Marking functions	Marks one or more signals on the signal list.
	SIGPOS	SELECT FRM LIST	Controls the cursor position in the signal list.
	SIGRESULT	- Farmer to an entitie of the common analysis of the common and th	Sends contents of an entry in the signal list to the controller.
Name of the state	SIGSORT	Sort Signals functions	Sorts internal signal list.
	SIGUNMARK	CLEAR MARK, CLR ALL MARKS	Unmarks one or more signals on the signal list.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
SPAN	FS	FULL SPAN	Sets the frequency span of the instrument to full span.
	HN		Returns the harmonic number of the current harmonic band in which the instrument is tuning.
	HNLOCK <sup>1</sup>	Band Lock functions	Forces the instrument to use only the selected harmonic band.
	HNUNLK <sup>1</sup>	BND LOCK ON OFF (OFF is underlined)	Unlocks the harmonic band.
	LSPAN	LAST SPAN	Changes the instrument's span to the previous span setting.
	SP	SPAN	Changes the total displayed frequency range symmetrically about the center frequency.
	SPZOOM	SPAN ZOOM	Places a marker on the highest on-screen signal (if an on-screen marker is not present), turns on the signal track function, and activates the span function.
SWEEP	CONTS	SWEEP CONT SGL (CONT is underlined)	Sets the instrument to the continuous sweep mode.
	LOGSWEEPSPD	LOGF SPD STD FAST	Optimizes the frequency accuracy (standard) or minimizes the scan time (fast) when the LOG frequency sweep type is activated.
	ST	SWP TIME AUTO MAN	Specifies the time in which the instrument sweeps the displayed frequency range.
	SWEEPTYPE	SWEEP LOG LIN	Selects either logarithmic or linear frequency axis.
SYNCHRONIZATION	DONE		Allows you to determine when the instrument has started to execute all commands prior to and including DONE.
	TS		Starts and completes one full sweep before the next command is executed.
TRACE MATH	AMB	A - B -> A ON OFF	Subtracts trace B from trace A and sends the result to trace A during every sweep of the instrument.
	AMBPL	NORMLIZE ON OFF	Subtracts trace B from trace A, adds the display line value to the difference, and sends the result to trace A during every sweep of the instrument.
	AXB	A <> B	Exchanges trace A and trace B.
	BLANK	BLANK A , BLANK B , BLANK C	Blanks trace A, trace B, or trace C and stops taking new data into the specified trace.
	BML	B - DL -> B	Subtracts display line from trace B and places the result in trace B.
	BTC	B -> C	Transfers trace B into trace C.
	BXC	B <> C	Exchanges trace B and trace C.

<sup>1</sup> For an HP 8546A/HP 85462A only.

Table 4-4. Functional Index (continued)

Function Category	Command	Corresponding Key Function	Description
TRACE MATH (continued)	CLRW	CLEAR WRITE A , CLEAR WRITE B ,	Clears the specified trace and enables trace data acquisition.
		CLEAR WRITE C	
	DET	DETECTOR SMP PX	Selects the instrument detection mode.
	IB		Provides a method for putting values into trace B.
	MERGE		Merges the source trace into the specified area of the destination trace.
	MINH	MIN HOLD C	Updates trace C elements with minimum level detected.
	MOV		Copies the source values into the destination.
	мхмн	MAX HOLD A, MAX HOLD B	Updates trace elements with maximum level detected.
	TA		Returns trace A data.
	TB		Returns trace B data.
	TRA TRB TRC	A. Arteria	Controls trace data input and output.
	TRCMEM		Returns a nonnegative integer that indicates the total number of trace registers available for SAVET and RCLT.
	TRDSP		Turns on or off the display of trace A, B, or C without clearing the trace (measurements can still be taken).
	TRPRST		Sets the trace operations to their preset values.
	TRSTAT		Returns the status of traces A, B, and C clear write, blank, view, minimum hold, or maximum hold.
	TWNDOW		Creates a window trace array for the fast Fourier transform (FFT) function.
	VAVG	VID AVG ON OFF	Enables the video-averaging function, which averages trace points to smooth the displayed trace.
	VIEW	VIEW A, VIEW B, VIEW C	Displays trace A, trace B, or trace C, and stops taking new data into the viewed trace.
	АРВ		Adds trace A to trace B and sends the result to trace A.
	CLRAVG	VID AVG ON OFF	Restarts video averaging.
	COMPRESS		Reduces the number of trace elements while retaining the relative frequency and amplitude characteristics of the trace data.
	CONCAT		Combines two traces.
	FFT		Calculates fast Fourier transform.
	LINFILL		Fills linear interpolated data into the specified trace data points of a destination trace.

Table 4-4. Functional Index (continued)


Function Category	Command	Corresponding Key Function	Description
TRACE MATH (continued)	MIRROR		Displays the mirror image of a trace.
	PEAKS		Sorts signal peaks by frequency or amplitude, stores the results in the destination trace, and returns the number of peaks found.
	SMOOTH		Smooths the trace according to the number of points specified for the running average.
	SUM		Returns the sum of the amplitudes of the trace elements in measurement units.
	SUMSQR		Returns the sum of the squares of the amplitude of each trace element.
	XCH		Exchanges traces.
TRIGGER	SNGLS	SINGLE, SWEEP CONT SGL (SGL is underlined)	Selects single-sweep mode.
	TM	FREE RUN, LINE, VIDEO, EXTERNAL	Specifies trigger mode.
	TS		Begins a new sweep.
USER-DEFINED	DISPOSE	DISPOSE USER KEY	Deletes user-defined functions.
	ERASE		Clears trace A and trace B, disposes of the contents of the user memory, and resets the state registers and the instrument to the instrument preset state.
	TRDEF		Declares a user-defined trace.
	UDKDEFINE	DEFINE USER KEY	Redefines a user-defined key.
	UDKSET	DEFINE USER KEY	Changes the definition of the user-defined key.
	VARDEF		Creates a user-defined variable and assigns it a value.
WINDOWS	WINNEXT	NEXT	Makes the window that is currently not the active window, active.
	WINOFF	WINDOWS OFF	Turns off the windows display.
	WINON	ON	Activates the windows display mode.
	WINZOOM	ZOOM	Expands the size of the active window so that it fills the entire display.
	ZMKCNTR	ZONE CENTER	Positions the zone marker at the specified frequency.
	ZMKPNL	ZONE PK LEFT	Places the zone marker at the next signal peak that is left of the zone marker's current position.
	ZMKPNR	ZONE PK RIGHT	Places the zone marker at the next peak to the right of th zone marker's current position.
	ZMKSPAN	ZONE SPAN	Allows you to change the width of the zone marker.

# **ABS**

## **Absolute**

Places the absolute value of the source values in the destination.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using user-defined trace VARDEF when using user-defined variable. TS when using trace data.

XABS

#### **ABS Absolute**

#### Example

```
10 OUTPUT 718; "IP; SNGLS;"
                                       Initializes instrument, stops sweeping.
20 OUTPUT 718; "VARDEF P_OINT,0;"
                                       Defines a variable, called P_OINT, and initializes it
                                       to 0.
30 OUTPUT 718; "ABS P_OINT, -2;"
                                       Places the absolute value of -2 into POINT.
40 OUTPUT 718;"P_OINT?;";
                                       Returns value of POINT to computer.
50 ENTER 718; Second
                                       Assigns value to computer variable, Second.
60 DISP Second
                                       Displays the absolute value (2).
70 END
```

#### **Description**


The ABS command places the absolute value of the source values in the destination.

The source and the destination may be different lengths. The lengths of predefined traces (trace A, trace B, or trace C) is 401, while user-defined traces have a length of up to 2047, and variables have a length of 1. When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

# ADD Add

Adds the sources and sends the sum to the destination.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined funn	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using user-defined trace. VARDEF when using

user-defined variable. TS when using trace data.

Related Commands: AMBPL, APB, SUB.

#### ADD Add

#### Example

Add 38 MHz to the center frequency, then store the sum in a user-defined variable.

```
10 OUTPUT 718;"IP;"
                                        Initializes instrument.
20 OUTPUT 718; "CF 300MHZ;"
                                        Changes the center frequency.
30 OUTPUT 718; "VARDEF N_EW,0;"
                                        Defines a variable, N_EW, and initializes it to 0.
40 OUTPUT 718; "ADD N_EW, CF, 38E6;"
                                        Adds 38 MHz to the center frequency, then places
                                        the sum in N_{-}EW.
50 OUTPUT 718;"N_EW?;"
                                        Returns value of N_EW to the computer.
60 ENTER 718; Freq
                                       Assigns value to variable, Freq.
70 DISP Freq
                                        Displays Freq on computer display.
80 END
```

#### Description

The ADD command adds values of source 1 and source 2 (point by point), and sends the sum to the destination.

Traces, user-defined traces, and trace ranges are added as 16-bit integers. Negative numbers are represented in two's complement format. Single variables and numbers are treated as floating point numbers and must be within the real number range as defined in Table 4-1.


The sources and destination may be different lengths. The length of predefined traces (trace A, trace B, or trace C) is 401. User-defined traces have a length of up to 2047, and variables have a length of 1. When sources differ in length, the last element of the shorter source is repeated for the addition process. After the addition, the last element is repeated if the destination is longer than the sum trace. When the sources are longer than the destination, they are truncated to fit.

#### **AMB**

#### Trace A Minus Trace B

Subtracts trace B from trace A.

#### **Syntax**



Preset State:

AMB OFF

Related Commands:

CLRW, CONTS, MXMH, SNGLS, TS, VAVG, VIEW

Equivalent Softkey:

A - B -> A ON OFF

#### Example 1

10 OUTPUT 718; "IP; AUNITS DBUV; RL 80;"

20 OUTPUT 718; "CLRW TRB; TS; VIEW TRB; AMB ON;"

Initializes instrument.

Displays trace B and turns on the AMB function. If trace A and trace B contain exactly the same trace data, the result is trace data at 0 measurement units, at the bottom of the display.

Queries the state of the AMB function. The query response is placed in a string variable.

"ON" is displayed on the computer display.

30 OUTPUT 718; "AMB?;"

40 ENTER 718; Reply\$

50 DISP Reply\$

60 END

#### **AMB Trace A Minus Trace B**

#### Example 2

10 OUTPUT 718; "IP; AUNITS DBUV; RL 80; SNGLS;" *Initializes instrument.* 20 OUTPUT 718; "MOV TRA, 8000;" Each element of trace A is set to 8000 measurement units. 30 OUTPUT 718; "VIEW TRA;" Places trace A in the view mode. Each element of trace B is set to 7000 40 OUTPUT 718; "MOV TRB, 7000;" measurement units. 50 OUTPUT 718; "VIEW TRB;" Places trace B in the view mode. 60 OUTPUT 718; "AMB ON;" Subtracts trace B from trace A. 70 OUTPUT 718; "BLANK TRB; VIEW TRA;" The result is displayed at 1000 measurement units. 80 END

#### Example 3

```
10 OUTPUT 718; "IP; SNGLS; AUNITS DBUV; RL 80DB;"
                                                       Initializes the instrument and sets
                                                       the reference level.
20 OUTPUT 718; "MOV TRA, 5000;"
                                                       Sets trace A to 5000 measurement
                                                       units, which is equal to 50 dB\muV.
30 OUTPUT 718; "VIEW TRA;"
                                                       Places trace A in the view mode.
40 OUTPUT 718; "MOV TRB, 4000; "
                                                       Sets trace B to 4000 measurement
                                                       units, which is equal to 40 \text{ } dB\mu V.
50 OUTPUT 718; "VIEW TRB;"
60 OUTPUT 718; "DL 60DB;"
                                                       Sets display line to 60 dB\mu, which is
                                                       at 6000 measurement units.
70 OUTPUT 718; "BML;"
                                                       Subtracts trace B minus display line.
                                                       Result\ is\ 4000-6000=-2000\ mea
                                                       surements units (off screen).
80 OUTPUT 718; "AMB ON;"
                                                       Subtracts trace A minus modified
                                                       trace B(5000 - (-2000) = 7000 \text{ or } 70
                                                       dBμV. Notice that this has resulted
                                                       in a subtraction of amplitude in
                                                       dB\mu V, 50 dB\mu V -(-20 \ dB\mu V) = 70
                                                       dBuV.
90 OUTPUT 718; "BLANK TRB: VIEW TRA:"
```

#### Description


100 END

The AMB command subtracts trace B from trace A (point by point), and sends the result to trace A. The AMB function remains in effect until it is turned off by executing "AMB OFF;".

The AMB command is a trace math command and subtracts trace B from trace A in measurement units (see "CTA" for information about measurement units). Because subtracting trace B from trace A can cause the result in trace A to be displayed off screen, the trace A minus trace B plus display line (AMBPL) command can be used. As shown in example 2, if the trace data value of trace A is 92 dB $\mu$ V (107 dB $\mu$ V for the receiver RF section only), (8000 measurement units), and trace B is -10 dBm (7000 measurement units), the result of executing AMB is 1000 measurement units. If the AMBPL command is used instead of AMB, and the display line is set at -50 dB $\mu$ V (mid-screen), the result in trace A is kept at mid-screen.

A common use of trace subtraction is to normalize one trace with respect to another. For example, traces are frequently subtracted to normalize the instrument response when a tracking generator is used. In such applications, amplitude units in  $dB\mu V$  should be subtracted. As shown in example 2, subtraction of measurement units is not equivalent to subtraction of amplitude units. Correct results are obtained if the display line is set to 0 dB $\mu$ V using DL, and BML is used to subtract the display line from trace B. See example 3 for an example of subtracting the display line from trace B.

#### **Query Response**




002

#### AMBPL

# Trace A Minus Trace B Plus Display Line

Subtracts trace B from trace A.

#### **Syntax**



XAMBPL

Equivalent Softkey:

NORMLIZE ON OFF

Preset State:

AMBPL OFF

Related Commands:

ADD, AMB, CONTS, CLRW, DL, MXMH, SNGLS, SUB, TS, VAVG,

**VIEW** 

#### Example

10 OUTPUT 718; "IP; AUNITS DBUV; SNGLS; RL 80DB;"

20 OUTPUT 718; "MOV TRA, 5000;"

30 OUTPUT 718; "VIEW TRA;"

40 OUTPUT 718; "MOV TRB, 4000; "

50 OUTPUT 718; "VIEW TRB;"

60 OUTPUT 718;"DL 60DM;"

70 OUTPUT 718; "AMBPL ON;"

80 OUTPUT 718; "BLANK TRB; VIEW TRA;"

90 END

Initializes instrument, activates singlesweep mode.

Sets trace A to 5000 measurement units, which is equal to 50 dB $\mu$ V.

Sets trace B to 4000 measurement units, which is equal to 40  $dB\mu V$ .


Sets display line to  $60 \text{ dB}_{\mu}\text{V}$ , which is at 6000 measurement units. Performs trace A – trace B + display line. The result is 5000 – 4000 + 6000 = 7000 or  $70 \text{ dB}_{\mu}\text{V}$ . Note that this has resulted in a subtraction of amplitude in  $\text{dB}_{\mu}\text{V}$ ,  $50 \text{ dB}_{\mu}\text{V}$  –(-20  $\text{dB}_{\mu}\text{V}$ ) =  $70 \text{ dB}_{\mu}\text{V}$ .

#### Description

The AMBPL command subtracts trace B from trace A (point by point), adds the display line value to the difference, and sends the result to trace A. The AMBPL function remains in effect until it is turned off by executing "AMBPL OFF;".

A common use of trace subtraction is to normalize one trace with respect to another. For example, traces are frequently subtracted to normalize the instrument response when a tracking generator is used. In such applications, amplitude units in  $dB_{\mu}V$  should be subtracted. To accomplish this, the display line should be set to  $0 dB\mu V$  using DL as shown in the example. To compare how you would use the AMB command to do the same operation, see examples 2 and 3 for the AMB command.

#### **Query Response**




#### **AMPCOR**

# **Amplitude Correction**

Applies amplitude corrections at specified frequencies.

#### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is	Frequency: 0 to 1000 GHz Amplitude:
	dB.	±327 dB.

Equivalent Softkeys:

the softkeys accessed by Correctn Factors

Preset State:

AMPCOR ALL OFF

Related Commands:

XUNITS, AUNITS

#### Note

ANTENNA corrections interact with the instrument's AUNITS setting. When AMCOR ANTENNA corrections are on, AUNITS are as specified by the XUNITS command. When ANTENNA corrections are off, AUNITS are the currently selected amplitude units, that is, as specified by the AUNITS command (default dBm). Refer to the XUNITS command for more information.

#### Example

Compensate for frequency-dependent amplitude inaccuracies at the input.

10	DIM A\$[200]	
20	OUTPUT 718;"CF 1GHZ;SP 200MHZ;"	Sets center frequency and span.
30	OUTPUT 718; "AMPCOR CABLE, 100MHZ, 5DB,	Stores frequency-amplitude pairs in
	1GHZ,-5DB,1.5GHZ,10DB;"	receiver. Notice that frequencies are in ascending order.
40	OUTPUT 718; "AMPCOR CABLE?;"	Returns correction values to computer.
50	ENTER 718;A\$	
60	PRINT A\$	Displays the frequency-amplitude pairs.
70	OUTPUT 718; "AMPCOR OFF;"	Turns off the amplitude correction constants.
80	OUTPUT 718; "AMPCOR CABLE?;"	
90	ENTER 718;A\$	
100	PRINT A\$	Because AMPCOR is off, "0,0" is displayed.
110	FND	

## Description

Use AMPCOR to compensate for frequency-dependent amplitude variations at the receiver input.

AMPCOR consists of three independent sets of correction data. The three data sets are: ANTENNA, CABLE, and OTHER. Each data set may be turned on or off independently and the entire AMPCOR system may be turned on or off.

Turning on any of the ANTENNA, CABLE, or OTHER data sets causes ALL currently enabled AMPCOR data to be used. Setting AMPCOR ALL OFF disables the feature. Setting AMPCOR ALL ON will restore the current mix of data. That is, sending the following commands disables all amplitude correction.

AMPCOR ANTENNA, ON;

AMPCOR CABLE, OFF;

AMPCOR OTHER, ON;

AMPCOR ALL, OFF;

Sending, AMPCOR ALL,ON; enables ANTENNA and OTHER, since these two data sets were turned on.

Up to 80 pairs of frequency-amplitude correction points can be entered in each of the three data sets, restricted to a total of 80 frequency points among the three sets.

Each set of corrections (or data set) is interpolated using either a linear frequency scale or a logarithmic frequency scale.

(SETUP) Correctn Factors


The individual amplitude correction factors can be saved or edited on disk using the softkeys in the SETUP menu under Correctn Factors or by using the STOR command.

Note
When AMPCOR ANTENNA correction factors are ON, the current XUNITS is used. When AMPCOR ANTENNA correction factors are OFF, the current AUNITS is used.

#### **AMPCOR Amplitude Correction**

## **Query Response**

 $AMPCOR\ ANTENNA?,\ AMPCOR\ CABLE?,\ and\ AMPCOR\ OTHER?$  return the frequency and amplitude correction pairs.




Returned values are 0,0 when AMPCOR is set to OFF.

#### **AMPLEN**

# **Amplitude Correction Length**

Returns the number of frequency-amplitude correction factors that have been entered.

## **Syntax**



xampleng

Related Commands:

AMPCOR

#### Example

OUTPUT 718; "AMPLEN CABLE?;"

#### **Description**


The AMPLEN command returns the number of frequency-amplitude correction factors that have been entered. The absolute value of the number that AMPLEN? returns is the number of frequency-amplitude correction factors that have been entered. If no amplitude correction factors have been entered, AMPLEN? returns a 0. (See "AMPCOR" for more information about frequency-amplitude correction factors.)

AMPLEN returns the number of frequency-amplitude correction factors

as a positive or negative number. If AMPLEN returns a positive number, the frequency-amplitude correction factors are turned on. If AMPLEN returns a negative number, the frequency-amplitude correction factors are turned off.

#### **Query Response**

AMPLEN can return a number from 80 to -80.




## ANNOT

#### Annotation

Turns on or off the display annotation.

#### **Syntax**



XANNOT

Equivalent Softkey:

ANNOTATN ON OFF

Preset State:

ANNOT ON

Related Commands:

GRAT, TITLE

#### Example

10 OUTPUT 718; "ANNOT ON;" Turns on the annotation.

20 OUTPUT 718; "ANNOT?;"

Queries state of the annotation function.

30 ENTER 718; Reply\$

Places response in a variable.

40 DISP Reply\$


Displays response on the computer screen.

50 END

### Description

The ANNOT command turns on or off all the words and numbers (annotation) on the display (except for the softkey labels).

### **Query Response**



#### **APB**

#### Trace A Plus Trace B

Adds trace A to trace B and sends the result to trace A.

#### Syntax



XAPB

Related Commands:

CLRW, SNGLS, TS, VIEW

#### Example

10 OUTPUT 718; "IP; SNGLS;" Initializes instrument, changes to singlesweep mode. 20 OUTPUT 718;"TS;" Updates the trace. 30 OUTPUT 718; "VIEW TRA; RL 80DM; CLRW TRB;" Changes the reference level. 40 OUTPUT 718; "TS; VIEW TRB;" Takes a measurement sweep. 50 OUTPUT 718; "APB;" Activates APB command. 60 OUTPUT 718; "BLANK TRB; VIEW TRA;" Displays the result of APB. 70 END

#### Description


The APB command adds trace A to trace B and sends the result to trace A. The traces are added as 16-bit integers. Negative numbers are represented in two's complement format. The two's complement representation of a negative number is obtained by changing the 1s to 0s in the binary representation of the number, and then binarily adding 1.

#### ARNG

## **Auto Range**

Enables or disables the auto-range function.

#### **Syntax**



Equivalent Key:

(AUTO RANGE)

Preset State:

ARNG OFF

Related Commands:

OVLD, AT, RL

#### Example

OUTPUT 718; "ARNG ON;"


## Description

The ARNG command allows the user to enable, disable, or query the current state of the instrument's auto-range function. When enabled, the auto-range function automatically adjusts RF attenuation or reference level (IF step-gain) in response to either an IF or RF overload condition detected during the previous sweep.

Auto range requires overload detection capability. The RF filter section must be present (and not in a bypass state) for RF overload detection. IF overload detection does not require the RF filter section.

When enabled, auto range automatically enables overload detection. When disabled, auto range does *not* disable overload detection.

#### **Query Response**




xot

#### AT

## Attenuation

Specifies the RF input attenuation.

#### **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer. Default units are dB.
 Input attenuator range of receiver.

Equivalent Softkey: ATTEN AUTO MAN

Preset State: 10 dB

Step Increment: in 10 dB steps

Related Commands: AUTO, CPL, ML, RL

#### Example

OUTPUT 718; "AT 40DB;" Sets the attenuation to 40 dB.

OUTPUT 718; "AT UP;" Increases the attenuation to 50 dB.

#### Description

The AT command specifies the input attenuation in 10 dB steps. Normally, the input attenuator is coupled to the reference level. When a continuous wave signal is displayed with its peak at or below the reference level, the coupling keeps the mixer input level at or below the specified level. The AT command allows less than the specified value at the mixer input.

When the attenuation is increased with the AT command, the reference level does not change. If the attenuation is decreased from the coupled value using the AT command, the reference level will be decreased. When the reference level is changed using the RL command, the input attenuation changes to maintain a constant signal level on the display if attenuation is auto-coupled. Using auto-couple resets the attenuation value so that a continuous wave signal

#### AT Attenuation

displayed at the reference level yields -10 dBm (or the specified mixer level) at the mixer input.


The step keys, knob, and DN parameter do not allow an attenuation entry below 10 dB. Only direct entry of "AT 0DB;" will achieve 0 dB attenuation.

**CAUTION** Signal levels above +30 dBm will damage the receiver.

The CPL and UNCPL parameters allow greater control in distribution of system input attenuation when the optional RF filter section is present in the system. At instrument preset, the input attenuator is used exclusively to control system input attenuation when the filter section is in either the 9 kHz to 50 MHz input path (INPUT 1), or the 20 MHz to 2.9 GHz input path (INPUT 2).

The UNCPL parameter "uncouples" the filter section's attenuator from system control, leaving it at its current setting. When the filter section's attenuator has been uncoupled, changes to system attenuation will not change the setting of the filter section's input attenuator. The CPL parameter re-establishes system control of the filter section's attenuator.

#### **Query Response**




#### **AUNITS**

# **Amplitude Units**

Specifies the amplitude units for input, output, and display.

#### **Syntax**



XAUNITS .

Equivalent Softkey:

Amptd Units

Related Commands:

CAL, DL, MKA, RL, TH, AMPCOR ANTENNA, XUNITS

#### Example

OUTPUT 718;"LN;"

Changes instrument to linear mode.

OUTPUT 718; "AUNITS DBMV;"

Changes the linear amplitude units to DBMV.

OUTPUT 718; "AUNITS?;"

Queries current amplitude units.

ENTER 718; Reply\$

Puts response in a variable.

DISP Reply\$

Displays response on the computer screen.

#### Description

The AUNITS command sets the amplitude readouts (reference level, marker, display line, and threshold) to the specified units. Different amplitude units can be set for log and linear amplitude scales.


#### Note

When AMPCOR antenna correction factors are ON, the current XUNITS is used. When AMPCOR antenna correction factors are OFF, the current AUNITS is

## **AUNITS Amplitude Units**

## **Query Response**

The query response returns the current amplitude units for the current amplitude scale.



QAUNITS .

#### **AUTO**

## Auto Couple

Couples the active functions automatically.

#### **Syntax**



Equivalent Softkey:

AUTO ALL

Related Commands:

AVBW, AT, DL, HD, IFBW, MKA, MKD, MKF, MKFCR, MKN, SRCPSTP, SRCPSWP, SRCPWR, SS, ST, TH, VAVG, VBR

#### Example

OUTPUT 718; "AT AUTO;" Couples the attenuation.

OUTPUT 718; "HD; AUTO; "

Couples all functions.

OUTPUT 718; "AUTO;"

Couples and deactivates a related function (if one was active), or

couples all functions (if no functions were active).

#### **Description**

The result of the AUTO command depends on the active function it acts upon. The functions that are affected by the AUTO parameter are:

AT couples attenuation to the reference level.

**AVBW** couples average video bandwidth to intermediate frequency.

DLturns off display of line but does not change the value of the display line.

**IFBW** couples intermeditate frequency bandwidth to frequency.

MKA turns off marker. turns off marker. MKD turns off marker. MKF

MKFCR deactivates use of user-supplied counter resolution value, however, the value

remains unchanged.

turns off marker. **MKN** 

SRCPSTP sets source power step to 0 (it may value may be displayed at 10 however).

SRCPSWP turns off power sweep. SRCPWR turns off source power.

SS couples step size to frequency span. ST couples sweep time to frequency span.

TH turns off display of threshold, but does not change its value or prevent usage in

peak searching.

VAVG stops averaging.

VB couples video bandwidth to resolution bandwidth.

**VBR** sets the video to bandwidth ratio to 0.3.

#### **AUTO Auto Couple**

Individual functions can be coupled by entering the keyword for the command before AUTO, for example, "AT AUTO;".


AUTO has no effect if the active function is not in the above list.

Executing "AUTO;" if no functions are active, couples all functions. Executing "HD; AUTO;" couples all functions, turns off the reference position, and turns off normalization.

# **AUTOAVG Auto Average**

Turns on and off the automatic measuring of the average detector.

#### **Syntax**



xautavg

Equivalent Softkey:

DETECTOR PK QP AV

Preset Value:

AUTOAVG ON

Related Commands:

AUTOQPD, MEASFREQ, MEASSIG, REMEASSIG, MEASALLSIGS


#### Example

OUTPUT 718; "AUTOAVG ON:"

## **Description**

The AUTOAVG command turns on and off automatic measuring of the average detector. This affects which detectors are measured using the MEAS STEPPED softkey or during the MEASFREQ, MEASSIG, REMEASSIG and MEASALLSIGS commands.

## **Query Response**




## **AUTOCAL**

## **Automatic Calibration**

Returns the status of the EMI receiver automatic calibration feature.

#### **Syntax**



xautocl

Equivalent Softkey:

AUTO CAL ON OFF

Related Commands:

CAL AUTOON, CAL AUTOOFF, CALTIME


#### Example

OUTPUT 718; "AUTOCAL;" ENTER 718; A DISP A

#### **Description**

The AUTOCAL command returns the status of the EMI receiver automatic calibration feature. A "0" is returned if an automatic calibration is disabled, a "1" is returned if auto cal is enabled.

#### **Query Response**




qgen1

# **AUTOQPD**

## **Quasi-Peak Detector**

Turns on and off the automatic measuring of the quasi-peak detector.

#### **Syntax**



xoutqpk

Equivalent Softkey:

DETECTOR PK QP AV

Preset Value:

AUTOQPD ON

Related Commands:

AUTOAVG, MEASSIG, REMEASSIG, MEASALLSIGS


#### Example

OUTPUT 718; "AUTOQPD ON:"

## Description

The AUTOQPD command turns on and off automatic measuring of the quasi-peak detector. This affects which detectors are measured during the MEASSIG, REMEASSIG, and MEASALLSIGS commands.

#### **Query Response**




#### **AVBW**

# Average Video Bandwidth

Specifies the average video bandwidth.

## **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number. Default unit is Hz.
 30 Hz to 3 MHz.

Equivalent Softkeys:

AVG BW AUTO MAN

Preset State:

300 kHz

Step Increment:

In a 1, 3, 10 sequence

Related Commands:

AUTO, IFBW, RB, SP, ST, VB, VBR

#### Example

OUTPUT 718; "AVBW 10KHZ;"


Changes the average video bandwidth to 10 kHz.

#### **Description**

The AVBW command specifies the average video bandwidth, which is a post-detection, low-pass filter. The intermediate frequency bandwidth, video bandwidth, and sweep time are normally coupled to the span. Executing AVBW uncouples the average video bandwidth from intermediate frequency bandwidth (it does nothing to the sweeptime and span coupling). Executing AUTO recouples average video bandwidth to the intermediate frequency bandwidth.

Frequency values other than the values in the 1, 3, 10 sequence are rounded to the nearest permissible value.

#### **Query Response**




# **AVG**

# Average

Averages the source and the destination.

## **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	***************************************
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable. TS when using trace data.

Related Commands:

CLRAVG, TS

# Example

10	OUTPUT	718;"IP;"	Initializes instrument.
20	OUTPUT	718; "SNGLS;"	Activates single-sweep mode.
30	OUTPUT	718;"DET POS;TS;"	Activates the positive-peak detector and updates the trace.
<b>4</b> 0	OUTPUT	718; "VIEW TRA;"	Stores results and displays trace A.
50	OUTPUT	718;"DET SMP;"	Activates sample detection.
60	OUTPUT	718; "CLRW TRB; TS; "	Activates trace B and takes a sweep of trace B.
70	OUTPUT	718;"VIEW TRB;"	Displays trace B.
80	OUTPUT	718;"AVG TRA,TRB,2;"	Averages traces B and A with ratio of 2 and stores the result in trace A.
	OUTPUT D END	718; "BLANK TRB;"	Blanks trace B and displays result in trace A.

# Description

The AVG command averages the source and the destination and then stores the result in the destination according to the following algorithm:

$$Average = \frac{((ratio - 1) \times destination) + source}{ratio}$$

The results of AVG are invalid if the ratio is equal to zero.

When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

# **AXB**

# **Exchange Trace A and Trace B**

Exchanges trace A and trace B.

# **Syntax**



XAXB

Equivalent Softkey:

A <--> B

Related Commands:

CLRW, SNGLS, TS, VIEW

# Example

10	OUTPUT	718;"IP;"	Initializes instrument.
20	OUTPUT	718;"SNGLS;"	Activates single-sweep mode.
30	OUTPUT	718;"DET POS;TS;"	Activates positive-peak detection of trace A.
40	OUTPUT	718;"VIEW TRA;"	Stores results, displays trace A.
50	OUTPUT	718;"DET SMP;"	Activates sample detection.
60	OUTPUT	718; "CLRW TRB; TS;"	Clear-writes trace B and takes sweep.
70	OUTPUT	718;"VIEW TRB;"	Stores results of sweep in trace R
80	OUTPUT	718;"AXB;"	Exchanges trace A with trace B.
90	OUTPUT	718; "BLANK TRB;"	Blanks trace B, leaving only trace A on screen.
10	O END		

# Description

The AXB command exchanges trace A and trace B, point by point. AXB sets trace A and trace B to the view mode.

# **BAUDRATE**


# **Baud Rate of Instrument**

Specifies the baud rate of an instrument with the RS-232 interface installed.

Note

The RS-232 interface is only available with Option 023.

#### **Syntax**



XBAUDRATE

Item	Description/Default	Range
Number	Any valid integer number.	4 to 57600.

Equivalent Softkey:

BAUD RATE

Require Option:

Option 023

## Example

OUTPUT 718; "BAUDRATE 1200;"


#### **BAUDRATE** Baud Rate of Instrument

#### **Description**

The BAUDRATE command changes the baud rate of the instrument to one of the standard baud rates. The standard baud rates are as follows: 300, 1200, 2400, 4800, 9600, and 19200. If you specify a baud rate other than one of the standard baud rates, the nearest standard baud rate will be used.

To communicate with the computer, the baud rates of the instrument and the computer must be the same. Because changing the baud rate of the instrument within a program ends communication with the computer, you should only use BAUDRATE when using the external keyboard to enter programming commands. To reestablish communication with the computer, you must set the baud rate back to the baud rate of the computer.


## **Query Response**



# BIT Bit

Places the state ("1" or "0") of a bit in the destination.

# **Syntax**



Item	Description/Default	Range
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	,
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number (source)	Any valid integer number.	64-bit integer.
Number (bit number)	Any valid integer number.	0 to 63.

Prerequisite Commands: VARDEF when using a user-defined variable.

Related Commands: INT, STB

#### **BIT Bit**

#### Example

10 CLEAR 718		Clears HP-IB bus.
20 OUTPUT 718;"IP;		Initializes instrument.
30 OUTPUT 718;"VAF	RDEF E_RROR,0;"	Defines user-defined variable E_RROR and sets it equal to 0.
40 OUTPUT 718;"BIT	E_RROR,STB,5;"	Stores value of bit 5 of status byte in E_RROR.
50 OUTPUT 718;"E_F	RROR?;"	Returns value of E_RROR.
60 ENTER 718;Err		Assigns value to computer variable, Err.
70 IF NOT Err THEN	DISP "NO ";	If Err equals zero, displays "NO" on computer screen.
80 DISP "ERROR PRE 90 END	SENT";	Displays "ERROR PRESENT" on computer screen.

#### **Description**

The BIT places either a "0" or a "1" in the destination. A "0" indicates the bit is off, a "1" indicates the bit is on.

Specifying the bit number: When you specify the bit number, remember the following:


- The bit number is limited from 0 to 63. If you enter a negative number for the bit number, the bit number defaults to 0. If you enter a number that is greater than 63, the bit number defaults to the remainder of the number divided by 64.
- The least significant bit is bit 0. The most significant bit is bit 63.
- Floating-point numbers are changed to a 64-bit integer before BIT is executed.

The BIT command can be used to determine information about the status byte or a memory disk inserted into the instrument's memory disk reader. (See "HAVE" for more information about determining information about the memory disk.)

# **BITF** Bit Flag

Returns the state ("1" or "0") of a bit.

# **Syntax**



XBITE .

Item	Description/Default	Range
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number (source)	Any valid integer number.	64-bit integer.
Number (bit number)	Any valid integer number.	0 to 63.

Prerequisite Commands: VARDEF when using a user-defined variable.

Related Commands:

BIT

#### **BITF Bit Flag**

#### Example

10 CLEAR 718 Clears HP-IB bus. 20 OUTPUT 718;"IP;" Initializes instrument. 30 OUTPUT 718; "BITF STB,5;" Determines the value of bit 5 of status byte. 40 ENTER 718:Err Assigns value to computer variable, Err. 50 IF NOT Err THEN DISP "NO"; If Err equals zero, displays "NO" on computer screen. 60 DISP "ERROR PRESENT": Displays "ERROR PRESENT" on computer screen. 70 END

#### **Description**

The value returned by BITF is either a "0" or a "1." A "0" indicates the bit is off, a "1" indicates the bit is on. Unlike BIT, BITF returns the state of the bit directly; the state of the bit is not stored in a destination.

Specifying the bit number: When you specify the bit number, remember the following:


- The bit number is limited from 0 to 63. If you enter a negative number for the bit number, the bit number defaults to 0. If you enter a number that is greater than 63, the bit number defaults to the remainder of the number divided by 64.
- The least significant bit is bit 0. The most significant bit is bit 63.
- Floating-point numbers are changed to a 64-bit integer before BITF is executed.

The BITF command can be used to determine information about the status byte or a memory disk inserted into the instrument's memory disk reader. (See "HAVE" for more information about determining information about the memory disk.)

# **BLANK Blank Trace**

Blanks trace A, trace B, or trace C and stops taking new data into the specified trace.

## **Syntax**



Equivalent Softkeys:

BLANK A, BLANK B, and BLANK C

Preset State:

BLANK TRB, BLANK TRC

Related Commands:

CLRW, MXMH, TRDSP, VIEW

# Example

OUTPUT 718; "BLANK TRA;"

# Description

The BLANK command blanks trace A, trace B, or trace C and stops taking new data into the specified trace.

#### **BML**

# Trace B Minus Display Line

Subtracts display line from trace B and places the result in trace B.

### **Syntax**



XBML

Equivalent Softkey:

 $B - DL \rightarrow B$ 

Related Commands:

BLANK, CLRW, SUB, TS

### Example

10 OUTPUT 718;"IP;SNGLS;"

Initializes instrument, activates single-sweep mode.

20 OUTPUT 718; "BLANK TRA;"

Blanks trace A.

30 OUTPUT 718;"CLRW TRB;TS;"

Clear-writes trace B, takes sweep.

40 OUTPUT 718;"DL 22DB;"

Sets the display line to 22  $dB\mu V$ .

50 OUTPUT 718; "BML;"

Activates BML function.

60 END

Note

For a receiver RF section standalone, set the display line to 37 dB $\mu$ V.

#### **Description**

The BML command subtracts the display line from trace B (point by point), and sends the difference to trace B.

# BTC

#### Transfer Trace B to Trace C

Transfers trace B into trace C.

#### **Syntax**



Equivalent Softkey:

B -> C

Related Commands:

BLANK, CLRW, SNGLS, TS, VIEW

### Example

10 OUTPUT 718;"IP;" Initializes instrument. 20 OUTPUT 718; "SNGLS;" Activates single-sweep mode. 30 OUTPUT 718; "BLANK TRA;" Blanks trace A. 40 OUTPUT 718; "CF 300 MHZ; SP 1MHZ;" Sets up measurement range. 50 OUTPUT 718; "CLRW TRB; TS;" Takes measurement sweep. 60 OUTPUT 718; "BTC;" Moves trace B to trace C. 70 OUTPUT 718; "BLANK TRB; VIEW TRC;" Displays result in trace C. 80 END

## Description

The BTC command moves trace B into trace C, then stops updating trace C by placing it in the view mode. Trace B is unchanged by BTC. Trace B must contain a complete sweep of measurement information.

#### **BXC**

# **Trace B Exchange Trace C**

Exchanges trace B and trace C.

#### **Syntax**



XBXC

Equivalent Softkey:

B <--> C

**Related Commands:** 

BLANK, CLRW, SNGLS, TS

#### Example

10 OUTPUT 718;"IP;BLANK TRA" Initializes instrument. 20 OUTPUT 718; "SNGLS;" Activates single-sweep mode. 30 OUTPUT 718; "DET POS; CLRW TRB; TS; " Activates positive-peak detection of trace R 40 OUTPUT 718; "VIEW TRB;" Stores results and displays trace B. 50 OUTPUT 718; "DET SMP; CLRW TRC;" Activates sample detection. 60 OUTPUT 718;"TS;" 70 OUTPUT 718; "VIEW TRC;" Stores results of sweep in trace C. 80 OUTPUT 718;"BXC;" Exchanges trace B with trace C. 90 OUTPUT 718; "BLANK TRB;" Blanks trace B leaving only trace C on screen. 100 END

#### **Description**

The BXC command exchanges the contents of traces B and C, then places both traces in the view mode.


To retain all data, trace B and trace C should contain a complete sweep of measurement data before BXC is executed.

## **BYPASS**

# **Bypass Path**

Switches in and out of the bypass input path.

#### **Syntax**



xbyposs

Equivalent Softkey:

INPUT 2 BYPASS

Related Commands:

RFIN, HAVE

### Example

OUTPUT 718; "BYPASS ON:"

#### Description


The BYPASS command switches in and out of the bypass input path for INPUT 2 of the optional RF filter section.

#### Note

An illegal command SRQ will be set if you issue the BYPASS command when:

- the optional RF filter section is not present and operational in the system, or
- the optional RF filter section input path is set to INPUT 1 (9 kHz-50 MHz). INPUT 1 cannot be put into bypass.


#### **Query Response**



# CAL Calibration

Initiates self-calibration routines.

#### Syntax



xcalib

Equivalent Key: softkeys accessed by CALIBRATE

# Example

OUTPUT 718; "CAL FREQ;" Performs the frequency correction routine.

### Description

The CAL command controls calibration functions. CAL initiates action according to the CAL parameters. The various parameters correspond to receiver softkeys as shown below.

**ALL** initiates frequency and amplitude correction routines. It corresponds to

CAL ALL for a full system calibration for the EMI receiver.

AMP initiates the amplitude correction routine and corresponds to CAL AMP. This

softkey is available for the receiver RF section only.

**AUTOON** enables the AUTOCAL function. **AUTOOFF** disables the AUTOCAL function.

**CALSW** measures the difference in amplitude between a calibrator signal attached

to the receiver RF section RFIN connector and the calibrator signal routed

through the internal switches to the RF attenuator input.

**DISP** displays some of the correction factors on the receiver display.

**DUMP** returns correction factors to the controller.

FETCH recalls the correction factors from the "working" random-access memory. The

"working" random-access memory is the section of memory that is accessed when the receiver is turned on. CAL FETCH corresponds to CAL FETCH.

FREQ initiates the frequency correction routine and corresponds to CAL FREQ. This

softkey is available for the receiver RF section only.

**INIT** sets the calibration data back to predetermined values. CAL INIT corresponds

to DEFAULT CAL DATA. Before executing CAL INIT, you must set the receiver's center frequency  $-37~\rm Hz$  to access this function. After a CAL INIT has been performed, you should perform CAL YTF (For an HP 8546A/

HP 85462A only.).

OFF turns correction factors off and corresponds to CORRECT ON OFF (OFF is

underlined). (See also "CORREK.")

ON turns correction factors on and corresponds to CORRECT ON OFF (ON is

underlined). (See also "CORREK.")

INPUT1 calibrates the receiver's conducted measurement band, 9 kHz to 50 MHz, for

amplitude flatness through each filter.

**RECEIVER** performs a full receiver cal. receiver RF section CAL FREQ and AMP. External

level loop cal and the two input cals of the RF filter section). This parameter

corresponds to CAL ALL.

**INPUT2** calibrates the receiver's radiated measurement band, 20 MHz to 2.9 GHz, for

amplitude flatness through each filter.

**STORE** moves the correction factors to an area of receiver memory that is accessed

when the receiver is powered on. STORE corresponds to CAL STORE. The CAL STORE command cannot be executed if the correction data is not valid. Correction data is valid if CORRECT ON OFF (ON is underlined) causes CORR to be displayed on the receiver display. Executing the CAL STORE command with

invalid data generates an SRQ 110.

85422 performs a calibration only on the HP 85422E receiver RF section when

configured as an HP 8542E EMI receiver.

#### **CAL Calibration**

85462	performs a calibration only on the HP 85462A receiver RF section when configured as an HP 8546A EMI receiver.
Note	Execute CAL STORE after successful completion of the self-calibration routines.
TG	performs the tracking generator calibration routines. CAL TG corresponds to CAL TRK GEN.
Note	Before executing the CAL TG command, a cable must be connected between the tracking generator output and the receiver input.
	For an HP 8546A/HP 85462A only.
YTF	initiates the correction routine for the YIG-tuned filter. The CAL YTF command corresponds to CAL YTF.

Refer to the EMI Receiver Series User's Guide for more information about the self-calibration routines, which includes the correct instrument setup for each routine.

CAL DISP and CAL DUMP do not return all of the correction factors because the number of characters that can be displayed on the receiver display is limited. CAL DUMP only returns the correction factors (as ASCII values) that would be displayed on the receiver display. Refer to the service guide for more information about displaying calibration data and reinitializing calibration data.

If the calibration data has been corrupted or is obviously inaccurate, use CAL FETCH to retrieve the calibration data that has been previously saved. If the calibration data fetched is corrupt, the following example can be used to set the calibration data back to predetermined values. Execute OUTPUT 718; "CF -37HZ; CAL INIT;", then perform the CAL AMP, CAL FREQ, or CAL ALL calibration routines. Use CAL STORE if the calibration routines have finished successfully.


Note	Using the default calibration data may cause the calibration routine to fail. If this occurs, execute "OUTPUT 718; CF -37HZ;" before performing the CAL FREQ or CAL ALL calibration routines.

The take sweep (TS) and DONE commands can be used to indicate that the correction routine has finished. Query the CORREK command to check that the calibration routines have finished successfully.

# **CALCHECK Calibration Check**

Performs a quick confidence check of the EMI receiver calibration.

#### **Syntax**



Equivalent Key:

(CAL CHECK)

#### Example


OUTPUT 718; "CALCHECK;" ENTER 718;A DISP A

# Description

The CALCHECK command performs a quick confidence check of the EMI receiver calibration and returns the result. The receiver RF section amplitude accuracy is tested at 300 MHz to assure ±0.75 dBm accuracy relative to the calibrator signal level. If a RF filter section is present the system calibration data will be checked for validity.

A "0" is returned if calibration check fails, a "1" is returned if calibration check passes.

#### Query Response




qqen1

# **CALSW**

# **Calibration Switch**

Switches the 300 MHz calibrator signal.

#### **Syntax**



xcalsw

Equivalent Softkey:

VIEW CAL ON OFF

Preset Value:

EXT

Related Commands:

RFIN, CAL


### Example

OUTPUT 718; "CALSW INT;"

# **Description**

The CALSW command switches the 300 MHz calibrator signal so that it is routed internally to the instrument's input or externally to the instrument's 300 MHz output.

# **Query Response**




qcalsw

# **CALTIME**

# **Calibration Time**

Allows you to set the time of day of an automatic calibration.

#### **Syntax**



xctime

Item	Description/Default	Range
Number	A number in the HHMMSS (24 hour) format.	Valid hour, minutes,
		and seconds.

Equivalent Softkey:

SET TIME

Related Commands:

CAL AUTOON, CAL AUTOOFF, AUTOCAL

#### Example

OUTPUT 718; "CALTIME 141000;"

Sets the autocal time to 2:10 PM.

#### Description


The CALTIME command allows you to set the time of day that an automatic calibration of the instrument or system will execute. The CALTIME command will not enable or disable the AUTOCAL function.

# CAT


# Catalog

Catalogs either internal memory or the floppy disk.


# **Syntax**



Where DOS filename is:




Where LIF filename is:



xcat2a

xeat

Where internal filename is:



Refer to Table 4-5 for a list of DOS suffixes and LIF prefixes..

Equivalent Softkeys:

Catalog Internal or CATALOG DISK

Related Commands:

MSI, STOR, LOAD

## Example

This example returns the catalog information for the instrument setups stored on the floppy disk in DOS format. Catalog information is sent as individual catalog lines that are separated by a carriage return and a line feed. A carriage return, a line feed, and a line feed with an EOI (equivalent to a carriage return, a line feed, and a line feed) is asserted after the last item.

1		,
10	DIM User\$[2000],Catalog\$(1:100)[80]	Dimensions strings to store the catalog information. User\$ stores the entire string of catalog information. Catalog\$ stores the catalog information line by line (up to 100 lines and 80 characters long).
20	INTEGER I,Pos_1f	I and Pos_If are used to search through User\$ string.
30	OUTPUT 718;"CAT *.ALL,DISK;"	The instrument sends catalog information for all the states stored on the floppy disk.
40	ENTER 718 USING "#,-K";User\$	Reads the catalog information into the User\$ string.
50	I=0	v
60 70	WHILE LEN(User\$)>1 I=I+1	Loops until the User\$ string is empty.
80	Pos_lf=POS(User\$,CHR\$(10))	Checks for line feeds. CHR\$(10) represents the line feed, the ASCII code for a line feed is "10."
90	<pre>Catalog\$(I)=User\$[1,Pos_lf-2]</pre>	Extracts catalog line.
100	OUTPUT CRT; Catalog\$(I)	Displays catalog line.
120	User\$=User\$[Pos_lf+1]	
130	END WHILE	
140	END	

#### **CAT Catalog**

### Description

The CAT command catalogs either internal memory or the floppy disk and returns the catalog information to the controller.

To use the CAT command, you must specify the type of information to be cataloged and either the internal memory or the floppy disk as the catalog source. After the instrument has sent the catalog information to the controller, the instrument sends two line feed characters to the controller.

**Specifying the type of information:** The types of information that can be cataloged depend on the source. See the following sections, "Cataloging the Floppy Disk" and "Cataloging Internal Memory" for more information.

Specifying the source: You can specify the internal memory or the floppy disk as the source by specifying INT or DOS respectively. If source (INT) is omitted, the default is the current mass storage device. See "MSI" for more information about setting the current mass storage device.

Note

When CAT is executed from a remote port, the catalog information is sent to the remote port and is not displayed on the screen.

#### Cataloging the Floppy Disk

When cataloging a floppy disk, you can specify the type of information to be cataloged, in either LIF or DOS format. Specify a prefix for LIF format or a suffix for DOS format to indicate the data type (see the following table). For example, if you execute "CAT 1\*, DISK;" all of the limit line files on a LIF formatted floppy disk will be returned, executing "CAT \*.LIM,DISK;" all of the limit line files on a DOS formatted floppy disk will be returned. The file prefix or suffix corresponding to the data types are as follows:

LIF Prefix DOS Suffix File Description STA Instrument state S t TRC Trace 1 LIM Limit lines i **BMP** Display image file g SIG Signal list n ANT Antenna correction factors  $\mathbf{c}$ CBL Cable correction factors OTH Other correction factors 0 ALL e All information

Table 4-5. LIF or DOS File Types

CAT returns the directory information only if a file has been found.

### **Cataloging Internal Memory**

When cataloging internal memory, you can use "reg" or "prefix" to specify information to be cataloged.

- prefix\* Catalogs the variables in internal memory according to the current prefix. (Use Change Prefix or PREFX to change the current prefix.)
- reg\* Catalogs the contents of the state and trace registers. The center frequency and span of the state registers are displayed; the title and date of the trace registers are displayed.
- Catalogs all the variables stored in internal memory, but does not return the contents of the state and trace registers.

Cataloging instrument (internal) memory returns the following information:

- MSI device (internal).
- Bytes of internal memory used.
- Total amount of internal memory (in bytes). This number includes the amount of internal memory in use and the amount of internal memory available.
- Name of the stored data and the number of bytes used.

#### Note


The difference between the bytes of internal memory used and the total internal memory available is the amount of internal memory available.

# CF

# **Center Frequency**

Specifies the center frequency.

## **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	Frequency range of
		the instrument.

Equivalent Softkey:

CENTER FREQ

Step Increment:

If uncoupled, step size is determined by the SS command. If coupled,

XCF

step size is 10% of span.

Related Commands:

HNLOCK, FA, FB, FOFFSET, FS, MKCF, MKSS, SP, SS

Note

Although the instrument allows entry of frequencies not in the specified frequency range, using frequencies outside the frequency span of the instrument is not recommended and is not warranted to meet specifications.


# Example

OUTPUT 718; "CF 300MHZ;" Sets the center frequency to 300 MHz.

# Description

The CF command specifies the value of the center frequency.

# **Query Response**



QQ1

# **CLRAVG**

# Clear Average

Restarts video averaging.

#### **Syntax**



XCLRAVG .

Related Commands:

AMB, CLRW, MINH, MXMH, VAVG

#### Example

OUTPUT 718;"IP;" Initializes the instrument. OUTPUT 718; "VAVG 100;" Initializes video averaging. WAIT 30 OUTPUT 718; "CLRAVG;" Restarts video averaging.

#### **Description**


The CLRAVG command restarts the VAVG command by resetting the number of averaged sweeps to one. The video averaging routine resets the number of sweeps, but does not stop video averaging. Use "VAVG OFF;" to stop video averaging.

#### **CLRW**

# Clear Write

Clears the specified trace and enables trace data acquisition.

#### **Syntax**



XCLRW

Equivalent Softkeys:

CLEAR WRITE A, CLEAR WRITE B, and CLEAR WRITE C

Preset State:

**CLRW TRA** 

Related Commands:

BLANK, DET, MINH, MXMH, VAVG, VIEW

#### Example

OUTPUT 718; "CLRW TRA;"

## **Description**

The CLRW command places the indicated trace in the clear-write mode. Data acquisition begins at the next sweep. (See "TS" for more information about data acquisition.)

# CLS

# Clear Status Byte

Clears all status bits.

## **Syntax**



XCES

Related Commands:

RQS, SRQ, STB

# Example

OUTPUT 718;"CLS;"

## Description


The CLS command clears all the status bits in the status byte. (See "SRQ" for more information on the status byte.)

### **CNTLA**

# **Auxiliary Interface Control Line A**

Sets the control line A of the auxiliary interface high or low.

#### **Syntax**



XCNTLA

Equivalent Softkey:

CNTL A O 1

Related Commands:

CNTLB, CNTLC, CNTLD, CNTLI

#### Example

OUTPUT 718; "CNTLA ON;"

Sets control line A high.

OUTPUT 718; "CNTLA?;"

Queries the state of control line A.

ENTER 718; A\$

 ${\it Gets \ the \ response \ from \ the \ instrument.}$ 

DISP A\$

Displays the response.


## Description

CNTLA ON sets control line A to high, CNTLA OFF sets it to low (the auxiliary interface connector outputs use transistor-transistor logic).

Note

This command is not accessible if the RF filter section is present.

#### **Query Response**




QQ2

# **CNTLB**

# **Auxiliary Interface Control Line B**

Sets the control line B of the auxiliary interface high or low.

#### **Syntax**



XCNTLB .

Equivalent Softkey:

CNTL B O 1

Related Commands:

CNTLA, CNTLC, CNTLD, CNTLI

#### Example

OUTPUT 718; "CNTLB ON;"

Sets control line B high.

OUTPUT 718; "CNTLB?:"

Queries the state of control line B

ENTER 718; A\$

Gets the response from the instrument.

DISP A\$

Displays the response.


#### Description

CNTLB ON sets control line B to high, CNTLB OFF sets it to low (the auxiliary connector outputs use transistor-transistor logic).

Note

This command is not accessable if the RF filter section is present.

## **Query Response**




002

#### **CNTLC**

# **Auxiliary Interface Control Line C**

Sets the interface control line C of the auxiliary interface high or low.

#### **Syntax**



XCNTLC .

Equivalent Softkey:

CNTL C 0 1

Related Commands:

CNTLA, CNTLB, CNTLD, CNTLI

## Example

OUTPUT 718; "CNTLC ON;" Sets control line C high.

OUTPUT 718; "CNTLC?;"

Queries the state of control line C.

ENTER 718; A\$

Gets the response from the instrument.

DISP A\$

Displays the response.


#### Description

CNTLC ON sets control line C to high, CNTLC OFF sets it to low (the auxiliary interface connector outputs use transistor-transistor logic).

Note

This command is not accessable if the RF filter section is present.

## **Query Response**




002

## **CNTLD**

# **Auxiliary Interface Control Line D**

Sets the interface control line D of the auxiliary interface high or low.

#### **Syntax**



XCNTLD

Equivalent Softkey:

CNTL D 0 1

Related Commands:

CNTLA, CNTLB, CNTLC, CNTLI

#### Example

OUTPUT 718; "CNTLD ON;"

Sets control line D high.

OUTPUT 718; "CNTLD?;"

Queries the state of control line D.

ENTER 718; A\$

Gets the response from the instrument.

DISP A\$

Displays the response.


## **Description**

CNTLD ON sets control line D to high, CNTLD OFF sets it to low (the auxiliary connector outputs use transistor-transistor logic).

Note

This command is not accessable if the RF filter section is present.

## **Query Response**




QQ2

## **CNTLI**

# **Auxiliary Interface Control Line Input**

Returns a "1" when the interface control line I of the auxiliary interface is high, and "0" if the line input is low.

### **Syntax**



XCNTL1 ...

Equivalent Softkey:

DISPLAY CNTL I

Related Commands:

CNTLA, CNTLB, CNTLC, CNTLD

#### Example

OUTPUT 718; "CNTLI;" Gets the status of control line I.


ENTER 718; A

DISP A

Displays status.

## Description

The CNTLI command returns a "1" when the interface control line I of the auxiliary interface is high, and "0" if the line input is low.




agen1

# **COMPRESS**

# **Compress Trace**

Reduces the number of trace elements.

#### **Syntax**



XCOMPRESS

Item Description/Default		Range
User-defined trace	A trace defined by the TRDEF command	Any valid trace name.
Trace Range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using user-defined trace. TS when using trace data.

#### Example

This example compresses trace B into "C\_OMPTRAC" using the positive (POS) algorithm.

10	OUTPUT	718;"IP;"	Initializes instrument.
20	OUTPUT	718; "TRDEF C_OMPTRAC, 100;"	Creates a trace called C_OMPTRAC with
			a length of 100 elements.
30	OUTPUT	718; "BLANK TRA; SNGLS;"	Blanks trace A, activates single-sweep
			mode.
40	OUTPUT	718; "CLRW TRB; TS;"	Measures with trace B
50	OUTPUT	718; "COMPRESS C_OMPTRAC, TRB, POS;"	Compresses trace $B$ into $C$ _OMPTRAC.
60	OUTPUT	718; "BLANK TRB;"	Blanks trace B

#### **COMPRESS Compress Trace**

70 OUTPUT 718; "MOV TRA, C\_OMPTRAC;" 80 OUTPUT 718; "VIEW TRA;"

Moves C\_OMPTRAC into trace A. Displays the result.

90 END

#### Description

The COMPPRESS command reduces the number of trace elements while retaining the relative frequency and amplitude characteristics of the trace data. It stores a compressed copy of the source trace into a smaller destination trace. The source trace is divided into the same number of intervals as there are points in the destination trace, and the data within each interval are compressed into the value for the corresponding destination trace point. The algorithm used to compress the data is given as an parameter to the command.

The algorithms available are as follows:

**AVERAGE** (AVG)

The average of the points within an interval is used.

NORMAL (NRM)

NRM computes the compressed value of the interval by using a rosenfell algorithm. The rosenfell algorithm is a mathematical operation defined in instrument firmware. The algorithm compresses a locally continuously rising or falling signal into the peak value detected in each interval. If the detected signal is not continuously rising or falling, then the data value alternates between minimum and maximum in the compressed interval. This shows the peak-to-peak noise variations. The rosenfell option is useful for accurately displaying noise, because peak detection can give misleading representation of noise.

**NEGATIVE** 

**POSITIVE** 

The lowest value in each interval is used.

(NEG)

Specifying POS selects the highest point in the interval as the compressed

(POS) value.

SAMPLE (SMP) Specifying SMP selects the last point in the interval as the compressed value.

**PEAK** AVERAGE (PKAVG)

The PKAVG algorithm selects the difference between the peak and the average

value of the interval as the compressed value.

PEAK PIT (PKPIT)

The PKPIT algorithm returns the difference between the positive and the


negative peaks within the interval.

# CONCAT

#### Concatenate

Combines two traces.

## **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that return a value. Refer to Table 4-1.	
Trace Range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable. TS when using trace data.

Related Commands: MOV, VIEW

## Example

```
10 OUTPUT 718;"IP;"
                                                            Initializes the instrument.
20 OUTPUT 718; "SNGLS;"
                                                            Activates the single-sweep mode.
30 OUTPUT 718; "TS; VIEW TRA;"
                                                            Stores and displays trace A.
40 OUTPUT 718; "CLRW TRB; TS:"
                                                             Takes a measurement sweep
                                                            with trace B.
50 OUTPUT 718; "CONCAT TRC, TRA[1,200], TRB[201,401];"
                                                            Concatenates the last half of
                                                            trace B to the first half of
                                                            trace\ A.
60 OUTPUT 718; "BLANK TRA; BLANK TRB:"
                                                            Blanks trace A and trace B.
70 OUTPUT 718; "VIEW TRC;"
                                                            Displays the result.
80 END
```

#### Description

The CONCAT command concatenates source 2 to the end of source 1, then stores the result in the destination. If the destination length is less than the length of source 1 and source 2, the list is truncated. For example, executing "CONCAT TRA[1,15], TRB[3,6], TRB[7,207];" results in trace A elements 1 to 4 being replaced by trace B elements 3 to 6, and trace A elements 5 to 15 being replaced by trace B elements 7 to 17. Trace B elements 18 to 207 are ignored. If necessary, reduce trace lengths with the COMPRESS command.


If the length of the destination is greater than the length of source 1 and source 2, the last value is repeated. For example, executing "CONCAT TRA[1,15], TRB[3,6], TRB[7,9]; " results in trace A elements 1 to 4 being equal to trace B elements 3 to 6, trace A elements 5 and 6 being replaced by trace B elements 7 and 8, and trace A elements 7 to 15 being replaced by trace B element 9.

## **CONTS**

# **Continuous Sweep**

Sets the instrument to the continuous sweep mode.

#### **Syntax**



XCONTS .

Equivalent Softkey:

SWEEP CONT SGL (when CONT is underlined)

Preset State:

CONTS

Related Commands:

SNGLS, ST, TM

## Example

OUTPUT 718; "CONTS;"

#### **Description**


The CONTS command sets the instrument to continuous sweep mode. In the continuous sweep mode, the instrument takes its next sweep as soon as possible after the current sweep (as long as the trigger conditions are met). A sweep may temporarily be interrupted by data entries made from the front panel or over the remote interface.

## CORREK

#### **Correction Factors On**

Returns status of the correction factors.

#### **Syntax**



XCORREK .

Equivalent Softkey:

CORRECTN ON OFF

Related Commands:

CAL

#### Example

OUTPUT 718; "CORREK;" ENTER 718; A DISP A


# Description

The CORREK command returns a "1" if the correction factors are on, a "0" if they are off.

Note

CORREK OFF will also disable AMPCOR amplitude correction. However, CORREK ON will not enable AMPCOR amplitude correction.

## **Query Response**




003

# **COUPLE**

# Couple

Selects direct-current (dc) coupling or alternating-current (ac) coupling.

## **Syntax**



XCOUPLE

Equivalent Softkey:

COUPLE AC DC

Preset State:

AC

Related Commands:

IΡ

#### Example

OUTPUT 718; "COUPLE DC;"

## Description

The COUPLE command selects direct-current (dc) coupling or alternating-current (ac) coupling.


#### **CAUTION**

Do not use dc coupling if there is *any* dc voltage at the instrument input. Do not exceed the power stated on the instrument input. See the specifications for the instrument in the Calibration Guide for your instrument for more information.

If there is no dc voltage at the instrument input, dc coupling is useful for observing low frequency signals at the instrument input. Use ac coupling when there is dc voltage at the instrument input (ac coupling blocks the dc voltage and allows only the ac voltage at the instrument input).

When used as a predefined variable, COUPLE returns a "0" if COUPLE has been set to DC, a "1" if COUPLE has been set to AC.

## **Query Response**




QCOUPLE .

#### CTA

#### **Convert to Absolute Units**

Converts the source values from measurement units to the current absolute amplitude units.

#### **Syntax**



Item	Description/Default	Range
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Number	Any valid integer number.	-32,768 to $+32,767$ .
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that return a value. Refer to Table 4-1.	1

Prerequisite Commands: VARDEF when using a user-defined variable

Related Commands: AUNITS, LG, LN, RL

## Example

10 OUTPUT 718; "VARDEF C\_ONLV,O;"

20 OUTPUT 718;"LG;"

30 OUTPUT 718;"RL 80DB;"

40 OUTPUT 718; "CTA C\_ONLV, 8000;"

50 OUTPUT 718; "RL 70DB;"

60 OUTPUT 718; "CTA C\_ONLV,8000;"

70 OUTPUT 718; "C\_ONLV?;"

80 ENTER 718; A

90 DISP A

100 END

Declares a variable called C\_ONLV.

Puts the instrument in log mode.

Changes the reference level.

Stores 80 in C\_ONLV.

Changes the reference level.

Stores 70 in C\_ONLV.

#### CTA Convert to Absolute Units

#### Description

The CTA command converts the source values from measurement units to the current absolute units and then stores the results in the destination.

The result of the CTA command depends on the reference level, the current amplitude units, and the amplitude scale (log or linear).


Measurement units are the internal binary data representation of measured results. The internal binary data representation is 16-bit amplitude values that are stored in traces. The values range from -32,768 to 32,767. The value of 8000 corresponds to an amplitude equal to the reference level. In log mode, each count represents 0.01 dB. A signal 0.01 dB above the reference level is at 8001, and signal 1.0 dB below the reference level is at 8000 minus 100, or 7900. In linear mode, 8000 is the reference level and 0 is the 0 volt level. If the reference level is at 80 mV, each count would represent 0.080 divided by 8000 or 10 µV, but a reference level of 2.4 volts would represent 2.4 divided by 8000 or 300  $\mu V$  per count.

#### CTM

#### Convert to Measurement Units

Converts the source values to measurement units.

#### **Syntax**



Item	Description/Default	Range
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Number	A number expressed in integer, decimal, or exponential form.	Real number range.

Prerequisite Commands: VARDEF when using a user-defined variable

Related Commands: AUNITS, CTA, LG, LN, RL

## Example

OUTPUT 718; "VARDEF A\_MPV,0;" Declares a variable called A\_MPV. OUTPUT 718;"LG;" Puts the instrument in log mode. OUTPUT 718;"RL 70DB;" Changes the reference level. OUTPUT 718; "CTM A\_MPV, 70;" Stores 8000 in A\_MPV.

#### **Description**

The CTM command converts the source values to measurement units and places the result in the destination.


The result of the CTM command depends on the reference level, the current amplitude units, and the amplitude scale (log or linear).

Measurement units are the 16-bit amplitude values stored in traces. The values range from -32,768 to 32,767. The value of 8000 corresponds to an amplitude equal to the reference level. In log mode, each count represents 0.01 dB. A signal 0.01 dB above the reference level is at 8001, and a signal 1.0 dB below the reference level is at 8000 minus 100, or 7900. In linear mode, 8000 is the reference level and 0 is the 0 volt level. If the reference level is at 80 mV, each count would represent 0.080 divided by 8000 or 10  $\mu$ V, but a reference level of 2.4 volts would represent 2.4 divided by 8000 or 300  $\mu$ V per count.

# DATEMODE Date Mode

Sets the format for displaying the real-time clock.

#### **Syntax**



XDATEMODE

Equivalent Softkey:

DATEMODE MDY DMY

#### Example 1

```
OUTPUT 718; "DATEMODE DMY;" Sets the date mode to day, month, year format.

OUTPUT 718; "DATEMODE?;" Queries the format of the display of the real-time clock.

ENTER 718; A$

DISP A$
```

#### Example 2

```
OUTPUT 718; "VARDEF T_EMP,0;"

OUTPUT 718; "DATEMODE DMY;"

Sets the date mode to day, month, year format.

OUTPUT 718; "MOV T_EMP, DATEMODE?;"

Queries the format of the display of the real-time clock as a predefined variable.

OUTPUT 718; "T_EMP?;"

Gets the result.

ENTER 718; A


DISP A
```

## Description

The DATEMODE command sets the format for displaying the real-time clock in either the month, day, year format or day, month, year format.

When used as a predefined variable, DATEMODE returns a "0" if DATEMODE has been set to MDY, a "1" if DATEMODE has been set to DMY. See example 2.

#### **Query Response**




QDATEMODE

## **DEMOD**

## **Demodulation**

Turns the demodulator on or off, and selects between AM, FM, or quasi-peak demodulation.

#### **Syntax**



XDEMOD

Equivalent Softkey:

DEMOD ON OFF

Related Commands:

DET, FMGAIN, HAVE, MKPAUSE, SP, SPEAKER, SQLCH

#### Example

This example demonstrates FM demodulation in a span greater than zero.

10 OUTPUT 718;"IP;FA 90MHZ;"

Sets start frequency.

20 OUTPUT 718; "FB 110MHZ;"

Sets stop frequency.

30 OUTPUT 718; "TS; MKPK HI; MKCF;"

Places marker on the highest peak and brings the

peak to center frequency.

40 OUTPUT 718; "DEMOD ON; DEMOD FM; "

Turns on FM demodulation.

50 OUTPUT 718:"MKPAUSE 500MS:"

Turns on marker pause. The detector switches

automatically to the FMV detector during the

dwell time.

60 END

# Description

Execute "DEMOD ON;" to turn on the demodulator. "DEMOD AM;", "DEMOD FM;", or "DEMOD QPD;" selects the demodulation mode, but does not turn on the demodulator.


For AM or FM demodulation in nonzero frequency spans, use MKPAUSE to set the dwell time of the marker.

#### DET

#### **Detection Mode**

Selects the instrument detection mode.

#### **Syntax**



Equivalent Softkey:

DETECTOR SMP PK

Preset State:

DET POS

Related Commands:

DEMOD, MEANTH, TV

#### Example

		718;"IP;"	Initializes the instrument.
		718; "SNGLS;"	Activates single-sweep mode.
		718;"DET POS;TS;"	Activates the positive-peak detection of trace A.
40	OUTPUT	718;"VIEW TRA;"	Stores results in trace A.
50	OUTPUT	718;"DET SMP;"	Activates sample detection for trace B.
60	OUTPUT	718; "CLRW TRB; TS; "	Measures with trace R
70	OUTPUT	718;"VIEW TRB;"	Stores results in trace B
80	OUTPUT	718;"AVG TRA,TRB,2;"	Averages trace A and B with a ratio of 2, and stores the results in trace A.
	OUTPUT END	718; "BLANK TRB;"	Blanks trace B, leaving only averaged results on screen.

#### **Description**


The DET command selects the type of instrument detection (positive-peak, sample, quasi-peak, or average) and accesses service-diagnostic detection functions.

- POS enables positive-peak detection, which displays the maximum video signal detected over a number of instantaneous samples for a particular frequency.
- SMP enables sample detection, which uses the instantaneous video signal value. Video averaging and noise-level markers, when activated, activate sample detection automatically.
- QPD switches the active detector to the quasi-peak detector.
- AVG switches the active detector to the average detector.

When used as a predefined variable, DET returns a number. The number that is returned corresponds to the DET parameter as shown in the following table.

DET Parameter Setting	Value DET Returns
POS	1
SMP	0
QPD	45
AVG	58

# **Query Response**




#### DISPOSE

## **Dispose**

Frees internal memory that was previously allocated for user-defined operands.

#### **Syntax**



XDISPOSE

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by the VARDEF.	Any valid variable
		name.
Number	Any valid softkey number.	1 to 6, 601 to 1200.

Equivalent Softkey:

DISPOSE USER KEY

Prerequisite Commands:

TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable.

Related Commands:

ERASE, LIMIDEL,

#### Example

OUTPUT 718; "VARDEF T\_EMP,10;"

Defines a variable for use in a program. When the

variable is no longer needed, it can be deleted using the

DISPOSE command

OUTPUT 718; "DISPOSE T\_EMP;"

Deletes T\_EMP from instrument memory.


#### Description

The DISPOSE command frees internal memory that was previously allocated for user-defined operands. Using the TRDEF, VARDEF, programming commands create a trace, variable, that remains in the instrument's memory until you delete it with the DISPOSE command, or execute the ERASE command. With the DISPOSE command, you can select which item is to be deleted. Or, if you execute DISPOSE ALL, all of the traces, variables, functions, softkeys that have created will be deleted from internal memory. Executing "DISPOSE ALL;" or the ERASE command frees all available internal memory (except the state registers and predefined traces), to make the total available user-allotted memory the maximum size.

# DIV Divide

Divides source 1 by source 2 and places the result in the destination.

## **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable. TS when using trace data.

Related Commands: MPY, SNGLS, TS

#### DIV Divide

#### Example

```
OUTPUT 718;"IP;"
                                 Initializes the instrument.
OUTPUT 718; "SNGLS;"
                                 Activates single-sweep mode.
OUTPUT 718;"TS;"
                                 Updates trace information.
OUTPUT 718; "DIV TRB, TRA, 2;"
                                 Divides trace A by two and places it in trace B.
OUTPUT 718; "VIEW TRB;"
                                 Displays the result.
```

#### Description

The DIV command divides source 1 by source 2 and places the result in the destination. Integer values are used when a trace is either the destination or one of the sources. If trace data is used both as the source and the destination, the DIV function is done with 32-bit arithmetic on 16-bit integer data. If a user-defined variable or predefined variable is used as either the source or the destination, the DIV function is done in floating-point format. If a real number is used as a source, but the destination is an integer value, the result is truncated. If a trace is used as a source, be sure the trace contains a complete sweep of measurement information before executing DIV.

When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.


The results of the DIV function are invalid if source 2 is equal to zero.

## DL

# **Display Line**

Defines the level of the display line in active amplitude units.

## **Syntax**



XDL

Item	Description/Default	Range
Number	Any real or integer number. Default units are dBm.	Dependent on the
		reference level.

Equivalent Softkey:

DSP LINE ON OFF

Preset State:

DL OFF

Step Increment:

1 major division

Related Commands:

AUNITS, AUTO, LG, LN, NRL, RL, ROFFSET, TH

# Example

OUTPUT 718;"DL ON;"

Turns on the display line.


OUTPUT 718; "DL 80DB;" Changes display line to 80  $dB\mu V$ 

## **DL** Display Line

#### Description

The DL command defines the level of the display line in active amplitude units and displays the display line on the screen. Activating video trigger mode activates the display line. The AUTO command and "DL OFF;" turn off the display line. See "AUNITS" for more information on changing the active amplitude units.


#### **Query Response**



# DN Down

Reduces the active function by the applicable step size.

#### **Syntax**



XDN

Related Commands:

See the list of active functions listed in the description for DN

#### Example

OUTPUT 718; "SS 1MHZ; CF 999 MHZ; DN;" Sets center frequency to 999 MHz.

OUTPUT 718; "SP 40MHZ; MKPK; DN;" Decreases the frequency span.

#### **Description**

The DN command reduces the active function by the applicable step size. Before executing DN, be sure that the function to be decreased is the active function. For example, the second line of the programming example decreases the span, because marker peak (MKPK) is not an active function.


The active functions are: AT, AVBW, CF, DL, FA, FB, FMGAIN, IFBW, LG, MKA, MKD, MKFCR, MKN, MKPAUSE, MKPX, ML, NRL, RB, RCLS, ROFFSET, RL, RLPOS, SAVES, SETDATE, SETTIME, SP, SQLCH, SRCALC, SRCAT, SRCPOFS, SRCPSWP, SRCPWR, SRCTK, SS, ST, TH, VB, VBR.

## DONE

#### Done

Determines when the instrument has separated the instrument commands and has started to execute all commands prior to and including DONE.

#### **Syntax**



XDONE

Related Commands:

TS

#### Example

OUTPUT 718; "IP; SNGLS; CF 1GHZ; SP 1GHZ; DONE; "

Because TS does not precede the DONE command in this line, the center frequency and span values are set before DONE returns a "1." Functions coupled to SP, such as RB, have not been changed, and there is no trace data associated with the new frequency settings.

ENTER 718; Done DISP Done

#### Example 2

OUTPUT 718; "IP; SNGLS; CF 1GHZ; SP 1GHZ; TS; DONE; "

Because the take sweep (TS) must be completed before the DONE command is executed, the autocoupled functions and trace data have been changed before the DONE command is executed.

Stores 1 in computer variable, called Done.

ENTER 718; Done

DISP Done

#### Description

The DONE command determines when the instrument has separated the instrument commands and has started to execute all commands prior to and including DONE. The instrument returns a value of "1" when all commands in a command string entered before DONE have been started.

As shown by the example, if a take sweep (TS) precedes the DONE command, DONE is executed after all the preceding commands have been completed. Use a take sweep (TS) to ensure all previous commands have completed before DONE returns a "1."


#### **Query Response**



# **EDITANNOT Edit Annotation**

Enters the annotation editor.

#### **Syntax**



xeditan

Related Softkey:

EDIT ANNOTATN

Related Commands:

**EXITANNOT** 

#### Example

OUTPUT 718; "EDITANNOT NEW;"

# Description

The EDITANNOT command enters the annotation editor (NEW or LAST) or sends the contents of the annotation buffer to a printer (LIST) or to a controller (DUMP). The NEW parameter clears the annotation editor of all text.

#### EK

## **Enable Knob**

Allows data entry with the front-panel knob when the instrument is under remote control.

#### **Syntax**



XEK

## Example

1 PRINTER IS 1	
10 OUTPUT 718;"MKN;EK;"	Activates a marker and enables the front-panel knob.
20 PRINT "USE KNOB TO PLACE MARKER"	While the program pauses, the operator positions a marker on a signal that needs further analysis.
30 PRINT "PRESS CONTINUE WHEN DONE" 40 PAUSE :	Prompts user. The operator positions a marker on a signal that needs further analysis. Insert analysis program here.
100 END	

## **Description**

The EK command allows data entry with the front-panel knob when the instrument is under remote control.

With the EK command, the knob is functional, but other front-panel functions remain inoperative. Moving the knob changes the active function. If no function is active, moving the knob has no effect.

#### EP

#### **Enter Parameter Function**

Sends values entered on the instrument number keyboard to the present active function value.

#### **Syntax**



(EP

Related Commands:

See the list of active functions listed in the description for EP

#### Example

OUTPUT 718; "ST; EP;" The sweep time can be entered by using the front-panel keys.

#### Description

The EP command allows the user to enter a value manually through the numeric keypad. When the value is terminated by a unit or ENTER key on the instrument, the instrument will be ready to execute more remote commands. EP must be invoked each time a new value is entered.

Note

Because the EP command uses the current active function, confirm that the desired function is active before executing the EP command.


The active functions are: AT, AVBW, BAUDRATE, CF, DL, FA, FB, FMGAIN, FOFFSET, IFBW, LG, MKA, MKD, MKFCR, MKN, MKPAUSE, MKPX, ML, M4, NRL, PREAMPG, PRNTADRS, RB, RCLS, ROFFSET, RL, RLPOS, SAVES, SETDATE, SETTIME, SP, SQLCH, SRCAT, SRCPOFS, SRCPSTP, SRCPSWP, SRCPWR, SRCTK, SS, ST, TH, TIMEDATE, VB, VBR.

## **ERASE**

#### **Erase**

Clears trace A and trace B.

#### **Syntax**



XERASE .

Related Commands:

DISPOSE, PSTATE

## Example

OUTPUT 718; "ERASE;"

#### **Description**

The ERASE command erases *all* of the user memory by performing a DISPOSE ALL, moving zeros into the trace elements of trace B, and performing an instrument preset (IP). If PSTATE is set to OFF, ERASE clears the state registers also.

# **EXITANNOT Exit Annotation**

Exits from the annotation editor.

## **Syntax**



xexitant

Item	Description/Default	Range
	Any integer.	0 to 5461

Equivalent Softkey:

Exit Edit

Related Commands:

EDITANNOT, MENU

## Example

OUTPUT 718; "EXITANNOT;"

## Description


The EXITANNOT command exits from the annotation editor. The parameter specifies which menu to display on the screen and make active.

# **EXP**

# **Exponent**

Places the exponential of the source in the destination.

## **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

TRDEF when using a user-defined trace. VARDEF when using a Prerequisite Commands:

user-defined variable. TS when using trace data.

Related Commands: LOG

#### **EXP** Exponent

#### Example 1

This example converts the marker amplitude to power units.

```
10 OUTPUT 718;"IP;"
                                      Initializes the instrument.
20 OUTPUT 718; "SNGLS;"
                                      Activates the single-sweep mode.
30 OUTPUT 718; "VARDEF P_MW,0;"
                                      Initializes variable P_MW to 0.
40 OUTPUT 718; "TS; MKPK HI;"
                                      Finds highest peak of sweep.
50 OUTPUT 718; "EXP P_MW, MKA, 10;"
                                      Divides the marker amplitude by 10, raises the
                                      value of the marker amplitude to the power of 10,
                                      and stores the results in P_MW.
60 OUTPUT 718; "P_MW?;"
                                      Returns the value of P_MW to computer.
70 ENTER 718; Number
                                      Assigns value to computer variable.
80 DISP Number; "mW"
                                      Displays result on the computer screen.
90 END
```

#### Example 2

This example finds the natural exponential of a number and uses the LOG command to return the original source value of the EXP function.

10 OUTPUT 718; "VARDEF E_XP,0;"	Defines a variable called E_XP.
20 OUTPUT 718;"EXP E_XP,2,2.30259;"	Finds the natural exponential of 2.
30 OUTPUT 718;"E_XP?;"	Returns the natural exponent of 2.
40 ENTER 718; Value	
50 PRINT Value	Prints the value of the exponential.
60 OUTPUT 718;"LOG E_XP,E_XP,2.30259;"	Uses the log function on the exponential value.
70 OUTPUT 718;"E_XP?;"	The log of the exponential value is approximately 2.
80 ENTER 718; Logvalue	
90 PRINT Logvalue	Prints value.
100 OUTPUT 718; "VARDEF E_XPY,0;"	Declares a variable called E_XPY.
110 OUTPUT 718; "EXP E_XPY, -5,2.30259;"	Finds the natural exponential of $-5$ .
120 OUTPUT 718; "E_XPY?;"	Returns the value of the natural exponential of $-5$ .
130 ENTER 718; Value2	•
140 PRINT Value2	Prints the value of the exponential.
150 OUTPUT 718; "LOG E_XPY,E_XPY,2.30259;"	Uses the log function on the exponential value.
160 OUTPUT 718;"E_XPY?;"	The log of the exponential value is approximately -5.
170 ENTER 718; Logval	•
180 PRINT Logval	
190 END	

#### Description

The EXP command places the exponential of the source in the destination. It first divides the source by the scaling factor, then uses the quotient as an exponent of 10:

 $10^{\rm source/scaling\ factor}$  is placed into the destination.

The EXP command can be used to evaluate a natural exponential function by using 2.30259 as the scaling factor. Because EXP and LOG are inverse functions, the EXP command has a scaling factor that may be used to "undo" the scaling factor of the LOG command. (See example 2.)

When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.


The EXP command is useful for converting log values to linear values. See "LOG" for more information on the scaling factor.

## FA

# **Start Frequency**

Specifies the start frequency.

#### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	Frequency range of
		the instrument.

Equivalent Softkey:

START FREQ

Step Increment:

Frequency span divided by 10

Related Commands:

CF, FB, FOFFSET, FS, HNLOCK, HNUNLK, MKF, SP

# Example

OUTPUT 718;"FA 88MHZ;FB 108MHZ;"

Sets the start frequency to 88 MHz, the stop frequency

XFA

to 108 MHz.

OUTPUT 718; "FA?; "

Returns the start frequency.

ENTER 718; Freq

Stores the response from the instrument.

DISP Freq

 $Displays \ the \ frequency \ on \ the \ computer \ screen.$ 


## Description

The FA command specifies the start frequency value. The start frequency is equal to the center frequency minus the span divided by two (FA = CF - SP/2).

Note

Changing the start frequency changes the center frequency and span. The start frequency may be limited by the harmonic band, if harmonic band locking is in effect, or may be limited by the input frequency range of the RF filter section.

## **Query Response**




QQ1

# FASTMRKR Fast Marker

Increases the range of the marker-positioning functionality of the knob and step keys.

#### **Syntax**



xfatmrk

Equivalent Softkey:

TUNE SLO FAST

Prerequisite Command:

RCVRMRKR

Preset Value:

FASTMRKR OFF

Related Commands:

MKN, MKD, MKACT, MKACTV, MKFC, RCVRMRKR, UP, DN, CF

## Example

10 OUTPUT 718; "FASTMRKR ON:"


#### **Description**

The FASTMRKR command increases the speed of the marker positioning and center frequency tuning functionality of the knob and step keys.

For marker positioning, there is no effect unless RCVMRKR is also on. With FASTMRKR ON, the knob changes the marker position by four times the normal rate.

For center frequency, irregardless of the RCVRMRKR setting, with FASTMRKR ON, the knob tuning is eight times the normal rate.

#### **Query Response**




QQ2

XFB

# FB **Stop Frequency**

Specifies the stop frequency.

#### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	Frequency range of
		the instrument.

Equivalent Softkey: STOP FREQ

Step Increment: Frequency span divided by 10

Related Commands: CF, FA, FOFFSET, FS, HNLOCK, MKF, SP

#### Example

OUTPUT 718; "FA 88MHZ; FB 108MHZ; " Sets the start frequency to 88 MHz, the stop frequency

to 108 MHz.

OUTPUT 718;"FB?;" Returns the stop frequency.

ENTER 718; Freq Stores the response from the instrument.

DISP Freq Displays the frequency on the computer screen.

#### **FB Stop Frequency**


## Description

The FB command specifies the stop frequency value. The stop frequency is equal to the center frequency plus the span divided by two (FA = CF + SP/2).

#### Note

Changing the stop frequency changes the center frequency and span. The stop frequency may be limited by the harmonic band, if harmonic band locking is in effect, or may be limited by the input frequency range of the RF filter section.

## **Query Response**




QQ1

## **FCALDATE**

## **Last Calibration Date**

Returns the date of the last calibration that was performed.



xfcaldt

Item	Description/Default	Range
Number	A number in YYMMDD format.	Valid year, month, and
		day.

## Example

10 DIM Serial\$[24]

20 OUTPUT 718; "FCALDATE"

30 ENTER 718; Serial\$

40 DISP Serial\$

Reserves memory space for a string.

Gets the cal date from the system.

Puts the system response into the computer vairable.

Displays the cal date on the computer screen.

#### Description

The FCALDATE command returns the date of the last service calibration that was performed on the EMI receiver.

#### **Query Response**




qfcaldt

#### FFT

#### **Fast Fourier Transform**

Performs a discrete fast Fourier transform on the source trace array.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.

Prerequisite Command:

TWNDOW

Related Commands:

MKREAD, TWNDOW

#### Example

OUTPUT 718; "IP; SNGLS;"

OUTPUT 718; "CF 300MHZ; TS; MKPK HI; MKTRACK ON; "

OUTPUT 718; "CONTS; SP 200KHZ; IFBW 100KHZ;"

OUTPUT 718; "MKTRACK OFF; SP OHZ;"

OUTPUT 718; "MKPK HI; MKRL; LN; SNGLS; "

OUTPUT 718; "ST 800MS; TS; "

OUTPUT 718; "TWNDOW TRB, FLATTOP;"

OUTPUT 718; "FFT TRA, TRA, TRB; VIEW TRA;"

OUTPUT 718; "MKPK HI;"

Initializes instrument.

Tunes center frequency to the carrier and decreases span.

Changes resolution bandwidth to cap-

ture modulation. Reduces span to zero Hz to demodu-

Reduces span to zero Hz to demodulate carrier.

Changes to linear amplitude scale. Sets sweep time to correspond to modulation frequency, the executes FFT function.

The TWNDOW must be defined before using the FFT function.

Executes the FFT function with the

trace window function. Finds the highest signal.

#### FFT Fast Fourier Transform

OUTPUT 718; "MKD;" OUTPUT 718:"MKPK NR:" OUTPUT 718; "MKREAD FFT;"

OUTPUT 718; "MKF?;"

ENTER 718; A DISP A

Activates the marker delta function. Finds the next peak to the right. Selects the FFT marker to display the marker delta value as a frequency instead of time value. Finds the difference between the two peaks.

Displays the frequency difference.

#### Description

The FFT command performs a discrete fast Fourier transform on the source trace array and stores the result in the destination array.

FFT weights the source trace with the function in the window trace (the window trace is described below). The transform is computed and the results are placed in the destination

The instrument should be in linear mode when using the FFT command. The FFT results are displayed on the instrument in logarithmic scale. For the horizontal dimension, the frequency at the left side of the graph is 0 Hz, and at the right side is Fmax.

Note

An illegal command SRQ error will be returned if this command is used when the SWEEPTYPE is set to "LOG".

Fmax can be calculated using a few simple equations and the sweep time of the instrument. The sweep time divided by the number of trace array elements containing amplitude information is equal to the sampling period. The reciprocal of the sampling period is the sampling rate. The sampling rate divided by two yields Fmax.

For example, let the sweep time of the instrument be 20 ms and the number of trace elements be 400. The sweep time (20 ms) divided by 400 equals 50  $\mu$ s, the sampling period. The sample rate is  $1/50 \mu s$ . Fmax equals  $1/50 \mu s$  divided by 2, or 10 kHz.

FFT is designed to be used in transforming zero span information into the frequency domain. Performing FFT on a frequency sweep (when the frequency span is greater than zero) will not provide time-domain results.

The windowing function stored in the window trace may be selected with the trace window (TWNDOW) command or you can store your own values in that trace. The trace window function modifies the contents of a trace array according to one of three built-in algorithms: UNIFORM, HANNING, or FLATTOP. See Figure 4-2, Figure 4-3, and Figure 4-4. The TWNDOW command multiplies a trace array with one of these windows.

Selecting a window: The amplitude and frequency uncertainty of the Fourier-transformed display depends on both the choice of trace windows and the instrument sweep time. Amplitude uncertainty is maximum when the spectral component falls midway between the filter shapes. Passbands that are flatter in shape, like the FLATTOP filter, contribute less amplitude uncertainty, but frequency resolution and sensitivity are compromised.

The UNIFORM window algorithm has the least frequency uncertainty and greatest amplitude uncertainty. The UNIFORM window does not contain time-domain weighing and leaves the data alone. Use the UNIFORM window for transforming noise signals or transients that decay within one sweep time period. The UNIFORM window yields the best frequency resolution, but also produces the highest side lobes for periodic signals.

#### FFT Fast Fourier Transform

The FLATTOP window has the greatest frequency uncertainty of the windows, but it has outstanding side lobe suppression and amplitude flatness. Use FLATTOP to transform periodic signals.

The HANNING window is a traditional passband window found in most real-time instruments. The HANNING window offers a compromise between the FLATTOP and UNIFORM windows. Use the HANNING window when transforming periodic or random data.


The values in the window trace range from -32,768 to 32,767 and are treated as fractional numbers. No offset is used. When FFT is called, the average window value is computed and used to correct the results in absolute units.

The Fourier transforms of the window functions (created with TWNDOW) are shown below. Use the graphs to estimate resolution and amplitude uncertainty of a Fourier transform display. Each horizontal division of the graphs equals 1/sweep-time or Fmax/200, and represents two trace array elements.

When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

Note

TWNDOW should always be set before FFT is executed. Execute MKREAD FFT to read the marker value as a frequency value instead of time value.



cu115e

Figure 4-2. Hanning Filter Window




Figure 4-3. Uniform Filter Window





Figure 4-4. Flat Top Filter Window

cu117e

## FMGAIN FM Gain

Sets the total FM frequency deviation for full screen demodulation.

## **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number. Default unit is Hz.
 10 kHz to 500 kHz.

Equivalent Softkey:

FM GAIN

Preset Value:

100 kHz

Related Commands:

DEMOD, SPEAKER, SQLCH

#### Example

OUTPUT 718; "FMGAIN 10KHZ;" Sets the FM gain.

## **Description**

The FMGAIN command sets the total FM frequency deviation for full screen demodulation. The center of the display (the fourth graticule) represents zero frequency deviation from the instrument center frequency. The top graticule and the bottom graticule represent a positive or negative value of FM gain frequency deviation from the instrument center frequency. The value of FMGAIN divided by four yields the FM gain per division.

#### **Query Response**



QQ1


XEMGAIN

## **FOFFSET**

## **Frequency Offset**

Specifies the frequency offset for all absolute frequency readouts such as center frequency.

## **Syntax**



XFOFFSET.

Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	

Equivalent Softkey:

FREQ OFFSET

Preset State:

0 Hz

Related Commands:

CF, FA, FB, MKN, MKF, MKSP, MKSS

#### Example

10 OUTPUT 718; "IP; FA 200MZ;"

Initializes instrument. Sets start frequency.

20 OUTPUT 718;"FB 1GZ;"

Sets stop frequency.

30 OUTPUT 718;"TS;MKPK HI;"

Places marker on signal peak.

40 OUTPUT 718; "MF;"

Finds frequency of marker.

50 ENTER 718; A

Prints frequency of marker.

60 PRINT A

Adds a frequency offset.

70 OUTPUT 718; "FOFFSET 500MZ;"

80 OUTPUT 718;"TS;MF;"

The frequency of the marker now is the frequency of

the signal peak plus the frequency offset.

90 ENTER 718; A

100 PRINT A

The displayed frequency is 500 MHz greater than the

frequency displayed in line 60.

110 END

#### **FOFFSET Frequency Offset**

## Description

The FOFFSET command selects a value that offsets the frequency scale for all absolute frequency readouts (for example, center frequency). Relative values such as span and marker delta are not offset.

After execution, the FOFFSET command displays the frequency offset in the active function readout. When an offset is in effect, it is displayed beneath the bottom graticule line on the screen.

Execute "FOFFSET 0;" or "IP;" to turn off the offset.

## **Query Response**




QQ1

xformatd

## FORMAT Format Disk

Formats the floppy disk.

#### **Syntax**



 Item
 Description/Default
 Range

 Character
 Any valid character.
 0 to 6 characters long, A through Z and the underscore (the underscore cannot be the first character of the label).

 Delimiter
 Matching characters marking the beginning and end of the list of instrument commands.
 " & " \* " \* "

Equivalent Softkey:

FORMAT DOS DISK or FORMAT LIF DISK

#### Example

OUTPUT 718; "FORMAT 'MYDISK' DOS;" Formats a floppy disk, DOS format, with the label "MYDISK."

#### Description

The FORMAT command formats the floppy disk. If the DOS/LIF specifier is not present, the disk will be formatted to its current format (DOS or LIF). If the disk is not currently DOS or LIF formatted, and neither DOS or LIF is specified, the disk will be formatted as a DOS disk.

The volume label is limited to eleven characters. If a label is not specified, the label defaults to HP 8546A (the label defaults to HP 8542E for an HP 8542E).

## FS

## Full Span

Sets the frequency span of the instrument to full span.

## **Syntax**



XFS

Equivalent Softkey:

FULL SPAN

Related Commands:

CF, FA, FB, HNLOCK, RFINLK, SP, SS

## Example

OUTPUT 718; "FS;" Puts the instrument in full-span mode.

## Description

The FS command sets the start frequency to 0 Hz and the stop frequency to 6.5 GHz (2.9 GHz for an HP 8542E/HP 85422E). Resolution bandwidth, video bandwidth, and sweep time are all set to autocoupled.

In harmonic lock, "FS;" sets both the center frequency and the span to: according to the harmonic band shown in the following table.

#### Center Frequency and Span Settings

Harmonic Band	Center Frequency	Span
0	1.45 GHz	2.9 GHz
11	4.638 GHz	3.6 GHz

1 For an HP 8546A/HP 85462A only.

Note


If the HP 85420E/HP 85460A RF filter section is present, the span resulting may be limited by the currently applicable input paths frequency range.

#### **FSER**

## RF Filter Section Serial Number

Returns the serial number of the RF filter section.

### **Syntax**



Related Commands:

ID, REV, SER

#### Example

10 DIM Serial\$[24] !Reserves memory space for a string. 20 OUTPUT 718; "FSER;" !Gets the serial number from the instrument. 30 ENTER 718; Serial\$ !Puts the instrument response in the computer variable. 40 DISP Serial\$ !Displays the serial number on the computer screen.

## **Description**

The FSER command returns the serial number suffix of the RF filter section.

### **Query Response**

The last five digits of the serial number are returned.




qq4

## **GRAT**

## Graticule

Turns on or off the graticule.

## **Syntax**



XGRAT

Equivalent Softkey:

GRAT ON OFF

Preset State:

**GRAT ON** 

Related Commands:

ANNOT

## Example

OUTPUT 718;"GRAT OFF;"

Turns off the graticule.

OUTPUT 718;"GRAT?;"

Queries graticule status.

ENTER 718;Grat\$

Gets response from the instrument.


DISP Grat\$

Displays OFF on the computer screen.

## **Description**

The GRAT command turns on or off the graticule.

## **Query Response**




QQ2

#### HAVE

#### Have

Returns status of the device.

### **Syntax**



xhave

Equivalent Softkey:

SHW INST CONFIG

#### **Example**

OUTPUT 718;"HAVE RFFS;"

Queries whether the RF filter section is installed.

ENTER 718; A

Receives response from instrument.

DISP A

Displays response.

#### **Description**

The HAVE command returns the status of devices installed. In most cases, a "1" indicates that the device is installed; a "0" if the device is not installed. For specific device conditions, refer to the listing below.

**HPIB** 

**HP-IB** interface

RS232

RS-232 interface, Option 023

Ю

Either the HP-IB interface or RS-232 interface (Option 023)

TG

Tracking generator

**FMD** 

FM demodulator

QPD

Quasi-peak detector

#### **HAVE Have**

CNT Counter-lock returns a 1 if installed but not enabled, or a 3 if installed and

enabled

OVEN Precision frequency reference

BANDS Returns a value (1 or 2) for the number of frequency bands.

NBW Narrow bandwidths

RFFS RF filter section

DISK Returns additional information about the disk drive.

"HAVE DISK;" returns additional information about the disk drive. By checking the bit status of the byte returned from "HAVE DISK;" you can determine the following:

Bit Position	Bit Status = 0	Bit Status = 1
0	Disk controller/drive not installed.	Disk controller/drive is installed.
1	Disk is write protected.	Disk is not write protected.
2	Always 0	N/A
3	Disk not inserted into disk drive.	Disk is inserted into disk drive.
4	Inserted disk is not LIF format.	Inserted disk is LIF format.
5	Inserted disk is not DOS format.	Inserted disk is DOS format.
6	Always 0	N/A
7	Always 0	N/A.

You can use the BIT or BITF command to determine the status of the bits. For example,

OUTPUT 718;"VARDEF R\_ESULT,0;"

OUTPUT 718; "BIT R\_ESULT, HAVE DISK, 3;"

OUTPUT 718;"R\_ESULT?;"

ENTER 718; A

DISP A

Stores the bit status in R\_ESULT.

Checks the status of bit 3.

Gets the result.

Displays the bit status of bit 3.

#### **Query Response**



001

## HD

## **Hold Data Entry**

Disables data entry via the instrument numeric keypad, knob, or step keys.

#### **Syntax**



HD

Equivalent Softkey:

HOLD

Related Commands:

Any active function. See the description below for a list of the

active functions.

#### Example

OUTPUT 718;"HD;"

Disables the active function and clears the active

function block area on the screen.

OUTPUT 718; "CF 600MHZ; HD; 700MHZ;"

This will leave the center frequency at 600 MHz, because HD deactivates any current function.

#### Description


The HD command disables data entry via the instrument numeric keypad, knob, or step keys. The active function readout is blanked, and any active function is deactivated. The active functions are: AT, AVBW, BAUDRATE, CF, COUPLE, DL, FA, FB, FMGAIN, FOFFSET, GL, GP, IFBW, INZ, LG, MKA, MKD, MKFC, MKFCR, MKN, MKPAUSE, MKPX, ML, NRL, PREAMPG, RB, RCLS, ROFFSET, RL, RLPOS, SAVES, SETDATE, SETTIME, SP, SQLCH, SRCAT, SRCPOFS, SRCPSTP, SRCPSWP, SRCPWR, SRCTK, SS, ST, TH, TIMEDATE, VAVG, VB, VBR, ZMKSPAN, and ZMKCNTR.

## HN

## Harmonic Number

Returns the harmonic number of the current harmonic band.

#### **Syntax**



XHN

Related Commands:

FS, HNLOCK, HNUNLK

## Example

OUTPUT 718;"HN?;"

Queries harmonic band of instrument.

ENTER 718; Number

Gets response from the instrument.

DISP Number

Displays the result on computer screen.

## **Query Response**

The HN command returns the harmonic number of the current harmonic band in which the instrument is tuning. A -1 is returned if the instrument is sweeping multiband.



QQ 1


#### HNLOCK

## **Harmonic Number Lock**

For an HP 8546A/HP 85462A only.

Forces the instrument to use only the selected harmonic band.

#### **Syntax**



XHNLOCK

Item	Description/Default	Range
Number		0 to 1

Equivalent Softkey:

the softkeys accessed by Band Lock

Preset State:

HNLOCK OFF

Related Commands:

CF, FA, FB, FOFFSET, HN, HNUNLK, SNGLS, SP

#### Example

INPUT "SELECT THE DESIRED FREQUENCY BAND", Harm Gets harmonic band from user.

OUTPUT 718; "HNLOCK "; Harm; "; "

Locks harmonic band.

## **Description**

The HNLOCK command forces the instrument to use only the selected harmonic band. HNLOCK ON locks onto the harmonic band that is appropriate for the current center frequency, lowering the span, if necessary, due to the limits of the harmonic band.

HNLOCK <number>, where <number> is an integer, locks onto harmonic band <number> and automatically selects the settings shown in the following table.

Remote Commands	Equivalent Softkey	Frequency Settings	
HNLOCK 0	BAND 0	Center frequency 1.450 GHz	Span 2.900 GHz
HNLOCK 1	BAND 1	Center frequency 4.638 GHz	Span 3.600 GHz

Once HNLOCK is set, only frequencies and spans that fall within the frequency band of the current harmonic may be entered. The span is reduced automatically to accommodate a center frequency specified near the end of the band range.

N	Δ1	۴	Δ
14	U	ı,	c

Before changing the frequency range to another harmonic, unlock the band with the harmonic unlock command, "HNLOCK OFF;" or "HNUNLK;".

### BAND LOCK ON (HNLOCK ON)

#### Start Frequency

If a start frequency is entered that is outside of the current band boundaries, it will be set to the nearest band edge instead. If a start frequency that is greater than the current stop frequency is entered, the (possibly modified) start frequency is used for both the start and the stop frequency; therefore, the span will be set to zero. If the start and stop frequencies specify too large a span, they will be modified. (Also see "FA.")

#### Stop Frequency

If a stop frequency is entered that is outside of the current band boundaries, it will be set to the nearest band edge instead. If a stop frequency that is less than the current start frequency is entered, the (possibly modified) stop frequency will be used for both the start and stop frequency; therefore, the span will be set to zero. (Also see "FB.")

#### Center Frequency

The span will be modified if necessary to get the center frequency specified without crossing the band edges. (Also see "CF.")


#### Span

The span will be limited as necessary to keep the start and stop frequencies within the band edges without changing the center frequency. The maximum span allowed is 2.943 GHz in band 0, 3.600 GHz in band 1. (Also see "SP.")

## BAND LOCK OFF (HNLOCK OFF)

The start and stop frequencies are bounded by the range of the instrument, and limits the RF filter section inputs.

#### **Query Response**



QQ2

# HNUNLK

## **Unlock Harmonic Number**

For an HP 8546A/HP 85462A only.

Unlocks the harmonic band.

## **Syntax**

HNUNLK

XHNUNLK

Equivalent Softkey:

BND LOCK ON OFF

Preset State:

HNUNLK OFF

Related Commands:

CF, FA, FB, FOFFSET, FS, HN, HNLOCK, SP

## Example

OUTPUT 718; "HNUNLK;"

## Description


The HNUNLK command allows you to select frequencies and spans outside the range of a single harmonic band.

## $\mathbf{IB}$

## Input B

Provides a method for putting values into trace B.

#### **Syntax**



Item	Description/Default	Range
Data byte	8-bit byte containing numeric or character data.	

## Example

10 ASSIGN @Sa TO 718; FORMAT ON	
20 ASSIGN @Sa_bin TO 718; FORMAT OFF	
30 INTEGER Binary(1:401)	Dimensions an array called "Binary."
40 OUTPUT @Sa;"CF 300MZ;CLRW TRB;BLANK TRA;SP	Takes a measurement sweep.
10MZ;SNGLS;TS;"	
50 OUTPUT @Sa;"TDF B;MDS W;TB;"	Outputs trace $B(in\ binary)$ to computer.
60 ENTER @Sa_bin;Binary(*)	Stores trace data in array.
70 OUTPUT @Sa;"CF 100MZ; IFBW 30KZ; SP 1MZ; TS;"	Changes the instrument settings.
80 DISP "PRESS CONTINUE WHEN READY"	
90 PAUSE	

110 OUTPUT @Sa\_bin;Binary(\*)
120 OUTPUT 718;"VIEW TRB;"
130 END

100 OUTPUT @Sa;"IB";

Prepares instrument to receive trace B data stored in array.
Sends trace B data to instrument.

## Description


The IB command sends trace B data as binary data only; IB is independent of the measurement data size (MDS) command. The IB command expects 802 data bytes (401 data points, two bytes each). The data values can represent the range of the integer numbers.

## $\mathbf{ID}$

# **Identify**

Returns the instrument model number.

## **Syntax**



Equivalent Softkey:

SHW INST CONFIG

Related Commands:

REV, SER

## Example

10 ALLOCATE A\$[50]

Allocates string to hold model number.

20 OUTPUT 718;"ID;"

Gets model number.

30 ENTER 718;A\$

Transfers number to computer.

40 DISP A\$

Displays model number.

50 END

## Description

The ID command returns the instrument model number to the controller; for example, HP 8546A or HP 8542E is returned for an EMI receiver, HP 85462A or HP 85422E for a receiver RF section.

## **Query Response**




## **IFBW**

## Intermediate Frequency Bandwidth

Specifies the intermediate frequency bandwidth.

## **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	30 Hz to 3 MHz

Equivalent Softkeys:

IF BW AUTO MAN

Preset State:

120 kHz

Step Increment:

1, 3, 10

Related Commands:

AUTO, AVBW, SP, ST, VB, VBR, RB

## Example

OUTPUT 718; "IFBW 1KHZ;" Sets the intermediate frequency bandwidth to 1 kHz.


### Description

The IFBW command disables the coupling between sweep time and intermediate frequency bandwidth. Execute IFBW AUTO to reestablish coupling. (Also see "AUTO.")

The 200 Hz, 9 kHz, and 120 kHz 6-dB intermediate frequency bandwidths (used for EMI testing) are available by specifying 200 Hz, 9 kHz, or 120 kHz as the frequency value; the front-panel knob, step increment keys, and auto-coupled settings provide the 1, 3, 10 intermediate frequency bandwidth sequence only. Frequencies are rounded to the nearest value in the 1, 3, 10 sequence if the frequency is other than 200 Hz 9 kHz, 120 kHz, 5 MHz, or in the 1, 3, 10 sequence.

The instrument provides uncalibrated bandwidths of 10 Hz and 5 MHz.

#### **Query Response**




## INT

## Integer

Places the greatest integer that is less than or equal to the source value into the destination.

## **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Command:

TRDEF when using a user-defined trace. VARDEF when using a

XINT

user-defined variable. TS when using trace data.

Related Commands:

REPEAT/UNTIL

## Example

OUTPUT 718; "INT RL, 93.75;" Resets the reference level using the integer value of 93.

## Description

The INT command places the greatest integer that is less than or equal to the source value into the destination. When the number of items in the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

When the instrument is sweeping across more than one band, taking the integer value of the sweep time (ST) may yield a real number.


#### INZ

## Input Impedance

For the HP 85422E/HP 85462A only.

Specifies the value of input impedance expected at the active input port.

#### **Syntax**



XINZ

Equivalent Softkey:

INPUT Z 50 $\Omega$  75 $\Omega$ 

Preset Value:

Returns impedance to the power-on value.

Related Commands:

**AUNITS** 

## Example


OUTPUT 718; "INZ 75;" Changes input impedance to 75 ohms.
OUTPUT 718; "AUNITS V;" Changes amplitude units to volts.

### Description

The INZ command specifies the value of input impedance expected at the active input port. The actual impedance can be affected only by internal hardware. The instrument hardware supports  $50\Omega$  only. The INZ command is used for computation purposes during power or voltage conversions.

The INZ command affects only the amplitude results that are reported in absolute relative power (dBm units or watts). (See "AUNITS.")

## **Query Response**



OINZ

#### IP

#### **Instrument Preset**

Performs an instrument preset.

### **Syntax**



(IP

Equivalent Key:

(PRESET)

#### Example

OUTPUT 718;"IP;"

## Description

The instrument preset command, IP, executes the following commands:

AMB:

Turns off A - B mode.

AMBPL:

Turns off A - B plus display line mode.

AMPCOR:

Turns off amplitude correction factors.

ANNOT:

Turns on annotation.

AT:

Sets attenuation to 10 dB.

**AUNITS:** 

Loads the amplitude units from a configuration location in internal

memory.

AUTO:

Couples AVBW, IFBW, RB, AT, SS, ST, and VB. Turns off display line and

threshold.

AUTOAVG:

Turns on automatic measuring of the average detector.

AUTOQPD:

Turns on automatic measuring of the quasi-peak detector.

AVBW:

Sets the video bandwidth to 300 kHz.

C:

BLANK B,BLANK Blanks trace B and trace C.

CLRW A:

Clears and writes trace A.

CONTS:

Selects continuous sweep mode.

COUPLE:

Selects ac coupling.

DET:

Selects positive peak detection.

DL:

Turns off the display line. Sets FM gain to 100 kHz.

FMGAIN:

Sets the frequency offset to 0 Hz.

FOFFSET:

Turns on the graticule.

HD:

GRAT:

Hold (deactivates active function).

#### **IP Instrument Preset**

HNLOCK OFF: Unlocks harmonic band, allowing multiband sweeping.

IFBW: Sets the resolution bandwidth to 125 kHz.

INZ: Loaded from a configurable location in instrument memory.

LG: Selects 10 dB per division log scale.

LIMIDISP: Sets LIMIDISP to AUTO.

LIMIHI or LIMILO: Clears any limit-line trace specified by LIMIHI or LIMILO.

LIMITEST: Turns off limit-line testing.

MDS: Selects data size of one word, which is two 8-bit bytes.

MEASURE: Sets measurement to signal analysis.

MEASTIMEAVG: Sets the average detector measurement time.

MEASTIMEQPD: Sets the quasi-peak detector measurement time.

MEASTIMEPK: Sets the peak detector measurement time.

MEASWITHPP: Turns on the preselector.

MKFCR: Marker counter resolution is set to AUTO, but a calculated value other than

0 may be returned if the marker counter resolution is queried.

MKNOISE: Turns off noise markers.

MKOFF: Turns off all markers.

MKPAUSE: Turns off marker pause mode.

MKPX: Minimum excursion for peak identification is set to 6 dB.

MKREAD: Sets marker readouts to frequency.

MKTRACK: Turns off marker tracking.

MKTYPE: Sets the marker type as position type.

ML: Sets mixer level to -10 dBm.

MSI: Selects the disk drive as the mass storage device.

QPOFFSET: Sets the QPOFFSET to 20.

RL: Sets reference level to 92 dB $\mu$ V.

RLPOS: Sets the reference level position to 8.

ROFFSET: Sets reference offset to 0.

RQS 41: Allows SRQ 110, SRQ 140 for illegal commands, broken hardware, or

overload detection.

SPEAKER: Turns on the speaker.

SQLCH: Sets the squelch level to 0.

SRCALC: Sets the source leveling control to internal.

SRCPSWP: Sets the source power sweep to off.

SRCPWR: Sets the source power level to 97 dB $\mu$ V.

SS: Sets the center frequency step size to 100 MHz.

STATUS BYTE: Clear the status byte.

#### **IP Instrument Preset**

TDF: Selects parameter units output format.

One division above bottom graticule line, threshold line off. TH:

TITLE: Clears the title from the screen. TM: Selects free run trigger mode.

TRC: Sets the trace values to 8000.

VAVG: Turns off video averaging and sets the video averaging limit to 100.

VBR: Sets VBR to 0.300.

IP also clears all user graphics, and turns off the windows display mode.

Instrument preset automatically occurs when you turn on the instrument. IP is a good starting point for many measurement processes. When IP is executed remotely, the instrument does not necessarily execute a complete sweep, however. You should execute a take sweep (TS) to ensure that the trace data is valid after an IP.

# **LASTKEYMENU** Last Key Menu

Changes the menu to the last hardkey menu that was active.

## **Syntax**



xlostkm

Equivalent Softkey:

LAST HRD KEY MENU

## Example

OUTPUT 718; "LASTKEYMENU:"

## Description

The LASTKEYMENU command changes the menu to the last hardkey menu that was active. This command provides quick access between two separate hardkey menus.

## LF

## **Base Band Instrument Preset**

Performs an instrument preset.

#### **Syntax**



XLF

Related Commands:

IP

#### Example

OUTPUT 718; "LF;"

## Description

EMI Receiver Mode

The LF command is the same as the IP command. Refer to the IP command for a complete description of its functions.

Signal Analysis Mode


The LF command performs an instrument preset (IP) into base band (band 0). Use LF instead of IP if harmonic band 0 is desired.

## LG

## Logarithmic Scale

Specifies the vertical graticule divisions as logarithmic units, without changing the reference level.

### **Syntax**



Item	Description/Default Range	
Number	Any real or integer number. Default units are dB.	0.1 to 20 dB.

Equivalent Softkey:

SCALE LOG LIN

Preset State:

10 dB

**Related Commands:** 

LN

#### Example


OUTPUT 718;"LG 1DB;"

#### Description

The LG command specifies the vertical graticule divisions as logarithmic units, without changing the reference level. The vertical scale can be specified (in tenths) from 0.1 to 0.9 dB, or in integers from 1 to 20 dB per graticule division.

If LG is used as the destination in a MOV command, it changes the log scale, but does not change the scale from linear to logarithmic.

#### **Query Response**



QQ 1


XLG

## LIMIAMPSCL

## Limit-Line Amplitude Scale

Specifies the limit-line amplitude scale definition as logarithmic or linear.

#### **Syntax**



xlimiamp

Equivalent Softkey:

AMPL SCL LOG LIN

Prerequisite Command:

LIMINUM

**Related Commands:** 

LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI,

LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT,

LIMITEST, SEGDEL, SENTER, SENTERT


## Example

```
OUTPUT 718; "LIMINUM LIMIT_1;"
OUTPUT 718; "LIMIFRQSCL LIN;"
OUTPUT 718; "LIMIAMPSCL LOG;"
```

#### Description

The LIMIAMPSCL command specifies whether the limit line is derived from a logarithmic or linear amplitude axis. Use LIN to set the amplitude axis to linear and LOG to set the amplitude axis to logarithmic. The LIMINUM command must be issued prior to issuing the LIMIAMPSCL command.

### **Query Response**



aa5

## LIMIDEL

## **Delete Limit-Line Table**

Deletes segments in the current limit-line table.

### **Syntax**

LIMIDEL +() +

XLIMIDEL

Equivalent Softkey:

DELETE LIMIT, PURGE LIMITS

Related Commands:

LIMIAMPSCL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT,

LIMITEST, SEGDEL, SENTER, SENTERT

### Example

OUTPUT 718; "LIMIDEL;"

## Description

The LIMIDEL command deletes the selected limit-line table specified by LIMINUM.

Note

Use STOR or SAVET if you want to save the current limit-line table. LIMIDEL does not affect stored limit-line data.


#### LIMIDISP

## Limit Line Display

Controls when the limit lines are displayed.

Signal analysis mode only.

#### **Syntax**



XLIMIDISE

Equivalent Softkey:

LMT DISP Y N AUTO

Preset Value:

AUTO

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILO, LIMIMIRROR, LIMIMODE, LIMIREL, LIMISEG,

LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

#### Example

OUTPUT 718; "LIMIDISP ON;"

Displays any portion of the limit lines that are currently within the screen boundaries.

#### Description

The LIMIDISP command controls when the limit line (or limit lines) are displayed. If a limit line is currently in internal memory, you can use LIMIDISP to control the display of the limit lines. The parameters of LIMIDISP do the following:

ON

Turns on the limit line display.

**OFF** 

Turns off the limit line display.

AUTO

Allows LIMITEST to control the display of the limit lines. If LIMITEST is on,

the limit lines will be displayed. If LIMITEST is off, the limit lines will not be

displayed.

**UPPER** 

Displays the upper limit line only.

LOWER


Displays the lower limit line only.

When used as a predefined variable, LIMIDISP returns a number from 0 to four, depending on the setting of the LIMIDISP parameter. The number corresponds to the LIMIDISP parameter as shown in the following table.

## LIMIDISP Limit Line Display

LIMIDISP Parameter	Value Returned
OFF	0
UPPER	1
LOWER	2
ON	3
AUTO	4

# **Query Response**




QLIMIDISP

## LIMIFAIL Limits Failed

Returns the status of limit-line testing.

## **Syntax**



XLIMIFAIL

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

Related Softkey:

LMT TEST ON OFF

## Example

10	OUTPUT 718; "IP; SNGLS; CF300MHZ; SP100MHZ;"	Initializes instrument and changes the frequency and span settings.
20	OUTPUT 718;"LIMIDEL;"	Deletes any limit-line tables, sets the table type to fixed.
30	OUTPUT 718; "LIMIMODE UPPER;"	Specifies the upper limit-line table.
40	OUTPUT 718;"LIMISEG 250MHZ,-60DB,FLAT;"	Creates an entry for the upper limit-line table. Because the LIMISEG command is used, the limit-line will be based on the frequency.
50	OUTPUT 718; "LIMISEG 290MHZ, -60DB, SLOPE;"	
60	OUTPUT 718; "LIMISEG 295MHZ, -15DB, FLAT;"	
70	OUTPUT 718; "LIMISEG 305MHZ, -15DB, SLOPE;"	
80	OUTPUT 718; "LIMISEG 310MHZ, -60DB, FLAT;"	
90	OUTPUT 718; "LIMISEG 910MHZ, -60DB, FLAT;"	
100	OUTPUT 718; "LIMITEST ON; TS;"	Turns on limit-line testing.
110	OUTPUT 718; "LIMIFAIL?;"	Returns the status of the limit-line testing.
120	ENTER 718;A	
130	DISP A	Displays the result.
140	END	

## LIMIFAIL Limits Failed

## **Description**

The LIMIFAIL command returns one of the following values:

0 indicates that the measurement sweep was within the limit-line bounds. 1 indicates that the measurement sweep failed the lower limit, or LIMIT\_2 and its related margin. 2 indicates that the measurement sweep failed the upper limit, or LIMIT\_1 and its related margin. 3 indicates that the measurement sweep failed both the lower and upper limits. 4 indicates that no test was performed. A "4" is returned if LIMITEST is set to OFF.


## **Query Response**



## LIMIFRQSCL Limit-Line Frequency Scale

Specifies the limit-line frequency axis definition as logarithmic or linear.

#### **Syntax**



xlimitre

Equivalent Softkey:

FREQ SCL LOG LIN

Prerequisite Command:

LIMINUM, LIMIAMPSCL

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFT, LIMIHI, LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT,

LIMITEST, SEGDEL, SENTER, SENTERT


#### Example

OUTPUT 718; "LIMINUM LIMIT\_1;"
OUTPUT 718; "LIMIAMPSCL LIN;"
OUTPUT 718; "LIMIFRQSCL LOG;"

## Description

The LIMIFRQSCL command specifies whether the limit line is derived from a logarithmic or linear frequency axis. Use LIN to set the frequency axis to linear and LOG to set the frequency axis to logarithmic. The LIMINUM command must be issued prior to issuing the LIMIFRQSCL command.

#### **Query Response**



**4**q5


### LIMIFT

## **Select Frequency or Time Limit Line**

Selects how the limit-line segments are defined.

Signal analysis mode only.

#### **Syntax**



XLIMIFT

Equivalent Softkey:

LIMITS FRO TIME

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIHI, LIMILINE, LIMILO, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

## Example

OUTPUT 718; "LIMIFT TIME;"


If the current limit-line table is a frequency limit-line table, it is purged. LIMIFT TIME places the limit-line segments on the display with respect to the sweep time of the instrument.

## Description

The LIMIFT command selects how the limit-line segments are defined: according to frequency, or according to the sweep-time setting of the instrument.

If you execute "LIMIFT TIME;", LIMISEGT, or SENTERT, the limit-line segments are placed on the display with respect to the sweep time setting of the instrument. If you execute "LIMIFT FREQ;", LIMISEG, or SENTER, the limit-line segments are placed according to the frequency that is specified for each segment. If a limit line has already been defined, changing the LIMIFT setting clears the existing limit line.

## **Query Response**



QLIMIFT .


XLIMIHI .

# LIMIHI

# **Upper Limit**

Specifies a fixed trace as the upper limit line or limit 1.

# **Syntax**



Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

# Example

10	OUTPUT 718; "TRDEF M_ASK, 401;"	Defines a trace called "M_ASK."
20	OUTPUT 718; "MOV M_ASK[1,100],1000;"	Moves values into sections of the M_ASK
		trace.
30	OUTPUT 718; "MOV M_ASK[101,200],2000;"	
40	OUTPUT 718; "MOV M_ASK[201,300],3000;"	
50	OUTPUT 718; "MOV M_ASK[301,401],4000;"	
60	OUTPUT 718;"LIMIHI M_ASK;"	Specifies M_ASK as the upper limit
		line.
70	OUTPUT 718;"LIMITEST ON;"	Turns on limit-line testing.
80	OUTPUT 718;"LIMIFAIL?;"	Tests if trace A fails limit-line testing.
90	ENTER 718;A	
100	DISP A	Displays result of limit-line testing.
110	END	

#### LIMIHI Upper Limit

### Description

The LIMIHI command specifies a fixed trace as the upper limit line or limit 1. Unlike specifying a limit line with LIMISEG, LIMISEGT, SENTER, or SENTERT, the limit line specified with LIMIHI is not updated if the center frequency, frequency span, sweep time, or reference level are changed.


Note	Executing IP, LIMIDEL, LIMISEG, LIMISEGT, SENTER, or SENTERT will delete the limit line specified with LIMILO or LIMIHI. Executing LIMILO or LIMIHI
	will delete the limit line specified with LIMISEG, LIMISEGT, SENTER, or SENTERT.

Use LIMIDISP ON to display the limit line trace specified by LIMIHI. Use LIMIDISP OFF to blank the limit line trace specified by LIMIHI.

# LIMILINE Limit Lines

Outputs the current limit-line table definitions.

### **Syntax**



XLIMILINE

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

### Example

10	DIM States\$[2000]	Dimensions an array to store the
		limit-line information.
20	OUTPUT 718;"IP;CF300MHZ;SP100MHZ;"	Initializes instrument.
30	OUTPUT 718;"LIMIDEL;"	Deletes any limit-line tables, sets
		the table type to fixed.
40	OUTPUT 718; "LIMIMODE UPPER;"	Specifies the upper limit-line table.
45	OUTPUT 718;"LIMIFT FREQ;"	Selects a limit line based on frequency.
50	OUTPUT 718;"LIMISEG 250MHZ,-60DB,FLAT;"	Enters a value for the upper limit- line table. Because the LIMISEG command is used, the limit-line segment is for a limit-line based on frequency.
60	OUTPUT 718; "LIMISEG 290MHZ, -60DB, SLOPE;"	
70	OUTPUT 718; "LIMISEG 295MHZ, -15DB, FLAT;"	
80	OUTPUT 718; "LIMISEG 305MHZ, -15DB, SLOPE;"	
90	OUTPUT 718; "LIMISEG 310MHZ, -60DB, FLAT;"	
100	OUTPUT 718; "LIMISEG 910MHZ, -60DB, FLAT;"	
110	OUTPUT 718;"LIMILINE?;"	Gets the current limit-line table
	,,	definitions.
120	ENTER 718 USING "#,-K";States\$	Enters information into array.
130	PRINT States\$	Prints the current limit-line table
		definitions.
140	END	weg 0100000 2 2000

#### LIMILINE Limit Lines

### **Description**

The LIMILINE command is used to query the current limit line. Executing LIMILINE returns an ASCII string containing the commands needed to create the limit line.

Use these commands (in the order given) to build a limit line:

- 1. Use LIMIDEL to clear the limit-line table.
- 2. Use LIMIFT to select a limit line that is either based on frequency or sweep time.
- 3. Use LIMIREL to determine whether the values of the limit line are absolute values or positioned relative to the reference-level and center-frequency settings.
- 4. Use LIMIMODE, LIMISEG, LIMISEGT, SENTER, SENTERT to enter the limit-line segments. (Use LIMISEG or SENTER for a limit-line based on frequency; use LIMISEGT or SENTERT for a limit-line based on sweep time.)
- 5. Use the LIMIDISP or LIMILINESTA command to select if the limit line is displayed or not.
- 6. Use the LIMITEST command to turn on limit-line testing.
- 7. Use the LIMIFAIL command to determine if the measurement sweep passed or failed the limit line boundaries.


**Enabling limit-line testing:** When limit testing is enabled, the segments in the current table are interpolated into the limit-line traces according to the current span and center frequency or sweep time of the instrument. After the sweep, each value in trace A is compared to its corresponding value in the limit-line traces. If the current limit-line table is empty (for instance after using the command LIMIDEL) and limit testing is enabled, then the limit-line traces are blanked and set to out-of-range values. By using the SUB, MKPK HI, and MKF? commands, you can read the point of greatest difference between the trace and limit line. See "LIMITEST" for more information about limit-line testing.

Saving the limit line table: Once you have built the limit line, you can save the limit-line table on the disk drive or in internal memory. Use the STOR command, to store the current limit-line table on the disk drive. Use SAVET, to store the limit-line table in internal memory.

#### **Query Response**

The query response is a character string consisting of LIMIDEFNTYP, LIMINUM, LIMIMARGAMP, LIMILINESTA, LIMIMARGSTA, LIMIAMPSCL, LIMIFRQSCL, LIMIDISP, LIMITEST, LIMILINE, LIMIREL, LIMIHALF, LIMISEG, LIMISEGT, SENTER, or SENTERT commands. (The LIMIHALF command is for backward compatibility; it is not used as an HP 8546A/HP 8542E EMI system programming command.)

### **LIMILINE** Limit Lines




# LIMILINESTA Limit-Line State

Displays the selected limit line.

Note

EMI receiver mode only.

### **Syntax**



xlinsto .

Equivalent Softkeys:

LIMIT 1 ON OFF or LIMIT 2 ON OFF

Prerequisite Command:

LIMINUM

Preset State:

OFF

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIFAIL, LIMIFRQSCL, LIMIHI, LIMILINE,

LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMINUM, LIMISEG,

LIMITEST, SEGDEL

### Example

OUTPUT 718; "LIMINUM LIMIT\_1;"
OUTPUT 718; "LIMILINESTA ON;"


# Description

The LIMILINESTA command displays the selected limit line. Setting LIMILINESTA to off disables the display of the selected limit line. Setting LIMILINESTA to on enables the display of the selected limit line. The LIMINUM command must be issued to select the limit line prior to issuing the LIMILINESTA command.

Note

In order for limit-line testing to occur, LIMIMARGSTA or LIMILINESTA must be set to on.

# **Query Response**




QQ2

### LIMILO

### **Lower Limit**

Specifies a fixed trace as the lower limit line or limit 2.

### **Syntax**



XLIMILO .

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILINESTA, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

#### Example

10	OUTPUT 718;"TRDEF M_ASK,401;"	Defines a trace called "M_ASK."
20	OUTPUT 718; "MOV M_ASK[1,100],1000;"	Moves values into sections of the M_ASK
		trace.
30	OUTPUT 718; "MOV M_ASK[101,200],2000;"	
<b>4</b> 0	OUTPUT 718; "MOV M_ASK[201,300],3000;"	
50	OUTPUT 718; "MOV M_ASK[301,401],4000;"	
60	OUTPUT 718;"LIMILO M_ASK;"	Specifies M_ASK as the lower limit
		line.
70	OUTPUT 718; "LIMITEST ON;"	Turns on limit-line testing.
80	OUTPUT 718; "LIMIFAIL?;"	Tests if trace A fails limit-line testing.
90	ENTER 718; A	•
100	DISP A	Displays result of limit-line testing.
110	END	

#### Description

The LIMILO command specifies a fixed trace as the lower limit line or limit 2. Unlike specifying a limit line with LIMISEG, LIMISEGT, SENTERT, or SENTER, the limit line specified with LIMILO is *not* updated if the center frequency, frequency span, sweep time, or reference level is changed.

Executing IP, LIMIDEL, LIMISEG, LIMISEGT, SENTERT, or SENTER will delete the limit line specified with LIMILO or LIMIHI. Executing LIMILO or LIMIHI
will delete the limit line specified with LIMISEG or SENTER.

Use LIMIDISP ON to display the limit line trace specified by LIMILO. Use LIMIDISP OFF to blank the limit line trace specified by LIMILO.


# LIMIMARGAMP Limit Margin Amplitude

Sets the amplitude in negative dB for the limit margin.

Note

EMI receiver mode only.

### **Syntax**



x I imamp

Item	Description/Default	Range
Number	Any real or integer. Units are in decibels	-40 dB to 0 dB.

Equivalent Softkey:

MARGIN 1 ON OFF or MARGIN 2 ON OFF

Prerequisite Command:

LIMINUM

Preset State:

0.00 dB

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIFAIL, LIMIFRQSCL, LIMIHI, LIMILINE,

LIMILO, LIMILINESTA, LIMIMARGSTA, LIMINUM, LIMITEST,

**SEGDEL** 

### Example

OUTPUT 718; "LIMINUM LIMIT\_1;"
OUTPUT 718; "LIMIMARGAMP -3DB;"

#### **Description**

The LIMIMARGAMP command sets the amplitude (in negative decibels) for the limit margin. The limit margin is a fixed amplitude relative to the limit line. The LIMINUM command must be issued to select the limit margin prior to issuing the LIMIMARGAMP command and a limit line must be defined for limit margin to be active.

### **Query Response**



QQ:


# LIMIMARGSTA Limit-Margin State

Displays the selected limit margin.

Note

EMI receiver mode only.

### **Syntax**



xlimrst

Equivalent Softkey:

MARGIN 1 ON OFF or MARGIN 2 ON OFF

Prerequisite Command:

LIMINUM

Related Commands:

 $LIMIAMPSCL, \ LIMIDEL, \ LIMIFAIL, \ LIMIFRQSCL, \ LIMIHI, \ LIMILINE,$ 

LIMILO, LIMILINESTA, LIMIMARGAMP, LIMINUM, LIMISEG,

LIMITEST, SEGDEL

### Example

10 OUTPUT 718; "LIMINUM LIMIT\_1;"

20 OUTPUT 718; "LIMILINESTA ON;"

30 OUTPUT 718; "LIMIMARGSTA ON;"


# **Description**

The LIMIMARGSTA command displays the selected limit margin. Setting LIMIMARGSTA to 0 or OFF disables the display of the selected limit margin. Setting LIMIMARGSTA to 1 or 0N enables the display of the selected limit margin. The LIMINUM command must be issued to select the limit margin prior to issuing the LIMIMARGSTA command.

Note

In order for limit-line testing to a margin to occur, LIMIMARGSTA or LIMILINESTA must be set to on.

# **Query Response**



QQ2

# LIMIMIRROR **Mirror Limit Line**

Reflects the current definition about the amplitude axis at the largest frequency or sweep time.

Note

Signal analysis mode only.

### **Syntax**



XLIMIMIRROF

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILO, LIMIMODE, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

# Example

10	OUTPUT 718;"IP;CF300MHZ;SP100	,
20	OUTPUT 718;"LIMIDEL;"	frequency and span.  Deletes any limit-line tables, sets  the table type to fixed.
30	OUTPUT 718; "LIMIMODE UPPER;"	Specifies the upper limit-line table.
35	OUTPUT 718; "LIMIFT FREQ;"	Selects a limit line based on frequency
40	OUTPUT 718;"LIMISEG 250MHZ,-6	v 1 0
50	OUTPUT 718; "LIMISEG 290MHZ, -5	ODB,SLOPE;"
60	OUTPUT 718; "LIMISEG 295MHZ, -1	
70	OUTPUT 718; "LIMISEG 300MHZ, -1	ODB, SLOPE; "
80	OUTPUT 718; "LIMIMIRROR;"	Mirrors the upper limit-line entries.
90	OUTPUT 718;"LIMITEST ON;"	Turns on the limit-line testing and displays the limit lines.
100	END	- ·

The example results in the limit-line table shown in the following table.

SEG	START_FREQ	UPPER_AMP	TYPE
1	250.0 MHz	-60.0 dBm	FLAT
2	290.0 MHz	-60.0 dBm	SLOPE
3	295.0 MHz	-15.0 dBm	SLOPE
4	300.0 MHz	-10.0 dBm	SLOPE
5	305.0 MHz	-15.0 dBm	SLOPE
6	310.0 MHz	-50.0 dBm	POINT
7	310.0 MHz	-60.0 dBm	FLAT
8	350.0 MHz	-60.0 dBm	FLAT

# **Description**

Reflects the current definition about the amplitude axis at the largest frequency (for a limit line based on frequency) or the largest sweep time (for a limit line based on the sweep time) in the definition.

You may notice that the LIMIMIRROR command may create more than one table entry for a frequency (for example, see segment 6 in the above table). The LIMIMIRROR command creates an extra segment so that the previous segment is explicitly ended at the correct amplitude.

#### LIMIMODE


# Limit-Line Entry Mode

Determines how the limit-line entries are treated.

Note

Signal analysis mode only.

### **Syntax**



XLIMIMODE

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILO, LIMIMIRROR, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

### Example

This example uses LIMIMODE to enter segments into the upper limit-line table, and then to enter a segment into the lower limit-line table (upper and lower limit lines are treated as separate tables). Line 80 demonstrates entering a segment into a combined upper and lower limit-line table.

- 10 OUTPUT 718; "LIMIDEL;"
- 20 OUTPUT 718; "LIMIMODE UPPER;"
- 30 OUTPUT 718; "LIMIFT FREQ;"
- 40 OUTPUT 718; "LIMISEG 300MHZ, -30DB, SLOPE;"
- 50 OUTPUT 718; "LIMIMODE LOWER;"
- 60 OUTPUT 718; "LIMISEG 300MHZ, -70DB, SLOPE;"
- 70 OUTPUT 718; "LIMIMODE UPLOW;"
- 80 OUTPUT 718; "SENTER 350MHZ, -30DB, -80DB, FLAT;"
- 90 OUTPUT 718; "LIMIDISP ON;"

100 END

Deletes the current limit-line table, sets the table type to fixed. Specifies the upper limit-line table. Selects a limit line based on frequency. Enters a segment into the upper limit-line table. Because the LIMISEG command is used, the limit-line table will be based on frequency.

Specifies the lower limit-line table. Enters a segment into the lower limit-line table.

Specifies the upper and lower limit-

 $line\ tables.$ 

Enters a segment into the upper and lower limit-line tables. Displays the limit lines.

### Description

The LIMIMODE command determines whether the limit-line entries are treated as upper-amplitude values, lower-amplitude values, upper and lower amplitude values, or mid-amplitude and delta values.


Use LIMIMODE in conjunction with LIMISEG, LIMISEGT, SENTER, or SENTERT. Specify LIMIMODE UPPER or LIMIMODE LOWER before using LIMISEG or LIMISEGT. Specify LIMIMODE UPLOW or LIMIMODE DELTA before using SENTER or SENTERT.

The LIMIMODE command determines whether the limit-line table entries are to be treated separately (upper or lower) or together (upper and lower) when deleting a segment with SEGDEL (see "SEGDEL"). If limit-line table entries are entered with LIMISEG or LIMISEGT, they are treated as entries to separate tables even if LIMIMODE UPLOW or LIMIMODE DELTA had been previously specified.

When used as a predefined variable, LIMIMODE returns a number from 0 to three, depending on the setting of the LIMIMODE parameter. The number corresponds to the LIMIMODE parameter as shown in the following table.

LIMIMODE Parameter	Value Returned
UPLOW	0
DELTA	1
UPPER	2
LOWER	3

### **Query Response**



QLIMIMODE

# **LIMINUM**


# **Limit-Line Number**

Selects limit-line number 1 or 2 and its corresponding margin.

Note

EMI receiver mode only.

### **Syntax**



xlimnum .

Equivalent Softkey:

Limit 1 or Limit 2

Preset State:

LIMIT\_1

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIFAIL, LIMIFRQSCL, LIMIHI, LIMILINE,

LIMILO, LIMILINESTA, LIMIMARGAMP, LIMIMARGSTA, LIMISEG,

LIMITEST, SEGDEL


# Example

OUTPUT 718; "LIMINUM LIMIT\_1;"

#### **Description**

The LIMINUM command selects limit-line number 1 or 2 and its corresponding margin. This command must be issued prior to issuing any of the related commands listed above.

# **Query Response**



qlimnum

#### LIMIREL


# **Relative Limit Lines**

Specifies whether the current limit lines are fixed or relative.

Note

Signal analysis mode only.

#### **Syntax**



XLIMIREL

Equivalent Softkey:

LIMITS FIX REL

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILO, LIMIMIRROR, LIMIMODE, LIMISEG,

LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

### Example

OUTPUT 718; "LIMIFT FREQ;"

Selects a limit line based on frequency.

OUTPUT 718; "LIMIREL ON;"

Specifies that the limit line will be relative to the reference-

level and center-frequency settings.

### Description

The LIMIREL command specifies whether the current limit lines are fixed or relative. Use the LIMIFT command to select whether the limit lines are based on frequency or sweep time before using LIMIREL, because changing between a frequency or sweep time limit line purges the current limit line table and sets LIMIREL to OFF.

LIMIREL and the reference level: Regardless of whether the limit line is based on frequency or sweep time, LIMIREL determines if the amplitude parameter in a limit line table represents absolute values or relative values. If LIMIREL is set to OFF, the limit lines amplitude values are specified in absolute amplitude and do not depend on the reference level (RL) setting. If LIMIREL is set to ON, the limit line amplitude values are relative to the current reference level (RL) setting.

For limit lines that are based on frequency: The LIMIREL command determines whether the frequency parameter in a limit-line table represent absolute or relative values that are referenced to the center-frequency settings.


■ Executing "LIMIREL OFF;" specifies that the frequency values in a limit-line table are fixed values, and the limit line is positioned accordingly. Fixed limit lines are specified in absolute frequency and do not depend upon the center frequency value.

#### **LIMIREL Relative Limit Lines**

■ Executing "LIMIREL ON;" specifies that the frequency values in a limit-line table are relative values and positions the limit line relative to the center-frequency settings. Relative limit lines are specified in relative frequency and are positioned with respect to the current center frequency. When the current center frequency value is changed, the segment frequencies are converted according to the current center frequency value.

For limit lines that are based on the sweep time: Limit lines that are based on sweep time are always relative to the start time, and the horizontal position of the limit line is not affected by the setting of LIMIREL.

### **Query Response**




QQ2

# LIMISEG

# **Enter Limit-Line Segment for Frequency**

Adds new segments to the current frequency limit line.

### **Syntax**



xlimiseg .

Item	Description/Default	Range
Number	Any real or integer number. Default unit is dBm.	Varies with FOFFSET
		and ROFFSET.

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEGT, LIMITEST, SEGDEL, SENTER, SENTERT

#### LIMISEG Enter Limit-Line Segment for Frequency

### Example

10	OUTPUT 718; "IP; SNGLS; CF300MHZ; SP100MHZ; IFBW 3MHZ; "	Initializes instrument, change the frequency, span, and
20	OUTPUT 718;"LIMIDEL;"	bandwidth.  Deletes the current limit- line table, sets the table
30	OUTPUT 718;"LIMIMODE UPPER;"	type to fixed.  Specifies the upper limit- line table.
35	OUTPUT 718;"LIMIFT FREQ;"	Selects a limit line based on frequency.
40	OUTPUT 718; "LIMISEG 250MHZ, -60DB, FLAT;"	Adds segment to the upper limit-line table.
50	OUTPUT 718; "LIMISEG 290MHZ, -60DB, SLOPE;"	
60	OUTPUT 718; "LIMISEG 295MHZ, -15DB, FLAT;"	
70	OUTPUT 718; "LIMISEG 305MHZ, -15DB, SLOPE;"	
80	OUTPUT 718; "LIMISEG 310MHZ, -60DB, FLAT;"	
90	OUTPUT 718; "LIMISEG 910MHZ, -60DB, FLAT;"	
100	OUTPUT 718; "LIMIMODE LOWER;"	Specifies the lower limit- line table.
110	OUTPUT 718; "LIMISEG 250MHZ, -75DB, FLAT;"	Adds segment to the lower limit-line table.
120	OUTPUT 718; "LIMISEG 910MHZ, -75DB, FLAT;"	
130	OUTPUT 718; "LIMITEST ON; TS; "	Enables limit-line testing.
140	OUTPUT 718; "LIMIFAIL?;"	Returns the result of limit-
		line testing.
150	ENTER 718;A	, and the second
160	DISP A	Displays the result.
170	END	

# Description

The LIMISEG command adds new segments to the current frequency limit line in either the upper limit line or the lower limit line. If the current limit line table contains lines based on sweep time (as opposed to a limit line based on the frequency), executing LIMISEG will clear the current sweep time limit line table, and set LIMIREL to OFF.

Each limit-line segment is specified with a starting frequency, an amplitude, and a segment type. The segment type defines how the line segment is to extend from its starting point to the next segment. The segment types are FLAT, SLOPE, and POINT.

- FLAT draws a zero-slope line between the coordinate point of the current segment and the coordinate point of the next segment, producing limit-line values equal in amplitude for all frequencies between the two points. If the amplitude values of the two segments differ, the limit line will "step" to the value of the second segment.
- SLOPE draws a straight line between the coordinate point of the current segment and the coordinate point of the next segment, producing limit-line values for all frequencies between the two points.
- POINT specifies a limit value for the coordinate point, and no other frequency points, so that a POINT segment specifies a limit value for a single frequency. The POINT segment type should be used as the last segment in the limit-line table. However, if the last segment in the

#### LIMISEG Enter Limit-Line Segment for Frequency

table is not specified as the POINT segment type, an implicit point is used automatically. If a visible POINT segment at the right edge of the display is not desired, add an explicit last point segment (higher in frequency than the stop frequency) to the limit-line table.

Segments are sorted according to starting frequency. A maximum of 30 segments can be defined in each of the upper and lower halves of a limit line. When the segment type is omitted, the last type given (or SLOPE if no previous type has been given) is used.

Use LIMISEG if you want to enter amplitude data in the upper or lower limit lines. If you want to enter amplitude data as upper and lower amplitude pairs or as mid and delta pairs, use the SENTER command instead of LIMISEG. Use LIMIMODE to specify entry into the upper limit-line table or the lower limit-line table (see line 30 of example).

# LIMISEGT


# **Enter Limit-Line Segment for Sweep Time**

Adds new segments to the current sweep time limit line.

Note

Signal analysis mode only.

# **Syntax**



xlimisegt

Item	Description/Default	Range
Number		The range of the sweep time is 0 to 100 s. The range of the amplitude varies with ROFFSET.

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILO, LIMIMIRROR, LIMIMODE, LIMIREL, LIMISEG, LIMITEST, SEGDEL, SENTER, SENTERT

### Example

```
OUTPUT 718; "LIMIDEL;"
                                               Deletes the current limit-line table, sets the
                                                table type to fixed.
OUTPUT 718; "LIMIMODE UPPER;"
                                                Specifies the upper limit-line table.
OUTPUT 718; "LIMIFT TIME;"
                                                Selects a limit line based on the sweep time.
OUTPUT 718; "LIMISEGT OMS, -60DB, FLAT;"
                                               Adds segment to the upper limit-line table.
OUTPUT 718; "LIMISEGT 6MS, -60DB, SLOPE;"
OUTPUT 718; "LIMISEGT 8MS, -15DB, FLAT;"
OUTPUT 718; "LIMISEGT 11MS, -20DB, SLOPE;"
OUTPUT 718; "LIMISEGT 14MS, -60DB, FLAT;"
OUTPUT 718; "LIMISEGT 20MS, -60DB, POINT;"
OUTPUT 718; "LIMIMODE LOWER;"
                                               Specifies the lower limit-line table.
OUTPUT 718; "LIMISEGT OMS, -75DB, FLAT:"
                                               Adds segment to the lower limit-line table.
OUTPUT 718; "LIMISEGT 20MS, -75DB, POINT;"
OUTPUT 718; "LIMITEST ON; TS; "
                                               Enables limit-line testing.
OUTPUT 718: "LIMIFAIL?;"
                                               Returns the result of limit-line testing.
ENTER 718:A
DISP A
                                               Displays the result.
```

#### **Description**

The LIMSEGT command adds new segments to the current sweep time limit line in either the upper or lower limit line. Each limit-line segment is specified with a starting sweep time, an amplitude, and a segment type.

#### Note

If the current limit line table contains limit lines based on frequency (as opposed to a limit line based on the sweep time), executing LIMISEGT will clear the current frequency limit line table, and set LIMIREL to OFF.

Starting sweep time: When you specify the starting sweep time, you are specifying the starting sweep time with respect to the sweep time of the instrument. For example, if you specify a starting sweep time of 0, the limit-line segment will start at the left side of the display.

**Segment type:** The segment type defines how the line segment is to extend from its starting point to the next segment. The segment types are FLAT, SLOPE, and POINT.

- FLAT draws a zero-slope line between the coordinate point of the current segment and the coordinate point of the next segment, producing limit-line values equal in amplitude for all sweep times between the two points. If the amplitude values of the two segments differ, the limit line will "step" to the value of the second segment.
- SLOPE draws a straight line between the coordinate point of the current segment and the coordinate point of the next segment, interpolating amplitude values for all sweep times between the two points.
- POINT specifies a limit value for the coordinate point, and no other sweep time points, so that a POINT segment specifies an amplitude value for a single sweep time. For an upper limit line, a POINT segment is indicated by a line drawn from the coordinate point, to a point that is vertically off the top of the graticule area. For a lower limit line, a POINT segment is indicated by a line drawn from the coordinate point, to a point that is vertically off the bottom of the graticule area. The POINT segment type should be used as the last segment in the limit-line table. However, if the last segment in the table is not specified as the POINT segment type, an implicit point is used automatically. If a visible POINT segment at the right

#### LIMISEGT Enter Limit-Line Segment for Sweep Time

edge of the display is not desired, add an explicit last point segment to (higher in sweep time than the current sweep time setting of the instrument) the limit-line table.

Segments are sorted according to starting sweep time. A maximum of 30 segments can be defined in each of the upper and lower halves of a limit line.


Use LIMISEGT if you want to enter amplitude data in the upper or lower limit lines. Use LIMIMODE to specify entry into the upper limit-line table or the lower limit-line table (see line 30 of example). If you want to enter amplitude data as upper and lower amplitude pairs or as mid and delta pairs, use the SENTERT command instead of LIMISEGT.

#### LIMITEST

# **Enable Limit-Line Testing**

Enables testing to the displayed limit line and limit margin.

#### **Syntax**



XLIMITEST

Equivalent Key:

LMT TEST ON OFF

Prerequisite Command:

LIMINUM

Preset State:

**OFF** 

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL,

LIMIFT, LIMIHI, LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP,

LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL,

LIMISEG, LIMISEGT, SEGDEL, SENTER, SENTERT

#### Example

OUTPUT 718; "LIMITEST ON;"

#### Description

The LIMITEST command enables testing to the displayed limit line and limit margin. Setting LIMITEST to 0 or OFF disables testing, and setting LIMITEST to 1 or ON enables testing.

EMI Receiver Mode Only

The LIMINUM command must be issued to select the limit line prior to issuing the LIMITEST command. LIMITEST may be independently turned on or off for LIMIT 1 and LIMIT 2.

#### Note

For EMI mode only.

In order for limit-line testing to a margin to occur, LIMIMARGSTA or LIMILINESTA must be set to on.

### LIMITEST Enable Limit-Line Testing


For signal analysis mode only.

LIMITEST ON turns testing on for both the upper and lower limits. LIMITEST OFF turns testing off for both the upper and lower limits.

Note

Testing may be enabled even though the limit lines are not displayed.

# **Query Response**




QQ2

### LINCHK

# **Linearity Check**

Determines whether a measured signal level is undergoing compression.

### **Syntax**



xlinchk

Equivalent Key:

(LINEARITY CHECK)

Related Commands:

AT, RL, MKN, MKPK

Preset State:

LINCHK OFF

# Example

OUTPUT 718; "LINCHK ON;"


### Description

The LINCHK command modifies the input RF attenuation to allow the user to determine if a measured signal level is undergoing compression. The LINCHK command is designed to be used with the Marker subsystem in order to measure a specific signal level at different RF attenuation values.

#### Note

An "illegal command" SRQ will be sent if you issue the "LINCHK ON" command and no additional RF attenuation is available from the system. In this case, the error message: "LINCHK: RF Attenuation at Max" wil appear on the screen.

### Query Response:




QQ2

# LINFILL

# Linear

Fills linear interpolated data into the specified trace data points of a destination trace.

# **Syntax**



Item	Description/Default	Range
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number	Any valid integer number.	For the starting value or number of elements, the range of the number is 0 to the length of the trace minus 1. For the ending value, the range is $-32,768$ to $+32,767$ .

### Example

OUTPUT 718; "LINFILL TRC,0,0,0:" OUTPUT 718; "MOV TRC[1,10], TRA[1,10];"

OUTPUT 718; "LINFILL TRC, 10, 40, 8000;"

Initializes trace C.

Moves the first 10 elements of trace A into trace C.

Uses the 10th element of trace C as the starting value, fills trace C elements 11 through 50 with the interpolated data, and places ending value (8000) into the 50th element of trace

### Description

The LINFILL command uses the starting value and the ending value to calculate the linear interpolation data (the values for ending value should be in measurement units). The "number of elements" field allows you to specify the number trace data points that are "filled in" with linear interpolation data. The number of elements field includes the starting element, so if the starting value is 10 and the number of elements is 40, the ending element will be 50.

The data will not be interpolated if the starting value is 0. If the starting value is 0, the ending value is copied into the first element of the destination trace. You may want to set the starting value to 0 to initialize a trace before using LINFILL to fill the trace with interpolated data. If the starting value and the number of elements exceed the length of the destination trace, the interpolation ends at the end of the trace array; the ending value is never reached.

# LN

# Linear Scale

Specifies the vertical graticule divisions as linear units.

### **Syntax**



XLN

Equivalent Softkey:

SCALE LOG LIN

Related Commands:

LG, RL

### Example

OUTPUT 718;"LN;"

Selects linear mode.

OUTPUT 718;"LN;RL 30MV;"

### **Description**


The LN command scales the amplitude (vertical graticule divisions) proportionally to the input voltage, without changing the reference level. The bottom graticule line represents a signal level of zero volts.

Voltage entries are rounded to the nearest 0.1 dB. Thus, 30.16 mV becomes 89.6 dB $\mu$ V.

# LOAD Load

Loads a file from the disk drive.

### **Syntax**



Item	Description/Default	Range
Character	Any valid character.	Any valid file name.
Delimiter	Matching characters marking the beginning and end of the list of	~ \@=/^\$%;!':
	instrument commands.	" &

Equivalent Softkey:

LOAD FILE

**Related Commands:** 

CAT, STOR

# Example

LIF Format

OUTPUT 718; "LOAD %tMYTRA%, TRA;"

Loads MYTRA from the disk drive into trace

A.

OUTPUT 718; "LOAD %eMYSETUP%;"

Loads all information from MYSETUP.

DOS Format

OUTPUT 718; "LOAD %MYTRA.TRC%,TRA;"

Loads MYTRA from the disk drive into trace

A.

OUTPUT 718; "LOAD %MYSETUP.ALL%;"

Loads all information from MYSETUP.

#### LOAD Load

### **Description**

The LOAD command loads a file from the disk drive.

To use the LOAD command, you must specify the file name of the file to be loaded from the disk drive into internal memory, and, if you are loading trace data, you must also specify the trace destination.

file name: When Loading data from a floppy disk, you must specify the file name of the file to be loaded, in either LIF or DOS format. Specify a prefix for LIF format or a suffix for DOS format to indicate the data type (see the following table).

Table 4-6. LIF or DOS Data Types

LIF Prefix	DOS Suffix	File Description	Result	
S	.STA	Instrument state	Loads the instrument state, and changes the current instrument state to the state that was loaded.	
t	.TRC	Trace	Loads the trace and state. The current instrument trace and state is changed to the trace and state that was loaded.	
1	.LIM	Limit lines	Loads the limit-line values into the current limit-line table.	
g	.SIG	Signal list	Loads the signal list and its associated annotation.	
n	.ANT	Antenna correction factors	Loads the antenna correction factors.	
c	.CBL	Cable correction factors	Loads the cable correction factors.	
0	.ОТН	Other correction factors	Loads other correction factors.	
e	.ALL	All information	Loads all information.	

Destination: When recalling trace data, you need to specify either TRA, TRB, TRC, or a user-defined trace as the destination. Omit the destination parameter when recalling all other file types.


Note	The LOAD command recalls data from the disk drive. Refer to "RCLT" or
	"RCLS" to recall data from internal memory.

# LOG

# Logarithm

Takes the logarithm (base 10) of the source, multiplies the result by the scaling factor.

# **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable. TS when using trace data.

Related Commands:

**EXP** 

#### LOG Logarithm

### Example 1

```
OUTPUT 718; "IP;"

Initializes instrument.

OUTPUT 718; "VARDEF P_OWER, 0;"

Defines a user-defined variable, called P_OWER, and sets it equal to 0.

OUTPUT 718; "LOG P_OWER, 5, 10;"

P_OWER = 10 × LOG(5).

OUTPUT 718; "P_OWER?;"

Returns value to computer.

ENTER 718; N

Assigns value to computer variable.

DISP USING "D.DD,K"; N;" dB"

Displays value on the computer screen.
```

#### Example 2

This example finds the natural exponential of a number and uses the LOG function to return the original source value of the EXP function.

```
10 OUTPUT 718; "VARDEF E_XP,0;"
                                                Defines a variable called E\_XP.
20 OUTPUT 718; "EXP E_XP,2,2.30259;"
                                                Finds the natural exponential of 2.
30 OUTPUT 718;"E_XP?;"
                                                Returns the natural exponential of 2.
40 ENTER 718: Value
50 PRINT Value
                                                Prints the value of the exponential.
60 OUTPUT 718;"LOG E_XP,E_XP,2.30259;"
                                                Uses the log function on the exponential
                                                value.
70 OUTPUT 718; "E_XP?;"
                                                The log of the exponential value is ap-
                                                proximately 2.
80 ENTER 718; Logvalue
90 PRINT Logvalue
100 OUTPUT 718; "VARDEF E_XPY,O;"
                                                Declares a variable called E\_XPY.
110 OUTPUT 718; "EXP E_XPY, -5,2.30259;"
                                                Finds the natural exponential of -5.
120 OUTPUT 718; "E_XPY?;" -
                                                Returns the value of the natural exponen-
                                                tial of -5.
130 ENTER 718: Value2
140 PRINT Value2
                                                Prints the value of the exponential.
150 OUTPUT 718; "LOG E_XPY,E_XPY,2.30259;"
                                                Uses the log function on the exponential
                                                value.
160 OUTPUT 718; "E_XPY?;"
                                                The log of the exponential value is ap-
                                                proximately -5.
170 ENTER 718; Logval
180 PRINT Logval
190 END
```

# Description

The LOG command takes the logarithm (base 10) of the source, multiplies the result by the scaling factor, then stores it in the destination. The scaling factor may be used to improve numerical computations when calculating logarithms of integer trace data. For example, the log of a trace value of 8000 is 3.9, which would be stored as the value 4 in a trace.

The log of trace value of 1 is 0, so the log of a trace containing values from 1 to 8000 would be compressed to values 0, 1, 2, 3, 4. Computational accuracy can be improved by using the scaling factor to scale up the log values before they are stored. In this case, because 3.903 is the log of 8000 and the largest positive trace value is 32,767, a scaling factor of 32,767 divided by 3.903 or 8,395 may be applied to the data. Because EXP and LOG are inverse functions, the

EXP command has a scaling factor that may be used to "undo" the scaling factor of the LOG command.

The LOG command can be used to calculate the natural logarithm by using 2.30259 as the scaling factor.

The LOG function returns an invalid result if the source is zero or a negative number.


When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

# **LSPAN**

# Last Span

Changes the span of the instrument to the previous span setting.

# **Syntax**



XLSPAN

Equivalent Softkey:

LAST SPAN

Related Commands:

SP

### Example

OUTPUT 718; "LSPAN;"


# Description

The LSPAN command changes the span of the instrument to the previous span setting.

# LOGSWEEPSPD Log Sweep Speed

Sets the log sweep speed to fast or standard.

#### **Syntax**



Equivalent Softkey:

LOGF SPD STD FAST

Preset Value:

LOGSWEEPSPD STD

Related Commands

**SWEEPTYPE** 

#### Example

OUTPUT 718; "LOGSWEEPSPD FAST:"


# **Description**

The LOGSWEEPSPD command sets the log sweep speed to fast or standard whenever the LOG frequency sweep type is active. LOGSWEEPSPD is only in effect when the instrument is operating in the log frequency sweep mode, as set by the SWEEPTYPE command. It has no effect when a linear frequency sweep is active.

Setting LOGSWEEPSPD to "STD" optimizes the frequency accuracy of the sweep. Setting LOGSWEEPSPD to "FAST" minimizes the scan time of the sweep.

Changing LOGSWEEPSPD has an effect on the minimum sweep time set by the SWEEPTIME command. When LOGSWEEPSPD is set to "FAST", the minimum sweep time is less than or equal to the minimum sweep time when LOGSWEEPSPD is set to "STD".

#### **Query Response**




cloaswo

# **M4**

# Marker Zoom

Keeps the marker at center frequency.

# **Syntax**



Item	Description/Default	Range
Number	T	Start frequency to stop frequency of
		instrument.

Step Decrement:

Span divided by 2

Step Increment:

Span multiplied by 2

Related Commands:

MKCF, MKN, SP


# Example

OUTPUT 718;"M4;"

## Description

The M4 command activates a single marker on the trace and enables the knob to change the position of the marker. When changing the frequency span, M4 keeps the marker at center frequency. Used with a marker on the signal peak or at a position of interest, M4 keeps the marker at center screen while the frequency span is decreased.

## **Query Response**




#### **MDS**

### **Measurement Data Size**

Specifies measurement data size as byte or word.

#### **Syntax**



XMDS

Related Commands:

MKA, TDF, TRA

Preset State:

W

#### Example

These commands transfer trace A in binary, 2 bytes per word.

INTEGER TRACE\_A (1:401)

Declares variable, Trace\_A.

OUTPUT 718; "SNGLS; TS; "

Activates single-sweep, updates trace A.

OUTPUT 718; "TDF B; MDS W; TRA?;"

Reads trace A in "word" format.

ENTER 718 USING "#,401(W)";TRACE\_A(\*)

Formats trace A output using data size of one

word.

PRINT TRACE\_A(\*)

Prints trace A.

#### Description

The MDS command formats binary data in one of the following formats:

**B** selects a data size of one 8-bit byte. When transferring trace data, MDS B transfers trace data faster than MDS W because only 401 bytes are transferred. Because MDS B combines two bytes into one byte, some resolution is lost.

W selects a data size of one word, which is two 8-bit bytes. When transferring trace data, MDS W transfers 802 bytes of trace data with no loss of resolution.

How data is represented with MDS W: When data is sent with MDS W, the trace data is converted into two bytes as follows:

- 1. The trace element's amplitude (in measurement units) is divided by 256. The binary representation of the result is placed in the most significant byte (MSB).
- 2. The binary representation of the remainder is placed in the least significant byte (LSB).

For example, a trace element that is at the reference level has the value of 8000 (in measurement units). The result of 8000 divided by 256 is 30, with a remainder of 120. For this data, the contents of the MSB would contain the binary representation for 30.

#### Contents of the MSB

00011110

For this data, the contents of the LSB would contain the binary representation for 120.

#### Contents of the LSB

0 1 1 1 0 0 1 0

How data is represented with MDS B: When data is sent with MDS B, the trace data is converted into one byte as follows:

■ The trace element's amplitude (in measurement units) is divided by 32. The binary representation of the result is placed into one byte.


For example, a trace element that is at the reference level has the value of 8000 (in measurement units). The result of 8000 divided by 32 is 250. For this data, the contents of the byte would contain the binary representation for 250.

#### Contents of Byte

1 1 1 1 1 0 1 0

See "TDF" for information about using MDS for trace data transfers.

## Query Response:



QMDS

#### **MDU**

#### **Measurement Data Units**

Returns values for the instrument baseline and reference level.

#### **Syntax**



NUMX

Related Commands:

TDF

#### Example


10 OUTPUT 718;"IP;TDF M;" Initializes the instrument and formats the trace data in measurement units. 20 OUTPUT 718;"RL 80DB;" Changes the reference level to 80 dB $\mu$ V. 30 OUTPUT 718; "MDU?;" Queries the position of the instrument baseline and reference level. 40 ENTER 718; A, B, C, D, A\$ Moves the instrument response to the computer. 50 PRINT A,B,C,D,A\$ Displays the results on the computer screen. 60 END

The example returns the following to the controller: 0, 200, 0, 80 dB $\mu$ V. The first two numbers received indicate that the vertical scale spans from 0 to 200 plotter units. The third and fourth number received indicate that the baseline is at 0 dB $\mu$ V, and the reference level is at 80 dB $\mu$ V. So, the baseline value of  $0 dB\mu V$  is equal to 0 plotter units. The reference level of  $80 dB\mu V$  is equal to 200 plotter units.

#### Description

The MDU command returns values for the instrument baseline and reference level, in plotter units and measurement units.

# **Query Response**




### **MEAN**

## Trace Mean

Returns the mean value of the given trace in measurement units.

#### **Syntax**



XMEAN

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command	Any valid trace name.
Trace Range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands:

MEANTH, RMS, VARIANCE

### Example

80 END

10 OUTPUT 718;"IP;"

20 OUTPUT 718; "SNGLS;"

30 OUTPUT 718; "CF 300MHZ; SP 1MHZ; "

40 OUTPUT 718;"TS;"

50 OUTPUT 718; "MEAN TRA?;"

60 ENTER 718; Number

70 DISP "MEAN OF TRACE A IS "; Number

Initializes instrument.

Activates the single-sweep mode.

Sets measurement range.

Sweeps trace A.

Returns the mean value of trace A to the computer.


Assigns value to computer variable, Number.

Displays result on the computer screen.

# Description

The MEAN command returns the mean value of the given trace in measurement units.

# **Query Response**




QQ 1

### **MEANTH**

## Trace Mean Above Threshold

Returns the mean value of the given trace above the threshold, in measurement units.

#### **Syntax**



XMEANTH

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command	Any valid trace name.
Trace Range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands:

MEAN, RMS, TH, VARIANCE

## Example

10 OUTPUT 718;"IP;"

20 OUTPUT 718; "SNGLS; "

30 OUTPUT 718; "CF 300MHZ; SP 1GHZ; "

40 OUTPUT 718;"TH 45;"

50 OUTPUT 718:"TS:"

60 OUTPUT 718; "MEANTH TRA?;"

70 ENTER 718; Number

80 DISP "MEAN OF TRACE A ABOVE THE THRESHOLD IS ": Number

90 END

Initializes instrument.
Activates the single-sweep mode.
Sets measurement range.
Sets threshold level to 45

Sweeps trace A.

 $dB\mu V$ .

Returns the mean value of trace A above the threshold to the computer.

Assigns value to computer

variable, Number.

Displays result on the computer screen.

# Description

MEANTH returns the mean value of the trace above the threshold; MEAN returns the mean value of the trace, regardless of the threshold level. MEANTH returns a "0" if there is not a signal above the threshold.

Use TH (threshold) to set the threshold level.

## **Query Response**




QQ1

# MEASALLSIGS Measure All Signals

Finds all signals on the display, or all signals above a margin on the display, then makes an EMI measurement.

#### **Syntax**



xmallsg .

Equivalent Softkey:

AUTO-MEASURE

Related Commands:

AUTOAV, AUTOQPD, LIMIMARGAMP, LIMIMARGSTA, MEASSIG, MEASTIMEAVG, MEASTIMEPK, MEASTIMEQPD, REMEASSIG,

SIGDEL, SIGLIST

#### Example

OUTPUT 718; "MEASALLSIGS;"

## Description

The MEASALLSIGS command finds all signals on the display and makes an EMI measurement using specified detectors. Each signal is tuned to in sequence, the span is reduced in steps to zero span, and a maximum of three detectors are measured. The detectors used are chosen using AUTOAVG, and AUTOQPD commands. Measurement time is determined by MEASTIMEPK, MEASTIMEQPD, and MEASTIMEAVG commands. After each signal is measured it is added to the signal list.


When a limit margin is turned on, only those signals whose initial amplitude are above a margin are measured. If both margin 1 and margin 2 are on, the signal is compared to the lowest amplitude margin at that frequency.

xmeasav

# **MEASAVG** Measure Average

Makes a measurement with the peak and average detectors.

## **Syntax**



Related Commands:

MEASPEAK, MEASQPD, MEASSIG, MEASTIMEAVG, MEASURE

## Example

DIM A\$ [140] OUTPUT 718; "MEASAVG;" OUTPUT 718; "MEASRESULT?" ENTER 718; A\$


## Description

The MEASAVG command makes a measurement with the peak and average detectors, using the marker position as the measurement frequency. It spans down on the signal located at the marker, then in zero span, measures the average detector using the measurement time set by the MEASTIMEAVG command. The result of the measurement can be obtained using the MEASRESULT command.

# MEASFREQ Measure Frequency

Makes a measurement at the specified frequency.

#### **Syntax**



xmeafre

Related Commands:

AUTOAVG, AUTOQPD, MEASTIMEAVG, MEASTIMEPK, MEASTIMEQPD, MEASRESULT

# Example

DIM A\$ [140] OUTPUT 718;"MEASFREQ 300MZ;" OUTPUT 718;"MEASRESULT?" ENTER 718; A\$

# **Description**

The MEASFREQ command makes a measurement by tuning directly to the specified frequency in zero span. Then, it measures the detectors specified by AUTOQPD and AUTOAVG commands. Measurement time is determined by MEASTIMEPK, MEASTIMEQPD, AND MEASTIMEAVG commands. The result of the measurement can be obtained by using the MEASRESULT command.

# MEASPEAK Measure Peak

Makes a measurement using the peak detector.

## **Syntax**



xmeaspk .

Related Commands:

MEASAVG, MEASQPD, MEASSIG, MEASTIMEPK, MEASRESULT

## Example

DIM A\$ [140] OUTPUT 718; "MEASPEAK;" OUTPUT 718; "MEASRESULT?" ENTER 718; A\$

### Description

The MEASPEAK command makes a measurement using the peak detector with the marker position as the measurement frequency. First, it spans down on the signal located at the marker, then in zero span, measures the peak detector using the measurement time set by the MEASTIMEPK command. The result of the measurement can be obtained by using the MEASRESULT command.

# **MEASQPD**

# Measure Quasi-Peak Detector

Makes a measurement using the quasi-peak and peak detectors.

#### **Syntax**



xmeaqpd

Related Commands:

MEASAVG, MEASPEAK, MEASRESULT, MEASSIG, MEASTIMEQPD

#### Example

DIM A\$ [140] OUTPUT 718;"MEASQPD;" OUTPUT 718;"MEASRESULT?" ENTER 718; A\$


## Description

The MEASQPD command makes a measurement with the peak and quasi-peak detector using the marker position as the measurement frequency. First, it spans down on the signal located at the marker, then in zero span, measures the quasi-peak detector using the measurement time set by the MEASTIMEQPD command. The result of the measurement can be obtained by using the MEASRESULT command.

# **MEASRESULT** Measure Result

Sends the results of the last EMI measurement to the controller.

#### **Syntax**



xmeares

Related Commands:

MEASAVG, MEASPEAK, MEASQPD, MEASSIG, REMEASSIG

### Example


- 10 DIM Result\$ [140]
- 20 OUTPUT 718; "CF 300MZ;"
- 30 OUTPUT 718; "SP 10MZ;"
- 40 OUTPUT 718; "MKPK HIGH;"
- 50 OUTPUT 718; "MEASSIG;"
- 60 OUTPUT 718; "MEASRESULT;"
- 70 ENTER Result\$
- 80 PRINT Result\$

## Description

The MEASRESULT command sends the results of the last EMI measurement to the controller. The measurements are performed using MEASSIG, REMEASSIG, MEASPEAK, MEASQPD, or MEASAVG commands and their corresponding front-panel keys (if any). If no measurement has been performed, an ASCII NULL with EOI asserted is sent.

#### **Query Response**


## **MEASRESULT** Measure Result



# **MEASSIG** Measure Signal

Makes a measurement using specified detectors.

## **Syntax**



xmeasig .

Equivalent Softkey:

MEASURE AT MKR

Related Commands:

AUTOAVG, AUTOQPD, MEASALLSIGS, REMEASSIG, SIGDEL,

SIGLIST, SIGMARK, SIGUNMARK

#### Example

DIM A\$ [140] OUTPUT 718; "MEASSIG;" OUTPUT 718; "MEASRESULT?" ENTER 718; A\$

### Description

The MEASSIG command makes a measurement using specified detectors with the marker position as the measurement frequency. The detectors used are chosen from the AUTOAVG and AUTOQPD commands. The result of the measurement can be obtained by using the MEASRESULT command.


#### Note

When the selected bandwidth is a non-CISPR bandwidth the message, Non-CISPR bandwidth being used, press CONTINUE to resume or press USE CISPR to change, is displayed.

# MEASTIMEAVG Measure Time Average

Sets the average detector measurement time.

## **Syntax**



xmstmav

Item	Description/Default	Range
Number	Any real or integer.	20 mS to 65.535 S

Equivalent Softkey:

AV DWELL TIME

Preset State:

200 mS

**Related Commands:** 

AUTOAVG, AUTOQPD, MEASALLSIGS, MEASTIMEQPD,

MEASTIMEPK, REMEASSIG

## Example

OUTPUT 718; "MEASTIMEAVG 500MS;"

### **Description**

The MEASTIMEAVG command sets the measurement time when the average detector is measured in conjunction with MEASAVG, MEASSIG, MEASFREQ, MEASALLSIGS, and REMEASSIG commands.

### **Query Response**




QQ1

xmstmpk

# MEASTIMEPK Measure Time Peak

Sets the peak detector measurement time.

## **Syntax**



ItemDescription/DefaultRangeNumberAny real or integer.20 mS to 65.535 S

Equivalent Softkey:

PK DWELL TIME

Preset State:

200 mS

Related Commands:

AUTO AVG, AUTOQPD, MEASFREQ, MEASTIMEAVG,

**MEASTIMEQPD** 


#### Example

OUTPUT 718; "MEASTIMEPK 500MS;"

### Description

The MEASTIMEPK command sets the measurement time when the peak detector is measured in conjunction with MEASPEAK, MEASSIG, MEASFREQ, MEASALLSIGS, and REMEASSIG commands.

### **Query Response**




# **MEASTIMEQPD**

# Measure Time Quasi-Peak Detector

Sets the quasi-peak detector measurement time.

### **Syntax**



Item	Description/Default	Range
Number	Any real or integer.	20 mS to 65.535 S

Equivalent Softkey:

QP DWELL TIME

Preset State:

200 mS

Related Commands:

AUTOAVG, AUTOQPD, MEASALLSIGS, MEASFREQ, MEASTIMEAVG,

xmstqpd

MEASTIMEPK, REMEASSIG


## Example

10 OUTPUT 718; "MEASTIMEQPD 500MS;"

### **Description**

The MEASTIMEQPD command sets the measurement time when the quasi-peak detector is measured in conjunction with MEASQPD, MEASSIG, MEASFREQ, MEASALLSIGS, and REMEASSIG commands.


### **Query Response**



# MEASURE **Measure Mode**

Determines what kind of measurements the instrument makes.

## Syntax



XMEASURE

Equivalent Softkey:

SWP CPLG SR RECV

**Related Commands:** 

AUNITS, DL, INZ, LN, MKA, MKREAD, MKRL, RL, RLPOS,

ROFFSET, TH

Preset State:

MEASURE SA

#### Example

Activate the tracking-generator source output.

OUTPUT 718; "MEASURE SR;"

Sets instrument to stimulus-response mode.

OUTPUT 718; "SRCPWR 80DB:"

Makes the tracking generator source power the active

function.

#### Description

The MEASURE command determines what kind of measurements the instrument makes: signal analysis, stimulus response, or signal normalization.

"MEASURE SA;" activates receiver mode and auto couples the instrument functions. If AMB ON or AMBPL ON and RLPOS have been executed prior to MEASURE SA, MEASURE SA turns off the reference level position. When normalization is off, all amplitude units are specified in absolute values determined by:

- Amplitude units (AUNITS)
- Reference level (RL)
- Reference-level offset (ROFFSET)
- Input impedance (INZ)
- Logarithm scale (LG)
- Linear scale (LN)
- Amplitude Correction (AMPCOR)

"MEASURE SR;" activates stimulus-response measurements and uncouples the sweep time for faster sweep times. If AMB ON or AMBPL ON and RLPOS are executed, MEASURE SR activates the reference level position. When normalization is used, amplitude units are specified relative to the display level.

#### **MEASURE Measure Mode**

During this relative-amplitude mode, the following parameters are in dB:

- Trace data (TRA, TRB, TRC)
- Display line (DL)
- Threshold (TH)
- Marker amplitude (MKA)


"MEASURE NRM;" recouples the sweep time for accurate signal analysis measurements. If AMB ON or AMBPL ON and RLPOS are executed, MEASURE NRM activates the reference level position.

See "RLPOS" for more information about changing the reference level position.

When used as a predefined variable, MEASURE returns a value depending on the setting of the MEASURE parameter.

MEASURE Parameter	Value Returned
SA	0
SR	1
NRM	2

## **Query Response**




OME ASURE

# MEASWITHPP Measure With Preselector Peak

For an HP 8546A/HP 85462A only.

Peaks the preselector before making an EMI measurement.

## **Syntax**



хтирр

Preset State:

MEASWITHPP ON

Related Commands:

PP, MEASPEAK, MEASAVG, MEASQPD, MEASFREQ,

MEASALLSIGS, MEASSIG, REMEASSIG


#### Example

OUTPUT 718; "MEASWITHPP OFF;"

# **Description**

The MEASWITHPP command automatically peaks the preselector, for signals above 2.75 GHz, prior to making an EMI measurement. The EMI measurements affected are: Measure At Marker, Stepped Measurements, Signal List Remeasure, and Auto Measure. With MEASWITHPP ON, a Preselector Peak (PP) is done prior to measuring with any of the three detectors. With MEASWITHPP OFF, no preselector peak is done.

#### **Query Response**




002

## **MERGE**

# **Merge Two Traces**

Merges the source trace into the specified area of the destination trace.

# **Syntax**



Item	Description/Default	Range
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	riable A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
race element An element of trace A, trace B, trace C, or a user-defined trace.		
Number	Any valid integer number32,768 to +	

Related Commands:

All other trace math commands. See Table 4-4 for a list of trace math commands.

#### Example

OUTPUT 718; "MERGE TRC,1,200,TRA,200;"

Merges trace A into trace C. The trace A elements 200 through 399 are merged into trace C elements 1 through 200.

### Description

The MERGE command copies the trace data from the source trace, starting at the specified trace element, into the specified trace elements of the destination trace. MERGE differs from CONCAT because MERGE does not need the trace range of the source to be specified. If the source is not a trace, its value is copied to the destination trace. If the destination segment is longer than the specified source segment, the last element of the source trace is repeated to fill the destination.

#### MF

# Marker Frequency Output

Returns the frequency (or time) of the onscreen active marker.

## Syntax



Related Commands:

MA, MKA, MKCF, MKD, MKF, MKN, MKPK, MKREAD

#### Example

OUTPUT 718; "IP; SNGLS; CALSW INT;"

Initializes the instrument, activates single-sweep mode.

OUTPUT 718; "FA 280MHZ; FB 320MHZ; TS;"

OUTPUT 718; "MKN; MKPK HI;"

OUTPUT 718; "MF;"

ENTER 718; A

PRINT A

Initializes the instrument, activates single-sweep mode.

Sets up the measurement range.

Places marker on peak of calibrator signal.

Takes frequency of marker.

Returns frequency to the computer.

Prints the frequency on the computer screen.

#### Description

The MF command returns the frequency of the active marker to the controller if the marker is on screen. In delta marker mode, nonzero span, MF returns the frequency difference between the two markers. In zero span, "MF;" returns the marker time, or the delta marker time.

The data that is returned by MF depends on many command conditions including TDF, MKREAD, and MDS.

If the trace data format P is used with MF, the result is one real value in time units or frequency units, depending on the marker readout format. (See "MKREAD")

#### Example

```
OUTPUT 718; "TDF P; MKREAD FRQ: MF; "
                                         This returns a frequency value (in Hz) if not in
                                         zero-span.
OUTPUT 718; "TDF P; MKREAD FRQ: MF: "
                                         This returns a time value (in seconds) if in zero-
                                         span.
OUTPUT 718; "TDF P; MKREAD PER: MF: "
                                         This returns the time value (in seconds) of 1/(marker
                                         frequency).
OUTPUT 718; "TDF P; MKREAD SWT; MF; "
                                         This returns the marker time value (in seconds).
OUTPUT 718; "TDF P; MKREAD IST: MF: "
                                         This returns the frequency value (in Hz) for 1/(marker
                                         time).
OUTPUT 718; "TDF P; MKREAD FFT; MF;"
                                         This returns the frequency value (in Hz).
```

If the trace data format is used with trace data format A, the result depends on the setting of the MDS command.

## Example

OUTPUT 718; "TDF A; MDS B; MF;" Returns one byte representing the marker position. The byte can assume values 1 to 101.

OUTPUT 718; "TDF A; MDS W; MF;" Returns two bytes in a binary word format that has a value from 1 to 401.

If the trace data format is used with trace data format M, the result is the marker horizontal position value, from 1 to 401, in ASCII.

### Example

OUTPUT 718; "TDF M; MF;" Returns marker horizontal position value in ASCII.

### **Query Response**




QQ1

# MIN Minimum

Compares source 1 and 2, point by point, and stores the lesser of the two in the destination.

# **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	ed variable A command that acts as a variable. Refer to Table 4-1.	
Predefined function Function that returns a value. Refer to Table 4-1.		
Trace range A segment of trace A, trace B, trace C, or a user-defined trace.		
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable. TS when using trace data.

Related Commands: MINPOS, MXM, TS

#### Example

```
10 OUTPUT 718;"IP;"
                                             Initializes instrument.
20 OUTPUT 718; "SNGLS;"
                                             Activates the single-sweep mode.
30 OUTPUT 718; "VARDEF M_INIMUM,0;"
                                             Defines variable with an initial value of 0.
40 OUTPUT 718; "TS; MKPK HI;";
                                             Sweeps trace A and places the marker at the
                                             highest peak.
50 OUTPUT 718; "MIN M_INIMUM, MKA, 50;";
                                             Compares the marker amplitude to 50 dB\muV.
                                             Stores the lesser of the two in M_INIMUM.
60 OUTPUT 718; "M_INIMUM?;"
                                             Returns the result to the computer.
70 ENTER 718; Number
                                             Puts the result in the computer variable, Number.
80 DISP Number
                                            Displays the result.
90 END
```

#### Description

The MIN command compares source 1 and 2, point by point, and stores the lesser of the two in the destination. If one of the sources is a single value, it acts as a threshold, and all values equal to or less than the threshold pass to the destination. The values larger than the threshold are replaced by the threshold value in the destination.


When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

# **MINH**

# Minimum Hold

Updates trace C with the minimum level detected.

# **Syntax**



XM I NH

Equivalent Softkey:

MIN HOLD C

Related Commands:

BLANK, CLRW, MXMH, VAVG, VIEW

# Example

OUTPUT 718; "CLRW TRC; CONTS;" Clears trace C and begin taking data.

OUTPUT 718; "MINH TRC;"

Updates trace C with the minimum level detected.

## Description


The MINH command updates trace C with a new value.

## **MINPOS**

## **Minimum Position**

Returns the x-axis position of the minimum amplitude value.

#### **Syntax**



XMINPOS .

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands: MIN, MKMIN, PKPOS

### Example

10 OUTPUT 718;"IP;" Initializes instrument.

20 OUTPUT 718; "MINPOS TRA;" Finds the minimum value of trace A.

30 ENTER 718; Number Returns value to the computer.

40 DISP Number

Displays result. 50 END

#### **MINPOS Minimum Position**

# Description

The MINPOS command returns a value, which is the x-axis position (in display units) of the minimum amplitude value in trace A, trace B, trace C, or user-defined trace.

Using a trace range MINPOS returns a value relative to the first element of the trace range. For example, if a trace has a range of 150 to 300 elements, and the minimum value is element 200, MINPOS will return the value of 51.

#### **Query Response**




# MIRROR

# Mirror Image

Stores the mirror image of the trace.

# **Syntax**



XMIRROR .

Item Description/Default		Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

# Example

10	OUTPUT	718;"IP;"	Initializes instrument.
20	OUTPUT	718; "SNGLS; "	Activates the single-sweep mode.
30	OUTPUT	718;"TS;"	Takes sweep.
40	OUTPUT	718; "BLANK TRA;"	Blanks trace A from screen.
50	OUTPUT	718; "MIRROR TRB, TRA;"	Moves the mirror image of trace A into trace B
60	OUTPUT	718; "VIEW TRB;"	Displays the result.
70	END	•	

### **MIRROR Mirror Image**

## Description

The MIRROR command stores the mirror image (with respect to the frequency axis) of a source trace in a destination trace.

When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.


**XMKA** 

### **MKA**

## Marker Amplitude

Specifies the amplitude of the active marker in the current amplitude units.

#### Syntax



Description/Default Item Range Number Any real or integer number. Unit is current amplitude type. Amplitude range of instrument.

Equivalent Softkey:

MARKER AMPTD

Step Increment:

1 dB

Related Commands:

AUNITS, AUTO, MA, MKD, MKN, MKTYPE, TDF

#### Example

OUTPUT 718;"IP;"

Initializes the instrument.

OUTPUT 718; "MKTYPE AMP;"

Changes the marker type to amplitude.

OUTPUT 718;"MKA 50;"

Places the marker at 50 dB $\mu$ V.

### Description

The MKA command specifies the amplitude of the active marker in current units when the marker is the fixed or amplitude type (see "MKTYPE"). If both the delta marker and active marker are on the screen, "MKA?;" returns the amplitude difference between the two markers. Specifying the marker amplitude moves the marker to the point of the trace closest to the given marker amplitude.

If the trace data format P (TDF P), is used with MKA, the result is one real value in the current amplitude units (AUNITS can be used to change the current amplitude units).

#### MKA Marker Amplitude

### **Example**

OUTPUT 718; "TDF P; AUNITS DBM; MKA?;" This returns the amplitude value of the marker (amplitude unit is dBm).

If the trace data format is used with trace data format A, the result depends on the setting of the MDS command.

### Example

OUTPUT 718; "TDF A; MDS B; MKA?;" Returns one byte representing the marker vertical

position (-32,768 to 32,767) divided by 32 and then

 $ANDed\ with\ 255.$ 

OUTPUT 718; "TDF A; MDS W; MKA?;" Returns two bytes in a binary word format that has

a value from -32,768 to 32,767. The value represents


the binary trace amplitude value.

Using the trace data format I is equivalent to the TDF A format. If the trace data format is used with trace data format M, the result is returned in ASCII measurement units (-32,768 to 32,767).

### Example

OUTPUT 718; "TDF M; MKA?;" Returns one vertical position value in measurement units.

### **Query Response**




QQ 1

### **MKACT**

### **Activate Marker**

Specifies the active marker.

#### **Syntax**



XMKACT

Item	Description/Default	Range
Number	Any valid integer. Default value is 1.	1 to 4.

Equivalent Softkey:

SELECT 1 2 3 4

Related Commands:

MA, MKA, MKF

### Example

OUTPUT 718; "MKACT 4;" Marker 4 becomes marker 1.

### **Description**

The MKACT command specifies the active marker.

There can be four different markers, but only one marker can be active at any time.

When this command is used, the following results occur:


The marker number supplied by the command is made marker 1, the active marker.

If the marker number is not already on, the marker is turned on with preset type (position), and the marker is placed at center screen. The trace chosen is the first displayed trace found: trace A, trace B, or trace C.

Note

Using MKACT replaces marker 1 with the new marker function. The amplitude and frequency for the previous marker are not saved.

### **Query Response**




QQ1

### **MKACTV**

### Marker As the Active Function

Makes the current active marker the active function.

### **Syntax**



XMKACTV

Equivalent Softkey:

MARKER <number> ON OFF

Related Commands:

MKACT, MKN, MKTYPE

### Example

OUTPUT 718; "MKACT 2;"

Makes marker number 2 the active marker.

OUTPUT 718; "MKACTV;"

Makes marker number 2 the active function.

### Description

The MKACTV command makes the current active marker the active function. If you have more than one marker displayed on the display, you need to make the desired marker the active function before you can manipulate the marker.

To make the marker the active function:

- 1. Select the desired marker with the MKACT command (MKACT makes the specified marker the active marker).
- 2. Execute MKACTV to make the active marker the active function.


If there is no active marker, executing MKACTV makes marker 1 the active marker and the active function. MKACTV makes the marker an active function according to its marker type (see "MKTYPE" for more information about marker type).

### **MKBW**

### Marker Bandwidth

Returns the bandwidth at the specified power.

### **Syntax**



XMKBW

Item	Description/Default	Range
Number	Any valid negative integer.	0 to the amplitude of
		the noise floor.

## Example

OUTPUT 718;"IP;" Initializes instrument. OUTPUT 718; "CF 300MHZ; SP 100MHZ; SNGLS;" Changes the center frequency and span, then activates the single-sweep mode. OUTPUT 718; "TS; MKPK HI;" Updates the sweep, places marker on signal peak. OUTPUT 718; "MKBW -3;" Uses the MKBW function to find the signal bandwidth at -3 dB below the marker.

## Description

The MKBW command returns the bandwidth at the specified power level relative to an onscreen marker (if present) or the signal peak (if no onscreen marker is present). It also displays (in the message area) the bandwidth at the power level in dB below the current marker position or the current signal peak.

MKBW finds the bandwidth at the specified power level for one measurement sweep.

## **MKCF**

## Marker to Center Frequency

Sets the center frequency equal to the marker frequency.

### **Syntax**



XMKCF

Equivalent Softkey:

MARKER -> CF

**Related Commands:** 

CF, MKF

### Example

This example provides a quick way to center the desired frequency on the screen.

10 OUTPUT 718; "IP; SP 1MHZ; SNGLS; "

Initializes instrument, activates single-sweep

mode

20 INPUT "ENTER IN DESIRED STATION FREQUENCY, IN MHZ", Freq

30 OUTPUT 718; "CF "; Freq; "MHZ; "

Changes instrument center frequency.

40 OUTPUT 718; "TS; MKPK HI; MKCF; TS; "

Updates the trace, places marker at the signal peak and centers it on screen.

60 END

## Description

The MKCF command sets the center frequency equal to the marker frequency and moves the marker to the center of the screen.

This command is performed only if an active marker is present on screen.

## **MKCONT Marker Continue**

Resumes the sweep after execution of a MKSTOP command.

### **Syntax**



XMKCONT .

Related Commands:

**MKSTOP** 

## Example

```
10 OUTPUT 718;"IP;TS;"
                           Initializes instrument.
20 OUTPUT 718; "MKPK HI;" Creates an active marker.
30 OUTPUT 718;"MKSTOP;"
                           Stops sweep at marker.
40 OUTPUT 718; "MKCONT;"
                           Resumes sweep.
50 END
```

### Description


The MKCONT command resumes the sweep after execution of a MKSTOP command.

### **MKD**

## Marker Delta

Activates the delta marker.

### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz, default value is	Start frequency to
	value of the active marker.	stop frequency of
		instrument.

Equivalent Softkey:

MARKER A

Step Increment:

: by 1/10 of the frequency span

Related Commands:

AUTO, MA, MKCF, MKF, MKN, MKSP, MKSS, MKPK

### Example

10 OUTPUT 718;"IP;"

Initializes instrument.

20 OUTPUT 718; "MKMIN;"

Places a marker at the minimum amplitude of trace.

30 OUTPUT 718;"MKD;"

Activates marker delta.

40 OUTPUT 718; "MKPK HI;"

Places marker at highest amplitude of trace.

50 OUTPUT 718; "MKSP;"

Changes span to the values of the left and right markers.

60 END

### Description

The MKD command computes the frequency and amplitude difference of the active marker and a special marker, called the delta or differential marker. These values are displayed in the display readout.

The differential value of the frequency is equal to the active marker frequency minus the delta marker frequency. The differential value of the amplitude is equal to the active marker amplitude minus the delta marker amplitude.

If an active marker is not on the screen, MKD positions an active marker at center screen. If a delta marker is not on the screen, MKD places one at the specified frequency, or at the current active marker. If the active marker is in amplitude mode, the delta marker is placed at the same amplitude as the active marker (or a specified value).

To read the amplitude, use MKA?. To read the frequency, use MKF? The results are displayed on the screen.


In linear mode, MKD computes the ratio of the amplitudes of the active and delta markers rather than the difference. This results in similar treatment for logarithmic and linear data because the delta of the difference of two logarithmically generated numbers results in the logarithmically generated value of the ratio of the two numbers. (You should not change amplitude units when making a marker delta measurement, however.)

### **MKF**

## **Marker Frequency**

Specifies the frequency value of the active marker.

### **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number. Default unit is Hz.
 Start frequency to stop frequency of instrument.

XMKF

Related Commands:

AUTO, MKA, MKD, MKCF, MKPK

### Example

OUTPUT 718; "MKF 600MHZ;" Places an active marker at 600 MHz.

### Description

The MKF command specifies the frequency value of the active marker. In nonzero frequency spans, MKF returns the active marker frequency as a real number when MKF is queried. In zero span, "MKF?;" returns the time value.

The data that is returned by MKF depends on many command conditions, including TDF, MKREAD, and MDS.

MKF results with TDF set to P: If the trace data format P is used with MKF, the result is one real value in time units or frequency units, depending on MKREAD.

### Example

OUTPUT	718;"TDF	P;MKREAD	FRQ;MKF?;"	This returns a frequency value (in Hz) if not in zero-span.
OUTPUT	718;"TDF	P;MKREAD	FRQ;MKF?;"	This returns a time value (in seconds) if in zero- span.
OUTPUT	718;"TDF	P;MKREAD	•	This returns the time value (in seconds) of $1/(marker frequency)$ .
OUTPUT	718;"TDF	P; MKREAD	SWT; MKF?;"	This returns the marker time value (in seconds).
OUTPUT	718;"TDF	P;MKREAD	<pre>IST;MKF?;"</pre>	This returns the frequency value (in Hz) for 1/(marker time).
OUTPUT	718;"TDF	P; MKREAD	FFT; MKF?;"	This returns the frequency value (in Hz).

MKF results with TDF set to A or I: If the trace data format is used with trace data format A, the result depends on the setting of the MDS command.

### Example

```
OUTPUT 718; "TDF A; MDS B; MKF?;" Returns one byte representing the marker position.

OUTPUT 718; "TDF A; MDS W; MKF?;" Returns two bytes in a binary word format that has a value from 1 to 401.
```


Using the trace data format I is equivalent to the TDF A format.

MKF results with TDF set to M: If the trace data format is used with trace data format M, the result is the marker horizontal position value, from 1 to 401, in ASCII.

### Example

OUTPUT 718; "TDF M; MKF?;" Returns marker horizontal position value in ASCII.

### **Query Response**




## **MKFC**

## **Marker Counter**

Turns on or off the marker frequency counter.

### **Syntax**



XMKFC

Equivalent Softkey:

MK COUNT ON OFF

Related Commands:

MKFCR, MKN.

## Example

OUTPUT 718; "MKFC ON;"  $\ \ \textit{Turns on the marker counter.}$ 

## **Description**


The MKFC command turns on or off the marker frequency counter.

## **MKFCR**

## **Marker Counter Resolution**

Sets the resolution of the marker frequency counter.

### **Syntax**



XMKFCR .

Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	0 Hz to 100 kHz.

Equivalent Softkey:

CNT RES AUTO MAN

Preset State:

Marker counter resolution is set to AUTO. The calculated value for the marker counter resolution is returned if the MKFCR is queried.

Related Commands:

AUTO, MKFC

### Example

OUTPUT 718; "MKFCR 10KHZ;"

Sets the marker counter resolution to 10 kHz.

OUTPUT 718; "MKFCR?;"

Queries the marker counter resolution.

ENTER 718;A

Gets the query response.

DISP A


Displays the marker counter resolution.

### **MKFCR Marker Counter Resolution**

## Description

The MKFCR command sets the resolution of the marker frequency counter. Executing either "MKFCR 0;" or "MKFCR AUTO;" auto-couples the marker counter resolution to the frequency span.

## **Query Response**




# **MKMIN**

## Marker Minimum

Moves the active marker to the minimum value detected.

### **Syntax**



XMKMIN

Equivalent Softkey:

MARKER -> MINIMUM

Related Commands:

MKPK, SMOOTH, TH, VAVG

### Example

10 OUTPUT 718; "IP; SNGLS; "

Initializes instrument, activates single-

20 INPUT "ENTER IN THE START FREQUENCY,

IN MHZ",Start\_freq 30 INPUT "ENTER IN THE STOP FREQUENCY,

IN MHZ", Stop\_freq

40 OUTPUT 718; "FA "; Start\_freq; "MHZ"

50 OUTPUT 718; "FB "; Stop\_freq; "MHZ" 60 OUTPUT 718; "TS; MKPK HI; MKD; MKMIN; MKF?;" Sets the start frequency. Sets the stop frequency.

Updates trace, finds trace peak, turns on marker delta function, finds the minimum value of trace, and return the fre-

quency delta.

sweep mode.

70 ENTER 718; Delta\_freq

80 PRINT "DIFFERENCE IN FREQUENCY IS ", Delta\_freq,"HZ"

90 END

Gets the result from instrument.

### Description


The MKMIN command moves the active marker to the minimum value detected.

### **MKN**

### **Marker Normal**

Activates and moves the marker to the specified frequency.

### **Syntax**



Item	Description/Default	Range
1	Any real or integer number. Default unit is Hz. Default value is the center frequency of the instrument.	Start frequency to stop frequency of instrument.

Equivalent Softkey:

MARKER NORMAL

Step Increment:

by 1/10 of the frequency span when RCVRMRKR is off

Related Commands:

AUTO, DEMOD, MKA, MKD, MKF, MKPK, RCVRMRKR

### Example

10 INPUT "ENTER IN THE START FREQUENCY, IN MHZ", Start\_freq

20 INPUT "ENTER IN THE STOP FREQUENCY, IN MHZ", Stop\_freq

30 OUTPUT 718; "IP; FA "; Start\_freq; "MHZ"

40 OUTPUT 718; "FB "; Stop\_freq; "MHZ"

50 OUTPUT 718; "MKN EK;"

60 PRINT "PLACE MARKER ON THE DESIRED SIGNAL"

70 PRINT "PRESS HOLD THEN PRESS CONTINUE"

80 PAUSE

Initializes instrument and changes the start frequency. Changes the stop frequency. Enables the front-panel knob.

XMKN

#### **MKN Marker Normal**

90 OUTPUT 718; "MKN?;"

100 ENTER 718; Mkr


110 PRINT "MARKER FREQUENCY IS ",Mkr,"Hz" 120 END

Gets the frequency of the marker.
Puts the frequency value into the computer variable, Mkr.
Prints the result.

## Description

The MKN command activates and moves the marker to the specified frequency. In nonzero span, "MKN?;" returns the frequency value. In zero span, "MKN?;" returns the time value.

### **Query Response**




### **MKNOISE**

### Marker Noise

Displays the average noise level at the marker.

#### **Syntax**



XMKNO1 SE

Equivalent Softkey:

MK NOISE ON OFF

Related Commands:

MKA, MKF, MKMIN, MKN

### Example

OUTPUT 718; "IP; CF 300MHZ; SNGLS; "

OUTPUT 718; "SP 10MHZ; DET SMP; TS; "

OUTPUT 718; "MKPK HI; MKA?;"

ENTER 718; Amp\_one

OUTPUT 718; "MKD UP; UP; MKNOISE ON; MKA?;"

ENTER 718; Amp\_two

OUTPUT 718; "MKNOISE OFF;"
DISP Amp\_two
C\_to\_n=Amp\_one - Amp\_two
PRINT "CARRIER TO NOISE RATIO IN 1 HZ
BANDWIDTH IS "; C\_to\_n
PRINT " DB"

Initializes instrument, changes center frequency, activates single-sweep mode.

Changes span, activates sample detector, updates trace.

Places marker on highest point of trace, queries marker amplitude.

Puts the instrument response in the computer variable, Amp\_one.

Moves marker and turns on the marker noise function.

Puts the instrument response in the computer variable, Amp\_two.

Turns off the marker noise function.

Displays the result.

Calculates the carrier to noise ratio.

Outputs result.

### Description

The MKNOISE command displays the average noise level at the marker. The marker value is normalized to a 1-Hz bandwidth. Use "MKA?;" to read the noise marker value.

The noise marker averages 32 trace data values about the location of the marker on the frequency or time scale. The 32 values averaged, except for the first 15 or last 14 values in the trace, commence with the 16th point to the left of the marker, and end with the 15th point to the right of the marker. Note that the data values averaged are not exactly symmetrical with respect to marker position. At the trace end points, the instrument uses the nearest 32 data values. So while the marker may be moved to trace position 1 to 15, the actual amplitude value returned will be the same value for any marker position from 1 to 15. A similar situation applies for markers at the end of the trace.

A nominal correction for equivalent noise bandwidths is made by the firmware based on a nominal 3 dB resolution bandwidth. The firmware assumes the noise bandwidth is 1.12 times the resolution bandwidth. This means the shape of the resolution bandwidth filters cause the noise power to be overstated by 1.12 times. The detection mode also affects the measurement. If in log mode, the log detector understates the noise response. To compensate, 2.5 dB is added to the measurement. If the detector is in linear mode, the firmware uses 1.05 dB as a correction value.

In log detector mode, the final reported value will then be, with the result reported in dBm in a 1-Hz bandwidth:

(Averaged value over 32 values)  $-10 \times (\log[1.12 \times \text{Resolution bandwidth}]) + 2.5 \text{ dB}$ 

In linear detector mode (dBm) units, the final reported value will then be, with the result reported in dBm in a 1-Hz bandwidth:

(Averaged value over 32 values)  $-10 \times (\log[1.12 \times \text{Resolution bandwidth}]) + 1.05 \text{ dB}$ 


In linear detector mode with the normal display of voltage units, the noise marker voltage value will be related to the present marker voltage by this relation.

 $(V_{noise\_marker})^2 = (V_{average})^2 \times 1.12 \times Resolution bandwidth \times 0.7824$ 

 $V_noise_marker = V_average/(1.12 \times Resolution bandwidth \times 0.7824)^{0.5}$ 

 $V_noise_marker = V_average \times 1.06633/(Resolution bandwidth)^{0.5}$ 

#### **Query Response**




002

## **MKOFF** Marker Off

Turns off either the active marker or all the markers.

### Syntax



XMKOFF

Equivalent Softkey:

MARKER ALL OFF

Related Commands:

MKA, MKACT, MKACTV, MKCF, MKD, MKF, MKN, MKPK

### Example

OUTPUT 718; "MKOFF ALL;" Turns off all the onscreen markers.

## **Description**


The MKOFF command turns off either the active marker or all the markers. If the ALL parameter is omitted, only the active marker is turned off.

## **MKP**

## **Marker Position**

Places the active marker at the given x-coordinate.

## **Syntax**



Item Description/Default Range Number Any valid integer. -401 to 401. User-defined variable A variable defined by VARDEF command. Any valid variable name. Predefined variable A command that acts as a variable. Refer to Table 4-1. Predefined function Function that returns a value. Refer to Table 4-1. Trace element An element of trace A, trace B, trace C, or a user-defined trace.

Prerequisite Commands: VARDEF when using a user-defined variable.

**Related Commands:** MKA, MKCF, MKD, MKMIN

### Example

OUTPUT 718;"IP;" Initializes instrument.

OUTPUT 718; "MKP 100;" Moves the active marker to a element 100 of trace A.

#### **MKP Marker Position**

### Description

The MKP command places the active marker at the given x-coordinate. If no marker is active, the marker is turned on with preset type (position) and marker is placed at the given screen position. The marker is placed on the first displayed trace that is found (in order): trace A, trace B, or trace C.

If the marker delta mode is active, the value of the marker position is relative to the fixed marker, and therefore MKP can return a negative position.

Note that MKP and MKCF commands perform different functions. MKCF sets the center frequency equal to the marker frequency and moves the marker to the center of the screen. MKP places the marker to the position of the element specified.

### **Query Response**




001

## **MKPAUSE Marker Pause**

Pauses the sweep at the active marker.

## **Syntax**



XMKPAUSE .

Item	Description/Default	Range
	Any real or integer number.	2 ms to 100 s.

Equivalent Softkey:

MK PAUSE ON OFF

Step Decrement:

Time value divided by 2

Step Increment:

Time value multiplied by 2

Related Commands:

DEMOD, MKA, MKF, MKFC, MKN, MKOFF, ST

## Example

OUTPUT 718; "MKPAUSE 10SC;" Changes the marker pause time to 10 seconds.

#### **MKPAUSE Marker Pause**


### Description

The MKPAUSE command pauses the sweep at the active marker for the duration of the delay period. To turn MKPAUSE off, turn off markers or send "MKPAUSE 0;".

The MKPAUSE command requires a sweep time of 50 ms or longer. The sweep time is changed to 50 ms if MKPAUSE is used with a sweep time that is less than 50 ms.

After MKPAUSE is executed, the sweep must be completed before another command will be executed.

### **Query Response**




# MKPK

### Marker Peak

Positions the active marker on a signal peak.

### **Syntax**



XMKPK

Equivalent Keys:

NEXT PEAK, NEXT PK RIGHT, NEXT PK LEFT, and (PEAK SEARCH)

Related Commands:

MKCF, MKF, MKOFF, MKPX, TH

### Example

10 OUTPUT 718; "IP;" Initializes the instrument.

20 OUTPUT 718; "SNGLS; TS; MKPK HI;" Places active marker on highest peak.

30 OUTPUT 718; "MKA?;" Returns amplitude value of marker to the computer.

40 ENTER 718; A Puts the instrument response in the computer vari-

able, A.

50 DISP A

60 END

Displays amplitude value.

### **Description**

The MKPK command positions the active marker on a signal peak. Executing MKPK HI, or simply MKPK, positions the active marker at the highest signal detected. If an active marker is on the screen, the MKPK parameters move the marker as follows:

**HI** (highest) moves the active marker to the highest peak.

NH (next highest) moves the active marker to the next signal peak of higher amplitude.

NR (next right) moves the active marker to the next signal right of the current marker.

**NL** (next left) moves the active marker to the next signal left of the current markerleft of the current marker. .

Note


This function is for use with the frequency markers only.

### **MKPX**

### **Marker Peak Excursion**

Specifies the minimum signal excursion.

### **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number. Default unit is dB.
 0 to 100 dB.

Equivalent Softkey:

PEAK EXCURSN

Preset State:

6 dB

Step Increment:

by 1 dB

Related Commands:

MKPK, PEAKS

### Example

10 OUTPUT 718; "IP; CF 300MHZ; SP 1GHZ;"

20 INPUT "ENTER IN PEAK EXCURSION, IN DB ", Excursion

30 OUTPUT 718; "MKPX "; Excursion; "DB;"

40 OUTPUT 718;"TS; MKPK HI; MKPK NH;"

50 OUTPUT 718;"MKF?;"

60 ENTER 718; Freq

70 IF Freq <> 0 THEN

80 PRINT "PEAK FOUND"

90 ELSE

100 PRINT "NO PEAKS FOUND"

110 END IF

120 END

Initializes instrument, changes start and stop frequencies.

XMKPX

Changes peak excursion level. Searches for highest peaks

of trace.

Finds frequency difference

between peaks.

Puts the instrument response in the computer variable,

Freq.

Outputs results if marker

amplitude was not 0.

Prints "NO PEAKS FOUND"

if Freq = 0.

### Description


The MKPX command sets the minimum amplitude variation of signals that the marker can identify as a peak. If a value of 10 dB is selected, the marker moves only to peaks that rise and fall more than 10 dB above the threshold line (or the noise floor of the display). Pressing PRESET or turning on power resets the excursion to 6 dB, and the threshold to 70 dB below the reference level.

#### Note

When a peak has a lump on its skirt that is the peak-excursion value above the threshold, the lump is considered a peak only if it has a peak excursion drop on both sides. Two peaks that are so close that only a valley divides them are not differentiated if the valley is not the peak-excursion value deep.

When the peak excursion value is less than 6 dB, the marker-peaking functions may not recognize signals less than 6 dB above the noise floor. To correct this, when measuring signals near the noise floor, the excursion value can be reduced even further. To prevent the marker from identifying noise as signals, reduce the noise floor variance to a value less than the peak-excursion value by reducing the average video bandwidth or by using video averaging.

### Query Response




QQ1

### **MKREAD**

### **Marker Readout**

Selects the type of active trace information displayed by the instrument's marker readout.

### **Syntax**



XMKREAD .

Equivalent Softkey:

MK READ F T I P provides the marker readouts in the frequency,

sweep time, inverse sweep time, and period. The fast Fourier transform readout is not available with the softkey, however.

Related Commands:

FFT, MKF, MKTYPE

### Example

OUTPUT 718; "MKREAD FFT;"

## Description

The MKREAD command can select the following types of active trace information:

FRQ: frequency

SWT: sweep time

**IST**: inverse sweep time

PER: period


FFT: fast Fourier transform readout

The results of the data depend on the MKREAD parameter, the frequency span, and if the marker delta function is used.

### MKREAD Marker Readout

MKREAD Type	Non-Zero Span	Non-Zero Span Delta	Zero Span	Zero Span Delta
FRQ	Reads frequency	Reads delta frequency	Reads time	Reads delta time
SWT	Reads time since the start of sweep	Reads delta time between end points	Waveform measurements of detected modulation	Waveform measurements of detected modulation
IST	N/A	N/A	N/A	Computes frequency corresponding to delta of markers. Performs $1/(T_1-T_2)$
PER	Period of frequency	(Pulse measurement) delta time	N/A	N/A
FFT	N/A	N/A	Reads frequency corresponding the to FFT bucket	Reads delta frequency corresponding to delta FFT bucket

## **Query Response**



OMKREAD .

### MKRL

### Marker to Reference Level

Sets the reference level to the amplitude value of the active marker.

### **Syntax**



XMKRL

Equivalent Softkey:

MARKER -> REF LVL

Related Commands:

MKOFF, RL

### Example

10 OUTPUT 718; "IP; SNGLS; CF 300MHZ; SP 20MHZ; "

20 OUTPUT 718; "TS; MKPK HI; MKRL; TS; "

30 OUTPUT 718; "RL?;"

40 ENTER 718 USING "K"; Ref\_level

50 OUTPUT 718; "AUNITS?;"

60 ENTER 718; Aunits\$

50 PRINT "REFERENCE LEVEL IS", Ref\_level, Aunits\$

60 END

Initializes instrument, changes center frequency and span.

Places a marker on trace peak, sets the reference level to the amplitude of the active marker, updates the sweep.

Gets the reference level.

Puts the instrument response in the computer variable, Ref\_level. Gets the current amplitude units.

### **Description**

The MKRL command sets the reference level to the amplitude value of the active marker.

### **MKSP**

## Marker to Span

Sets the start and stop frequencies to the values of the delta markers.

### **Syntax**



XMKSP

Equivalent Softkey:

MKR A SPAN

Related Commands:

MKD, SP

### Example

10 OUTPUT 718;"IP;" Initializes instrument. 20 OUTPUT 718; "MKMIN;" Places a marker at the minimum amplitude of trace. 30 OUTPUT 718; "MKD;" Activates marker delta. 40 OUTPUT 718; "MKPK HI;" Places marker at highest amplitude of trace. 50 OUTPUT 718; "MKSP;" Changes span to the values of the left and right markers. 60 END

### Description

The MKSP command sets the start and stop frequencies to the values of the delta markers. The left marker specifies start frequency, and the right marker specifies stop frequency. If MKD is off, no operation is performed.

### **MKSS**

## Marker to Step Size

Sets the center-frequency step-size to the marker frequency.

### **Syntax**



XMKSS

Equivalent

MARKER -> CF STEP

Softkey:

CF, MKA, MKCF, MKD, MKF, SS

Related Commands:

### Example

This example measures a harmonic of the CAL OUT signal.

10 DISP "CONNECT THE CAL OUT TO THE INPUT"

20 OUTPUT 718; "IP; SNGLS; CF 300MHZ; SP 20MHZ; TS; "

30 OUTPUT 718; "MKPK HI; MKSS; MKD; CF UP; TS; MKPK HI; "

40 OUTPUT 718; "MKA?;"

50 ENTER 718; Delta\_amp

60 OUTPUT 718; "MKF?;"

70 ENTER 718; Delta\_freq

80 PRINT "DIFFERENCE IN AMPLITUDE IS ",Delta\_amp,"dB"
90 PRINT "DIFFERENCE IN FREQUENCY IS ",Delta\_freq,"Hz"
100 END

Initializes instrument, activates single-sweep mode, changes center frequency and span, updates trace. Places the marker on the highest point of the trace, changes the step size to the marker frequency, activates marker delta, increase center frequency, update trace, places the marker at highest point of the trace.

Gets the amplitude of the marker.

marker.

Puts the instrument response in the computer variable, Delta\_Amp.
Gets the frequency of the marker.

Puts the instrument response in the computer variable, Delta\_freq.

## Description

The MKSS command sets the center-frequency step-size equal to the marker frequency. If in the delta mode, the step size is set to the delta frequency (absolute value).

## **MKSTOP Marker Stop**

Stops the sweep at the active marker.

### **Syntax**



XMKSTOP

Equivalent Softkey:

MARKER -> STOP

Related Commands:

MKCONT

## Example

10 OUTPUT 718; "IP; TS; " Initializes instrument. 20 OUTPUT 718; "MKPK HI;" Creates an active marker. 30 OUTPUT 718; "MKSTOP;" Stops sweep at marker. 40 OUTPUT 718; "MKCONT;" Resumes sweep. 50 END


## Description

The MKSTOP command stops the sweep at the active marker.

## MKTRACE Marker Trace

Moves the active marker to a corresponding position.

## **Syntax**



XMKTRACE .

Equivalent Softkey:

MK TRACE AUTO ABC

## Example


10 OUTPUT 718;"IP;"	Initializes instrument.
20 OUTPUT 718;"MKMIN;"	Finds the lowest amplitude of trace.
30 OUTPUT 718;"MKTRACE TRB;"	Moves marker to corresponding position on trace B
40 OUTPUT 718; "BLANK TRA; CLRW TRB;"	Blanks trace A and displays trace B.

## Description

50 END

The MKTRACE command moves the active marker to a corresponding position in trace A, trace B, or trace C.

## **Query Response**




QMKTRACE.

## **MKTRACK** Marker Track

Moves the signal at the active marker, to the center of the instrument display.

### **Syntax**



XMKTRACK.

Equivalent Softkey:

MK TRACK ON OFF

Related Commands:

MKA, MKCF, MKF

### Example

OUTPUT 718;"IP;" Initializes instrument. OUTPUT 718; "CF 300MHZ; TS; " Changes the center frequency. OUTPUT 718; "MKTRACK ON;" Activates the marker track.

OUTPUT 718; "SP 10MHZ; TS; "

Changes the span.


OUTPUT 718; "MKTRACK OFF;"

Turns off the marker track.

### Description

The MKTRACK command moves the signal at the active marker, to the center of the display and keeps the signal peak at center screen. To keep a drifting signal at center screen, place the active marker on the desired signal before turning on MKTRACK.


## **Query Response**



# MKTYPE Marker Type

Changes the type of the current active marker.

#### **Syntax**



XMKTYPE

Preset State:

MKTYPE PSN

Related Commands:

MKA, MKBW

#### Example

OUTPUT 718; "MKTYPE AMP; MKA 50;"

Positions the marker at 50  $dB\mu V$ 

#### **Description**

The MKTYPE command changes the type of the current active marker. The marker types are as follows:

**PSN** allows markers to be positioned according to the horizontal position on the display. The marker type is set to PSN after an instrument preset.


**AMP** allows markers to be positioned according to amplitude, as shown in the example. If two or more points on the trace are at the same amplitude, the marker is moved to the closest point on the trace with the correct amplitude. If no point on the trace is at the specified amplitude, the marker is placed at the specified amplitude and not on the trace.

**FIXED** allows a marker to be placed at any fixed point on the instrument screen. The position of the marker cannot be changed unless another marker type is used.

**DELTA** allows the marker frequency to be positioned with respect to another marker.

Use "MKTYPE PSN" to return from using the AMP, FIXED, or DELTA types.

### **Query Response**




OMKTYPE .

#### ML

### **Mixer Level**

Specifies the maximum signal level that is applied to the input mixer.

#### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is dBm.	-10 to -60 dBm.

Equivalent Softkey:

MAX MXR LEVEL

Preset State:

-10 dBm

Step Increment:

by 10 dBm

Related Commands:

AT, ROFFSET

### Example

OUTPUT 718;"ML -40DM;"

As the reference level is changed, the coupled input attenuator is changed automatically. This limits the maximum signal at the mixer input to  $-40~\mathrm{dBm}$  for signals less than or equal to the reference level.


XML

### **Description**

The ML command specifies the maximum signal level that is applied to the input mixer for a signal that is equal to or below the reference level.

The effective mixer level is equal to the reference level minus the input attenuator setting. When ML is activated, the effective mixer level can be set from -10 dBm to -60 dBm in 10 dB steps.

### **Query Response**




QQ T

# MOD Modulo

Stores the remainder from the division of source 1 by source 2 in the destination.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable. TS when using trace data.

Related Commands: DIV

#### Example

```
10 OUTPUT 718; "VARDEF S_ONE, 15; "
                                                    Places 15 into S_ONE.
20 OUTPUT 718; "VARDEF S_TW0,4;"
                                                    Places 4 into S_TWO.
30 OUTPUT 718; "VARDEF D_EST,0;"
                                                    D_EST holds the result.
40 OUTPUT 718; "MOD D_EST,S_ONE,S_TWO;"
50 OUTPUT 718;"D_EST?;"
                                                    Moves the result to the computer.
60 ENTER 718: Number
                                                    Puts the instrument response in the
                                                    computer variable, Number.
70 DISP Number
                                                    Displays a 3.
80 END
```

#### Description

The MOD command stores the remainder from the division of source 1 by source 2 in the destination.

If source 1 is a negative number and source 2 is a positive number, the MOD function returns a negative remainder. If both sources are negative, the MOD function returns a negative remainder.


Integer values are used when a trace is the destination or one of the sources. If trace data is used as the source and the destination, the MOD function is done with 32-bit arithmetic using 16-bit integer data. If a user-defined variable or predefined variable is used as the source or destination, the MOD function is done in floating point format. If a real number is used as a source, but the destination is an integer value, the result is truncated. If a trace is used as a source, be sure the trace contains a complete sweep of measurement information before executing MOD.

When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

# MOV Move

Copies the source values into the destination.

### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

**VOMX** 

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a user-defined variable.

#### Example

10 CLEAR 718
20 OUTPUT 718;"IP;"
30 OUTPUT 718;"FA 100MHZ;FB 1100MHZ;"
40 OUTPUT 718;"TS;MKPK HI;"
50 OUTPUT 718;"DL ON;"
60 OUTPUT 718;"MOV DL,MKA;"

Clears the HP-IB bus and instrument.
Initializes instrument.
Sets up the measurement range.
Places a marker at the highest peak.
Turns on display line.

Sets the display-line value equal to the marker amplitude by storing the value of the marker amplitude variable, MKA, in the display line variable, DL.

variable,

70 END


#### Description

The MOV command copies the source values into the destination. When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

# MPY Multiply

Multiplies the sources.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a user-defined variable. TS when using trace data.

#### Example

OUTPUT 718; "MPY CF, CF, 2;" Doubles the center frequency.

#### Description

The MPY command multiplies the sources, point by point, and places the results in the destination.

Traces, user-defined traces, and trace ranges are multiplied as 16-bit integers. Negative numbers are represented in two's complement format. Single variables and numbers are treated as floating point numbers and must be within the real number range as defined in Table 4-1.


When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

#### **MSI**

### **Mass Storage Is**

Specifies the current mass storage device as the internal memory or a disk drive.

### **Syntax**



xmsi

Related Commands:

CAT

Preset State:

DISK

#### Example

OUTPUT 718; "MSI DISK;" Selects the disk drive as the current mass storage device.


#### **Description**

The MSI command specifies the current mass storage device as the internal memory or a disk drive.

If you specify INT, the current mass storage device is set to internal memory.

If MSI is used as a predefined variable, it returns a "0" if the mass storage device is the internal memory and a "2" if it is the disk drive.

#### **Query Response**




OMSI

## **MXM** Maximum

Compares source 1 and source 2.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF when using a

user-defined variable. TS when using trace data.

Related Commands: MIN, PKPOS, TS

#### **MXM Maximum**

#### Example

10 OUTPUT 718;"IP;" Initializes instrument. 20 OUTPUT 718; "CF 300MHZ; SNGLS;" Changes the center frequency and activate singlesweep mode. 30 OUTPUT 718; "TS; VIEW TRA;" Updates trace. Displays and stores the results of  $trace\ A.$ 40 OUTPUT 718; "MXM TRB, TRA, 4000;" Moves elements of trace A that exceed 4000 trace data points (above center screen) to trace B. 50 OUTPUT 718; "BLANK TRA; VIEW TRB;" Displays result. 60 END

### **Description**

The MXM command compares source 1 and source 2, point by point, sending the greater value of each comparison to the destination.

If one of the sources is a single value, it acts as a threshold; all values equal to or greater than the threshold pass to the destination.


When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

### **MXMH**

### Maximum Hold

Updates each trace element with the maximum level detected.

#### **Syntax**



**HMXMX** 

Equivalent Softkeys:

MAX HOLD A and MAX HOLD B

Related Commands:

BLANK, CLRW, MINH, VAVG, VIEW

#### Example

OUTPUT 718;"MXMH TRA;"

### Description


MXMH updates the specified trace (either trace A or trace B) with a new value from a detector only if the new value is larger than the previous trace data value.

### NRL

# Normalized Reference Level

Sets the normalized reference level.

# Syntax



XNRL

Item	Description/Default	Range
Number	Any real or integer number. Default unit is $dB\mu V$ .	

Preset State:

0 dB

Related Commands:

MEASURE, RL, RLPOS

### Example

10	OUTPUT 718;"IP;"	Initializes instrument.
20	OUTPUT 718;"SRCPWR 80DB;"	Sets tracking generator output
30	PRINT "CONNECT TRACKING GENERATOR OUTPUT TO INPUT"	
40	PRINT "THEN PRESS CONTINUE"	
50	PAUSE	
60	OUTPUT 718;"MEASURE SR;"	Sets the measurement mode
		to stimulus-response.
70	OUTPUT 718;"CLRW TRB;TS;"	Takes a measurement sweep
		of the flatness of the system.
80	OUTPUT 718; "BLANK TRB;"	
90	PRINT "CONNECT DEVICE TO INSTRUMENT"	
10	O PRINT "THEN PRESS CONTINUE"	
11	O PAUSE	
120	O OUTPUT 718;"CLRW TRA;TS;"	Takes a measurement sweep
		of the device under test in
		the system.
13	O OUTPUT 718;"AMBPL ON;"	Normalizes the response.
14	O OUTPUT 718;"RLPOS 4;"	Changes the location of the
		reference level to the fourth
		graticule from the bottom.
150	O OUTPUT 718;"SUB NRL,RL,40;"	Offsets trace A so it is on-
		screen. (Subtract 40 dB
	_ ====	from the reference level.)
160	O END	

#### Description

The NRL command sets the normalized reference level. This function is a trace-offset function that enables you to offset the displayed trace without introducing hardware-switching errors into the stimulus-response measurement. The input attenuator and IF step gains are not affected when using NRL.

In absolute power mode  $(dB\mu V)$ , reference level affects the gain and RF attenuation settings of the instrument, which affects the measurement or dynamic range. In normalized mode (relative power or dB-measurement mode), NRL offsets the trace data onscreen and does not affect the instrument gain or attenuation settings. This allows the displayed normalized trace to be moved without decreasing the measurement accuracy due to changes in gain or RF attenuation. If the measurement range must be changed to bring trace data onscreen, then the range level should be adjusted. Adjusting the range-level normalized mode has the same effect on the instrument settings as does reference level in absolute power mode (normalize off).

#### **Query Response**




### OA

### **Output Active Function Value**

Sends the value of the active function to the controller.

#### **Syntax**




### **Example**

- 10 OUTPUT 718; "ST 3SC; OA;" Changes the sweep time, activates the OA command.
- 20 ENTER 718; Number Gets the response from the instrument.
- 30 DISP Number Displays "3" on the computer screen.
- 40 END

#### Description

The OA command sends the value of the active function to the controller.

### **Query Response**




#### OL

### **Output Learn String**

Transmits information to the controller.

#### **Syntax**



Related Commands:

RCLS, SAVES

#### Example

10 DIM Learn\_String\$[202]

20 OUTPUT 718; "OL;"

30 ENTER 718 USING "#,202A"; LEARN\_STRING\$

40 DISP "CHANGE INSTRUMENT TO ANOTHER STATE, THEN CONTINUE TO RESTORE FIRST STATE;"

50 PAUSE

60 OUTPUT 718; LEARN\_STRING\$

Allocates memory space for the Learn\_String. Asks for first state.

Computer receives the information.

Returns the instrument to its former state (when OL was first activated in line 20).

70 END


#### Description

The OL command transmits information to the controller that describes the state of the instrument when the OL command is executed. The information received from the instrument is called the learn string. The learn string can be sent from the controller back to the instrument to restore the instrument to its original state.

The learn string requires 202 bytes of storage space. See "Saving and Recalling Instrument States," in Chapter 3 for more information.

To restore the instrument to the learn string state, you must return the learn string to the instrument. The learn string contains information to tell the instrument that it is learn string data. (Also see "RCLS" and "SAVES.")

### **Query Response**




QQ3

#### OVLD

#### Overload

Enables or disables RF and IF overload status and returns overload status.

#### **Syntax**



xovid

Equivalent Softkey:

OVLD ON OFF

Preset State:

OVLD ON

Related Commands:

ARNG, AT, RL, RQS, SRQ

#### **Example**

10 OUTPUT 718; "OVLD ON;"

#### Description

The OVLD command enables, disables, or queries the current RF and IF overload status (the status is always returned, not only on a query).

OVLD returns a 16-bit integer value upon every execution of the command. Return values are covered below.

#### Note


If overload detection is enabled, the instrument will issue a service request (SRQ) and set bit 0 in the HP-IB status byte, at the end of the sweep, in which an overload is detected. You can query OVLD to ascertain the type of overload detected. The instrument will not issue a service request if a trace which has an associated overload is brought into VIEW from being BLANKed. However, an overload message will be displayed on the instrument screen.

#### Note

Overload status for a given sweep is valid from the end of that sweep up to the end of the next sweep. Overload status for each sweep is re-evaluated at the end of sweep. However, the HP-IB status byte will not be cleared at the time overload status is re-evaluated. In continuous sweep, it is possible for the user to get an HP-IB service request which indicates that an overload had been detected, but upon querying the OVLD command, no overload will be indicated. For this reason, it is recommended that the instrument be in single-sweep mode.

Overload status for the instrument's primary traces (A, B, and C) are maintained separately from overload status of each sweep. User traces have no associated overload status. Trace overload status is re-evaluated when data is written to that trace or when the trace is cleared. Thus, it is possible to see overload messages on the display, even if overload detection is disabled under the following conditions; if you were to recall or view a trace which was taken when overload detection was enabled and experienced an overload condition.

#### **Query Response**



qovid

Bit Postion	Bit Status = 0	Bit Status = 1
0	Overload detection disabled.	Overload detection enabled.
1	RF overload not detected.	RF overload detected.
2	IF overload not detected.	IF overload detected.
3	RF attenuation not at max.	Maximum RF attenuation.

If n=15 then, overload detection is enabled, RF overload on specified trace is detected, IF overload detection on specified trace is detected, and system RF attenuation is at maximum.

#### Note


If overload detection is disabled, only OVLD commands which query status of specified traces (OVLD A?;, OVLD B?;, or OVLD C?;) will return status information other than "0" (disabled). "OVLD ?;" will return "0" if overload detection is disabled no matter the setting of the instrument's RF attenuation.

#### **PDA**

# **Probability Distribution of Amplitude**

Sums the probability distribution of amplitude in the destination trace with the amplitude distribution function of the source trace.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Number	Any real or integer number.	Real number range.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF for a user-defined

variable. TS when using trace data.

Related Commands: RMS

#### Example

OUTPUT 718; "IP; SNGLS;"

Initializes instrument and activates the single-sweep mode.

OUTPUT 718; "AVBW 10KHZ; HD; TS;"

OUTPUT 718; "MOV TRB, 0;"

OUTPUT 718; "PDA TRB, TRA, 1;"

Determines the distribution of trace A and sums results into trace B

#### PDA Probability Distribution of Amplitude

OUTPUT 718; "MPY TRB, TRB, 5;"

Multiplies values in trace B by 5 to make the results more visible.

OUTPUT 718; "VIEW TRB;"

Displays the result.

#### Description

The PDA command sums the probability distribution of amplitude in the destination trace with the amplitude distribution function of the source trace.

The PDA command takes the data in the source trace on a point-by-point basis. Each amplitude value is divided by 100 times resolution value, and the result of the division is rounded to an integer. If the result falls within the range of the buckets of the destination trace, the content of the corresponding destination trace element is increased by one. For example, to show the distribution of amplitudes on a trace with values ranging from 0 to 8000, a resolution value of 1 dB would result in 81 buckets ( $(8000/(1 \times 100)) + 1$ ). Amplitude values ranging from 0 to 99 would go to bucket 1, values from 100 to 199 would go into bucket 2, and so forth. Finally, values from 7900 to 7999 would go to bucket 400. An amplitude value of 8000 would fall into bucket 81.

Due to the summing nature of the PDA command, the destination trace should always be initialized to all zeros.


The PDA function is similar to the probability density function in statistics. The probability density function has the y-axis as the probability of an occurrence, where the PDA function of the EMI receiver has the number of occurrences as its y-axis. The PDA could be converted to a probability density function by dividing, in an external controller, the value of each bucket by the total number of source elements. Note that performing the divide inside the instrument would not be appropriate because the result is less than 1, which would be truncated to 0.

### **PEAKS**

#### **Peaks**

Sorts signal peaks by frequency or amplitude.

#### **Syntax**



XPEAKS

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands: MKPX, TH

#### Example

OUTPUT 718; "IP; CALSW INT; "
OUTPUT 718; "CF 300MHZ; SP 1500MHZ; IFBW 30KHZ; SNGLS; "

OUTPUT 718; "TH 35DB

OUTPUT 718; "PEAKS TRB, TRA, FRQ?;"

Initializes instrument.
Changes the center frequency, span, bandwidth. Activates single-sweep mode.
Sets up threshold, sets minimum peak excursion.
Returns the number of peaks in trace A above the threshold.

```
ENTER 718; Number
DISP Number
FOR I=1 TO Number
    OUTPUT 718; "MKP TRB[":I:"]":
    OUTPUT 718; "MKA?;"
    ENTER 718; A
    OUTPUT 718; "MKF?;"
    ENTER 718;B
    PRINT A.B
NEXT I
```

Gets the number of peaks from the instrument. Displays the result on the computer screen. For one to the number of peaks, do the following steps. Place marker at the position of the first trace B element. Find the amplitude of the marker.

Find the frequency of the marker.

Print the amplitude and the frequency of the marker. Repeat the FOR NEXT loop for all of the peaks that were found.

#### **Description**

The PEAKS command sorts signal peaks by frequency or amplitude, stores the results in the destination trace, and returns the number of peaks found.

When sorting by frequency (FREQ), PEAKS first computes the horizontal position of all peaks. These positions are loaded into the destination trace consecutively, with the lowest frequency value occupying the first element. Thus, signal frequencies, from low to high, determine the amplitude of the destination trace from left to right.

When sorting by amplitude (AMP), PEAKS first computes the amplitudes of all peaks in the source trace in measurement units, and sorts these values from high to low. The positions of the peaks are then loaded into the destination trace, with the position of the highest amplitude value occupying the first element.

#### **PEAKS Peaks**

If the FREQ parameter is used with the PEAKS command, the programming example returns the values that shown in the following table.

Trace Element	Amplitude	Frequency
	$\mathbf{d}\mathbf{B}\mu\mathbf{V}$	Hertz
TRB[1]	78.02	-3E + 8
TRB[2]	92.98	4.E + 6
TRB[3]	78.79	3.04E + 8
TRB[4]	64.71	6.04E + 8
TRB[5]	74.31	9.07 + 8

If the AMP parameter is used with the PEAKS command, the programming example returns the values that are shown in the following table.

Trace Element	Amplitude $dB\mu V$	Frequency Hertz
TRB[1]	93.05	4.E + 6
TRB[2]	78.86	3.04E + 8
TRB[3]	78.11	-2.96E + 8
TRB[4]	74.40	9.07E + 8
TRB[5]	64.77	6.08 + 8


Notice that MKA? and MKF? are used to determine the amplitude and frequency of the peak position.

PEAKS sorts only signals that are above the threshold value. To be classified as a signal peak, a signal must be MKPX above the threshold value and it must rise and fall at least the peak excursion (MKPX value). To change the threshold, use the TH command before PEAKS is executed.

If necessary, the last sorted value is repeated to fill remaining elements of the destination trace.

PEAKS must be used as either a query or as a source in another instrument-command function. Form a query by ending the PEAKS statement with a "?." When used as a query, PEAKS returns the number of peaks found. When querying the trace elements of destination trace, the x-axis coordinate (relative to the first trace element) of the peak is returned.

#### **Query Response**




QQ1

## **PLOT** Plot

Initiates a plotter output of the screen data to the remote interface.

#### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number.	Number within the
		plotter coordinates.

Related Commands:

PRINT, SNGLS, TS

### Example for the HP-IB Interface

The plotter is at address 5 and the instrument is at address 18 in this example. (The program is only valid for HP 9000 series 200 and 300 computers.)

This example illustrates how an external controller can initiate the sending of print data to an external printer.

10 DIM P\$[80]	Allocates room in memory.
20 OUTPUT 705;"OP;"	Plotter outputs lower-left and upper-right display dimensions.
30 ENTER 705;P\$	Puts the plotter response in the computer string.
40 OUTPUT 718;"PLOT";P\$	Plots the display according to the dimensions stored in the computer string.
50 SEND 7; LISTEN 5 TALK 18 DATA	Configures the interface to output data from instrument to plotter.
60 END	

#### **PLOT Plot**

#### Description

The PLOT command transfers the trace data, graticule, and annotation of the screen to a plotter via the instrument interface (softkey labels excluded). The data is transferred in ASCII, HPGL format.

The example routes the data to an external plotter; however, the controller can read the data into a string if desired.

When using the PLOT command, the scaling points (P1x, P1y; P2x, P2y) can be specified. These scaling points specify the (x,y) coordinates, which determine the size of the plot. (P1x,P1y) refers to the lower-left plotter coordinates. (P2x,P2y) refers to the upper-right plotter coordinates.


Note	The HP 7470A plotter does not support 2 plots per page. If you use an HP 7470A plotter with an HP 8542E/HP 8546A EMI receiver or HP 8542E/
	HP 85462A receiver RF section, you can select one plot per page or four plots per page but not 2 plots per page.

#### **POWERON**

#### **Power-On State**

Selects the state of the instrument when the instrument is turned on.

#### **Syntax**



XPOWERON

Equivalent Softkeys:

POWER ON IP LAST

#### Example

OUTPUT 718; "POWERON LAST;"

### Description

The POWERON command selects the state of the instrument when the instrument is turned on: the IP state (same state as an instrument preset command) or last state (the state the insturment was in when it was turned off).

Limit-line testing is not considered to be a instrument state and is not resumed after the instrument is turned off. The limit-line table will be restored even if the instrument is turned off.


Note

The last state of the instrument is not retained in the case of battery power failure of the instrument's internal battery.

When used as a predefined variable, POWERON returns either a "0" or a "1," depending on the setting of the POWERON parameter. Refer to the following table.

Parameter Setting	Value Returned
IP	0
LAST	1

#### **Query Response**



QPOWERON .

#### PP

#### **Preselector Peak**

For an HP 8546A/HP 85462A only. Peaks the preselector.

**Syntax** 

Equivalent Softkeys:

PRESEL PEAK

**Related Commands:** 

MKA, MKCF, MKD, MKF, MKN, MKPK

#### Example

OUTPUT 718; "IP; CF 3GHZ; SP 500KHZ; "

Initializes instrument, changes center frequency,

span.

OUTPUT 718; "TS; MKPK HI; MKCF; PP; "

Peaks the highest onscreen signal.

#### Description

The PP command peaks the preselector. To use PP, set the desired trace to clear-write mode, place a marker on a desired signal, then execute PP. Commands following PP are not executed until after the instrument has finished peaking the preselector.

PP automatically adjusts the preselector tracking to peak the signal at the active marker. (When the marker is tuned to a signal and PRESEL PEAK is pressed, an internal routine searches for the peak response of the preselector and adjusts the tracking accordingly.) Using preselector peak prior to measuring a signal yields the most accurate amplitude reading.


Preselector peak operates with the MARKER NORMAL or MARKER A markers. If the marker is OFF, pressing PRESEL PEAK initiates a peak search routine and then peaks the response at that marker; otherwise, it peaks around the active marker. The CAL: PEAKING message appears on the active graticule area to indicate operation of the peaking routine. Preselector peak only operates in bands above 2.75 GHz.

#### **PREAMP**

### **Preamplifier**

Switches the system preamplifier in and out of the input path.

#### **Syntax**



xpreamp

Equivalent Key:

(PREAMP) acts as an ON/OFF toggle switch

**Equivalent Softkey** 

PREAMP ON OFF

Preset Value:

PREAMP OFF

Related Commands:

HAVE RFFS

#### Example

OUTPUT 718; "PREAMP ON;"

#### **Description**

The PREAMP command switches the system preamplifier in and out of the input path.

#### With PREAMP ON:

The receiver RF section with the RF filter section adds 12 dB of gain for 9 kHz to 50 MHz (INPUT 1) or 20 MHz to 2.9 GHz (INPUT 2) path excluding the bypass path.

A standalone receiver RF section or a receiver RF section with a RF filter section adds 27 dB of gain from 1 GHz to 6.5 GHz (INPUT 2) and the bypass path (INPUT 2).

Note

The 1 GHz to 6.5 GHz (INPUT 2) path is available for an HP 8546A/HP 85462A only.


#### **PREAMP** Preamplifier

#### Note

When the RF filter section is present in the system, the following changes to the input path will set PREAMP as follows:

- Moving into 9 kHz to 50 MHz path (INPUT 1) PREAMP OFF
- Moving into 20 MHz to 2.9 GHz path (INPUT 2) PREAMP OFF
- Moving into bypass path (INPUT 2) PREAMP OFF (For an HP 8546A/HP 85462A only.)
- Moving into 1 GHz to 6.5 GHz path (INPUT 2) PREAMP ON

### **Query Response**




QQ2

### **PREAMPG**

#### External Preamplifier Gain

Subtracts a positive or negative preamplifier gain value from the displayed signal.

#### **Syntax**



XPREAMPG

#### Example

OUTPUT 718: "PREAMPG 10DB:"

#### Description

The PREAMPG command subtracts a positive or negative preamplifier gain value from the displayed signal. Unlike using ROFFSET, PREAMPG can change the attenuation depending on the preamplifier gain entered.


A preamplifier gain offset is used for measurements that require an external preamplifier or long cables. The offset is subtracted from the amplitude readout so that the displayed signal level represents the signal level at the input of the preamplifier or long cable. The preamplifier gain offset is displayed at the top of the screen and is removed by entering zero.

Note

PREAMPG is not reset to 0 by an instrument preset (IP). Be sure to execute "PREAMPG 0;" when the preamplifier gain is no longer needed.

Press (CALIBRATE), CAL STORE if you want the instrument to use the current preamplifier gain offset when power is turned on. Preamplifier gain offset is set to zero by DEFAULT CONFIG.

#### **Query Response**




### **PREFX**

### **Prefix**

Specifies or changes the prefix used in save and recall operations.

### **Syntax**



Item	Description/Default	Range
Character	Any valid character.	0 to 6 characters long, A through Z and the underscore (the underscore cannot be the first character of the prefix).
Delimiter	Matching characters marking the beginning and end of the list of instrument commands.	

Equivalent Softkeys:

Change Prefix

Related Commands:

CAT, STOR

### Example

OUTPUT 718;"PREFX %DAVE%;"

### Description


The PREFX command specifies or changes the prefix used in save and recall operations.

XPRINT

### PRINT Print

Initiates an output of the screen data to the remote interface.

#### **Syntax**



Related Commands:

PLOT, PRNTTYPE, PRNTADRS, PRNTRES

#### Example for the HP-IB Interface

The printer usually resides at address 1 and the plotter at address 5. (The program is only valid for HP 9000 Series 200 and 300 computers and HP Vectra personal computer with a raster graphics printer, such as the HP DeskJet 550C.)

This example illustrates how an external controller can initiate the sending of print data to an external printer.

```
OUTPUT 718; "PRNTTYPE 10;"

OUTPUT 718; "PRNTADRS 1;"

OUTPUT 718; "PRINT COLOR;"

SEND 7;UNT UNL LISTEN 1 TALK 18 DATA

Sends data to printer.
```

#### Note

To print without disconnecting the computer, you must execute the following BASIC commands:

ABORT 7 LOCAL 7

Then press (COPY).

#### Description


The PRINT command initiates an output of the screen data to the remote interface. With appropriate HP-IB commands, the HP-IB can be configured to route the data to an external printer. The data is output in raster graphics format. This format differs for specific printers therefore, it is required to issue a PRNTTYPE command prior to the PRINT command. PRINT, PRINT 0, or PRINT BW produces a monochrome printout. PRINT 1 and PRINT COLOR produces a "color format" output for an HP PaintJet printer. Execute "MENU 0;" before printing to blank the softkeys.

# **PRNTADRS**

#### **Print Address**

Sets the HP-IB address of the printer.

#### **Syntax**



XPRNTADRS

Item	Description/Default	Range
Number	Any valid integer number.	0 to 30

Equivalent Softkeys:

PRINTER ADDRESS

Related Commands:

PRINT, PRNTTYPE, PRNTRES

### Example

OUTPUT 718; "PRNTTYPE 10;"

Selects DeskJet 550C

OUTPUT 718; "PRNTADRS 1;"

OUTPUT 718; "PRINT COLOR;"

SEND 7; UNT UNL LISTEN 1 TALK 18 DATA


Sends data to printer.

#### Description

The PRNTADRS command sets the HP-IB address of the printer. The address is used during execution of the PRINT command and when COPY and REPORT are pressed.

#### **Query Response**


PRNTADRS? returns the current HP-IB address of the printer.



# **PRNTPPG** Prints Per Page

Specifies the number of prints per page for printing.

#### **Syntax**



xprtppg .

Item	Description/Default	Range
Number	Any integer.	1 or 2

Equivalent Softkey:

PRN/PG 1 2

Related Commands:

PRNTRES, PRNTTYPE

#### Example

OUTPUT 718; "PRNTPPG 2;"


### Description

The PRNTPPG command specifies the number of prints per page for printing.

Note

On some printers 1 print per page will generate a full page printout, other printers are unaffected by the prints per page setting.

#### **Query Response**




### **PRNTRES**

### **Print Resolution**

Sets the resolution of subsequent prints.

#### **Syntax**



xprtres

Equivalent Softkey:

RESOLUTN LOW HIGH

Related Commands:

PRNTPPG, PRNTTYPE


### Example

OUTPUT 718; "PRNTRES LOW;"

### **Description**

The PRNTRES command sets the subsequent prints to low or high resolution.

### **Query Response**




qgen4

## **PRNTTYPE Printer Type**

Specifies which printer is connected to the output port.

## **Syntax**



xprtype

Item	Description/Default	Range
Number	Any integer number	0 to 10

Equivalent Softkey:

Printer Type

Related Command:

PRNTRES, PRNTPPG

## PRNTTYPE Printer Type

## Example


OUTPUT 718; "PRNTTYPE 1;"

## Description

The PRNTTYPE command specifies which printer is connected to the output port. Select your specific printer type from the parameters as defined in the integer index below:

- 0 = ThinkJet
- 1 = PaintJet
- 2 = DeskJet
- 3 = DeskJet 500C
- 4 = QuietJet
- 5 = Epson
- 6 = LaserJet
- 7 = LaserJet II
- 8 = LaserJet III
- 9 = DeskJet 500
- 10 = DeskJet 550C

## **Query Response**




qprtype

## **PROTECT Protect**

Silently overwrites files located on the disk drive, that are the same name.

#### **Syntax**



xovrwrt

Equivalent Softkey:

PROTECT ON OFF

Related Commands:

SAVRCLN, STOR

#### Example


OUTPUT 718; "PROTECT ON;"

## Description

The PROTECT command selects whether files on a floppy disk can be silently overwritten in the event that a file by the same name already exists on the medium.

When PROTECT is ON, an illegal command SRQ will be set if you try to overwrite a file that already exists.

## **Query Response**




QQ2

## **PSTATE**

## **Protect State**

Protects all of the instrument's user state and trace registers from being changed.

## **Syntax**



XPSTATE

Equivalent Softkeys:

SAV LOCK ON OFF

Related Commands:

ERASE, RCLS, SAVES


## Example

OUTPUT 718; "PSTATE ON;"

## **Description**

The PSTATE command protects all of the instrument's user state and trace registers from being changed.

## **Query Response**




002

## **PURGE**

## Purge File

Deletes the specified file from the current mass storage device.

## **Syntax**



Item	Description/Default	Range
Delimiter	Matching characters marking the beginning and end of the list of instrument commands.	~ \@ = /^\$%;!': "&
Character	Any valid character.	Any valid filename.

Equivalent Softkey:

DELETE FILE

Related Commands:

MSI

## Example

OUTPUT 718; "MSI DISK;"

OUTPUT 718; "PURGE %dMYFILE%;"

Selects the floppy disk as the mass storage device. Deletes the file called "dMYFILE" from the floppy disk.

## Description


The PURGE command deletes the specified file from the current mass storage device. Use the MSI command to select the mass storage device (either the internal memory or a floppy disk) before using the PURGE command. Files are repacked automatically after a PURGE command is executed, when deleting files from a floppy disk.

## **PWRBW**

## Power Bandwidth

Computes the bandwidth around the trace center.

## **Syntax**



XPWRBW

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	0 to 100.

Parameter Values:

The field used for the percentage must use a value between 0 and

100.

Prerequisite Commands:

TRDEF when using a user-defined trace. VARDEF for a user-defined

variable. TS when using trace data.

Related Commands:

IFBW, RB, SP

#### Example

OUTPUT 718; "IP; CALSW INT;"

OUTPUT 718; "SNGLS;"

OUTPUT 718; "CF 300MHZ; SP 1MHZ; IFBW 300KHZ; TS; "

OUTPUT 718; "MXMH TRA; TS; TS; TS; TS; "

OUTPUT 718; "PWRBW TRA, 99.0;"

ENTER 718;P

DISP "THE POWER BANDWIDTH AT 99 PERCENT IS"; P/1.0E+3; "kHz"

Initializes instrument. Activates single-sweep mode. Changes center frequency, span, and bandwidth. Activates the maximum hold of trace A, sweep 4 times. Returns the 99% power bandwidth.

Gets the result from the

instrument.

Displays the frequency of the power bandwidth specified on the computer


screen.

## **Description**

The PWRBW command computes the bandwidth around the trace center, which includes signals whose total power is a specified percentage of the total trace signal power. If trace A is the source, a delta marker is set at the start and stop frequencies.

If 100% is specified, the power bandwidth equals the frequency range of the screen display. If 50% is specified, trace elements are eliminated from either end of the array, until the combined power of the remaining signal responses equals half of the original power computed. The frequency span of these remaining trace elements is the power bandwidth returned.

## **Query Response**




001

## **PWRUPTIME Power Up Time**

Returns the number of milliseconds that have elapsed since the instrument was turned on.

## **Syntax**



XPWRUPTIME

## Example

OUTPUT 718; "PWRUPTIME;" ENTER 718; A A = A/1000

PRINT "Minutes elapsed ",A/60

Executes PWRUPTIME.

Places the result of PWRUPTIME into A.

Changes the milliseconds to seconds.


Prints the number of minutes that have elapsed since

the instrument was turned on.

#### **Description**

The PWRUPTIME command returns the number of milliseconds that have elaspsed since the instrument was turned on. PWRUPTIME can count the number of milliseconds for up to 2<sup>32</sup> milliseconds (232 milliseconds is equivalent to 49.7 days). If the instrument is left on for more than 49.7 days, PWRUPTIME is reset to 0 and restarts the count.

## **Query Response**




**OPWRUPTIME** 

## **QPGAIN**

## Quasi-Peak Gain

Turns on or off the linear 10x gain stage in the quasi-peak and average detector signal path.

## **Syntax**



xapgain

Equivalent Softkey:

QP/AVG 10X OFF

Preset State:

**QPGAIN OFF** 

## Example

OUTPUT 718; "QPGAIN ON;"

## Description

The QPGAIN command turns on or off the linear 10x gain stage in the quasi-peak and average detector signal path.


## RANGE

## Range

Puts the highest signal on the display close to the reference level.

UNRANGE

## **Syntax**



Related Commands:

## **Example**

OUTPUT 718; "RANGE QP;"

#### Description


The RANGE command puts the highest signal on the display close to the reference level. The parameter specifies whether the range is for the peak, quasi-peak, or average detector. For the peak detector, reference level is adjusted until the highest signal over the current frequency range is on the display. For the quasi-peak and average detectors, the quasi-peak/average gain stage is adjusted as necessary. The old reference level is saved away until a matching UNRANGE command is given. RANGE QP and RANGE AV require the detector to be selected and the amplitude scale to be linear.

## RB

## Resolution Bandwidth

Specifies the resolution bandwidth.

## **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	30 Hz to 3 MHz

Equivalent Softkeys:

IF BW AUTO MAN

Preset State:

3 MHz

Step Increment:

1, 3, 10

Related Commands:

AUTO, SP, ST, VB, VBR, IFBW, AVBW

## Example

OUTPUT 718; "RB 1KHZ;" Sets the resolution bandwidth to 1 kHz.

XRB

## **RB** Resolution Bandwidth


## **Description**

The RB command disables the coupling between sweep time and resolution bandwidth. Execute RB AUTO to reestablish coupling. (Also see "AUTO.")

The 200 Hz, 9 kHz, and 120 kHz 6-dB resolution bandwidths (used for EMI testing) are available by specifying 200 Hz 9 kHz, or 120 kHz as the frequency value; the front-panel knob, step increment keys, and auto-coupled settings provide the 1, 3, 10 resolution bandwidth sequence only. Frequencies are rounded to the nearest value in the 1, 3, 10 sequence if the frequency is other than 200 Hz, 9 kHz, 120 kHz, 5 MHz, or in the 1, 3, 10 sequence.

The instrument provides uncalibrated bandwidths of 10 Hz and 5 MHz.


#### **Query Response**



## RCLC Recall Colors

Recalls previously displayed palettes.

#### **Syntax**



xrclc

Item	Description/Default	Range
Number	Any integer.	0 to 4

Equivalent Softkey:

RECALL COLORS

Related Commands:

SAVEC, SETC

#### Example

OUTPUT 718; "RCLC 1;"

## Description

The RCLC command recalls previously saved display palettes (the color definitions for the features on the display) from the save/recall register number specified. Any value out of the legal parameter range will generate an error.

Note


The legal range of the values for this parameter is between 0 and 4. However, it is strongly advised that you do not use save/recall register 0 since this register is reserved for use by the instrument control firmware.

#### **RCLS**

#### **Recall State**

Recalls instrument state data from the specified state register.

## **Syntax**



XRCLS

Item	Description/Default Range	
Number Any real or integer number. 1 to 9		1 to 9

**Equivalent Softkeys:** 

INTERNAL -> STATE

Related Commands:

LOAD, POWERON, RCLT, SAVES

#### Example

OUTPUT 718; "IP; CF 300MHZ; SP 1MHZ;"

Changes center frequency, span.

OUTPUT 718; "SAVES 3;"

Saves state in register 3.

OUTPUT 718:"IP:"

OUTPUT 718; "RCLS 3;"

Recalls the contents of register 3.

## Description

The RCLS command recalls instrument state data from the specified state register in the internal memory. You can specify a state register number from one to nine. Registers one through eight are reserved for your use. Registers one through eight contain instrument state information if instrument state information has been stored in it with the SAVES command. State register nine contains the previous state data.

Note


The RCLS recalls state data from internal memory. Refer to "LOAD" to recall state data from the disk file.

## **RCLT**

## **Recall Trace**

Recalls previously saved trace data, or limit-line data.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any valid integer.	0 to TRCMEM - 1.

Equivalent Softkeys:

The RCLT command and the VIEW commands are equivalent to

Internal -> Trace.

Parameter Value:

0 to TRCMEM -1

Prerequisite Commands:

TRDEF when using a user-defined trace.

Related Commands:

CAT, CLRW, LOAD, SAVET, SNGLS, TRCMEM, TS, VIEW

#### Example

10 OUTPUT 718; "IP; CF 300MHZ; SP 20MHZ; TS; "

Initializes instrument, changes the cen-

ter frequency and span.

20 OUTPUT 718; "SAVET TRA,1;"

Saves instrument state and trace A data

in register 1.

30 OUTPUT 718;"IP;"

Initializes instrument.

40 OUTPUT 718; "RCLT TRA,1; VIEW TRA;"

Recalls instrument state, trace data; dis-

plays the result.

50 END

#### **RCLT Recall Trace**

## **Description**

The RCLT command recalls previously saved trace data, or limit-line data from the specified trace register in internal memory. Trace data is recalled with instrument state, date, and screen title.

The state and trace data are recalled when the trace destination is trace A, trace B, or trace C. When using a user-defined trace or a trace range for the trace destination, only the trace data is recalled.

When recalling limit-line table data, specify LIMILINE as the destination.

To avoid overwriting the recalled trace data, the VIEW command should be performed immediately after the RCLT command when recalling trace data (see line 40 in the example).

The RCLT recalls trace data from internal memory. Refer to "LOAD" to recall Note trace data from the disk file.


xrcvrmk

#### RCVRMRKR

## **Receiver Marker Position**

Modifies the behavior of the instrument's marker positioning functionality.

#### **Syntax**



Equivalent Softkey:

MARKER TUNE SPN

Preset State:

RCVRMRKR ON

Related Commands:

FASTMRKR, MKN, MKD, MKFC, MKACT, MKACTV, UP, DN

#### Example

OUTPUT 718; "RCVRMRKR ON;"

## Description

The RCVRMRKR command modifies the behavior of the instrument's marker positioning functionality when accessed through the front-panel numeric keypad, knob, or step-keys.

#### When RCVRMRKR is ON:


- Front-panel numeric keypad input, positions frequency and time markers at the specified numeric frequency input, tuning the instrument to the specified frequency if necessary. Numeric key-pad input terminators are "Hz, kHz, MHz, or GHz".
- Knob input, repositions the marker position as a function of frequency, tuning the instrument to its specified frequency if the knob input places the marker position beyond the limits of the current span.
- Step-key input:
  - □ Zero span, steps the marker to the edge of the display and retunes the instrument on succeeding step-key presses.
  - □ Non-zero span, positions the marker at the next peak left (DOWN) or next peak right (UP) by one half of the IFBW. If no signals exist, the marker is positioned at the left edge (DOWN) or the right edge (UP) of the display. If the marker is already at the edge of the display, subsequent steps return the receiver by a step equal to the size of the current span.

#### **RCVRMRKR** Receiver Marker Position

#### When RCVRMRKR is OFF:

■ Front-panel key-pad, knob, and step-key inputs, position the marker as appropriate for the marker "type" (frequency, time, and period) within the domain of the instrument's current span. The instrument is not retuned due to marker positioning input.

## **Query Response**




QQ2

## REMEASSIG Remeasure Signal

Remeasures one or more signals in the signal list.

#### Syntax



xremsiq

Equivalent Softkey:

the softkeys accessed by Re-measure

Related Commands:

AUTOAVG, AUTOQPD, MEASALLSIGS, MEASSIG, MEASTIMEPK,

MEASTIMEAVG, MEASTIMEQPD, SIGLIST, SIGMARK, SIGPOS,

**SIGUNMARK** 

#### Example

OUTPUT 718; "SIGLIST ON;"
OUTPUT 718; "SIGPOS 3;"

OUTPUT 718; "REMEASSIG;" Remeasures the third signal in the signal list.


#### Description

The REMEASSIG command remeasures one or more signals in the signal list. If there is no parameter given, the signal at the signal list cursor will be remeasured. A number parameter specifies the signal number to be remeasured. An ALL parameter specifies that all signals in the list will be remeasured. A MARKED parameter specifies that only those signals marked will be remeasured. To remeasure each signal the algorithm spans down on the signal using the initial frequency listed in the table. When zero span is reached, up to three detectors can be used to measure the signal. These detectors are selected using the AUTOAVG and AUOTQPD commands.

# REPEAT UNTIL Repeat Until

Forms a looping construct.

## **Syntax**



Item	Description/Default	Range
Instrument command	Any valid complete instrument command.	
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Number	Any real or integer number.	Real number range.
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: VARDEF when using a user-defined variable.

#### Example

The following program lowers any off-screen signal.

```
10 OUTPUT 718;"IP;"
                                             Initializes instrument.
20 OUTPUT 718; "SNGLS; TS; MKPK HI; "
                                             Activates single-sweep mode, takes sweep, places
                                             marker on signal peak.
30 OUTPUT 718;"IF MA,GT,RL THEN;"
                                             Performs lines 40, 50 and 60 if the marker
                                             amplitude is greater than the reference level.
40
     OUTPUT 718; "REPEAT;"
                                             Increases reference level, takes sweep, places
50
        OUTPUT 718; "RL UP; TS; MKPK HI;"
                                             marker on signal peak.
60
      OUTPUT 718; "UNTIL MA, LE, RL;"
                                             Does line 40 until peak amplitude is less than
                                             or equal to the reference level.
70 OUTPUT 718; "ENDIF;"
                                             Ends the IF THEN construct.
80 OUTPUT 718; "CONTS;"
```

#### Description

70 END

The REPEAT UNTIL command form a looping construct. All commands following the REPEAT command are executed until the comparison specified after the UNTIL command is true.

The following are used for comparing the operands:

GT Greater than

LT Less than

LE Less than or equal to

GE Greater than or equal to

EQ Equal to

NE Not equal to

## RESETRL

## Reset Reference Level

Resets the reference level to the preset level.

## **Syntax**



XRESETRL .

Related Commands:

AUNITS, IP, ML, RL, RLPOS

## Example

OUTPUT 718; "RESETRL;"

## Description


The RESETRL command resets the reference level to the preset level.

#### REV

## Revision

Returns the date code of the firmware revision date in YYMMDD format.

## **Syntax**



XREV

Equivalent Softkeys:

SHW INST CONFIG

Related Commands:

ID, SER, TIMEDATE

## Example

OUTPUT 718;"REV;"

Gets the firmware revision date of instrument.

ENTER 718; A

Puts the instrument response in the computer variable, A.

DISP A


Displays the firmware revision date on the computer screen.

## Description

The REV command returns the date code of the firmware revision date in YYMMDD format (for example, 931125 indicates 25 November 1993).

The date of the firmware revision also appears when the instrument is first turned on, but it is displayed in the day, month, year format.

## **Query Response**




#### **RFIN**

## RF Input Signal

Specifies the input signal routing path.

#### **Syntax**



xrtin

Note

If the RF filter section is present in the system, and RFINLK is ON, tuning is restricted to the input path currently in effect.

Equivalent Softkey:

the softkeys accessed by (Input)

Preset Value:

HF (INPUT 2 20 MHz to 2.9 GHz)

Related Commands:

CALSW, HAVE, RFINLK

#### Example

OUTPUT 718; "RFIN LF:"

## **Description**

The RFIN command specifies the input signal routing path through the HP 85420E/HP 85460A RF filter section. Where:

LF

indicates the 9 kHz to 50 MHz input path (INPUT 1)

HF

indicates the 20 MHz to 2.9 GHz input path (INPUT 2)

BYP

indicates the bypass input path (INPUT 2)

CAL


indicates the 300 MHz calibrator path is enabled

For an HP 8546A/HP 85462A only.

HHF

indicates the 1 GHz to 6.5 GHz input path (INPUT 2)

## **Query Response**



qrfin

Note


The parameter NONE is returned if the RF filter section is not present.

## RFINLK

## RF Input Lock

Limits tuning to values within the currently selected input path.

## **Syntax**



xrfinik .

Equivalent Softkey:

INPT LCK ON OFF

Preset Value:

RFINLK ON

Related Commands:

RFIN, HAVE

## Example

10 OUTPUT 718; "RFIN HF;"


20 OUTPUT 718; "RFINLK OFF;"

30 OUTPUT 718; "FA 10MHZ;"

## Description

The RFINLK command selects if frequency tuning is limited to values within the currently selected input path. For example, if RFINLK is ON, and a stop frequency is selected out of the range of the currently selected input path, the actual stop frequency used will be the highest possible value allowed by the selected input path. This command is only valid when the RF filter section is present.

## **Query Response**



**QQ**2


XRL

#### RL

#### Reference Level

Specifies the amplitude value of the reference level.

#### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is the current	Amplitude range of
	amplitude unit.	the instrument.

Equivalent Softkeys: REF LVL

Preset State: 92 dB $\mu$ V (107 dB $\mu$ V for an receiver RF section standalone)

Step Increment: by 10 dB

Related Commands: AT, MKRL, ML, RESETRL, RLPOS

## Example

10 OUTPUT 718; "IP; CALSW INT; SNGLS; CF 300MHZ; SP 20MHZ; "

mitializes instrument, activates single-sweep mode, changes center frequency,

span.

20 OUTPUT 718;"TS; MKPK HI; MKRL; TS;"

Takes sweep, places marker on signal peak, sets refer-

30 OUTPUT 718; "RL?;"

ence level to marker level. Queries reference level.

40 ENTER 718; Ref\_level

Puts the instrument response in the computer

50 OUTPUT 718;"AUNITS?;"

variable, Ref\_level.
Queries the Amplitude Units

60 ENTER 718;A\$

Puts the instrument response in the computer

variable, A\$

70 PRINT "REFERENCE LEVEL IS", Ref\_level, A\$

80 END

## **RL Reference Level**


## **Description**

The RL command specifies the amplitude value of the reference level. The reference level and input attenuator are coupled to prevent gain compression. Signals with peaks at or below the reference level are not affected by gain compression.

**CAUTION** Signal levels above +30 dBm will damage the instrument.

RL may affect the attenuation value.

## **Query Response**




QQ1

#### **RLPOS**

#### **Reference-Level Position**

Selects the position of the reference level.

#### **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number.
 0 to 8.

Step Increment:

1

**Related Commands:** 

IP, MEASURE, NRL, RL

Preset State:

RLPOS 8

#### Example

OUTPUT 718;"IP;"

Initializes instrument.

OUTPUT 718; "MEASURE NRM;"

Changes the measurement mode to normalized.

OUTPUT 718; "AMBPL ON;"

Activates trace normalization.

OUTPUT 718; "RLPOS 7;"


Positions the reference level at the seventh major gratic-

ule division.

#### Description

The RLPOS command changes the position of the reference level during log display mode. The top and bottom graticule lines correspond to 8 and 0, respectively. RLPOS must be used with MEASURE NRM or MEASURE SR, and AMBPL ON or AMB ON.

#### **Query Response**



QQ1


XRLPOS

## **RMS**

## Root Mean Square Value

Returns the root mean square value of the trace in measurement units.

## **Syntax**



XRMS

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands:

MEAN, PDA, VARIANCE

#### Example

OUTPUT 718;"IP;SNGLS;TS;"
OUTPUT 718;"RMS TRA?;"
ENTER 718;Number
DISP Number

## **Description**

The RMS command returns the root mean square value of the trace in measurement units. Trace data, user-defined trace data, and trace range data are treated as 16-bit integers.

## **Query Response**




QQ1

## ROFFSET

## Reference Level Offset

Offsets all amplitude readouts without affecting the trace.

#### **Syntax**



XROFFSET.

Item	Description/Default	Range
Number	Any real or integer number. Default unit is dB.	-200 dB to +200 dB.

Equivalent Softkeys:

REF LVL OFFSET

Preset State:

0 dB

Related Commands:

AT, RL

## Example

10 OUTPUT 718;"IP;"	Initializes instrument.
20 OUTPUT 718;"RL 80DB;"	Changes the reference level.
30 OUTPUT 718;"ROFFSET -10;"	Changes instrument reference offset value.
40 OUTPUT 718;"RL?;"	Gets the reference value from instrument.
50 ENTER 718; Ref	Puts the instrument response in the com-
	nuter nariable Ref

60 DISP "THE NEW REFERENCE LEVEL IS ", Ref Displays 70 as the new reference level.


70 END

## **Description**

Once activated, the ROFFSET command displays the amplitude offset in the active function block. And, as long as the offset is in effect, the offset is displayed on the left side of the screen.

Entering ROFFSET 0 or presetting the instrument eliminates an amplitude offset.

## **Query Response**




QQ1

## **RPTDEF**

## **Report Definition**

Specifies which report elements are output to a printer or a plotter.

## **Syntax**



xrptdef

Equivalent Softkey:

Define Report

Related Commands:

**TBLDEF** 

## Example

10 OUTPUT 718; "RPTDEF ANNOT ON;" 20 OUTPUT 718; "RPTDEF LOG ON;"

30 OUTPUT 718; "RPTDEF SETUP OFF;"

## Description

The RPTDEF command specifies which elements of a report are output to the printer or the plotter. If any of the elements are set to on, they will be sent to the printer followed by a form feed. The sequence sent is: ANNOT, LOG, LIN, TABLE, SETUP. Only LOG and LIN can be sent to the plotter. The report is generated by OUTPUT REPORT.


XROS

## RQS

## Service Request Mask

Sets a bit mask for service requests.

#### **Syntax**



Description/Default Range Item Number Any valid integer. 0 to 63

**Related Commands:** 

OVLD, SRQ, STB

#### Example

OUTPUT 718; "RQS 12;" Sends a mask bit for hardware broken and end of sweep.

## Description

The RQS command sets a bit mask for service request (see "SRQ"). Assignment of values for the mask is as follows:

- 32 = Illegal command (bit 5)
- 16 = Command complete (bit 4)
- 8 = Hardware broken (bit 3)
- 4 = End of sweep (bit 2)
- 2 =Units key pressed (bit 1)
- 1 = Overload detected (bit 0)

As shown in the example, a mask with hardware broken and end of sweep is equal to 12 (8 + 4). The mask also disables command complete and illegal command interrupts.

To activate all conditions in the mask, the mask value is equal to 63(32 + 16 + 8 + 4 + 2 + 1). To set the service request mask for all conditions, execute OUTPUT 718; "RQS 63;".

Each bit in the status byte is defined as follows:

- **0** Indicates an overload is detected. SRQ 101 appears on the screen.
- 1 Indicates that the units key was pressed. SRQ 102 appears on the screen. If you activate the units key bit, it will remain active until you activate "EE" and press a units key. (See "EE.")
- 2 Indicates end of sweep. SRQ 104 appears on the screen. If you send any RQS value that contains mask value 4, another sweep will be taken.
- 3 Indicates broken hardware. SRQ 110 appears on the screen.

#### **RQS Service Request Mask**


- 4 Indicates completion of a command. It is triggered by EOI at the end of a command string or the completion of a print or plot.
- 5 Indicates an illegal instrument command was used. SRQ 140 appears on the screen.
- 6 and 7 are not used.

The screen numbers 101, 102, 104, and 110 are the octal values corresponding to the status register values; that is, SRQ 102 = bit 6 = octal 100 and bit 2 = octal 2 are both true.

A service request is generated only if the proper request mask bit has been set, and either the condition itself or the Force Service Request (see "SRQ") is sent. To set the request mask, choose the desired interrupt conditions and sum their assigned values. Executing the RQS command with this value sets the bit mask. After setting the bit mask, only the chosen conditions can produce an interrupt. Generally, you must set the bit mask using the RQS command. However, the "hardware broken", "illegal remote command", and "overload detected" conditions are automatically enabled after presetting or sending the IP command. Pressing (PRESET) or sending the IP command, then, produces the same interrupt bit mask as sending "RQS 41;" (decimal 41 is the sum of the assigned values of these three interrupt bits, 32 = Bit 5 and 8 = Bit 3 and 1 = Bit 0).

For most conditions, the RQS mask bit stays set until the next IP or RQS command is executed. When a units key is pressed, the interrupt occurs and the Units Key Pressed bit in the RQS mask is reset. To reenable the Units Key Pressed interrupt, you must send a new RQS mask.

## **Query Response**




## **SAVEC**

## **Save Colors**

Saves the currently displayed palette.

## **Syntax**



xsavec

Item	Description/Default	Range
Number	Any integer.	0 to 4

Equivalent Softkey:

SAVE COLORS

Related Commands:

RCLC, SETC

## Example

OUTPUT 718; "SAVEC 1;"

## **Description**

The SAVEC command saves the currently displayed palette (the color definitions for the features on the display) to the save/recall register number specified. Any value out of the legal parameter range will generate an error.

Note


The legal range of values for this parameter is between 0 and 4. However, it is strongly advised that you do not use save/recall register 0 since this register is reserved for use by the instrument control firmware.

## **SAVES**

#### Save State

Saves the currently displayed instrument state in internal memory.

#### **Syntax**



XSAVES

Item	Description/Default	Range
Number	Any valid integer.	1 to 8.

Equivalent Softkeys:

STATE -> INTRNL

Related Commands:

OL, PSTATE, RCLS, SAVET, STOR

## Example

OUTPUT 718; "IP; CF 300MHZ; SP 20MHZ; " Initializes instrument, changes center frequency,

span.

OUTPUT 718; "SAVES 1;"

Saves instrument state in register 1.

## **Description**

The SAVES command saves the currently displayed instrument state in internal memory. The state data is saved in the specified state register if the state registers have not been locked by the PSTATE command.

Only state registers 1 through 8 are available for saving the instrument state. State register nine contains the previous state data, state register zero contains the current state.

Note


The SAVES command saves state data in internal memory. Refer to "STOR" to save state data on a floppy disk.

#### SAVET

## **Save Trace**

Saves the selected trace data and state information or limit-line tables.

#### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command with a length of 401 elements.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any valid integer.	0 to TRCMEM - 1.

Equivalent Softkeys:

Trace -> Intrnl

Prerequisite Commands:

TRDEF when using a user-defined trace.

Related Commands:

CAT, CLRW, PSTATE, RCLT, SNGLS, TS, VIEW

#### Example

OUTPUT 718;"IP;CF 300MHZ;SP 20MHZ;TS;"

Initializes instrument, changes the center

frequency and span.

OUTPUT 718; "VIEW TRA; SAVET TRA,1;"

Puts trace A in the view mode, saves instru-

ment state and trace A data in register 1.

OUTPUT 718;"IP;"

Initializes instrument.

OUTPUT 718; "RCLT TRA,1; VIEW TRA;"

Recalls instrument state, trace data.

#### Description

The SAVET command saves the selected trace data and state information, or limit-line tables in internal memory.

The trace data is saved in the specified register if the state registers have not been locked by PSTATE ON (see "SAVES"). Use LIMILINE to save limit-line tables.

#### **SAVET Save Trace**


The TS and VIEW commands should be executed prior to saving trace data. Note

The SAVET command saves trace data or limit-line tables in internal memory. Refer to "STOR" to save data on a floppy disk.

# SEGDEL Segment Delete

Deletes the specified segment from the limit-line tables.

#### **Syntax**



**Related Commands:** 

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILINESTA, LIMILO, LIMIMARGAMP, LIMIMARGSTA, LIMIMIRROR, LIMIMODE, LIMINUM, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SENTER, SENTERT

### Example

EMI receiver mode only

This example uses LIMISEG for entering segments into limit 1 table, then entering a segment into limit 2 table (limit 1 and limit 2 are treated as separate tables). Line 80 demonstrates the effect of deleting segment 1 from limit 1 table when limit 1 and limit 2 tables are treated separately.

10	OUTPUT	718; "LIMINUM LIMIT1;"	Specifies limit 1 table.
20	OUTPUT	718; "LIMIDEL;"	Deletes limit 1 table.
30	OUTPUT	718; "LIMISEG 300MHZ, -30DB, FLAT;"	Enters segment into limit 1 table.
40	OUTPUT	718; "LIMINUM LIMIT2;"	Specifies limit 2 table.
50	OUTPUT	718; "LIMIDEL;"	Deletes limit 2 table.
60	OUTPUT	718; "LIMISEG 300MHZ, -40DB, FLAT;"	Enters segment into limit 2 table.
70	OUTPUT	718;"LIMINUM LIMIT1;"	Specifies limit 1 table.
80	OUTPUT	718; "SEGDEL 1;"	Deletes segment 1 from limit 1 table.
90	END		

#### Signal analysis mode only

This example uses LIMISEG for entering segments into the upper limit-line table, then entering a segment into the lower limit-line table (upper and lower limit lines are treated as separate tables). Line 70 demonstrates the effect of deleting segment 1 from the lower limit table when the upper and lower limit-line tables are treated separately.

10	OUTPUT	718;"LIMIMODE UPPER;"	Specifies the upper limit-line table.
20	OUTPUT	718; "LIMIDEL;"	Deletes the upper limit-line tables.
30	OUTPUT	718; "LIMIFT FREQ;"	Limit lines to be based on frequency.
40	OUTPUT	718; "LIMISEG 300MHZ, -30DB, FLAT;"	Enters a segment into the upper limit-
			line table.
50	OUTPUT	718;"LIMIMODE LOWER;"	Specifies the lower limit-line table.
60	OUTPUT	718; "LIMIDEL;"	Deletes the lower limit-line table.
70	OUTPUT	718; "LIMISEG 300MHZ, -70DB, FLAT;"	Enters a segment into the lower limit-
			line table.

#### **SEGDEL Segment Delete**

80 OUTPUT 718; "SEGDEL 1;"

Deletes the segment from the lower limitline table.

90 END

Signal analysis mode only

With the addition of line 80, the upper and lower limit-line tables are no longer treated as separate tables, but as one table. In line 90, segment 1 is deleted from the upper and lower limit-line tables (for the given frequency).

10	OUTPUT	718; "LIMIMODE UPPER;"	Specifies the upper limit-line table.
20	OUTPUT	718; "LIMIDEL;"	Deletes deletes both the upper and lower
			limit-line table.
30	OUTPUT	718;"LIMIFT FREQ;"	Limit lines to be based on frequency.
40	OUTPUT	718; "LIMISEG 300MHZ, -30DB, FLAT;"	Enters segment into the upper limit-
			line table.
50	OUTPUT	718; "LIMIMODE LOWER;"	Specifies the lower limit-line table.
60	OUTPUT	718; "LIMIDEL;"	Deletes the lower limit-line table.
70	OUTPUT	718; "LIMISEG 300MHZ, -70DB, FLAT;"	Enters a segment into the lower limit-
			line table.
80	OUTPUT	718; "LIMIMODE UPLOW;"	Specifies both the upper and lower
			limit-line tables.
90	OUTPUT	718; "SEGDEL 1;"	Deletes the segment from both the up-
			per and lower limit-line tables.
100	END		

## **Description**

The result of SEGDEL depends on the setting of the LIMIMODE command as shown in the following table.

LIMIMODE Setting	Result of SEGDEL
LIMIMODE UPPER	Deletes specified segment from the upper limit-line table.
LIMIMODE LOWER	Deletes specified segment from the lower limit-line table.
LIMIMODE UPLOW	Deletes specified segment from the upper and lower limit-line table.
LIMIMODE DELTA	Deletes specified segment from the mid and delta limit-line table.

You may want to query LIMIMODE before using SEGDEL if you are unsure of the LIMIMODE setting.


To determine the number of each segment, you can use the softkeys accessed by Edit Limit to display the limit-line table. (Limit-line entries are sorted according to frequency or time.)

## **SENTER**

# **Segment Entry for Frequency Limit Lines**

Enters the limit-line data in the upper and lower limit-line table. Signal analysis mode only.

### **Syntax**



#### **SENTER Segment Entry for Frequency Limit Lines**

Item	Description/Default	Range
Number	Any real or integer number. Default unit is dBm.	Varies with FOFFSET and ROFFSET.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILO, LIMIMIRROR, LIMIMODE, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTERT

#### Example

This example enters limit-line values into the upper and lower limit-line tables.

10	OUTPUT	718;"LIMIFT FREQ;"	Sets the limit lines to be based on frequency and deletes any existing tables.
20	OUTPUT	718;"LIMIMODE UPLOW;LIMIREL OFF;"	Specifies the upper and lower limit- line table as fixed.
30	OUTPUT	718; "SENTER 300MHZ, -10DB, -50DB, FLAT;"	Enters in values for a segment.
40	OUTPUT	718; "SENTER 350MHZ, -15DB, -60DB, FLAT;"	Enters in values for another segment.
50	OUTPUT	718;"LIMIFT FREQ;"	Sets the limit lines to be based on frequency and deletes any existing tables.
60	OUTPUT	718; "LIMIMODE DELTA; LIMIREL OFF;"	Specifies the mid and delta table format and fixed type.
70	OUTPUT	718; "SENTER 300MHZ, -20DB, 10DB, FLAT;"	Enters in values for a segment.
		718; "SENTER 350MHZ, -30DB, 20DB, FLAT;"	Enters in values for another segment.

### **Description**

The SENTER command enters the limit-line data in the upper and lower limit-line table or the mid and delta table for limit lines based on frequency.

Each limit-line segment is specified with a starting frequency, an upper or median amplitude value, a lower or delta amplitude value, and a segment type. The segment type defines how the line segment is to extend from its starting point to the next segment.

a limit-line based on the frequency), executing SENTER will clear the current sweep time limit line table.	Note	If the current limit-line table contains lines based on sweep time (as opposed to a limit-line based on the frequency), executing SENTER will clear the current sweep time limit line table.	300+
--	------	--	------

The three segment types are FLAT, SLOPE, and POINT.

■ FLAT draws a zero-slope line between the coordinate point of the current segment and the coordinate point of the next segment, producing limit-line values equal in amplitude for all frequencies between the two points. If the amplitude values of the two segments differ, the limit-line will "step" to the value of the second segment.

#### **SENTER Segment Entry for Frequency Limit Lines**

- SLOPE draws a straight line between the coordinate point of the current segment and the coordinate point of the next segment, producing limit-line values for all frequencies between the two points.
- POINT specifies a limit value for the coordinate point, and no other frequency points, so that a POINT segment specifies a limit value for a single frequency. The POINT segment type may be used as the last segment in the limit-line table. However, if the last segment in the table is not specified as the POINT segment type, an implicit point is automatically used. If a visible POINT segment at the right-hand edge of the display is not desired, add an explicit last point segment to the limit-line table that is higher in frequency than the stop frequency.


Segments are sorted as they are entered according to frequency. A maximum of 30 segments can be defined using SENTER.

## **SENTERT**

# **Segment Entry for Sweep Time Limit Lines**

Enters the limit-line data in either the upper and lower limit-line table. Signal analysis mode only.

### **Syntax**



sentert	

Item	Description/Default	Range
Number	Any real or integer number. For amplitude, the default unit is dBm. For sweep time, the default unit is seconds.	The range for the amplitude varies with ROFFSET. The range for the sweep time is the sweep time range of the instrument.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	

#### **SENTERT Segment Entry for Sweep Time Limit Lines**

Related Commands:

LIMIAMPSCL, LIMIDEL, LIMIDISP, LIMIFAIL, LIMIFRQSCL, LIMIFT, LIMIHI, LIMILINE, LIMILO, LIMIMIRROR, LIMIMODE, LIMIREL, LIMISEG, LIMISEGT, LIMITEST, SEGDEL, SENTER

#### Example 1

This example enters limit-line values into the upper and lower limit-line tables.

10	OUTPUT	718;"RL -10DB;"	Sets the reference level to $-10 \text{ dB}$
20	OUTPUT	718;"LIMIFT TIME;"	Sets the limit lines to be based on sweep time and deletes any existing tables.
30	OUTPUT	718;"LIMIMODE UPLOW;LIMIREL ON;"	Specifies the upper and lower limit- line table as relative.
40	OUTPUT	718; "SENTERT 10MS, -10DB, -50DB, FLAT;"	Enters in values for a segment.
50	OUTPUT	718; "SENTERT OMS, -15DB, -60DB, FLAT;"	Enters in values for a segment.
60	OUTPUT	718; "LIMITEST ON; TS; "	Turns on the limit-line testing.
70	END		

### Example 2

10	OUTPUT	718;"LIMIFT TIME;"	Sets the limit lines to be based on sweep time and deletes any existing tables.
20	OUTPUT	718; "LIMIMODE DELTA; LIMIREL OFF;"	Specifies the mid and delta table format and fixed type.
30	OUTPUT	718; "SENTERT 10MS, -20DB, 10DB, FLAT;"	Enters in values for a segment.
40	OUTPUT	718; "SENTERT OMS, -30DB, 20DB, FLAT;"	Enters in values for a segment.
50	OUTPUT	718; "LIMITEST ON; TS"	Turns on the limit-line testing.
60	END		

#### **Description**

The SENTERT command enters the limit-line data in either the upper and lower limit-line table or the mid and delta table for limit lines based on sweep time.

Each limit-line segment is specified with a starting sweep time, an upper or median amplitude value, a lower or delta amplitude value, and a segment type. The segment type defines how the line segment is to extend from its starting point to the next segment.

Note	If the current limit-line table contains lines based on frequency (as opposed to a
	limit-line based on the sweep time), executing SENTERT will clear the current
	frequency limit line table.

The three segment types are FLAT, SLOPE, and POINT.

- FLAT draws a zero-slope line between the coordinate point of the current segment and the coordinate point of the next segment, producing limit-line values equal in amplitude for all sweep times between the two points. If the amplitude values of the two segments differ, the limit-line will "step" to the value of the second segment.
- SLOPE draws a straight line between the coordinate point of the current segment and the coordinate point of the next segment, producing limit-line values for all sweep times between the two points.

## **SENTERT Segment Entry for Sweep Time Limit Lines**

■ POINT specifies a limit value for the coordinate point, and no other sweep time points, so that a POINT segment specifies a limit value for a single sweep time. The POINT segment type may be used as the last segment in the limit-line table. However, if the last segment in the table is not specified as the POINT segment type, an implicit point is automatically used. If a visible POINT segment at the right-hand edge of the display is not desired, add an explicit last point segment to the limit-line table that is higher in sweep time than the current sweep time of the instrument.


Segments are sorted as they are entered according to starting sweep time. A maximum of 30 segments can be defined using SENTERT.

### SER

## **Serial Number**

Returns the serial number suffix of the instrument.

#### **Syntax**



XSER

Equivalent Softkey:

SHW INST CONFIG

Related Commands:

ID, REV

### Example

DIM Serial\$[24]

Reserves memory space for a string.

OUTPUT 718; "SER;" Gets the serial number from the instrument.

ENTER 718; Serial\$ Puts the instrument response in the computer variable.

DISP Serial\$


Displays the serial number on the computer screen.

## Description

The SER command returns the serial number suffix of the instrument.

## **Query Response**

The last five digits of the serial number are returned.




OSER

#### SETC

### **Set Colors**

Displays the subsystem's color editor.

#### **Syntax**



<u> </u>	Description/Default	Range
Number	Integer	-5 to 0
Number	Integer	0 to 16

Equivalent Softkey:

the softkeys accessed by Adjust Color

Related Commands:

RCLC, SAVEC

## Example 1

10 OUTPUT 718; "SETC -1;"

Sets the current palette to default palette.

#### Example 2

10 OUTPUT 718; "SETC 4,,50,75;"

Sets the HSL values for Trace C to Hue = 0, Saturation = 50, and Luminosity = 75.

#### Description

The SETC command provides a limited remote interface to the display subsystem's color editor.

If the first parameter selected for the SETC command is a positive value, it is interpreted as the display item number to be edited. The next three optional parameter values are interpreted as hue, saturation, and luminosity values, respectively, to set for the selected display item. The parameters for the associated items are defined in the integer index below:

- 0 = Background
- 1 = Graticule
- 2 = Trace A
- 3 = Trace B
- 4 = Trace C
- 5 = Limit line 1
- 6 = Active function
- 7 = Annotation

- 8 = Advisories
- 9 = Errors
- 10 = Markers
- 11 = Softkey labels
- 12 = Status
- 13, 14, and 15 are reserved

The three optional parameter values have a range of 0 to 100 (0 to 99 for hue, the first parameter). If you do not select a value for any of the optional parameters, the associated parameter will be set to zero.

#### Note

Values greater than 16 for the first parameter of the SETC command are evaluated using modulo 16 (see MOD command for more information). For example, a value of 18 is equivalent to 2.


If the first parameter supplied to the SETC command is a negative number, the second, third, and fourth optional parameters are ignored. The display palette is set to one of the standard palettes. The associated pallets are defined in the index below:

- -1 = Default pallet
- -2 = Monochrome pallet
- -3 = Vision enhance 1 pallet
- -4 = Vision enhance 2 pallet
- -5 = Optical filter pallet

# SETDATE Set Date

Sets the date of the real-time clock of the instrument.

## **Syntax**



XSETDATE .

Item	Description/Default	Range
Number	A number in the YYMMDD format.	Valid year, month, and
		day.

Equivalent Softkeys:

SET DATE

Related Commands:

SETTIME, TIMEDATE, TIMEDSP


# Example

OUTPUT 718; "SETDATE 890212;" Sets the date to February 12, 1989.

## Description

The SETDATE command sets the date of the real-time clock of the instrument.


## **Query Response**



# **SETTIME Set Time**

Sets the time of the real-time clock of the instrument.

#### **Syntax**



XSETTIME .

Item	Description/Default	Range
Number	A number in the HHMMSS (24 hour) format.	0 to 235959.

Equivalent Softkeys:

SET TIME

Related Commands:

SETDATE, TIMEDATE, TIMEDSP

## Example

OUTPUT 718; "SETTIME 135501;" Sets the time to 1:55:01 PM.

## Description


The SETTIME command sets the time of the real-time clock of the instrument.

Note

Trailing zero's are required when setting the real-time clock. For example, to set the clock to 12:00, enter 120000, entering 1200, will set the time to 00:12.

Leading zero's are not required.


### **Query Response**



# **SHOWSETUP** Show Set Up

Shows the setup on the display.

## **Syntax**



xsetup

Item	Description/Default	Range
Number	Any integer.	0 to 4

Equivalent Softkey:

SHOW SETUP

Preset State:

0 OFF

#### Example

OUTPUT 718; "SHOWSETUP 1;"


## Description

The SHOWSETUP command shows the current settings of the instrument on the display. This includes existing filenames, correction-factor data, limi-line data, frequency settings, trace data, and so on. SHOWSETUP consists of four pages of information. SHOWSETUP 1 displays the first page, SHOWSETUP 2 displays the second page, and so on. A SHOWSETUP of 0 turns the setup display OFF.

# SIGADD Signal Add

Adds a signal to the internal signal list.

#### **Syntax**



xsigadd .

Equivalent Softkey:

ADD TO LIST

Prerequisite Commands:

MEASAVG, MEASSIG, MEASFREQ, MEASQPD, MEASPEAK

Related Commands:

MEASALLSIGS, MEASAVG, MEASFREQ, MEASPEAK, MEASQPD,

MEASSIG, REMEASSIG, SIGDEL, SIGLIST

### Example

OUTPUT 718; "MEASSIG;" OUTPUT 718; "SIGADD;"


### Description

The SIGADD command adds a signal to the internal signal list. The signal must have been previously measured using the MEASAVG, MEASSIG, MEASFREQ, MEASQPD, or MEASPEAK commands.

# SIGDEL Signal Delete

Deletes one or more signal from the signal list.

#### **Syntax**



xsigdel

Equivalent Softkey:

the softkeys accessed by Delete Signals

Related Commands:

MEASALLSIGS, MEASSIG, SIGADD

#### Example

OUTPUT 718; "SIGDEL 5;"


## **Description**

The SIGDEL command deletes one or more signals from the signal list. If there is no parameter given, the signal at the cursor will be deleted. An integer parameter specifies a signal number to delete from the list. An ALL parameter deletes all signals from the list. A MARKED parameter deletes only those signals that are marked from the list.

# **SIGDLTAVIEW** Signal Delta View

Selectes which delta from limit is viewed on the display signal list.

### **Syntax**



xsigdvw

Equivalent Softkey:

the softkeys accessed by VIEW A OFF

Related Commands:

SIGLIST, SIGSORT

#### Example

OUTPUT 718; "SIGDLTAVIEW AVLX;"

### **Description**

The SIGDLTAVIEW command selects which delta from the limit-line table is viewed by the display signal list. The choices are:

VIEW PK

peak to limit 1 (PKLX), ALIM 1

VIEW PK

peak to limit 2 (PKLY), ALIM 2

VIEW QP

quasi-peak to limit 1 (QPLX), ALIM 1

quasi-peak to limit 2 (QPLY), ALIM 2

VIEW AVG

average to limit 1 (AVLX), ALIM 1

VIEW AVG

average to limit 2 (AVLY), ALIM 2


### SIGDLTAVIEW Signal Delta View

The viewing from delta to limit can also be turned off (NONE).

Note

If there is no data recorded for the signal, verify that the limit is defined and turned on, the frequency in the limit-line table is defined at the signal frequency, and the selected detector has been measured.

## **Query Response**




qsigdvw

# SIGGRAPH Signal Graph

Draws an EMI report graph on the display.

#### Syntax



xsiggrp

Equivalent Softkey:

SAVE LOG GRAPH and SAVE LIN GRAPH

Preset State:

SIGGRAPH OFF

Related Commands:

SIGLIST, REPORT

#### Example

OUTPUT 718; "SIGGRAPH LIN;"

## Description

The SIGGRAPH command draws an EMI report graph on the display. The graph can either be on a logarithmic or a linear scale.


SIGGRAPH LOG or LIN draws a full screen graticule, either logarithmic or linear frequency axis with limited annotation. On the graticule, drop lines for peak amplitude signals with cross-bars for quasi-peak and average amplitude readings are drawn. The quasi-peak cross-bar is the same color as Trace B (default is blue) and the average cross-bar is the same color as Trace C (default is magenta). The start and stop frequencies are defined based on the frequencies in the signal list.

## **SIGLEN**

## Signal List Length

Queries the current number of signals in the signal list.

### **Syntax**



xsiglen

Related Commands:

SIGLIST, SIGPOS, SIGRESULT

Item	Description/Default	Range
1.,	Any real number	0 to 240

## Example

OUTPUT 718; "SIGLEN?;" ENTER 718; Length

## Description

The SIGLEN command queries the current number of signals in the signal list.

### **Query Response**

The query returns an ASCII numeric corresponding to the position of the cursor in the signal list.




QQ 1

# SIGLIST Signal List

Turns on or off the signal list viewing and editing functions.

### **Syntax**



xsigist

Equivalent Softkey:

SIG LIST ON OFF

Preset Value:

SIGLIST OFF

Related Commands:

MEASALLSIGS, MEASSIG, REMEASSIG, SIGDEL, SIGLIST,

SIGMARK, SIGUNMARK, SIGDLTVIEW, SIGADD


## **Example**

10 OUTPUT 718; "SIGLIST ON;"

## Description

The SIGLIST command turns on or off the signal list viewing and editing functions.

## **Query Response**




QQ2

# SIGMARK Signal Mark

Marks one or more signals on the signal list.

## **Syntax**



xsigmrk

Equivalent Softkey:

the softkeys accessed by Signal Marking

**Related Commands:** 

SIGUNMARK, SIGPOS

## Example

OUTPUT 718; "SIGMARK LOWER;"

#### Description


The SIGMARK command marks one or more signals on the signal list. If there is no parameter specified, the signal at the cursor will be marked (see SIGPOS command). An integer parameter specifies a signal number in the list to be marked. An ALL parameter specifies all signals in the list will be marked. A COMP parameter compliments all marked signals in the list. A DUP parameter marks all signals that are duplicated in the list. A LOWER parameter marks all duplicate signals in the list that are lower in peak amplitude. A HIGHEST parameter marks the ten highest signals in the list. A BELOW parameter marks all signals below the signal currently pointed to in the signal list.

# **SIGPOS**

## **Signal Position**

Controls and queries the cursor position in the signal list.

### **Syntax**



xsigpos

Controls and queries the cursor position in the signal list.

Preset State:

Related Commands:

SIGRESULT, SIGLIST, SIGLEN

Related Softkey:

SELECT FRM LIST

Item	Description/Default	Range
Number	Any real number	0 to 240

### Example


OUTPUT 718; "SIGPOS 5;"

## Description

The SIGPOS command controls and queries the cursor position in the signal list.

### **Query Response**


The query returns an ASCII numeric corresponding to the position of the cursor in the list.



# SIGRESULT Signal Result

Sends the contents of an entry in the signal list to the controller.

### **Syntax**



xsigres

Related Commands:

MEASALLSIGS, MEASSIG, REMEASSIG, SIGADD, SIGDEL, SIGLEN, SIGLIST, SIGMARK, SIGUNMARK

#### Example

- 10 DIM Result\$ [140]
- 20 OUTPUT 718; "SIGLEN;"
- 30 ENTER 718; Ssize
- 40 OUTPUT 718; "SIGPOS 1;"
- 50 FOR I=1 to Ssize
- 60 OUTPUT 718; "SIGRESULT;"
- 70 ENTER 718; Result\$
- 80 PRINT Result\$
- 90 OUTPUT 718; "DN;"


100 NEXT I

!Moves down the list

#### **Description**

The SIGRESULT command sends the contents of an entry in the signal list to the controller. The signal entry which is sent is determined by first issuing the SIGPOS command. If the signal list is empty or the SIGPOS is outside the range of the signals within the list, an ASCII NULL with EOI asserted

#### **Query Response**




qq4

# **SIGSORT** Signal Sort

Sorts the internal signal list based on the field selected by the parameter.

#### **Syntax**



xsigsrt

Equivalent Softkey:

the softkeys accessed by Sort Signals

Related Commands:

SIGLIST, SIGDLTAVIEW

### Example

OUTPUT 718; "SIGSORT PKLX;"

## Description

The SIGSORT command sorts the internal signal list based on the field selected by the parameter. The fields to chose from are:

SORT BY

the frequency of the signals (FREQ), FREQ

SORT BY

the peak amplitude (PEAK), PK AMP

SORT BY

the quasi-peak amplitude (QP), QP AMP

SORT BY

the average amplitude (AVG), AVG AMP

the peak delta from limit 1 (PKLX)

the peak delta from limit 2 (PLKY)

### SIGSORT Signal Sort


the qp delta from limit 1 (QPLX) the qp delta from limit 2 (QPLY) the average delta from limit 1 (AVLX) the average delta from limit 2 (AVLY)

For the FREQ parameter, the list will be sorted in ascending order. For all other parameters, the list will be sorted in descending order.

# **SIGUNMARK** Signal Unmark

Unmarks one or more signals on the signal list.

## **Syntax**



xsunmrk

Equivalent Softkey:

CLEAR MARK or CLR ALL MARKS

Related Commands:

SIGMARK, SIGPOS

### Example

OUTPUT 718; "SIGUNMARK 5;"

## Description


The SIGUNMARK command unmarks one or more signals on the signal list. If there is no parameter selected, the signal at the cursor will be unmarked (see SIGPOS command). An integer parameter specifies a signal number to be unmarked from the signal list. An ALL parameter unmarks all signals in the signal list.

## **SMOOTH**

## **Smooth Trace**

Smooths the trace according to the number of points specified for the running average.

## **Syntax**



XSMOOTH .

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF for a user-defined

variable. TS when using trace data.

Related Commands: SNGLS, TS, VAVG

#### Example

```
10 OUTPUT 718;"IP;"
                                    Initializes instrument.
20 OUTPUT 718; "SNGLS; TS; "
                                    Activates single-sweep mode, takes a sweep.
30 OUTPUT 718; "VIEW TRA;"
                                    Stores results of trace A.
40 OUTPUT 718; "SMOOTH TRA, 10;"
                                    Smooths trace A.
50 OUTPUT 718; "VIEW TRA;"
                                    Displays the result.
60 END
```

#### **Description**

The SMOOTH command smooths the trace according to the number of points specified for the running average.

Each point value is replaced with the average of the values (in measurement units) of the given number of points centered on it. Increasing the number of points increases smoothing at the cost of decreasing resolution. If the number of points is an even number, then the number of points is increased by one. If the number of points is larger than the size of SOURCE, then the size of SOURCE is used (unless size of SOURCE is even, in which case the size of SOURCE minus one is used). Smoothing decreases at the endpoints.

The purpose of this function is to perform a spatial video averaging as compared to the temporal version supplied by the video-average (VAVG) command. The functions of SMOOTH and VAVG are not interchangeable however. Unlike VAVG, SMOOTH averages values that occur before and after the data point in time. This can cause some display irregularities at the start and stop frequencies. Use low values for the SMOOTH parameter to avoid signal distortion.

By replacing the value of each point in a trace with the average of the values of a number of points centered about that point, any rapid variations in video noise or signals are smoothed into more gradual variations. It thereby performs a function similar to reducing the average video bandwidth without the corresponding changes in sweep time. As such, it does result in a reduction of frequency resolution. Also, signal peaks are reduced with large smoothing values, and this can cause the amplitude to appear to be low.

This command requires user memory for its execution. Memory is not permanently allocated, so the largest amount of memory is available for the functions that are used in a particular application. When the command is complete, memory is returned to the free user memory.

# **SNGLS** Single Sweep

Sets the instrument to single-sweep mode.

### **Syntax**

SNGLS

XSNGLS

Equivalent Keys:

SWEEP CONT SGL or (SINGLE)

Related Commands:

CLRW, CONTS, TM, TS

## Example

OUTPUT 718; "SNGLS;"

# Description


The SNGLS command sets the instrument to single-sweep mode. Each time TS (take sweep) is sent, one sweep is initiated, as long as the trigger and data entry conditions are met.

XSP

# SP Span

Changes the total displayed frequency range symmetrically around the center frequency.

### **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	Frequency span of the
		instrument.

Equivalent Keys:

SPAN or (SPAN)

Step Increment:

1, 2, 5, 10 sequence (up to the stop frequency of the instrument)

Related Commands:

AVBW, CF, FA, FB, FOFFSET, FS, HNLOCK, HNUNLK, IFBW, RB, ST,

VB

#### Example

OUTPUT 718;"IP;SP 20MHZ;"

Initializes instrument, changes frequency span.

OUTPUT 718; "SP?;"

Gets the span value from the instrument.

ENTER 718; Span

Puts the instrument response in the computer variable, Span.

PRINT Span

Displays the span value.

#### SP Span

### **Description**

The SP command changes the total displayed frequency range symmetrically around the center frequency.

The frequency span readout refers to the displayed frequency range. Dividing the readout by 10 yields the frequency span per division.

If intermediate frequency resolution and average video bandwidths are coupled to the span width, the bandwidths change with the span width to provide a predetermined level of resolution and noise averaging. Likewise, the sweep time changes to maintain a calibrated display, if coupled. All of these functions are normally coupled, unless AVBW, IFBW, RB, VB, or ST have been executed.

Because span is affected by frequency, change the frequency before changing span (see "HNLOCK").

Specifying 0 Hz enables zero-span mode, which configures the instrument as a fixed-tuned instrument.

#### **Query Response**




QQ1

# **SPEAKER** Speaker

Turns on or off the internal speaker.

## **Syntax**



XSPEAKER

Equivalent Softkey:

SPEAKER ON OFF

Preset State:

SPEAKER ON

Related Commands:

DEMOD, FMGAIN, SQLCH

## Example

OUTPUT 718; "SPEAKER OFF;"


## Description

The SPEAKER command turns on or off the internal speaker.

# **SPZOOM** Span Zoom

Places a marker on the highest onscreen signal, turns on the signal track function, and activates the span function.

## **Syntax**



XSPZOOM

Equivalent Softkeys:

SPAN ZOOM

## Example

OUTPUT 718;"IP; CF 300MZ; TS;" OUTPUT 718; "SPZ00M;"


## Description

The SPZOOM command places a marker on the highest onscreen signal (if a marker is not present), turns on the signal track function, and activates the span function. If a marker is present before SPZOOM is executed, SPZOOM turns on the signal track function and activates the span function.

# SQLCH Squelch

Sets the squelch threshold by setting the squelch level.

### **Syntax**



XSQLCH

Item	Description/Default	Range
Number	Any valid integer.	0 to 100.

Equivalent Softkeys:

SQUELCH

Preset Value:

Λ

Related Commands:


DEMOD, FMGAIN, SPEAKER

### Example

OUTPUT 718; "SQLCH 100;"

# Description

The SQLCH command sets the squelch threshold by setting the squelch level. It mutes weak signals and passes strong signals.




# **SQR**

# **Square Root**

Places the square root of the source into the destination.

## **Syntax**



XSOR

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	name.
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF for a user-defined

variable. TS when using trace data.

Related Commands:

PDA

### Example

OUTPUT 718; "SQR SP,1E8;" Changes the span to 10 kHz.

# Description

The SQR command places the square root of the source into the destination. If the source is negative, the square root of the absolute value will be returned.


When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

### **SRCALC**

# **Source Leveling Control**

Selects internal or external leveling for use with the built-in tracking generator.

### **Syntax**



XSRCALC

Equivalent Softkey:

ALC INT EXT

Preset State:

SRCALC INT

Related Commands:

CF, FA, FB, FS, HNLOCK, SP

### Example

OUTPUT 718; "SRCALC EXT;"

## Description


The SRCALC command selects internal or external leveling for use with the built-in tracking generator.

The functions of SRCALC and ALC INT EXT are identical.

When used as a predefined variable, SRCALC returns either 0 or 1. The value that is returned by SRCALC depends on the SRCALC parameter, as shown in the following table.

Parameter setting	Value returned
INT	0
EXT	1

### **Query Response**



qsrcaic


XSRCAT .

## **SRCAT**

## **Source Attenuator**

Attenuates the source output level.

## **Syntax**



Item Description/Default Range 0 to 56 dB. Any real or integer number, specified in multiples of 8 dB. Number

Equivalent Softkeys:

SRC AIN MAN AUTO

Coupling:

Coupled to power level of the source output (SRCPWR) when set to

auto (SRCAT AUTO)

Related Commands:

**SRCPSTP** 

Preset State:

SRCAT AUTO

### Example

OUTPUT 718; "SRCAT 16DB;"

### **SRCAT Source Attenuator**

## Description

The SRCAT command attenuates the output level of the source. Use SRCAT to attenuate the power level of the source manually, from 0 to 56 dB in 8 dB steps.

"SRCAT AUTO;" automatically adjusts the attenuator to yield the source amplitude level specified by the SRCPWR command.

## **Query Response**




QQ 1

### **SRCPOFS**

### Source Power Offset

Offsets the source power level readout.

### **Syntax**



XSRCPOFS

Item	Description/Default	Range
Number	Any real or integer number.	

Equivalent Softkeys:

SRC PWR OFFSET

Related Commands:

SRCPWR, SRCPSWP

Step Increment:

Determined by SRCPSTP

**Preset State:** 

0 dB

### Example

Use SRCPOFS to offset the power-level readout for the tracking-generator source.

OUTPUT 718; "MEASURE SR;"

Sets instrument to stimulus-response mode.

OUTPUT 718; "SUB SRCPWR, RL, 20;"

Turns on source output and sets source amplitude to


20 db below the reference level.

OUTPUT 718; "SRCPOFS 13DB;"

Offsets power-level readout for source by 13 dB.

### Description

The SRCPOFS command offsets the displayed power of the built-in tracking generator. This function may be used to take into account system losses (for example, cable loss) or gains (for example, preamplifier gain) reflecting the actual power delivered to the device under test.




## **SRCPSTP**

# Source Power-Level Step Size

Selects the source-power step size.

### **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number.

Equivalent Softkeys:

SRC PWR STP SIZE

Step Increment:

0.1 dB

Related Commands:

SRCPWR, SRCPOFS, SRCPSWP

**Preset State:** 

SRCPSTP AUTO (one major vertical scale division)

### Example

Select incremental changes of power effected by "SRCPWR UP;", "SRCPWR DN;" commands, or the step keys.

OUTPUT 718; "MEASURE SR;"

Activates stimulus-response mode.

OUTPUT 718; "SUB SRCPWR, RL, 20;"

Turns on the source output and sets source ampli-

XSRCPSTP.

tude to 20 dB below the reference level.

OUTPUT 718; "SRCPSTP .3DB;"

Sets power-level step size to 0.3 dB.

OUTPUT 718; "SRCPWR UP;"

Increases the power level.

## Description


The SRCPSTP command selects the step size for the following source commands:

- Power offset (SRCPOFS)
- Power sweep (SRCPSWP)
- Power (SRCPWR)

Use SRCPSTP to set the step size to a specific value.

"SRCPSTP AUTO;" sets the step size to one vertical scale division.

## **Query Response**




QQ1

## **SRCPSWP**

# **Source Power Sweep**

Selects the sweep range of the source output.

### **Syntax**



XSRCPSWP

Item Description/Default		Range
Number	Any real or integer number.	

Equivalent Softkeys:

PWR SWP ON OFF

Step Increment:

Determined by SRCPSTP

Related Commands:

SRCPSWP, SRCPOFS, SRCPSTP

Preset State:

SRCPSWP OFF

# Example

Use SRCPSWP to sweep the power level of the source output.

OUTPUT 718; "MEASURE SR;"

Activates stimulus-response mode.

OUTPUT 718; "SUB SRCPWR, RL, 20;"

Turns on source output and sets source amplitude to

20 dB below the reference level.

OUTPUT 718;"SP 0;"

Sets span to 0 Hz.

OUTPUT 718; "SRCPSWP 10DB;"

Sweeps source output from 20 dB below the reference

level to 10 dB below the reference level.


## **Description**

The SRCPSWP command works in conjunction with the SRCPWR (source power) command to sweep the amplitude level of the source output. The SRCPWR setting determines the amplitude level at the beginning of the sweep. The SRCPSWP command determines the change in amplitude level of the sweep.

For example, if SRCPWR and SRCPSWP are set to −15 dBm and 4 dB respectively, the source sweeps from -15 dBm to -11 dBm.

Note	Power is swept from low to high.
Note	An SRQ error will be returned if this command is used when the SWEEPTYPE is set to "LOG".

The minimum sweep time is limited to 20 ms when performing a source power sweep.




## **SRCPWR**

## **Source Power**

Selects the source power level.

### **Syntax**



XSRCPWR

Item	Description/Default	Range
Number	Any real or integer number. Default unit is the current	Actual range is
	amplitude unit.	hardware dependent.

Equivalent Softkeys:

SRC PWR ON OFF

Step Increment:

Set by SRCPSTP

Related Commands:

SRCAT, SRCPSTP, SRCPSWP

Preset State:

 $97~\mathrm{dB}\mu\mathrm{V}$ 

### Example

Use SRCPWR to turn on the source and adjust its power level.

OUTPUT 718; "AUNITS DBM;"
OUTPUT 718; "SRCPWR -20DB;"


Changes the current amplitude units. Changes power level to -20 dBm.

OUTPUT 718; "AUNITS DBMV;"
OUTPUT 718; "SRCPWR 37;"

Changes the current amplitude unit. The source power is now 37 dBmV.

## Description

The SRCPWR command turns the source off or on and sets the power level of the source. The source is turned on automatically whenever its value is specified with SRCPWR. Also see "SRCPSTP."




# **SRCTK**

# **Source Tracking**

Adjusts the tracking of the source output with the instrument sweep.

### **Syntax**



XSRCTK .

Item	Description/Default Rai	
Number	Any real or integer number.	0 to 16,383.

Equivalent Softkeys:

MAN TRK ADJUST

Step Increment:

1

Related Commands:

RB, VB, ST, SP, CF, FA, FB, SP, FS, SRCTKPK

### Example

OUTPUT 718; "MEASURE SR;"

Activates the stimulus-response mode.

OUTPUT 718; "SUB SRCPWR, RL, 20;"

Turns on the power at the source output and sets

source amplitude to 20 dB below the reference level.

OUTPUT 718; "SP 1MHZ;" Sets measurement range.

OUTPUT 718;"RB 1KHZ;"

OUTPUT 718;"TS;"

OUTPUT 718; "SRCTK EP;"


Takes sweep.

Allows entry of from front-panel keys to adjust

tracking.

## **Description**

The SRCTK command adjusts the tracking of the tracking-generator output relative to the center frequency of the instrument. SRCTK is used typically for bandwidths less than 300 kHz. Bandwidths greater than 300 kHz do not require tracking adjustment. Use SRCTK to improve amplitude accuracy and maximize signal response. Use SRCTKPK to adjust tracking automatically. See "SRCTKPK."




### **SRCTKPK**

## **Source Tracking Peak**

Automatically adjusts the tracking of source output with instrument sweep.

### **Syntax**



XSRCTKPK

Equivalent Softkeys:

TRACKING PEAK

Related Commands:

RB, VB, ST, SP, CF, FA, FB, SP, FS, SRCTK

### Example

OUTPUT 718; "MEASURE SR;"

Activates the stimulus-response mode.

OUTPUT 718; "SUB SRCPWR, RL, 20;"

Turns on the source output and sets source amplitude

to 20 dB below the reference level.

OUTPUT 718; "SP 1MHZ;"

Sets measurement range.

OUTPUT 718; "RB 1KHZ;"

Takes sweep.

OUTPUT 718;"TS;" OUTPUT 718; "SRCTKPK;"

Automatically adjusts the tracking.

### **Description**

The SRCTKPK command adjusts the tracking of the tracking-generator source output automatically to maximize responses for measurements made with resolution bandwidths less than 300 kHz.


SRCTKPK maximizes the amplitude of the displayed active trace.

### SRQ

# **Force Service Request**

Used to simulate interrupts from the instrument.

### **Syntax**



XSRO

Item Description/Default		Range
Number	Any valid integer.	1 to 127.

Related Commands:

CLS, EE, RQS, STB

### Example

OUTPUT 718; "RQS 8; SRQ 8;" Sets bit mask for a hardware broken service request, generates a hardware broken interrupt.

Note

A program can respond to the interrupt in the same way it would under a true service request condition.

### Description

The SRQ command is used by an external controller to simulate interrupts from the instrument.

The service request condition is also displayed on the screen with the annotation SRQ XXX, where XXX is a three-digit octal number.

The conditions that can generate a service request are as follows:

32 = Illegal command

16 = Command complete

8 = Hardware broken

4 = End of sweep

2 = Units key pressed

1 = Overload detected

A service request is generated only if the proper request mask bit has been set (see "RQS"), and either the condition itself or the Force Service Request is sent. To set the request mask, choose the desired interrupt conditions and sum their assigned values. Executing the RQS command with this value sets the bit mask. After setting the bit mask, only the chosen conditions can produce an interrupt.

Each bit in the status byte is defined as shown in the following table.

Table 4-7. Instrument Status Byte

Bit Number	Decimal Equivalent	Instrument State	Description
5	32	Set when an illegal command is present.	SRQ 140 appears on the screen.
4	16	Set when any command is completed.	It is triggered by EOI at the end of a command string or the completion of a print or plot.
3	8	Indicates hardware broken condition.	SRQ 110 appears on the screen.
2	4	Indicates end of sweep.	SRQ 104 appears on the screen. If you send any RQS value that contains mask value 4, another sweep will be taken.
1	2	Indicates a units key was pressed.	SRQ 102 appears on the screen. If you activate the units key bit, it will remain active until you activate "EE" and press a units key. (See "EE.")
0	1	Indicates an overload was detected.	SRQ 101 appears on the screen.

Bit numbers 6 and 7 are not used.

The screen numbers 101, 102, 104, and 110 are the octal values corresponding to the status register values; that is, SRQ 102 = bit 6 = octal 100 and bit 2 = octal 2 are both true.

Generally, you must set the bit mask using the RQS command. However, the "hardware broken", "illegal remote command", and overload detected conditions are automatically enabled after presetting or sending the IP command. Pressing PRESET or sending the IP command, then, produces the same interrupt bit mask as sending "RQS 41;" (decimal 41 is the sum of the assigned values of the three interrupt bits, 32 = bit 5, 8 = bit 3 and 1 = bit 0).

For most conditions, the RQS mask bit stays set until the next instrument preset (IP), or RQS command is executed.

When a units key is pressed, the interrupt occurs and the Units Key Pressed bit in the RQS mask is reset. To reenable the Units Key Pressed interrupt, you must send a new RQS mask. See "RQS" for detailed information.

As mentioned, you can simulate a service request condition. Choose the desired interrupt conditions from the RQS command table (see "RQS"), and sum their assigned values. Use the RQS command with this value to set the bit mask. By setting the corresponding bits in the SRQ command and sending the SRQ command to the instrument, the desired interrupt occurs. This allows the user to verify proper operation of software routines designed to handle infrequent or unlikely interrupts.

### **Interface Differences**

As implemented on the HP-IB interface, an instrument service request asserts the SRQ control line on the HP-IB.

On the RS-232 interface, the instrument does not have a way of signaling the interrupt condition to a controller. In this case, the controller must operate in a polled mode if it requires interrupt information (see "Polled Mode of Operation" below for a discussion of the polled mode).

### Interrupt-Related Commands Common to All Interfaces:

- CLS Clear status byte, without read
- RQS Request mask
- SRQ Force service request
- STB Read then clear status byte

The HP-IB interface supports interface commands to read the status byte.

On HP-IB in HP 9000 Series 200 or 300 BASIC, the statement SPOLL (Device\_address) can be used to read the status byte.

### **Polled Mode of Operation**


The polled mode of operation is probably most applicable to an RS-232 interface user. Because there is no interrupt signal to the RS-232 controller, the user must periodically ask the instrument, via the "STB?" command, for the contents of its status register. For example, the RS-232 controller could periodically check for the hardware-broken condition by executing the "STB?" command and reading the results.

# SS

# Center Frequency Step Size

Specifies center frequency step size.

## **Syntax**



Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	Frequency range of
		the instrument.

Equivalent Softkeys:

CF STEP AUTO MAN

Preset State:

 $100\;\mathrm{MHz}$ 

Step Increment:

1, 2, 5, 10 sequence

Prerequisite Commands:

VARDEF when using a user-defined variable

Related Commands:

AUTO, CF, FOFFSET, SP

### Example

10 CLEAR 718

20 OUTPUT 718; "IP; SNGLS; CF 300MHZ; SP 20MHZ; TS; "

30 OUTPUT 718; "MKPK HI; MKRL; TS; MKF?; "

40 ENTER 718 USING "K"; Mk\_freq

50 OUTPUT 718: "MKA?:"

60 ENTER 718 USING "K"; Mk\_amp

70 OUTPUT 718; "SS "; Mk\_freq; "HZ"

80 OUTPUT 718; "CF UP; TS; MKPK HI; MKA?;"

90 ENTER 718; Mk\_ampl

100 PRINT "THE FUNDAMENTAL IS "; Mk\_amp-Mk\_ampl

110 PRINT "dB ABOVE THE SECOND HARMONIC"

120 END

Clears the HP-IB.

Initializes the instrument, activates single-sweep mode, changes the center frequency, span, takes

sweep.

Finds the highest peak, changes the reference level to the marker, takes sweep, returns the frequency

of the marker.

Puts the instrument response in the computer variable, Mk\_freq. Returns the amplitude of the marker. Puts the instrument response in

Puts the instrument response in the computer variable, Mk\_amp. Changes the step size to the marker

frequency.

Increases the center frequency, takes sweep, puts the marker on the highest peak and returns the amplitude of the marker.

Puts the instrument response in the computer variable, Mk\_ampl.

Outputs the result.

### **Description**

The SS command specifies center frequency step size.

The AUTO parameter removes SS as an active function but does not have an effect on its value.

### **Query Response**




901

## ST

# **Sweep Time**

Specifies the time in which the instrument sweeps the displayed frequency range.

### **Syntax**



Item Description/Default Range Number Any real or integer number. Default unit is seconds. Within the sweep time range of the instrument.

XST

Equivalent Softkeys:

SWP TIME AUTO MAN

Sweep Time Range in

Zero Span:

Sweep Time Range in

20 ms to 100 s

15 ms to 100 s

Non-zero Span:

Step Increment:

2, 3, 5, 7.5, 10, 15 sequence

Prerequisite Commands:

VARDEF when using a user-defined variable

Related Commands:

AUTO, AVBW, CONTS, HNLOCK, HNUNLK, IFBW, RB, SNGLS, SP,

SRCPSWP, TS


### Example

OUTPUT 718; "ST 100MS;" Sets the sweep time to 100 milliseconds.

# Description

The ST command specifies the time in which the instrument sweeps the displayed frequency range. When used as a predefined variable, ST returns the sweep time as a real number in

# **Query Response**




QQ1

## **STB**

# **Status Byte Query**

Returns to the controller the decimal equivalent of the status byte.

## **Syntax**



XSTB

Related Commands:


RQS, SRQ

### Example

1	O OUTPUT 718;"IP;"	Initializes instrument.
2	O OUTPUT 718; "SNGLS;"	Activates single-sweep mode.
3	O OUTPUT 718;"CLS;"	Clears the status bits.
4	O OUTPUT 718;"TS;"	Takes sweep.
5	O OUTPUT 718;"STB?;"	Returns the status bits.
6	O ENTER 718;Status_Byte	Puts the instrument response in the computer variable, Sta-
		tus_Byte.
7	O PRINT Status_byte	Displays the result.
8	O END	

### Description


The STB command returns to the controller the decimal equivalent of the status byte. The STB command is equivalent to a serial poll command. The RQS and associated bits are cleared in the same way that a serial poll command would clear them. The bits in the status byte are explained under the RQS command.



# **STOR** Store

Stores data to a disk file.

# **Syntax**



#### STOR Store

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Character (file name)	Any valid character. Characters form the file type and file name.	Data type (lowercase a, c, e, g, i, l, n, o, s, or t) should precede the file name in LIF format. In DOS format, the suffix should follow the file name. Refer to Table 4-8.
Character (prefix)	Any valid character.	
Delimiter	Matching characters marking the beginning and end of the list of instrument commands.	~ \@ = /^\$%;!': "&

Related Commands:

CAT, LOAD, PREFX, PROTECT

## Example

### LIF Format

OUTPUT 718;"TRDEF N_EW,400;"	Defines a trace.
OUTPUT 718;"MOV N_EW,TRA;"	Moves the contents of trace $A$ into $N_{-}EW$ .
OUTPUT 718;"STOR t, %F_UNCX%, N_EW;"	Stores N_EW under the file name of tFUNCX as trace data.
OUTPUT 718;"STOR n, %nA_MPDATA_7%;" OUTPUT 718;"STOR 1, %1L_IMITS_1%;" OUTPUT 718;"STOR s, %sS_TATE_1%;"	Stores the current antenna correction factors. Stores the current limit-line tables. Stores the instrument state.

#### DOS Format

OUTPUT 718;"TRDEF N_EW,400;"	Defines a trace.
OUTPUT 718; "MOV N_EW, TRA;"	Moves the contents of trace $A$ into $N_{-}EW$ .
OUTPUT 718; "STOR , "F_UNCX.TRC", N_EW;	Stores N_EW under the file name of tFUNCX as trace data.
OUTPUT 718; "STOR n, %A_MPDATA_7.ANT%;"	Stores the current antenna correction factors.
OUTPUT 718; "STOR 1, %L_IMITS_1.LIM%;"	Stores the current limit-line tables.
OUTPUT 718; "STOR s, %S_TATE_1.STA%;"	Stores the instrument state.

### **Description**

The STOR command stores the source data to a disk file under the specified file name and data type.

Data type: The data type is either s, t, l, i, g, n, c, o, or e, refer to Table 4-8 for a complete description. The selected data type will require the file name to include the matching prefix in LIF format or suffix in DOS format. A trace file has a data type of "t", therefore, in LIF format the file name must be preceded by "t". For example, "t ATRACE". In DOS format the suffix must be ".TRC". For example, "ATRACE.TRC".

Table 4-8. LIF or DOS Data Types

LIF Prefix	DOS Suffix	File Description	Result
S	.STA	Instrument state	Stores the instrument state.
t	.TRC	Trace	Stores the trace and state.
1	.LIM	Limit lines	Stores the limit-line values from the current limit-line table.
i	.ВМР	Display image file	Stores displays image as a 16-color bit map.
g	.sig	Signal list	Stores the signal list and its associated annotation.
n	.ANT	Antenna correction factors	Stores the antenna correction factors.
c	.CBL	Cable correction factors	Stores the cable correction factors.
o	.OTH	Other correction factors	Stores other correction factors.
ę	.ALL	All information	Stores all information, including traces, states, windows, correction factors, and limit lines.

**Note** The STOR command saves data to a floppy disk. See "SAVET" or "SAVES" to save data in internal memory.

### Specifying the source


When storing trace data, enter the location of the trace data (trace A, trace B, trace C, user-defined trace, user-defined variable or multiple variables (prefix\*)) as the source.

**Disk requirements:** To store a file to a floppy disk, there must be enough space on the floppy disk for the file. If the file name is already on the disk, PROTECT must be off for the file to be stored.

# SUB Subtract

Subtracts source 2 from source 1.

## **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	Real number range.

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF for a user-defined

variable. TS when using trace data.

Related Commands: AMB, AMBPL, BML, LIMITEST, SUM

## Example

OUTPUT 718; "SUB TRA, TRB, TRC;" Subtracts trace C from trace B and places the result in trace A.

# Description

The SUB command subtracts source 2 from source 1, point by point, and sends the difference to the destination.


When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

### SUM

# **Sum of Trace Amplitudes**

Returns the sum of the amplitudes of the trace elements in measurement units.

### **Syntax**



XSU⋈

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands: ADD, DIV, MEAN, MPY, SUB, TS, VARIANCE

### Example

10 OUTPUT 718; "IP;"

20 OUTPUT 718; "SNGLS; TS;"

30 OUTPUT 718; "SUM TRA?;"

40 ENTER 718; Trace\_sum

50 DISP Trace\_sum; "MEASUREMENT UNITS"

Initializes instrument.

Activates single-sweep mode, takes sweep.

Gets the result.


Puts the instrument response in the computer variable, Trace\_sum.

Displays the result.

60 END

# Description

The SUM command returns the sum of the amplitudes of the trace elements.




## **SUMSQR**

# **Sum of Squared Trace Amplitudes**

Returns the sum of the squares of the amplitude of each trace element in measurement units.

### **Syntax**



XSUMSOR

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a	
	user-defined trace.	***

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

### Example

OUTPUT 718;"IP;"

Initializes instrument.

OUTPUT 718; "SNGLS; TS; "

Activates single-sweep mode, takes sweep.

OUTPUT 718; "SUMSQR TRA?;"

Gets the result.

ENTER 718;Trace\_sqrsum

Puts the instrument response in the computer

variable, Trace\_sqrsum.


DISP Trace\_sqrsum; "MEASUREMENT UNITS"

Displays the result.

## **Description**

The SUMSQR command returns the sum of the squares of the amplitude of each trace element in measurement units.

### **Query Response**




QQ1

# **SWEEPTYPE** Sweep Type

Selects a linear or logarithmic frequency axis.

### **Syntax**



xswptyp

Equivalent Softkeys:

SWEEP LOG LIN

Preset State:

SWEEPTYPE LIN

Related Commands

LOGSWEEPSPD


### Example

OUTPUT 718; "SWEEPTYPE LIN;"

## **Description**

The SWEEPTYPE command selects the frequency axis stimulus and graticule display. When "LIN" is selected the frequency axis is linear. When "LOG" is selected the frequency axis is logarithmic.

## **Query Response**




qswptyp

# SWPCPL Sweep Couple

Selects either a stimulus-response or receiver auto-coupled sweep time.

### **Syntax**



XSWPCPL

Equivalent Softkeys:

SWP CPLG SR RECV

Preset State:

SWPCPL RECV

Related Commands:

**SRCPWR** 

### Example

10 OUTPUT 718; "IP; SNGLS;"

20 OUTPUT 718; "FA 300KHZ; FB 1GHZ; "

30 OUTPUT 718; "SUB SRCPWR, RL, 10;"

40 OUTPUT 718; "SWPCPL SR;"

50 OUTPUT 718; "SRCTKPK; DONE?;"

60 ENTER 718; Done

70 LOCAL 718

80 END


### **Description**

The SWPCPL command selects either a stimulus-response (SR) or receiver (SA) auto-coupled sweep time.

In stimulus-response mode, auto-coupled sweep times are usually much faster for swept-response measurements. Stimulus-response auto-coupled sweep times are typically valid in stimulus-response measurements when the frequency span is less than 20 times the bandwidth of the device under test.

When used as a predefined variable, SWPCPL returns either a "0" or a "1," depending on the setting of the SWPCPL parameters. Refer to the following table.

Parameter setting	Value returned
SA	0
SR	1




### TA

### Transfer A

Returns trace A amplitude values from the instrument to the controller.

### **Syntax**



Related Commands:

MDS, TB, TDF

### Example

This example stores the TA results in array A.

```
DIM A(401)
OUTPUT 718;"IP;"
OUTPUT 718;"SNGLS;CF 300MHZ;SP 2MHZ;TS;"

OUTPUT 718;"TDF P;TA;"

FOR N = 1 TO 401
    ENTER 718;A(N)
NEXT N
FOR N = 1 TO 401

PRINT A(N)
NEXT N
```

Reserves memory area for array.
Initializes instrument.
Activates single-sweep mode, changes center frequency and span, takes sweep.
Changes trace data format, outputs trace A.
FOR NEXT loop moves each element of

ATA

FOR NEXT loop moves each element of trace A to the computer.

FOR NEXT loop moves the trace values from the computer to the printer.

Prints out the results.

### Description

The TA command returns trace A amplitude values from the instrument to the controller. The display unit values are transferred in sequential order (from left to right) as seen on the screen.


Transfer of trace amplitude data should be done only as follows:

- 1. Select single sweep mode (SNGLS).
- 2. Select desired instrument settings.
- 3. Take one complete sweep (TS).
- 4. Transfer data (TA).

This procedure ensures that the current settings of the instrument are reflected in the transferred data.

See the section, "Different Formats for Trace Data Transfers," in Chapter 3 for more information about transferring trace data. Items are separated by a comma when in TDF P format.

## **Query Response**



### TB

### Transfer B

Transfers trace B amplitude values from the instrument to the controller.

### **Syntax**



Related Commands:

MDS, TA, TDF

### Example

```
DIM A(401)
OUTPUT 718;"IP;"
OUTPUT 718; "SNGLS; CF 300MHZ; SP 2MHZ; TS;"
OUTPUT 718; "TDF P; TB;"
FOR N = 1 TO 401
                                               trace A to the computer.
  ENTER 718; A(N)
NEXT N
FOR N = 1 TO 401
  PRINT A(N)
NEXT N
```

Reserves memory area for array. Initializes instrument. Activates single-sweep mode, changes center frequency and span, takes sweep. Changes trace data format, outputs trace FOR NEXT loop moves each element of

XTB


FOR NEXT loop moves the trace values from the computer to the printer. Prints out the results.

## **Description**

The operation of TB is similar to the operation of TA.

See the section, "Different Formats for Trace Data Transfers," in Chapter 3 for more information about transferring trace data.

#### **Query Response**




### **TBLDEF**

## **Table Definition**

Specifies which elements of a table are output to the printer.

### **Syntax**



ythidef

Equivalent Softkey:

the softkeys accessed by Define List

Related Commands:

RPTDEF

#### Example

OUTPUT 718; "TBLDEF MARK ON;"

#### **Description**


The TBLDEF command specifies which elements of a table are output to the printer upon receipt of OUTPUT REPORT. If any of the elements are set to on, they will be included as part of the list portion of the report. Each element will be its own labeled column. The sequence of columns is: signal marked (MARK), peak detector (DETPK), peak delta from limit 1 (DAPK), peak delta from limit 2 (DBPK), quasi-peak detector (DBQP), average detector (DETAV), average delta from limit 1 (DAAV), average delta from limit 2 (DBAV), and total correction factors (COR).

#### TDF

### Trace Data Format

Formats trace information for return to the controller.

### **Syntax**



Related Commands:

MDS, MKA, TA, TB, TRA

### Example

DIM A(401)

OUTPUT 718;"IP;"

OUTPUT 718;"BLANK TRA;CLRW TRB;"

OUTPUT 718;"SNGLS;CF 300MHZ;SP 2MHZ;TS;"

OUTPUT 718;"TDF P;TB;"

FOR N = 1 TO 401

ENTER 718;A(N)

NEXT N

FOR N = 1 TO 401

PRINT A(N)

NEXT N

Holds trace data.
Initializes instrument.
Views trace B
Activates single-sweep mode, changes center frequency and span.
Formats trace data.
Transfers trace data to array A, one element at a time.

XTDF

Loop prints out trace B data. Prints out the results.

#### Description

The TDF command formats trace information for return to the controller. The different trace data formats are as follows:

#### TDF P

**Description:** TDF P is the real number format. An example of a trace element returned with the real number format is 10.00 dB. When querying the trace or marker value, the value is returned using the amplitude unit set by AUNITS (for example, watts or dBm).

**Restrictions:** The instrument must be in log scale to use TDF P. To send the trace data back to the instrument, the data must be converted to measurement units.

How data is returned: The following table describes what is transferred when the trace data format is set to P, but the AUNITS are changed. In every case, the trace data transfer is ended by a carriage return, and a line feed with an EOI.

Trace Dat	a Transfers	with	TOF	P	
-----------	-------------	------	-----	---	--

AUNITS Setting	Example	Description
Watts	TDF P;AUNITS W;TA;	Transfers 401 real values, in watts, with each value separated by a carriage return and a line feed.
dBm	TDF P;AUNITS DBM;TA;	Transfers 401 real values, in dBm, with each value separated by a carriage return and a line feed.
dBmV	TDF P;AUNITS DBMV;TA;	Transfers 401 real values, in dBmV, with each value separated by a carriage return and a line feed.
dBμV	TDF P;AUNITS DBUV;TA;	Transfers 401 real values, in $dB_{\mu}V$ , with each value separated by a carriage return and a line feed.
Volts	TDF P;AUNITS V;TA;	Transfers 401 real values, in volts, with each value separated by a carriage return and a line feed.

**Example of how data is returned:** For example, if the reference level of the instrument is set to -10 dBm, the amplitude scale is set to 10 dB per division, and trace A contains the following data:

TRA[1] contains 8000 (in measurement units). The value 8000 indicates trace element 1 is at the reference level.

TRA[2] = 7000 measurement units (trace element 2 is -10 dB below the reference level). TRA[3] through TRA[401] each contain 6000 (in measurement units). The value 6000 indicates that the trace elements 3 through 401 are all at -20 dB below the reference level.

Querying trace A with the TDF P format and AUNITS set to DBM returns ASCII character codes for the following:

-10.00, -20.00, -30.00, (-30.00 is repeated 398 times), <CR><LF><EOI>

#### TDF A

**Description:** TDF A is the A-block data format. With the A-block data format, trace data is preceded by "#," "A," and a two-byte number (the two byte number indicates the number of trace data bytes). The setting of the MDS command determines whether the trace data is transferred as one or two 8-bit bytes.

**Restrictions:** To use the A-block format for sending data, you must provide the number of data bytes.

How data is returned: The following table describes what is transferred when the trace data format is set to A, but the MDS setting is changed.

#### **TDF Trace Data Format**

Trace Data Transfers with TDF A

MDS Setting	Example	Description
Binary	TDF A;MDS B;TA;	Transfers "#A," the number of bytes of trace data, then the 401 bytes of trace data. Using MDS B "reduces" each trace value into one byte by dividing (DIV) the trace value by 32. The trace data transfer is ended with an EOI.
Word	TDF A;MDS W;TA;	Transfers "#A," the number of bytes of trace data, then 802 bytes of trace data. MDS W uses two bytes per trace element to transfer trace data. The first byte contains the trace value divided by (DIV) 256, the second byte contains the remainder (MOD) of that division. The trace data transfer is ended with an EOI.

**Example of how data is returned:** For the same trace A data that is used in the TDF P description, querying trace A with the TDF A format and MDS set to binary (MDS B) would return the ASCII character codes for the following:

#A(401 div 256)(401 mod 256)(8000 div 32)(7000 div 32)(6000 div 32)(the number for 6000 div 32 is repeated 398 times)<EOI>

Notice that #A is followed by the two bytes that contain the number of trace elements. Because MDS is set to binary, the number of trace elements is 401.

If MDS is set to W, querying trace A with the TDF A format would return the ASCII character codes for the following:

#A(802 div 256)(802 mod 256)(8000 div 256)(8000 mod 256)(7000 div 32)(7000 mod 256)(6000 div 256)(6000 mod 256)(the number for 6000 div 256, then the number for 6000 mod 256 is repeated 398 times)

Notice that #A is followed by the two bytes that contain the number of trace elements. Because MDS is set to W (word), the number of trace elements is 802.

#### TDF I

**Description:** TDF I is the I-block data format. With the I-block data format, trace data must be preceded by "#," and "I." The setting of the MDS command determines whether the trace data is transferred as one or two 8-bit bytes. Unlike using the A-block format, you do not provide the number of data bytes when sending trace data back to the instrument.

Restrictions: This format is not recommended for use with an RS-232 interface.

**How data is returned:** The following table describes what is transferred when the trace data format is set to I, but the MDS setting is changed.

Trace Data Transfers with TDF I

MDS Setting	Example	Description
Binary	TDF I;MDS B;TA;	Transfers "#I," then the 401 bytes of trace data. Using MDS B "reduces" the trace value into 1 byte by dividing (DIV) the trace value by 32. The trace data transfer is ended with an EOI.
Word	TDF I;MDS W;TA;	Transfers "#A," then 802 bytes of trace data. MDS W uses two bytes per trace element to transfer trace data. The first byte contains the trace value divided by (DIV) 256, the second byte contains the remainder (MOD) of that division. The trace data transfer is ended with an EOI.

Example of how data is returned: For the same trace A data that is used in the TDF P description, querying trace A with the TDF I format and MDS set to binary (MDS B) would return the ASCII character codes for the following:

#I(8000 div 32)(7000 div 32)(6000 div 32)(the number for 6000 div 32 is repeated 398 times)

If MDS is set to W, querying trace A with the TDF I format would return the ASCII character codes for the following:

#I(8000 div 256)(8000 mod 256)(7000 div 32)(7000 mod 256)(6000 div 256)(6000 mod 256)(the number for 6000 div 256, then the number for 6000 mod 256 is repeated 398 times)

#### TDF B

**Description:** TDF B enables the binary format. With the binary format, the marker or trace data is transferred as bytes. Of all the trace data formats, TDF B transfers trace data the fastest. The setting of the MDS command determines whether the trace data is transferred as one or two 8-bit bytes.

**Restrictions:** The TDF B format cannot be used to send data back to the instrument (you must use the A-block format to send data back to the instrument).

How data is returned: The following table describes what is transferred when the trace data format is set to B, but the MDS setting is changed.

MDS Setting	Example	Description
Binary	TDF B;MDS B;TA;	Transfers the 401 bytes of trace data. Using MDS B "reduces" the trace value into 1 byte by dividing (DIV) the trace value by 32. The trace data transfer is ended with an EOI.
Word	TDF B;MDS W;TA;	Transfers the 802 bytes of trace data. MDS W uses two bytes per trace element to transfer trace data. The first byte contains the trace value divided by (DIV) 256, the second byte contains the remainder (MOD) of that division. The trace data transfer is ended with an EOI.

Trace Data Transfers with TDF B

**Example of how data is returned:** For the same trace A data that is used in the TDF P description, querying trace A with the TDF B format and MDS set to binary (MDS B) would return the ASCII character codes for the following:

(8000 div 32)(7000 div 32)(6000 div 32)(the number for 6000 div 32 is repeated 398 times)

If MDS is set to W, querying trace A with the TDF B format would return the ASCII character codes for following:

(8000 div 256)(8000 mod 256)(7000 div 32)(7000 mod 256)(6000 div 256)(6000 mod 256)(the number for 6000 div 256, then the number for 6000 mod 256 is repeated 398 times)

#### TDF M

Description: TDF M is the measurement data format. The measurement data format transfers trace data in measurement units, and the measurement data can range from -32768 to

Restrictions: TDF M cannot be used to send trace data back to the instrument.

How trace data is returned: The following table describes what is transferred when the trace data format is set to M.

#### **TDF Trace Data Format**

#### Trace Data Transfers with TDF M


Example	Description	
TDF M;TA;	Transfers 401 bytes, with each trace value in measurement units. The trace data transfer is	
	ended with a carriage return, a line feed with an EOI.	

Example of how data is returned: For the same trace A data that is used in the TDF P description, querying trace A with the TDF M would return the ASCII character codes for the following:

8000,7000,6000,(6000 repeated 398 times), < CR > < LF >

Refer to the section, "Different Formats for Trace Data Transfers," in Chapter 3 for more information about transferring trace data.

## **Query Response**



QTDF


XTH

## $\mathbf{TH}$

## **Threshold**

Clips signal responses below the threshold level.

## **Syntax**



Item	Description/Default	Range
Number	Any real or integer number.	Range dependent on
		RL setting.

Equivalent Softkeys:

THRESHLD ON OFF

Preset State:

Clip off, positioned at the bottom graticule line.

Step Increment:

One division

Related Commands:

AUTO, DL, MEANTH, MKPK, PEAKS, RL

# Example

OUTPUT 718; "TH UP;" Increases the threshold level.

#### TH Threshold

### **Description**

The TH command clips signal responses below the threshold level. The threshold level is eight graticule divisions below the top of the screen unless otherwise specified. The threshold level is annotated in reference level units at the lower-left corner of the screen. AUTO deactivates clipping. The TH level is used for next peak marker movements (see "MKPK") and the PEAKS command even if the display clipping is off.

## **Query Response**




QQ 1

# **TIMEDATE Time Date**

Sets the time and date for the instrument's real-time clock.

### **Syntax**



XTIMEDATE

Item	Description/Default	Range
Number	A number representing the date and time in the	A valid date and time.
	YYMMDDHHMMSS (24 hour) format.	

Equivalent Softkeys:

Time Date

Related Commands:

SETDATE, SETTIME, TIMEDSP

## Example

OUTPUT 718; "TIMEDATE 881231135501;"


Sets the instrument time and date to 1:55:01 PM

on 31 December 1988.

### **Description**

The TIMEDATE command sets the time and date for the instrument's real-time clock in the YYMMDDHHHMMSS format.


## **Query Response**



# TIMEDSP Time Display

Enables the display of the time and date.

## **Syntax**



XTIMEDSP.

Equivalent Softkeys:

TIMEDATE ON OFF

Related Commands:

ANNOT, SETDATE, SETTIME, TIMEDATE


## Example

OUTPUT 718; "TIMEDSP OFF;"

## **Description**

The TIMEDSP command enables the display of the time and date on the instrument screen.

## **Query Response**




QQ2

# TITLE Title

Activates the screen title mode.

### **Syntax**



Item	Description/Default	Range
Delimiter	Matching characters marking the beginning and end of the list of	~ \@=/~\$%;!':
	instrument commands.	" &

Equivalent Softkeys:

the softkeys accessed by Change Title

Related Commands:

IP, SAVES

## Example

OUTPUT 718; "TITLE "ADJUST ANTENNA"; " Displays "ADJUST ANTENNA" on the screen.

## Description

The TITLE command activates the screen title mode. The title is displayed above the top graticule and is left justified. The full width of the display is available for writing a maximum of 40 characters. However, the marker readout may interfere with the last 26 characters. IP clears the title.


The SAVET command saves the screen title along with the trace in the trace register.

#### TM

## **Trigger Mode**

Selects a trigger mode.

### **Syntax**



MTX

Equivalent Softkeys:

the softkeys accessed by (TRIG)

Related Commands:

DL

### Example

OUTPUT 718; "TM EXT;" Activates the external trigger mode.

## **Description**

The TM command selects a trigger mode: free, line, video, or external. The conditions of the four trigger modes are as follows:

FREE allows the next sweep to start as soon as possible after the last sweep. The functions of TM FREE and FREE RUN are identical.

VID allows the next sweep to start if the trace data rises across a level set by the display line. The functions of TM VID and VIDEO are identical.


LINE allows the next sweep to start when the line voltage passes through zero, going positive. The functions of TM LINE and LINE are identical.

allows the next sweep to start when an external voltage level passes through approximately 1.5 V, going positive. The external trigger signal level must be between 0 V and +5 V. Connect the external trigger to the EXT TRIG INPUT. The functions of TM EXT and EXTERNAL are identical.

Note

Some instrument functions are not performed until the instrument is triggered.

# **Query Response**




ΩТМ

## TRA/TRB/TRC

# **Trace Data Input and Output**

The TRA/TRB/TRC commands provide a method for returning or storing 16-bit trace values.

## **Syntax**



XTRA

Use the same syntax for TRB and TRC as shown for TRA, just substitute TRB or TRC for TRA.

Item	Description/Default	Range
Number	Any real or integer number.	Integer number range
Msb length	Most significant byte of a two-byte word that describes the number of bytes transmitted.	
Lsb length	Least significant byte of a two-byte word that describes the number of bytes transmitted.	
Data byte	8-bit byte containing numeric or character data.	
Data byte & EOI	8-bit byte containing numeric or character data followed by END.	

Related Commands:

LOAD, RCLT, SAVET, STOR, TDF

## Example

10 REAL Trace_a(1:401)	Creates a 401-point trace array.
20 OUTPUT 718;"IP;"	Initializes instrument.
30 OUTPUT 718;"TDF P;"	Changes the format for real numbers.
40 OUTPUT 718; "SNGLS;"	
50 OUTPUT 718;"CF 300MHZ;"	Changes the center frequency.
60 OUTPUT 718;"SP 200MHZ;"	Changes the span.
70 OUTPUT 718;"TS;"	
80 OUTPUT 718;"MKPK HI;"	
90 OUTPUT 718;"MKCF;"	Moves peak to center of screen.
100 OUTPUT 718;"TS;"	Updates measurement trace.
110 OUTPUT 718;"TRA?;"	Gets the trace data.

#### 4-428 Programming Commands

#### TRA/TRB/TRC Trace Data Input and Output

120 ENTER 718; Trace\_a(\*)
130 OUTPUT 718; "CONTS;"

Activates continuous sweep mode.

140 END

### Description


The TRA/TRB/TRC commands provide a method for returning or storing 16-bit trace values.

Trace data that is input in the A-block or the I-block format is treated as measurement units independent of trace data format (TDF). Enter words in measurement units only. The output format is specified according to TDF and MDS.

The command may be used to input integer data to traces. See "Saving Trace Data" in Chapter 3. Because the lengths of trace A, trace B, and trace C are fixed, there are always 401 or 802 bytes transferred during binary input or binary output mode, respectively.

### **Query Response**

The form of the query response is dependent upon the previously used TDF and MDS commands as follows:




## **TRCMEM**

# **Trace Memory**

Indicates the number of trace registers available for SAVET and RCLT.

### **Syntax**



XTRCMEM

Related Commands:

DISPOSE, RCLT, SAVET, TRDEF

## Example

OUTPUT 718; "TRCMEM?;" Gets the total number of trace registers.
ENTER 718; Number
DISP Number

### Description

The TRCMEM command returns a positive integer that indicates the total number of trace registers available for SAVET and RCLT. The value of TRCMEM is displayed on the instrument display when you save a trace, limit-line table, or table of amplitude correction factors in instrument memory with Trace -> Intern1.

## **Query Response**




QQ1

## **TRDEF**

## **Trace Define**

Creates a user-defined trace.

## **Syntax**



Item	Description/Default	Range
Character	Any valid character.	2 to 11 characters long, A through Z and the underscore (the underscore should be used as the second character of the label).
User-defined variable	A variable defined by VARDEF	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	
Number	Any real or integer number.	2 to 2047.

Parameter Value:

2 to 2047

Prerequisite Commands: VARDEF when using a user-defined variable

Related Commands:

DISPOSE

## Example

OUTPUT 718; "TRDEF NEW, 100;"

Defines a trace called NEW.


#### **TRDEF Trace Define**

## Description

The TRDEF command defines a trace and the number of points the trace will contain. Each trace element consists of 16 bits and stores the trace amplitude in measurement units. See the description for the TDF M format that is described in "Different Formats for Trace Data Transfers" in Chapter 3 for more information about measurement units.

## **Query Response**

The query response returns the number of trace elements in the trace.




QQ1

# **TRDSP**

# **Trace Display**

Turns on or off the display of trace A, B, or C.

## **Syntax**



XTRDSP

Related Commands:

TRPRST, TRSTAT

## Example

OUTPUT 718; "TRDSP TRA, OFF; "

## **Description**

The TRDSP command turns on or off the display of trace A, B, or C without clearing the trace (measurements can still be taken). TRDSP OFF reduces the time duration between sweeps.

## **TRPRST**

## **Trace Preset**

Sets the trace operations to their preset values.

### **Syntax**

TRPRST →(;)→

XTRPRST

Related Commands:

AMB, BLANK, CLRW, DISPOSE, DL, IP, TH

## Example

OUTPUT 718; "TRPRST;"

## Description

The TRPRST command sets the trace operations to their preset values. TRPRST executes these commands:

AMB OFF

AMBPL OFF

**BLANK TRB** 

**BLANK TRC** 

CLRW TRA

DL OFF

EM


TH OFF

## **TRSTAT**

#### **Trace Status**

Returns the status of traces A, B, and C.

### **Syntax**



Related Commands:

BLANK, CLRW, DET, MINH, TRDSP, VIEW

### Example

This example returns the measurement state of traces A, B, and C.

DIM States\$[40]

Declares array for results.

OUTPUT 718;"TRSTAT?;"

Returns the status results to the computer.

ENTER 718 USING "-K"; States\$


PRINT States\$

Prints out status of traces.

### Description

The TRSTAT command returns the status of traces A, B, or C: clear write, blank, view, minimum hold, or maximum hold.

### **Query Response**



QTRSTAT .

### TS

## Take Sweep

Starts and completes one full sweep before the next command is executed.

## **Syntax**



XTS

Related Commands:

SNGLS, TM

### Example

OUTPUT 718; "SNGLS; TS; "

Activates the single-sweep mode, and performs a take sweep.

### Description

The TS command starts and completes one full sweep before the next command is executed. A take sweep is required for each sweep in the single-sweep mode. TS prevents further input from the interface bus until the sweep is completed to allow synchronization with other instruments.

In the example below, the command sequence does not allow sufficient time for a full sweep of the specified span before VIEW is executed. Therefore, only the span set by the instrument is displayed in trace A.

OUTPUT 718; "IP; SNGLS; CF 400MHZ; SP 20KHZ; VIEW TRA; "

A TS command inserted before VIEW makes the instrument take one complete sweep before displaying trace A. This allows the instrument sufficient time to respond to each command in the

sequence.

OUTPUT 718; "IP; CF 400MHZ; SP 20MHZ; TS; VIEW TRA;"

TS is recommended before transmission of marker data and before executing marker operations such as peak search. This is because the active marker is repositioned at the end of each sweep. When the instrument receives a TS command, it is not ready to receive any more data until one full sweep has been completed. However, when slow sweep speeds are being used, the controller can be programmed to perform computations or address other instruments while the instrument completes its sweep.

Note


When MKPAUSE or MKSTOP are activated, TS considers the sweep complete when it reaches the active marker.

# **TWNDOW**

### Trace Window

Creates a window trace array for the fast Fourier transform (FFT) function.

### **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace Range	A segment of trace A, trace B, trace C, or a user-defined trace	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands: FFT

### Example

Connect calibrator signal to the instrument input.

OUTPUT 718; "IP; CALSW INT;" Initializes instrument. OUTPUT 718; "CF 300MHZ;" Changes the center frequency. OUTPUT 718; "SP OHZ; ST 800MS;" Changes span, sweep time. OUTPUT 718; "TRDEF NEW, 401;" Defines a trace called NEW. OUTPUT 718; "TWNDOW NEW, UNIFORM: " Trace NEW stores the window algorithm, UNIFORM. OUTPUT 718; "CLRW TRB;" OUTPUT 718; "SNGLS; TS; TS; " Activates single-sweep mode and updates trace. OUTPUT 718; "FFT TRA, TRB, NEW;" Performs fast Fourier transform on trace B and stores the results in trace A. OUTPUT 718; "BLANK TRB;" OUTPUT 718; "VIEW TRA;" Displays the result.


#### Description

The TWNDOW command creates a window trace array for the fast Fourier transform (FFT) function. The trace window function creates a trace array according to three built-in algorithms: UNIFORM, HANNING, or FLATTOP. When used with the FFT command, the three algorithms give resultant passband shapes that represent a give-and-take between amplitude uncertainty, sensitivity, and frequency resolution. See "FFT" for more information about these algorithms and the FFT function.

# **UDKDEFINE User-Defined Key**

Redefines a user-defined key.

### **Syntax**



xudkdef .

Equivalent Softkey:

DEFINE USER KEY

Related Commands:

UDKSET

### Example

10 PRINTER IS 1

20 OUTPUT 718; "UDKDEFINE;"

30 LOCAL 718

40 PRINT "Press a softkey on the instrument for a new USER-DEFINED KEY."

50 PRINT "Press 'Continue' on computer when finished."

60 PAUSE

70 OUTPUT 718; "UDKSET 2;"

80 END

### Description


The UDKDEFINE command sets the instrument in a mode for redefining a user-defined key. It freezes the display and presents instructions in the active function area. The mode is exited upon a UDKSET command which is issued remotely or by pressing one of two user-defined keys. IP and POWERON will also exit this mode.

#### **UDKSET**

## **User-Defined Key Set**

Changes the definition of a user-defined key.

#### **Syntax**



xudkset .

Equivalent Softkey:

DEFINE USER KEY

Related Commands:

**UDKDEFINE** 

#### Example

```
10 PRINTER IS 1
```

20 OUTPUT 718; "UDKDEFINE;"

30 LOCAL 718

40 PRINT "Press a softkey on the instrument for a new USER-DEFINED KEY."

50 PRINT "Press 'Continue' on computer when finished."

60 PAUSE

70 OUTPUT 718; "UDKSET 2;"

80 END

### Description

The UDKSET command changes the definition of one of the two user-defined keys. It replaces the key label and function of the user-defined key with the last softkey pressed prior to the executing the UDKSET command.


UDKSET 1 replaces the top user-defined softkey.

UDKSET 2 replaces the bottom user-defined softkey.

# UNRANGE UnRange

Restores the reference level to the value that was set prior to the last matching RANGE command.

## **Syntax**



xunrnge .

Related Commands:

RANGE

## Example

OUTPUT 718; "UNRANGE PK;"

## Description

The UNRANGE command restores the reference level, to the value that was set, prior to the last matching RANGE command.

 $\mathbf{UP}$ 

Up

Increases the value of the active function.

## **Syntax**



UP

Related Commands:

See the list of active functions listed in the description for UP.

### Example

OUTPUT 718; "IP; MKN; IFBW 10KHZ; MKPK NH; UP; "

Increases the intermediate frequency bandwidth to 30 kHz because MKPK NH does not change the active function.

### **Description**

The UP command increases the value of the active function by the applicable step size. Before executing UP, be sure that the function to be increased is the active function. For example, the programming example increases the resolution bandwidth, because marker peak (MKPK) is not an active function.


The active functions are: AVBW, AT, CF, DL, FA, FB, FMGAIN, IFBW, LG, MKA, MKD, MKFCR, MKN, MKPAUSE, MKPX, ML, NRL, RB, RCLS, ROFFSET, RL, RLPOS, SAVES, SETDATE, SETTIME, SP, SQLCH, SRCALC, SRCAT, SRCPOFS, SRCPSWP, SRCPWR, SRCTK, SS, ST, TH, VB, and VBR.

### **VARDEF**

### Variable Definition

Creates a user-defined variable and assigns it a value.

### **Syntax**



Item	Description/Default	Range
Character	Any valid character.	2 to 11 characters long, A through Z and the underscore (the underscore should be used as the second character of the label).
Number	Any real or integer number.	Real number range.
User-defined variable	A variable defined by VARDEF.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Predefined function	Function that returns a value. Refer to Table 4-1.	
Trace element	An element of trace A, trace B, trace C, or a user-defined trace.	

Related Commands:

DISPOSE, TRDEF

### Example

OUTPUT 718; "VARDEF V\_AR,O;"

DISP "ENTER THE VALUE OF THE VARIABLE USING THE INSTRUMENT KEYS"

OUTPUT 718;"V\_AR EP;"

OUTPUT 718;"V\_AR?;"

ENTER 718;N

PRINT N

OUTPUT 718;"IP;"

OUTPUT 718;"V\_AR?;"

Defines variable called  $V\_AR$  and assigns it a value of  $\theta$ .

The value of  $V\_AR$  is changed by using the front-panel controls.

Returns entered value of  $V\_AR$  to the computer.

Displays value on the computer screen. Initializes instrument.

The value of  $V\_AR$  changes to its initial value after an IP.

ENTER 718;N PRINT N

Displays "0."

### **Description**

The VARDEF command creates a user-defined variable and assigns it a value. User-defined variables can be used in many of the instrument remote-control processes. Use user-defined variables wherever "user-defined variable" appears in the syntax diagrams. An instrument preset (IP) sets user-defined variables to their initial value (see example).

An error results if a variable name is the same as any reserved word. Table 4-2 lists reserved words.


User-defined variables occupy instrument memory. Use the DISPOSE command to clear user-defined variables from memory.

### **VARIANCE**

# Variance of Trace Amplitudes

Returns the amplitude variance of the specified trace.

### **Syntax**



XVARIANCE

Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. TS when using trace data.

Related Commands: MEAN, RMS

#### Example

OUTPUT 718; "IP;" Initializes instrument.

OUTPUT 718; "SNGLS; TS;" Activates single-sweep mode.

OUTPUT 718; "VARIANCE TRA?;" Returns variance of trace A to computer.

ENTER 718; Number Stores value in computer variable.

DISP Number; "MEASUREMENT UNITS" Displays the results on computer screen.

### Description


The VARIANCE command returns the amplitude variance of the specified trace, in measurement units. Taking the square root of a variance yields the standard deviation value.

The formula to calculate the variance is as follows:

$$\frac{\sum_{i=1}^{n} (\overline{x} - x_i)^2}{n-1}$$

- n represents the number of data points.
- $x_i$  represents a data point.
- $\overline{x}$  represents the mean of data.

# **Query Response**




QQ1

### **VAVG**

## Video Average

Enables the video-averaging function.

## **Syntax**



XVAVG

Item	Description/Default	Range
Number	Any valid integer. Default is 100.	1 to 16384.

Equivalent Softkeys:

VID AVG ON OFF

Related Commands:

AUTO, CLRAVG, IP, SMOOTH

## Example


OUTPUT 718; "VAVG 150;"

Video averages the trace.

### Description

The VAVG command enables the video-averaging function, which averages trace points to smooth the displayed trace. Use VAVG to view low-level signals without slowing the sweep time. Video averaging can lower the noise floor by more than a 30 Hz average video bandwidth if a large number of sweeps has been specified for averaging. VAVG may also be used to monitor instrument state changes (for example, changing bandwidths, center frequencies) while maintaining a low noise floor. The active function readout indicates the number of sweeps to be averaged; the default for the number of sweeps is 100 unless otherwise specified. Executing "VAVG OFF;" turns off video averaging. Executing "VAVG ON;" turns on video averaging.

## **Query Response**



QQ 1


XVB

## **VB**

# Video Bandwidth

Specifies the video bandwidth.

## **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number. Default unit is Hz.
 30 Hz to 3 MHz.

Equivalent Softkeys:

AVG BW AUTO MAN

Preset State:

1 MHz

Step Increment:

In a 1, 3, 10 sequence

Related Commands:

AUTO, AVBW, IFBW, RB, SP, ST, VBR

## Example

OUTPUT 718;"VB 10KHZ;"

Changes the video bandwidth to 10 kHz.


#### **VB Video Bandwidth**

## Description

The VB command specifies the video bandwidth, which is a post-detection, low-pass filter. The resolution bandwidth, video bandwidth, and sweep time are normally coupled to the span. Executing VB uncouples video bandwidth from resolution bandwidth (it does nothing to the sweep-time, resolution-bandwidth, and span coupling). Executing AUTO recouples video bandwidth to the resolution bandwidth.

Frequency values other than the values in the 1, 3, 10 sequence are rounded to the nearest permissible value.

### **Query Response**



Note

Responses to "VB?;" query are rounded to the closest whole number in Hertz. Therefore, the response to the "VB;" query may be incorrect in certain cases when the average detector is in use. Due to this situation we recommend using the AVBW command which does not have this limitation.


XVBR

### **VBR**

## Video Bandwidth Ratio

Determines the automatic setting of video bandwidth.

## **Syntax**



 Item
 Description/Default
 Range

 Number
 Any valid real number.
 0 to 3000000

Equivalent Softkeys:

AV/IF RATIO

Preset State:

0.300

Step Increment:

1, 3, 10 sequence

Related Commands:

AUTO, AVBW, IFBW, RB, SP, VB

### Example


OUTPUT 718; "VBR 1;"

## Description

The VBR command determines the automatic setting of video bandwidth by multiplying the parameter by the resolution bandwidth. Ratio values other than the values in the 1, 3, 10 sequence are rounded to the nearest permissible value.

VBR returns a real number when used as a predefined variable.

## **Query Response**




## **VIEW**

## **View Trace**

Stops taking new data into the viewed trace.

## **Syntax**



XVIEW

Equivalent Softkeys:

VIEW A, VIEW B, and VIEW C

Related Commands:

BLANK, CLRW, MINH, MXMH

## Example


OUTPUT 718; "VIEW TRA;"

## Description

The VIEW command displays trace A, trace B, or trace C, and stops taking new data into the viewed trace. In the VIEW mode the trace is not updated. When VIEW is executed, the contents of the trace are stored in display memory.

## WAIT Wait

Suspends all instrument operation for the specified time duration.



TIAWX

Item	Description/Default	Range
Number	Any real or integer number. Default unit is seconds.	1 ms to 1000 s.

## Example

- 130 OUTPUT 718; "TRDSP TRA,OFF; TS;" Blanks trace A.
- 140 OUTPUT 718; "WAIT 2SC;" Suspends instrument operation for 2 seconds.
- 150 OUTPUT 718; "TRDSP TRA,ON;" Displays trace A.

## Description

The WAIT command suspends all instrument operation for the specified time.

## WINNEXT **Window Next**

Selects the upper or lower window as the active window.

## **Syntax**

WINNEXT

XWINNE XT

Equivalent Key:

(NEXT)

Related Commands:

WINON, WINOFF

## Example

OUTPUT 718; "WINON;"

Turns on the windows display mode.

OUTPUT 718; "WINNEXT;"

Selects the window that is currently not active to be the active

window.

## **Description**

The WINNEXT command selects the upper or lower window as the active window. When the windows display mode is activated, there will be two windows displayed on the screen. Only one of the windows is active (the currently active window will have a highlighted line around the graticule). You can use the WINNEXT command to select the active window.

## WINOFF Window Off

Turns off the windows display mode.

## **Syntax**

WINOFF

XWINOFF .

Equivalent Softkey:

WINDOWS OFF

Related Commands:

WINON

## Example

OUTPUT 718; "WINON;"

Turns on the windows display mode.

OUTPUT 718; "WINNEXT;"

Selects the window that is currently not active to be the active

window.

OUTPUT 718; "WINOFF;"

Turns off the windows display mode.

### **Description**

The WINOFF command turns off the windows display mode. When you execute WINON, there will be two windows displayed on the screen. You must execute WINOFF to turn the windows off and return to a single display, and the display will have the settings of the last active window. In contrast, WINZOOM also changes from two windows to one full screen display but does not exit the windows display mode; you can still access the second window by executing WINZOOM again.

## WINON Window ON

Displays the two windows on the display.

## **Syntax**

WINON ---

XWINON

Equivalent Key:

(CTRL)

Related Commands:

WINOFF, WINNEXT, WINZOOM

## Example

OUTPUT 718; "WINON;"

## Description

WINON activates the windows display mode and the zone marker.

#### Windows display mode:

When the windows display mode is first activated, there will be two windows displayed on the screen. Only one of the windows is active (the active window will have a highlighted line around the graticule). You can use the WINNEXT command to select the active window. The instrument state of the active window can be changed without affecting the state of the inactive window.

#### Zone marker:

The zone marker is shown in the upper window by two vertical lines. The frequency span between the two window. The zone marker can be moved and changed by using the ZMKCNTR, ZMKSPAN, ZMKPKNR, or ZMKPKNL programming commands. Changing the span or center frequency of the lower window will change the span or location of the zone marker on the upper window correspondingly.

Most programming commands can be executed when the windows display mode is used. Some functions cannot be used with the windows display mode, however. Table 4-9 lists the programming commands that, when executed, exit the windows display mode.

Table 4-9. **Programming Commands That Exit The Windows Display Mode** 

Command	Description
CAL	Performs the calibration routines.
IP	Performs an instrument preset.
LF	Performs an instrument preset into base band.

When in the windows display mode, saving the trace or state saves the state of the active window only. The recall state function recalls the stored state into the currently active window.

You must execute WINOFF to turn the windows off.

## **WINZOOM** Window Zoom

Expands the size of the window or displays both the upper and lower windows.

## **Syntax**

WINZOOM

XW1NZOOM

Equivalent Key:

(ZOOM)

Related Commands:

WINNEXT, WINON

## Example

OUTPUT 718; "WINON;"

Turns on the windows display mode.

OUTPUT 718; "WINZOOM;"

Expands the size of the active window.

## **Description**

The WINZOOM command is used to either expand the size of the active window so that it fills the entire display, or display both the upper and lower windows on the display.


The first time WINZOOM is executed, it expands the active window. Executing WINZOOM again restores the windows display mode so that both of the windows are displayed on the display.

## **XCH**

## Exchange

Exchanges the contents of sources 1 and 2.

## **Syntax**



Item	Description/Default	Range
User-defined trace	A trace defined by the TRDEF command.	Any valid trace name.
User-defined variable	A variable defined by VARDEF command.	Any valid variable name.
Predefined variable	A command that acts as a variable. Refer to Table 4-1.	
Trace range	A segment of trace A, trace B, trace C, or a user-defined trace.	

Prerequisite Commands: TRDEF when using a user-defined trace. VARDEF for a user-defined

variable. TS when using trace data.

Related Commands: AXB, BXC XXCH

### XCH Exchange

## Example

OUTPUT 718;"XCH TRA,TRB;" Exchanges the contents of trace A with trace B

## Description


The XCH command exchanges the contents of sources 1 and 2. When the source is longer than the destination, the source is truncated to fit. When the source is shorter than the destination, the last element is repeated to fill the destination.

## **XUNITS**

## **Transducer Conversion Units**

Selects the transducer conversion units for the AMPCOR correction factors.

## **Syntax**



xxunits

Equivalent Softkey:

Located under Edit Units

Related Commands:

AMPCOR, AUNITS

## Example

## Description

The XUNITS command selects the transducer conversion units for the AMPCOR antenna correction factors. This specifies the units of the physical attribute to which an antenna actually responds and which will be indicated on the display for reference level, display line level, threshold level, and marker readouts.

The AMPCOR antenna correction factors are interpreted as a model of your antenna. They specify a conversion between the signal at the input and the actual electric or magnetic field sensed by the antenna.

For example, if your antenna produces a 3  $\mu$ V signal in response to a 10  $\mu$ V/meter electric field at 400 MHz, the required correction is:

$$20 LOG (10 / 3) = 10.46 dB$$

specified by "AMPCOR ANTENNA, 400e6, 10.46" and the XUNITS setting is UVM.


Note	When AMPCOR antenna correction factors are ON, the current XUNITS is used. When AMPCOR antenna correction factors are OFF, the current AUNITS is used.
	doca.

## **ZMKCNTR**

## Zone Marker at Center Frequency

Positions the zone marker at the specified frequency.

## **Syntax**



XZMKCNTR

Item	Description/Default	Range
Number	Any real or integer number. Default unit is Hz.	Frequency range of
		the instrument.

Equivalent Softkey:

ZONE CENTER

Default value:

If a marker is onscreen, the frequency value of the marker. If a

marker is not onscreen, the instrument center frequency.

Related Commands:

CF, SP, WINON, ZMKSPAN

## Example

OUTPUT 718; "WINON;"

Turns on the windows display mode.

OUTPUT 718; "ZMKCNTR 300MHZ;"

Places the zone marker at 300 MHz.

## Description


The ZNKCNTR command positions the marker at the specified frequency. ZMKCNTR allows you to move the zone marker within the frequency range displayed in the upper window. When the lower window is the active window, changing the center frequency (CF) or frequency span (SP) of the lower window changes the position of zone marker in the upper window.

### **ZMKCNTR Zone Marker at Center Frequency**

**Restrictions:** Use ZMKCNTR only if the window is in non-zero span; ZMKCNTR does not apply if the window is in the time domain. The zone marker can be moved beyond the frequency range displayed by the upper window (the zone marker cannot exceed the frequency range of the instrument, however.) ZMKCNTR should only be used when the windows display mode is turned on.

You can use ZMKSPAN to change the span of the zone marker.

## **Query Response**



## **ZMKPKNL**

## Zone Marker for Next Left Peak

Places the zone marker at the next signal peak that is left of the zone marker's current position.

## **Syntax**



YZMKPKMI

Equivalent Softkey:

ZONE PK LEFT

Related Commands:

MKPX, WINON, ZMKCNTR, ZMKSPAN, ZMKPKNR

## Example

OUTPUT 718; "WINON: "

Turns on the windows display mode.

OUTPUT 718; "ZMKPKNL;"

Places the zone marker at the next peak to the left of the current

position of the zone marker.

## **Description**

ZMKPKNL does the following:

- 1. Searches for the next signal peak outside and to the left of the zone marker. ZMKPKNL only applies if the window is in a non-zero span; ZMKPKNL does not apply if the window is in the time domain.
- 2. If a peak is found, ZMKPKNL moves the zone marker so that it is centered around the peak. If a signal peak cannot be found, or the window is in zero span, the zone marker is not moved.
- 3. Changes the center frequency of the lower window to the frequency of the signal peak.

To be considered a signal peak, the signal must be greater than the peak excursion (see "MKPX" for more information about the peak excursion).

ZMKPKNL should only be used when the windows display mode is turned on.

## **ZMKPKNR**

## Zone Marker for Next Right Peak

Places the zone marker at the next peak to the right of the zone marker's current position.

## **Syntax**



XZMKPKNR

Equivalent Softkey:

ZONE PK RIGHT

Related Commands:

MKPX, WINON, ZMKCNTR, ZMKSPAN, ZMKPKNL

## Example

OUTPUT 718; "WINON;"

Turns on the windows display mode.

OUTPUT 718; "ZMKPKNR;"

Places the zone marker at the next peak to the right of the current

position of the zone marker.

## Description

ZMKPKNR does the following:

- Searches for the next signal peak outside and to the right of the zone marker. ZMKPKNR only applies if the window is in a non-zero span; ZMKPKNR does not apply if the window is in the time domain.
- 2. If a peak is found, moves the zone marker so that it is centered around the peak. If a signal peak cannot be found, or the window is in zero span, the zone marker is not moved.
- 3. Changes the center frequency of the lower window to the frequency of the signal peak.

To be considered a signal peak, the signal must be greater than the peak excursion (see "MKPX" for more information about the peak excursion).


ZMKPKNR should only be used when the windows display mode is turned on.

## **ZMKSPAN**

## **Zone Marker Span**

Changes the width of the zone marker.

## **Syntax**



 Item
 Description/Default
 Range

 Number
 Any real or integer number. Default unit is Hz.
 0 to maximum frequency span of the instrument.

Equivalent Softkey:

ZONE SPAN

Default value:

1/10 of the frequency span of the instrument

Related Commands:

SP, WINON, ZMKCNTR

## Example

OUTPUT 718; "WINON;"

Turns on the windows display mode.

OUTPUT 718; "ZMKSPAN 100MHZ;"

Sets the span of the zone marker to 100 MHz.


XZMKSPAN

## Description

The ZMKSPAN command allows you to change the frequency span of the zone marker that is displayed in the upper window. When the lower window is the active window, frequency span (SP) of the lower window changes the frequency span of zone marker in the upper window.

**Restrictions:** Use ZMKSPAN only if the window is in non-zero span; ZMKSPAN does not apply if the window is in the time domain. ZMKSPAN should only be used when the windows display mode is turned on.

## **Query Response**



		·	
			0

## **Error Messages**

The instrument can generate various messages that appear on its screen during operation to indicate a problem.

There are three types of messages: hardware error messages (H), user-created error messages (U), and informational messages (M).

- Hardware error messages indicate the instrument hardware is probably broken.
- User-created error messages appear when the instrument is used incorrectly. They are usually generated during remote operation (entering programming commands using either a controller or the external keyboard).
- Informational messages provide information indicating the progress of the instrument within a specific procedure.

The messages are listed in alphabetical order on the following pages; each message is defined. and its type is indicated by an (H), (U), or (M),

#### φ LOCK OFF

Indicates slow YTO tuning. This message may appear if the instrument is using default correction factors. If this message appears constantly, perform the self-calibration routine to try to eliminate this message.  $\phi$  LOCK OFF appears briefly during the self-calibration routine, during instrument preset, or when the frequency value is changed; this is normal and does not indicate a problem. (U) and (H)

#### ADC-2V FAIL

Indicates a hardware failure. (H)

#### ADC-GND FAIL

Indicates a hardware failure. (H)

#### ADC-TIME FAIL

Indicates a hardware failure. (H) and (U)

#### Bad device type in msus

An attempt has been made to read a disk that is neither LIF nor DOS format or a communication failure between the main processor and the floppy disk subsystem. If the disk in use is LIF or DOS format, try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative. (U) (H)

## Bad mass storage parameter

May be reported if an attempt is made to read a disk that is neither LIF nor DOS format. Attempt a catalog operation on the disk or try a different disk. (U)

#### Bad mass storage volume label

May be reported if an attempt is made to read a disk that is neither LIF nor DOS format. Attempt a catalog operation on the disk or try a different disk. (U)

#### Bad mass storage volume spec

May be generated if the user removes media while it is being accessed or if a read or write

operation is attempted on unformatted media. Try the operation again or try the operation on media you are sure has been appropriately formatted.

Cal harmonic >= 5.7 GHz NOT found For an HP 8546A/HP 85462A only.

Indicates that the CAL YTF routine cannot find a harmonic of the 300 MHz calibration signal. If this happens, perform the CAL FREQ and CAL AMP routines, and then perform the CAL YTF routine again. For the HP 8546A, press CAL ALL then perform the CAL YTF routine again. (U) and (H)

#### CAL: MAIN COIL SENSE FAIL

The instrument could not set up span sensitivity of the main coil. If this message appears, press (FREQUENCY), CENTER FREQ, -37, (Hz), (CALIBRATE), More 1 of 3, More 2 of 3, DEFAULT CAL DATA, and perform the self-calibration routine again. (H)

#### CAL: NBW 200 Hz notch amp failed

Indicates that the 200 Hz IF bandwidth is not the correct shape for the calibration routine. (H)

#### CAL: NBW 200 Hz notch failed

Indicates that the 200 Hz IF bandwidth is not the correct shape for the calibration routine. (H)

#### CAL: NBW 200 Hz width failed

Indicates that the 200 Hz IF bandwidth is not the correct bandwidth for the calibration routine. (H)

#### CAL: NBW gain failed

Indicates that one of the IF bandwidths is not the correct amplitude for the calibration routine. (H)

#### CAL: NBW width failed

Indicates that one of the IF bandwidths is not the correct width for the calibration routine. (H)

#### CAL: PASSCODE NEEDED

Indicates that the function cannot be accessed without the pass code. For the DEFAULT CAL DATA function, the pass code is setting the center frequency of the instrument to -37 Hz. (M)

### CAL: RES BW AMPL FAIL

The relative insertion loss of the IF bandwidth is incorrect. This message also sets SRQ 110. (H)

#### CAL SIGNAL NOT FOUND

Indicates the calibration signal cannot be found. Check that the instrument input connectors are connected properly. If the calibration signal is connected properly but cannot be found, press FREQUENCY, CENTER FREQ, -37, Hz, CALIBRATE, More 1 of 3, More 2 of 3, DEFAULT CAL DATA. If the calibration signal still cannot be found, press FREQUENCY, CENTER FREQ, -37, Hz and perform the CAL FREQ and CAL AMP (receiver RF section) or CAL ALL (EMI receiver) self-calibration routines. This message also sets SRQ 110. (U) and (H)

#### CAL: SPAN SENS FAIL

The self-calibration span sensitivity routine failed. This message also sets SRQ 110. (H)

#### CAL: USING DEFAULT DATA

Indicates that the calibration data is corrupt and the default correction factors are being used. Interruption of the self-calibration routines or an error can cause this problem. (M)

### CAL YTF FAILED For an HP 8546A/HP 85462A only.

Indicates that the CAL YTF routine could not be successfully completed. Perform the self-calibration routines, then perform the CAL YTF routine again. (U) and (H)

#### CAL: ZERO FAIL

The instrument could not set up the tuning sensitivity of the main coil. If this message appears, press FREQUENCY, CENTER FREQ, -37, (Hz), CALIBRATE, More 1 of 3, More 2 of 3, DEFAULT CAL DATA, and perform the self-calibration routines again. (H)

#### Cannot engage phase lock with current CAL FREQ data

Indicates that the CAL FREQ routine needs to be performed before phase locking can be turned on. (U)

### Cannot BYPASS Input 1

An attempt was made to execute the BYPASS command while the signal path is routed through INPUT 1 of the RF filter section. Only INPUT 2 of the RF filter section can be bypassed.

#### Checkread error

This error may be due to conflicting disk operations invoked from the front-panel keys and the remote I/O port, or it may indicate that the disk is corrupt. After pressing the "HOLD" key, (ENTER), on the front panel, retry the operation. If the operation fails again, check the disk using the catalog function. (U)

#### COMMAND ERROR:\_ \_ \_

The specified programming command is not recognized by the instrument. (U)

### **Configuration Error**

This error indicates a serious problem in the ability of the instrument to use the floppy disk drive. Try presetting the instrument. If the condition persists, contact your HP representative. (H)

#### CONF TEST FAIL

Indicates that the confidence test failed. Perform the self-calibration routines, and then perform the confidence test again. This message also sets SRQ 110. (H) and (U)

#### Directory not empty

Reported if an attempt is made to purge a non-empty directory. Ensure that all files in any directory have been purged or moved before attempting to purge the directory. (U)

## Directory overflow

Reported if the disk directory runs out of room. Change the media. (M)

#### Drive not found or bad address

An attempt has been made to read a disk that is neither LIF nor DOS format or a communications failure between the main processor and the floppy disk subsystem. If the disk in use is LIF or DOS format, try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative. (U) (H)

## Duplicate file name

Reported if the file system tries to write data to a file that already exists, but did not exist previously. May be due to changing media just before an operation attempts to create a new file. (U)

#### Duplicate file name, PROTECT is on

Reported if the user attempts to overwrite a previously existing file with PROTECT status set to ON (the default state). Use a different file name, purge the file, or turn off the PROTECT feature. (U)

#### End of file or buffer found

Reported if an attempt is made to read or write beyond the current file or directory is made. Also reported if an attempt is made to add files to a directory that is already full. Try using a new disk. (U)

### End of rec found, random mode

Reported if an attempt is made to read or write beyond the current record being accessed. Try the operation again. (U)

#### FAIL:\_ \_ \_

An error was discovered during the power-up check. The 4-digit by 10-digit code indicates the type of error. (H)

#### File name is undefined

May be reported if the user changes media immediately before a read operation is attempted on a file of a specific name. Ensure that the file exists on the disk by using the catalog feature. (U)

#### File not currently assigned

May be generated if the user removes media while it is being accessed. Try the operation again. (U)

#### File open on target device

May be due to conflicting file operations invoked simultaneously from the front-panel keys and the remote I/O port. Attempt the operation again. (U)

### File type incompatible

Indicates that the selected file is not a display image file. The file name for a display image file is always preceded by an "i." (U)

#### FREQ UNCAL

The FREQ UNCAL message appearing constantly, indicates a YTO-tuning error. Perform the CAL FREQ (receiver RF section) or CAL ALL (EMI receiver) routines. (U) and (H)

#### Function not available in current Mode

Indicates that the function that you have selected can only be used with the instrument mode. You can use the MODE key to select the instrument mode. (U)

#### HFS disc may be corrupt

This error may be due to conflicting disk operations invoked from the front-panel keys and the remote I/O port, or it may indicate that the disk is corrupt. After pressing the "HOLD" key, (ENTER), on the front panel, retry the operation. If the operation fails again, check the disk using the catalog function. (U)

### Improper destination type

Reported if an attempt is made to append data to a file and the file cannot be extended. Try the operation using another disk. (U)

#### Improper file name

Reported if a file or directory name is specified that in some manner does not conform to file name conventions: too many characters, illegal character in file name, and so on.

#### Improper file type

Reported in the event that an operation appropriate for a data file is attempted on a directory. Check the contents of the disk using the catalog function. (U)

## Improper value or out of range

Indicates an internal error in computing the amount of data to read from the disk or an invalid parameter. This may indicate corrupt media; try a new disk. If the condition persists, contact your HP representative. (H)

#### Incorrect unit code in msus

An attempt has been made to read a disk that is neither LIF nor DOS format or a communications failure between the main processor and the floppy disk subsystem. If the disk in use is LIF or DOS format, try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative. (U) (H)

#### Incorrect volume code in msvs

An attempt has been made to read a disk that is neither LIF nor DOS format or a communications failure between the main processor and the floppy disk subsystem. If the disk in use is LIF or DOS format, try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative, (U) (H)

#### **Insufficient Memory**

Indicates a temporary memory overflow condition. Attempt to free memory that may have been temporarily allocated by performing the following steps:

- 1. If there is a disk catalog on the display, exit the catalog.
- 2. Execute the dispose softkeys under Dispose User Hem in the (CONFIG) menu. (U)

#### **INTEGER overflow**

Indicates a computation error during disk access. This may indicate corrupt media; try a new disk. If the condition persists, contact your HP representative. (H)

#### Internal error

Indicates a failure of the floppy disk controller or a failure in communications between the main processor and the floppy disk controller. Try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative. (H)

#### INTERNAL LOCKED

The internal trace and state registers of the instrument have been locked. To unlock the trace or state registers, press (SAVE), Save Internal, SAV LOCK ON OFF so that OFF is underlined. (U)

#### INVALID AMPCOR: FREQ

For the AMPCOR command, the frequency data must be entered in increasing order. See the description for the AMPCOR programming command for more information. (U)

#### INVALID ENTER FORMAT

The enter format is not valid. See the appropriate programming command description to determine the correct format. (U)

#### INVALID <file name> NOT FOUND

Indicates that the specified file could not be loaded into internal memory or purged from memory because the file name cannot be found. (U)

#### INVALID FILENAME \_ \_ \_

Indicates the specified file name is invalid. A file name is invalid if there is no file name specified, if the first letter of the file name is not alphabetic, or if the specified file type does not match the type of file. See the description SAVRCLW or STOR programming commands for more information. (U)

#### INVALID FILE: NO ROOM

Indicates that there is insufficient space available on the floppy disk to store the data. (U)

#### INVALID HP-IB ADRS/OPERATION

An HP-IB operation was aborted due to an incorrect address or invalid operation. Check that there is only one controller (the EMI receiver) connected to the printer or plotter. (U)

#### INVALID HP-IB OPERATION REN TRUE

The HP-IB operation is not allowed. (This is usually caused by trying to print or plot when a controller is on the interface bus with the instrument.) To use the instrument print or plot functions, you must disconnect any other controllers on the HP-IB. If you are using programming commands to print or plot, you can use an HP BASIC command instead of disconnecting the controller. See the description for the PRINT command for more information. (U)

#### INVALID ITEM:\_ \_ \_

Indicates an invalid parameter has been used in a programming command. (U)

#### INVALID KEYLBL: \_ \_ \_

Indicates that the specified key label contains too many characters. A key label is limited to 8 printable characters per label line. (U)

#### INVALID KEYNAME:\_ \_ \_

The specified key name is not allowed. (The key name may have conflicted with a instrument programming command.) To avoid this problem, use an underscore as the second character in the key name, or avoid beginning the key name with the following pairs of letters: LB, OA, OL, TA, TB, TR, MA, MF, TS, OT, and DR. (U)

#### INVALID OUTPUT FORMAT

The output format is not valid. See the appropriate programming command description to determine the correct format. (U)

## INVALID RANGE: Stop < Start

Indicates that the first trace element specified for a range of trace elements is larger that ending trace element. When specifying a trace range the starting element must be less than the ending element. For example, TRA[2,300] is legal but TRA[300,2] is not. (U)

#### INVALID REGISTER NUMBER

The specified trace register number is invalid. (U)

#### **INVALID RS-232 ADRS/OPERATION**

An RS-232 operation was aborted due to an invalid operation. (U)

#### INVALID SAVE REG

Data has not been saved in the specified state or trace register, or the data is corrupt. (U)

#### INVALID SCRMOVE

Indicates the instrument may have a hardware failure. (H)

#### INVALID START INDEX

Indicates that the first trace element specified for a range of trace elements is not within the trace range of the specified trace. (U)

#### INVALID STOP INDEX

Indicates that the ending trace element specified for a range of trace elements is not within the trace range of the specified trace. (U)

## INVALID TRACE: \_ \_ \_

The specified trace is invalid. (U)

### INVALID VALUE PARAMETER: \_ \_ \_

The specified value parameter is invalid. (U)

#### INVALID WINDOW TYPE: \_ \_ \_

The specified window is invalid. See the description for the TWNDOW programming command. (U)

#### LOST SIGNAL

This message indicates that an internal hardware connection problem exists. (H)

#### LO UNIVL

Indicates that the local oscillator in the EMI receiver distribution amplifier is not functioning properly. (H)

#### **Marker Count Reduce SPAN**

Indicates the IF bandwidth to span ratio is too small to use the marker count function. Check the span and IF bandwidth settings. (U)

#### Marker Count Widen RES BW

Indicates that the current IF bandwidth setting is too narrow to use with the marker counter function. The marker counter function can be in narrow IF bandwidths (bandwidths that are less than 1 kHz) with the following procedure:

- 1. Place the marker on the desired signal.
- 2. Increase the IF bandwidth to 1 kHz and verify the marker is on the signal peak.
- 3. If the marker in on the signal peak, the marker count function can be used in either the 1 kHz IF bandwidth or the original narrow IF bandwidth setting. If the marker is not on the signal peak, it should be moved to the signal peak and the marker counter function should not be used with a IF bandwidth setting of less than 1 kHz. (U)

#### Mass storage hardware failure

Indicates a failure of the floppy disk controller or a failure in communications between the main processor and the floppy disk controller. Try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative. (H)

#### Mass storage medium overflow

Reported when a disk has no more room available to write data. Try a new disk. (U)

#### Mass storage system error

Indicates a failure of the floppy disk controller or a failure in communications between the main processor and the floppy disk controller. Try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative.

#### Mass storage volume not present

An attempt has been made to read a disk that is neither LIF nor DOS format or a communications failure between the main processor and the floppy disk subsystem. If the disk in use is LIF or DOS format, try turning the instrument off, wait a few seconds, then turn the instrument on again. If the condition persists, contact your HP representative. (U) (H)

### **MEAS UNCAL**

The measurement is uncalibrated. Check the sweep time, span, and bandwidth settings, or press (AUTO COUPLE), AUTO ALL. (U)

#### Medium changed or not in drive

Reported if disk is removed during disk access cycle. Try the operation without removing the disk. (U)

#### Medium uninitialized

Indicates that a file operation has been attempted on an uninitialized disk, or on a disk that is neither LIF nor DOS format. Be sure that any disk on which file operations are attempted is properly formatted. The format softkeys, in the (CONFIG) menu, may be used to format a disk, but any information on the disk will be erased during the formatting process. (U)

#### No points defined

Indicates the specified limit line or amplitude correction function cannot be performed because no limit line segments or amplitude correction factors have been defined. (U)

#### Operation failed on some files

Reported if, during a purge operation on a file specifier that contains wildcards, the number of files actually purged does not match the original number of files found that match the file specifier. Check the disk using the catalog function. (U)

### Operation not allowed on open file

May be due to conflicting file operations invoked simultaneously from the front-panel keys and the remote I/O port. Attempt the operation again. (U)

#### OVEN COLD

Indicates that the EMI receiver has been powered up for less than 5 minutes. (The actual temperature of the precision frequency oven is not measured.) (M)

#### PARAMETER ERROR: \_\_\_

The specified parameter is not recognized by the instrument. See the appropriate programming command description to determine the correct parameters. (U)

#### PASSCODE NEEDED

Indicates that the function cannot be accessed without the pass code. (U)

#### Permission denied

Indicates that a file write-operation was attempted on either a read-only file or on a directory. Check the disk using the catalog function and try the operation on an appropriate file again. (U)

## Possibly corrupt file

This error may be due to conflicting disk operations invoked from the front-panel keys and the remote I/O port, or it may indicate that the disk is corrupt. After pressing the "HOLD" key, (ENTER), on the front panel, retry the operation. If the operation fails again, check the disk using the catalog function. (U)

#### POS-PK FAIL

Indicates the positive-peak detector has failed. (H)

#### RCVR Limits not allowed in SA mode

This error is encountered when an attempt is made to enable limit-line display, limit-margin display, or limit testing of limits defined in Receiver mode when the instrument is operating in Signal Analysis mode. To correct the problem, either purge the limits or switch to Receiver mode. (U)

#### Read data error

This error may be due to conflicting disk operations invoked from the front-panel keys and the remote I/O port, or it may indicate that the disk is corrupt. After pressing the "HOLD" key, (ENTER), on the front panel, retry the operation. If the operation fails again, check the disk using the catalog function. (U)

#### Record address error

This error may be due to conflicting disk operations invoked from the front-panel keys and the remote I/O port, or it may indicate that the disk is corrupt. After pressing the "HOLD" key, (ENTER), on the front panel, retry the operation. If the operation fails again, check the disk using the catalog function. (U)

### Record not found

This error may be due to conflicting disk operations invoked from the front-panel keys and the remote I/O port, or it may indicate that the disk is corrupt. After pressing the "HOLD" key, (ENTER), on the front panel, retry the operation. If the operation fails again, check the disk using the catalog function. (U)

#### REF UNLOCK

Indicates that the frequency reference is not locked to the external reference input. Check that the 10 MHz REF OUTPUT connector is connected to the EXT REF IN connector, or,

when using an external reference, that an external 10 MHz reference source of sufficient amplitude is connected to the EXT REF IN connector. (U) and (H)

#### Require 1 signal > PEAK EXCURSION above THRESHOLD

Indicates that the N dB PTS routine cannot locate a signal that is high enough to measure. The signal must be greater than the peak excursion above the threshold level to measure. (U)

#### Require 3 signals > PEAK EXCURSION above THRESHOLD

Indicates that the % AM routine cannot locate three signals that are high enough to measure. The signals must be greater than the peak excursion above the threshold level to measure. (U)

#### Require 4 signals > PEAK EXCURSION above THRESHOLD

Indicates that the TOI routine cannot locate four signals that are high enough to measure. The signals must be greater than the peak excursion above the threshold level to measure.

#### Required option not installed

Some instrument functions require that an option be installed in the instrument. See the description for the function in the User's Guide for more information about which option is required. (U)

#### **RF Filter Section Absent**

This message is displayed if the bypass command is executed when the RF filter section is not connected to, or is not communicating with, the receiver RF section. (U) and (H)

#### RFFS Error: COMMAND

The RF filter section has received a command that it does not recognize. Assure that there is no cable connected to the RF filter section Service Bus interface. If the condition persists, and there is no cable connected to the RF filter section Service Bus interface, contact your HP representative. (U)

#### RFFS Error: HARDWARE

The RF filter section has experienced a hardware failure. If the condition persists after presetting the instrument or cycling power, contact your HP representative. (H)

#### RFFS Error: TIMEOUT

Communication failure between the receiver RF section and the RF filter section. Check power to the RF filter section and check that the AUX interface cable is properly connected between both instruments. (U) (H)

#### **RFFS Service Bus Active**

This message appears in the active function area of the receiver RF section display when an external controller communicates with the RF filter section via the RF filter section Service Bus interface. (H)

#### RF PRESEL ERROR For an HP 8546A/HP 85462A only.

Indicates that the preselector peak routine cannot be performed. (H)

## RF PRESEL TIMEOUT For an HP 8546A/HP 85462A only.

Indicates that the preselector peak routine cannot be performed. (H)

#### SA Limits not allowed in RCVR mode

This error is encountered when an attempt is made to enable limit-line display, limit-margin display, or limit testing of limits defined in Signal Analysis mode when the instrument is operating in Receiver mode. To correct the problem, either delete the limits or switch to Signal Analysis mode. (U)

#### SAMPLE FAIL

Indicates the sample detector has failed. (H)

#### SIGNAL CLIPPED

Indicates that the current FFT measurement sweep resulted in a trace that is above the top graticule line on the display. If this happens, the input trace (trace A) has been "clipped," and the FFT data is not valid. (U)

### Signal not found

Indicates the PEAK ZOOM routine did not find a valid signal. (U)

#### Signals do not fit expected % AM pattern

Indicates that the % AM routine cannot perform the percent AM measurement because the onscreen signals do not have the characteristics of a carrier with two sidebands. (U)

### Signals do not fit expected TOI pattern

Indicates that the TOI routine cannot perform the third-order intermodulation measurement because the onscreen signals do not have the characteristics of two signals and two distortion products. (U)

#### SMPLR UNLCK

Indicates that the sampling oscillator circuitry is not functioning properly. If this message appears, check that the external frequency reference is correctly connected to the EXT REF INPUT. (U) and (H)

#### SOFTKEY OVFL

Softkey nesting exceeds the maximum number of levels. (U)

#### SRQ \_ \_ \_

The specified service request is active. (M)

#### STEP GAIN/ATTN FAIL

Indicates the step gain has failed. (H)

#### TABLE FULL

Indicates the upper or lower table of limit lines contains the maximum number of entries allowed. Additional entries to the table are ignored. (U)

#### TG SIGNAL NOT FOUND

Indicates the tracking generator output signal cannot be found. For the receiver RF section, check that the TRACKING GENERATOR OUTPUT is connected to the RF INPUT connector with an appropriate cable. For the EMI receiver, check that the cable between the TRACKING GENERATOR OUTPUT and TRACKING GENERATOR is properly connected. (U)

#### TG UNLVL

This message can indicate the following: that the source power is set higher or lower than the instrument can provide, that the frequency span extends beyond the specified frequency range of the tracking generator, or that the calibration data for the tracking generator is incorrect. (U)

#### Too many open files

This error may be due to conflicting disk operations invoked from the front-panel keys and the remote I/O port, or it may indicate that the disk is corrupt. After pressing the "HOLD" key, (ENTER), on the front panel, retry the operation. If the operation fails again, check the disk using the catalog function. (U)

#### Too many signal with valid N dB points

Indicates the N dB PTS function has located two or more signals that have amplitudes within the specified dB from the signal peak. If this happens, you should decrease the span of the instrument so that only the signal that you want to measure is displayed. (U)

#### Trace A is not available

Indicates that trace A is in the store-blank mode and cannot be used for limit-line testing.

Use CLEAR WRITE A or VIEW A to change trace A from the store-blank mode to the clear write mode, and then turn on limit-line testing. (U)

#### Unable to replace file

Reported if an attempt is made to append data to a file and the file cannot be extended. Try the operation using another disk. (U)

#### USING DEFAULTS self cal needed

Indicates that the current correction factors are the default correction factors and that the self-calibration routines need to be performed. For either an HP 8546A or an HP 85462A, also perform the CAL YTF self-calibration routine. (U)

#### VID-BW FAIL

Indicates the averaging bandwidths have failed. (H)

#### Wildcard matches > 1 item

An attempt was made to use the wildcard matching character on an operation that requires a specific file name. For example, an attempt to load from a file name that contains a wildcard character. Try the operation using a specific file name. (U)

#### Wildcards not allowed

An attempt was made to use the wildcard matching character on an operation that requires a specific file name. For example, an attempt to load from a file name that contains a wildcard character. Try the operation using a specific file name. (U)

#### Write protected

Indicates that a write operation was attempted on a disk that is write protected. Move the write-protect tab on the floppy disk to the unprotected position, reinsert the disk in the disk drive and attempt the operation again. (U)

## **Nonrecoverable System Errors**

Certain situations can create error conditions from which the main processor cannot recover. In the event that the processor detects a nonrecoverable error, the instrument will be initialized, the display will be blanked, and special error messages will be written to the display.

The following is a sample nonrecoverable system error message display.

Syste	m Error 4, HP	8546A, S	N 4		
13:18	3:20 DEC 13, 19	93, Rev:	931210		
	SR: 0000	PC:	00FFB370	00FF6F1E:	00009300
D0:	00000000	A0:	00FFB238	00FF6F22:	00000000
D1:	00000000	A1:	00FF803E	00FF6F26:	00000000
D2:	00FFB238	A2:	00FF803C	00FF6F2A:	00FF803E
D3:	00FF803E	A3:	00FFB2FE	00FF6F2E:	000031B1
D4:	00008E7D	A4:	00FFB2F4	00FF6F32:	0004065E
D5:	00FF80E8	A5:	00FC6948	00FF6F36:	0004EDE8
D6:	00FFB39A	A6:	FFFFFFE	00FF6F3A:	00FF8000
D7:	00FFB392	A7:	00FF6F1E	00FF6F3E:	00FF88AE
				00FF6F42:	00FF87E0
				00FF6F46:	00FFB03C
				00FF6F4A:	000C9AEA
				00FF6F4E:	00FF8890
				00FF6F52:	040800FF
				00FF6F56:	000900FF
				00FF6F5A:	B23A0000
WAR	WARNING: Config Settings Defaulted				
	Press COPY to	print er	ror report and		
	advise your lo	cal HP r	epresentative		•
Press	Press PRESET to resume operation				

When a nonrecoverable error message is displayed, the instrument will only respond to the front-panel COPY and PRESET keys. If you have a printer configured and connected to the instrument, and if no remote controller is currently connected to the I/O port through which the printer is connected, you can generate a hardcopy of the diagnostic part of the error message by pressing the front-panel COPY key.

In order to resume instrument operation following a nonrecoverable system error, press the front-panel PRESET key. The instrument will resume operation from its preset state.

Among the conditions which can contribute to the occurrence of a nonrecoverable system error are:

- Hardware failure of the main processor
- Hardware failure of system memory available to the main processor
- Errors in the primary system control program
- Attempted execution of unsupported system commands


Nonrecoverable system errors may occur when attempting to load an improper file type into the machine. For example, loading a file with an incorrect format into a limit line or amplitude correction table may generate this error.

If nonrecoverable system errors occur regularly, contact your HP representative.

## HP-IB

This appendix tells you how to connect a computer to your EMI receiver or receiver RF section with the Hewlett-Packard Interface Bus (HP-IB).

Your instrument has an HP-IB connector on the rear panel, as shown in Figure A-1.



cu17e

Figure A-1. HP-IB Connector

The HP-IB system utilizes a party-line bus structure. Devices such as your instrument are connected on the party line with HP-IB cables. A computer gives instructions and is the "controller." The instrument takes orders and is the "listener." The instrument is also capable of transmitting data over the party line. Devices that transmit data back to the computer are "talkers."

Each device on the party line has an address. Device addresses are used by the controller to specify who talks and who listens. A device's address is usually set at the factory.

The number 7 preceding the device's address (for example, Instrument=718), signifies that the HP-IB interface is selected.

When you turn on the instrument, the HP-IB address appears on the screen (for example, HP-IB ADRS: 18). If necessary, you can reset the address of the instrument by pressing CONFIG, More 1 of 3, RECEIVER ADDRESS, entering in the address number using the front-panel number keys, then pressing ENTER. You may use any address between 0 and 30. (Usually, 1 is reserved for printers and 5 for plotters.)


# **RS-232 Option 023**

## What You'll Learn in This Appendix

This appendix explains how to connect a computer to your EMI receiver or receiver RF section using the RS-232 interface. It contains information pertaining to RS-232 signals, cable connections, and baud rate.

## Introducing the RS-232 Interface

Your instrument has an RS-232 connector on the rear panel, as shown in Figure B-1.



cu18e

Figure B-1. RS-232 Connector

The RS-232 interface utilizes serial data transmission. Data is sent, one bit at a time, in groups of 10 to 12 data-bits.

Two devices, such as the instrument and a computer, can exchange commands and data over the RS-232 connection. This interface uses two serial data lines and five handshaking lines. Handshaking signals are required for full hardware control of the information exchange. It is possible to use a three-wire connection, in some situations.

Another parameter for the RS-232 interface is the "baud," or data rate. This is the speed at which the computer and instrument exchange data. The baud rate of each of the two RS-232 devices must be the same.

#### The RS-232 Data Lines

RS-232 uses serial data transmission, meaning that data is transmitted one bit at a time. There are two data lines carrying signals:

- Transmit data (TxD)—the serial data output. This line is connected to the RxD input line.
- Receive data (RxD)—the serial data input. This line is connected to the TxD output line.

#### The RS-232 Handshaking Lines

In addition to the data signals, there are five other signals lines (called handshaking lines), used to control the flow of data. Listed below are the handshake signal descriptions:

- Request to send (RTS)—Output signal indicates that the instrument is ready to communicate. This line is true at power-up and stays true while power is on.
- Clear to send (CTS)—Input signal indicates that the external controller is ready to receive data.

- Data terminal ready (DTR)—Output signal from the instrument. When the input buffer is full, this line goes false.
- Data set ready (DSR)—Is not available.
- Data carrier detect (DCD)—Input to the instrument. If DCD is true, the instrument will receive data from the controller. If false, no data will be input. The data will be ignored.

The instrument checks its CTS input before transmitting data to the computer. If the CTS line is false, the instrument will not transmit data. The instrument transmits data when the CTS line is true.

The instrument sets the DTR line (PC CTS) false when its input buffer is full.

### **Baud Rate**

The speed at which data is exchanged is called the baud rate or data rate. This is usually expressed in baud or bits per second. Common baud rates are 1200 and 9600.

Note	Some of the programs in this manual use 1200 baud for proper operation. If your system uses the RS-232 handshake lines, you can use 9600 baud for all of
	the programs.

If you need to change the baud rate, refer to the "Setting the Instrument Baud Rate" in this appendix.

#### **Protocol**

The RS-232 protocol is as follows:

Baud rate 300 to 57,000 baud 8 bits per character 1 stop bit No parity Software handshake—none Xon/Xoff and ENQ/ACK not supported by the instrument

When BREAK is issued to the instrument, the following occurs:

- 1. The present command is aborted.
- 2. The input buffer is cleared.
- 3. The output buffer is cleared.
- 4. All trace output is stopped.
- 5. The command parser is reinitialized.

BREAK does not perform any of the following:

- Invoke instrument preset.
- Clear SRQ off screen.
- Clear illegal command off screen.

The RTS signal goes true on power-up and does not go false during any communication. It stays true while power is on.

Figure B-2 lists the signal connections between a personal computer and the instrument.


Personal	Computer		Receive	r
TxD 2	>	<del>&gt;</del>	3	RxD
RxD 3	<del>&lt;</del>		2	TxD
RTS 4	>	_	8	DCD
CTS 5	<del></del>	<b>─</b> ≺	20	DTR
DSR 6	$\leftarrow$			
GND 7	<del></del>	<	7	GND
DCD 8	<del></del>		4	RTS
DTR 20	>	$\longrightarrow$	5	CTS

cu19e

Figure B-2. Full Handshaking Connection

If your computer operates with only three wires, you can use the cable connections in Figure B-3.

Some computers require that the CTS, DSR, and DCD inputs be true before serial transmission can occur. To solve this problem, you can wire these three signals to the personal computer RTS line.



cu110e

Figure B-3. 3-Wire Connection

## Connecting a ThinkJet Printer

To connect an HP ThinkJet printer to the instrument, use the information in Figure B-4. Table B-1, Table B-2, and Table B-3. Be sure to turn the printer off and then back on after changing the printer settings. See the ThinkJet Printer Manual for more information.

ThinkJet	Receiver	
GND 1	<i>⟨</i>	1 GND
TxD 2	<del></del>	3 RxD
RxD 3	<del></del>	2 TxD
RTS 4	<del></del>	8 DCD
GND 7	$\longleftrightarrow$	7 GND
DTR 20	<del></del>	5 CTS

cullie

Figure B-4. ThinkJet Printer Connection

### ThinkJet Printer Mode Switches:

Table B-1. Setting of Thinkjet Printer Mode Switches

Switch Number	Setting	Comments
1	down	Printer performs a carriage return only.
2	down	Printer performs a line feed only.
3	up	Sets the printer to skip paper perforations.
4	down	Sets the printer for a paper length of 11 inches.
5	down	Sets the printer to HP MODE.
6	up	
7	down	Sets the printer to USASCII.
8	down	

Table B-2. Setting of RS-232 Switches

Switch Number	Setting	Comments
1	up	DTR.
2	down	no parity, 8 bits.
3	down	
4	down	9600 baud.
5	down	

Table B-3. Setting the Baud Rate

Baud Rate	Setting for Switch 4	Setting for Switch 5
1200	up	up
2400	up	down
9600	down	down

## Connecting a Modem

To connect a modem to the instrument, use the information in Figure B-5. The connection is for a Hayes 1200 Modem and the instrument.

Modem		Receiver	
GND 1	<del>(</del>	1 GND	
TxD 2	<del>~~~</del>	2 TxD	
R×D 3	$\rightarrow$	3 RxD	
CTS 5	<b>&gt;</b>	5 CTS	
GND 7	<del>(</del>	7 GND	
DCD 8	<del></del>	8 DCD	
DTR 20	<del></del>	20 DTR	

cu112e

Figure B-5. Modem Connection

#### System Settings

Select 1200 baud for both the modem and the instrument.

### Connecting an HP-GL Plotter

To connect an HP-GL plotter to the instrument, use the information in Figure B-6.

Plotter		Receiver	
GND 1		1 GND	
TxD 2	<u> </u>	3 RxD	
RxD 3	<del></del>	2 TxD	
RTS 4	>	8 DCD	
CTS 5	<del></del>	20 DTR	
DSR 6	$\leftarrow$		
GND 7	<del></del>	7 GND	
DTR 20	>	5 CTS	

cu113e

Figure B-6. HP-GL Plotter Connection

#### **Switch Settings**

Set the switches on the HP-GL plotter to the following settings. Set the baud rate of the plotter and instrument to the same value. After setting the switch positions, turn plotter off, then on again.

> **Switch Position Switch Position** Expand: ◀ Parity: ▶ (Off) Emulate: ◀ Even/Odd: ▶ (Odd) Stand-alone: 4 Duplex: ▶ (Full) Monitor Mode: ▶ (normal) Hardwire: ◀ Local ▶ (normal) DTR-Bypass: ▶ (normal)

## Setting the Instrument Baud Rate

The baud rates of the instrument and the personal computer must be the same. For example, to set the instrument to 9600 baud, use the following procedure:

- 1. Press the (CONFIG), More 1 of 3.
- 2. Press the BAUD RATE softkey.
- 3. Press these keys: 9600, (Hz). To set the baud rate to 1200 baud, press these keys: 1200, (Hz).

Note Some of the programs in this manual use 1200 baud for proper operation. If your system uses the RS-232 handshake lines, you can use 9600 baud for all of the programs.

# Index

A1, 4-9 A2, 4-9 A3, 4-9 A4, 4-9 A4, 4-9 A-block format, 3-10 ABS, 4-25 absolute value, 4-25 activate marker, 4-235 activate marker, 4-236 average detection, 4-87 average noise level at the marker MKNOISE, 4-250 average video bandwidth, 4-50 AVG, 4-52 AXB, 4-54 B1, 4-9 B2, 4-9 B2, 4-9 B3, 4-9 Bak, 4-9 Bak, 4-9 Baud rate of instrument preset, 4-151 BASIC INPUT command, 2-5 REAL command, 2-6 BAUDRATE, 4-55 B format, 3-9, 3-10 BIT, 4-57 BITT, 4-57 BITT, 4-59 BIT, 4-57 BITT, 4-59 BIT, 4-59 BILANK, 4-61 Blank trace, 4-61 BML, 4-62 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C CI, 4-9 CZ, 4-9 CAL, 4-9 CAL, 4-9 CAL, 4-9 CAL, 4-66 calibration check, 4-69	A1, 4-9 average detection, 4-87	
A2, 4-9 A3, 4-9 A4, 4-9 A-block format, 3-10 ABS, 4-25 activate marker, 4-235 activate marker, 4-25 axib, 4-59 all function, 4-150 base band instrument preset, 4-151 bassic function, 4-150 base band instrument, 4-150		
MKNOISE, 4-250 A4, 4-9 A-block format, 3-10 ABS, 4-25 absolute value, 4-25 activate marker, 4-235 active function, 4-135 decreasing value with DN, 4-105 ADD, 4-27 address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPOLR, 4-34 AMPLEN, 4-37 amplitude correction, 4-34 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ANNOT, 4-38 APB, 4-39 ANNOT, 4-38 APB, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto average, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line D, 4-84 auxiliary interface control l	A2 4-9 average noise level at the marker	
Ad, 4-9 A-block format, 3-10 ABS, 4-25 absolute value, 4-25 activate marker, 4-235 activate marker, 4-25 alx 4-9 activation, 4-150 base band instrument preset, 4-151 BASIC INPUT command, 2-5 REAL command, 2-6 BAUDRATE, 4-55 bit checking, 4-57 bit checking, 4-56 bad Tat-9 back space label function, 4-150 back space la	3.5773.4.050	
A-block format, 3-10 ABS, 4-25 absolute value, 4-25 activate marker, 4-235 active function, 4-135 decreasing value with DN, 4-105 ADD, 4-27 address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction, 4-34 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 automatic calibration, 4-48 AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line B, 4-82 auxiliary interface control line B, 4-82 auxiliary interface control line D, 4-84 auxiliary	**O, * O	
ABS, 4-25 absolute value, 4-25 activate marker, 4-235 active function, 4-135 decreasing value with DN, 4-105 ADD, 4-27 BADD, 4-27 address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 APB, 4-39 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTOQPD, 4-49 auto range, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line B, 4-82 auxiliary interface control line B, 4-82 auxiliary interface control line I, 4-85 auxiliary interface control line I, 4-84 auxiliary interface control line I, 4-85 auxiliar	,	
absolute value, 4-25 activate marker, 4-235 active function, 4-135 decreasing value with DN, 4-105 ADD, 4-27 address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude correction length, 4-37 amplitude correction length, 4-37 amplitude correction, 4-38 ANNOT, 4-38 annotation, 4-38 APB, 4-39 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOCALL, 4-48 auto average, 4-40 auto range, 4-40 auto range, 4-40 auto range, 4-40 auxiliary interface control line B, 4-82 auxiliary interface control line I, 4-85	- Victoria de la companya del companya della compan	
activate marker, 4-235 active function, 4-135 active function, 4-135 decreasing value with DN, 4-105 ADD, 4-27 address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 APB, 4-39 ARNO, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOCAL, 4-48 auto average, 4-40 auto range, 4-40 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line C, 4-83 auxiliary interface control line C, 4-84 auxiliary interface control line D, 4-	ABS, 4-25 AXB, 4-54	
active function, 4-135     decreasing value with DN, 4-105 ADD, 4-27     address     changing the HP-IB address, A-1     HP-IB operation, A-1     alternate commands, 4-9-10 AMB, 4-29     AMPPL, 4-32     AMPCOR, 4-34     AMPLEN, 4-37     amplitude     marker type, 4-269     amplitude correction, 4-34     amplitude correction length, 4-37     amplitude units, 4-4, 4-43 ANNOT, 4-38     annotation, 4-38     APB, 4-39     ARNG, 4-40     AT, 4-41     attenuation, 4-41     AUNITS, 3-8, 4-43     AUTO, 4-45     auto average, 4-47     AUTOCAL, 4-48     auto average, 4-40     auxiliary interface control line A, 4-81     auxiliary interface control line C, 4-83     auxiliary interface control line C, 4-84     auxiliary interface control line C, 4-84     auxiliary interface control line D, 4-84     auxiliary interface control line I, 4-85     address     Ba, 4-9     back space     label function, 4-150     base band instrument preset, 4-151     BASIC     INPUT command, 2-5     REAL command, 2-6     BAUDRATE, 4-55     baud rate of instrument, 4-55     BauDrate, 4-15     baud rate of instrument, 4-55     BauDrate, 4-5     Baudorate, 4-5     BauDrate, 4-5     BauDrate, 4-5     Baudrate, 4-9     back space     label function, 4-150     back space     label function, 4-	absolute value, 4-25	
decreasing value with DN, 4-105 ADD, 4-27 address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAUG, 4-47 AUTOCAL, 4-48 auto couple, 4-45 automatic calibration, 4-88 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line C, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  B2, 4-9 B3, 4-9 back space label function, 4-150 base band instrument preset, 4-151 BASIC INPUT command, 2-5 REAL command, 2-6 BAUDRATE, 4-55 baud rate of instrument, 4-55 B format, 3-9, 3-10 BIT, 4-57 bit checking, 4-57 BITF, 4-59 bit flag, 4-59 bit flag, 4-59 bit flag, 4-59 bit flag, 4-9 BLANK, 4-61 bANK, 4-61 bBALNK, 4-61	activate marker, 4-235	
ADD, 4-27 address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto marker, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line C, 4-85	TO 4.0	
address changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude units, 4-4, 4-43 ANNOT, 4-38 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line C, 4-83 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-85	door country thank that Dit i I loo	
changing the HP-IB address, A-1 HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 ANNOT, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-47 AUTOAVG, 4-45 auto couple, 4-45 auto couple, 4-45 auto couple, 4-45 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-85		
HP-IB operation, A-1 alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 ANNOT, 4-38 ANNOT, 4-39 APB, 4-39 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUTOAVG, 4-45 auto couple, 4-45 auto couple, 4-45 auto marker acc control line A, 4-81 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  Iabel function, 4-150 base band instrument preset, 4-151 BASIC INPUT command, 2-5 REAL command, 2-6 BAUDRATE, 4-55 baud rate of instrument, 4-55 B format, 3-9, 3-10 BIT, 4-57 bit checking, 4-57 BITF, 4-59 bit flag, 4-59 BLANK, 4-61 blank trace, 4-61 BML, 4-62 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	addi coo	
alternate commands, 4-9-10 AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 ANNOT, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAUG, 4-47 AUTOAVG, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  base band instrument preset, 4-151 BASIC INPUT command, 2-5 REAL command, 2-6 BAUDRATE, 4-55 baud rate of instrument, 4-55 Batudrate, 4-55 baudrate of instrument, 4-55 Batudrate, 4-5 Batudrate, 4-6 BIT, 4-5 BIT, 4-57 BITF, 4-59 bit flag, 4-59 bit flag, 4-59 BLANK, 4-61 blank trace, 4-61 BML, 4-62 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CAL, 4-96 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	01100110 010 111 12 00000 11 1	
AMB, 4-29 AMBPL, 4-32 AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  AMPCOR, 4-32 ARAMPCOR, 4-32 BASIC INPUT command, 2-5 REAL command, 2-6 BAUDRATE, 4-55 BIIT, 4-57 BITF, 4-59 bit flag, 4-59 BLANK, 4-61 blank trace, 4-61 BBLAK A-62 BREAK BREAK BRAC BREAL command, 2-6 REAL command, 2-6 REAL command, 2-6 REAL command, 2-6 REAL command, 2-6 BAUDRATE, 4-55 BAUDRATE, 4-55 BAUDRATE, 4-55 BITF, 4-59 bit flag, 4-59 BLANK, 4-61 blank trace, 4-61 BREAK BREAK BRAC CA-63 BXC, 4-64 BYPASS, 4-65 BYPASS, 4-65 CALCHECK, 4-69 CALCHECK, 4-69 CALCHECK, 4-69 Calibration check, 4-69		
AMBPL, 4-32  AMPCOR, 4-34  AMPLEN, 4-37  amplitude  marker type, 4-269  amplitude correction, 4-34  amplitude correction length, 4-37  amplitude units, 4-4, 4-43  ANNOT, 4-38  annotation, 4-38  APB, 4-39  ARNG, 4-40  AT, 4-41  AUNITS, 3-8, 4-43  AUTO, 4-45  auto average, 4-47  AUTOAVG, 4-45  auto couple, 4-45  auto range, 4-40  AUTOQPD, 4-49  auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line B, 4-82  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  INPUT command, 2-5  REAL command, 2-6  BAUDRATE, 4-55  BAUDRATE, 4-5  BIT, 4-55  BIT, 4-57  BIT		
AMPCOR, 4-34 AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-85 auxiliary inte		
AMPLEN, 4-37 amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-85		
amplitude marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  bauto caree instrument, 4-55 B format, 3-9, 3-10 BIT, 4-57 bit checking, 4-57 BITF, 4-59 BLANK, 4-61 blank trace, 4-61 BML, 4-62 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  CA, 4-9 CA, 4-9 CALCHECK, 4-69 calibration check, 4-69	111111111111111111111111111111111111111	
marker type, 4-269 amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 AUNITS, 3-8, 4-43 AUTOQAU, 4-47 AUTOCAL, 4-48 auto range, 4-40 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line I, 4-85 auto acceptage interface control line I, 4-85 auto correction, 4-34 BIT, 4-57 bit checking, 4-57 BITF, 4-59 bit flag, 4-59 BLANK, 4-61 blank trace, 4-61 BALANK, 4-61 blank trace, 4-61 BALANK, 4-61 CAL, 4-63 BALANK, 4-61 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	The manufacture of the first of	
amplitude correction, 4-34 amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto couple, 4-45 auto average, 4-40 auto range, 4-40 auto range, 4-40 auxiliary interface control line B, 4-82 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  BIT, 4-57 bit checking, 4-57 BITF, 4-59 bit flag, 4-59 BILANK, 4-61 blank trace, 4-61 BML, 4-62 BEAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	· · · · · · · · · · · · · · · · · · ·	
amplitude correction length, 4-37 amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto couple, 4-45 auto range, 4-40 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85 bit checking, 4-57 BITF, 4-59 bit flag, 4-59 BLANK, 4-61 blank trace, 4-61 BML, 4-62 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69		
amplitude units, 4-4, 4-43 ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  BITF, 4-59 bit flag, 4-59 blank trace, 4-61 blank trace, 4-61 blank trace, 4-61 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 c1, 4-9 cAL, 4-9 cAL, 4-66 cALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	wiipitotae correction 2 o r	
ANNOT, 4-38 annotation, 4-38 APB, 4-39 ARNG, 4-40 ARNG, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  bit flag, 4-59 BLANK, 4-61 blank trace, 4-61 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	manipantation of the contract and the co	
annotation, 4-38  APB, 4-39  ARNG, 4-40  AT, 4-41  attenuation, 4-41  AUNITS, 3-8, 4-43  AUTO, 4-45  auto average, 4-47  AUTOCAL, 4-48  auto couple, 4-45  auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  BL, 4-9  BLANK, 4-61  blank trace, 4-61  BML, 4-62  BREAK  RS-232 operation, B-2  BTC, 4-63  BXC, 4-64  BYPASS, 4-65  bypass path, 4-65  C  C1, 4-9  C2, 4-9  CAL, 4-66  CALCHECK, 4-69  calibration, 4-66  calibration check, 4-69	Winpitotico Willor, 1 1, 1 10	
APB, 4-39  ARNG, 4-40  AT, 4-41  attenuation, 4-41  AUNITS, 3-8, 4-43  AUTO, 4-45  auto average, 4-47  AUTOAVG, 4-47  AUTOCAL, 4-48  auto couple, 4-45  auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line C, 4-83  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  BLANK, 4-61  blank trace, 4-61  BML, 4-62  BREAK  RS-232 operation, B-2  BTC, 4-63  BXC, 4-64  BYPASS, 4-65  bypass path, 4-65  C  C1, 4-9  C2, 4-9  CAL, 4-66  CALCHECK, 4-69  calibration, 4-66  calibration check, 4-69		
ARNG, 4-40 AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto average, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  blank trace, 4-61 BML, 4-62 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CAL, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69		
AT, 4-41 attenuation, 4-41 AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto matic calibration, 4-48 AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  BML, 4-62 BREAK RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69		
attenuation, 4-41  AUNITS, 3-8, 4-43  AUTO, 4-45  auto average, 4-47  AUTOCAL, 4-48  auto couple, 4-45  auto matic calibration, 4-48  AUTOQPD, 4-49  auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line B, 4-82  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  BREAK  RS-232 operation, B-2  BTC, 4-63  BXC, 4-64  BYPASS, 4-65  bypass path, 4-65  C  C1, 4-9  C2, 4-9  CAL, 4-9  CALCHECK, 4-69  calibration, 4-66  calibration check, 4-69		
AUNITS, 3-8, 4-43 AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto matic calibration, 4-48 AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  RS-232 operation, B-2 BTC, 4-63 BXC, 4-64 BYPASS, 4-65 bypass path, 4-65  C C1, 4-9 C2, 4-9 CAL, 4-9 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69		
AUTO, 4-45 auto average, 4-47 AUTOAVG, 4-47 AUTOCAL, 4-48 auto couple, 4-45 auto matic calibration, 4-48 AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  BTC, 4-63 BXC, 4-64 BYPASS, 4-65  C C C1, 4-9 C2, 4-9 CAL, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	accordance in the second	
auto average, 4-47  AUTOAVG, 4-47  BYPASS, 4-65  BYPASS, 4-65  bypass path, 4-65  auto couple, 4-45  automatic calibration, 4-48  AUTOQPD, 4-49  auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line B, 4-82  auxiliary interface control line C, 4-83  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  BXC, 4-64  BYPASS, 4-65  C  C  C1, 4-9  C2, 4-9  CAL, 4-66  CALCHECK, 4-69  calibration, 4-66  calibration check, 4-69		
AUTOAVG, 4-47  AUTOCAL, 4-48  auto couple, 4-45  automatic calibration, 4-48  AUTOQPD, 4-49  auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line B, 4-82  auxiliary interface control line C, 4-83  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  BYPASS, 4-65  bypass path, 4-65  C  C1, 4-9  C2, 4-9  CAL, 4-66  CALCHECK, 4-69  calibration, 4-66  calibration check, 4-69		
AUTOCAL, 4-48  auto couple, 4-45  automatic calibration, 4-48  AUTOQPD, 4-49  auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line B, 4-82  auxiliary interface control line C, 4-83  auxiliary interface control line D, 4-84  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  bypass path, 4-65  C  C1, 4-9  C2, 4-9  CAL, 4-66  CAL, 4-66  CALCHECK, 4-69  calibration, 4-66  calibration check, 4-69	4400 41 CA 460; 1 1;	
auto couple, 4-45 automatic calibration, 4-48 AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  CC C1, 4-9 C2, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69		
automatic calibration, 4-48  AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85	AUTOCAL, 4-48 bypass path, 4-65	
automatic calibration, 4-48  AUTOQPD, 4-49 auto range, 4-40 auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  C1, 4-9 C2, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	auto couple, 4-45	
auto range, 4-40  auxiliary interface control line A, 4-81  auxiliary interface control line B, 4-82  auxiliary interface control line C, 4-83  auxiliary interface control line D, 4-84  auxiliary interface control line I, 4-85  auxiliary interface control line I, 4-85  C2, 4-9  CAL, 4-66  CAL, 4-66  CALCHECK, 4-69  calibration, 4-66  calibration check, 4-69	automatic candration, 4-48	
auxiliary interface control line A, 4-81 auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85  CAL, 4-9 CAL, 4-66 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69		
auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85 CALCHECK, 4-69 calibration, 4-66 calibration check, 4-69	water taken to the second of t	
auxiliary interface control line B, 4-82 auxiliary interface control line C, 4-83 auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85 CALCHECK, 4-69 CALCHECK, 4-69 calibration check, 4-69	demanded intollers some state in a second state	
auxiliary interface control line D, 4-84 auxiliary interface control line I, 4-85 calibration, 4-66 calibration check, 4-69	auxiliary interface control line B, 4-82 CAL, 4-66	
auxiliary interface control line I, 4-85 calibration check, 4-69		
ownerson J accordance contract and a co		
	ownerson J amount doo out to ou and at a co	
AVBW, 4-50 calibration switch, 4-70	AVBW, 4-50 calibration switch, 4-70	

calibration time, 4-71	CONTS, 4-90
CALSW, 4-70	convert to absolute units, 4-93
CALTIME, 4-71	convert to measurement units, 4-95
carriage return	copying the source to a destination
label function, 4-150	MOV, 4-274
CAT, 4-72	correction factors on, 4-91
catalog, 4-72	CORREK, 4-91
cataloging internal memory, 4-75	COUPLE, 4-92
cataloging the floppy disk, 4-74	CR, 4-9
center frequency, 2-4, 4-76	creating a trace window, 4-437
center frequency step size, 4-396	creating a user-defined trace, 4-431
CF, 2-4, 4-76	creating a user-defined variable, 4-443
changing the amplitude units	CS, 4-9
AUNITS, 4-43	CT, 4-9
changing the average video bandwidth	CTA, 4-93
AVBW, 4-50	CTM, 4-95
changing the HP-IB address, A-1	CTS
changing the video bandwidth	RS-232 handshaking line, B-1
VB, 4-447	current units, 4-4
character, 4-3	CV, 4-9
character & EOI, 4-3	07, 40
characters and secondary keywords, 4-5-8	D
clear average, 4-78	data byte, 4-3
clear status byte, 4-80	data byte & EOI, 4-3
clear to send	data carrier detect
RS-232 handshaking line, B-1	RS-232 handshaking line, B-2
clear write, 4-79	_ `
CLRAVG, 4-78	data entry
CLRW, 4-79	disabling, 4-135 data lines
CLS, 4-80	
CNTLA, 4-81	RS-232, B-1
CNTLB, 4-82	data terminal ready
CNTLC, 4-83	RS-232 handshaking line, B-2
CNTLD, 4-84	date mode, 4-96
•	DATEMODE, 4-96
CNTLI, 4-85	DCD  DC 222 handshahing line D 2
combining two traces, 4-88	RS-232 handshaking line, B-2
command mnemonic, 4-2	delete limit-line table, 4-154
commands, 2-2	deleting a file from a floppy disk, 4-309
command terminators, 4-2	deleting softkeys, 4-100
commenting programming lines, 2-8	delimiter, 4-3
compatible commands, 4-9-10	delta
COMPRESS, 4-86	marker type, 4-269
compress trace, 4-86	DEMOD, 4-97
CONCAT, 4-88	demodulation, 4-97
concatenate, 4-88	DET, 4-98
configuring your computer system, 1-1	detection mode, 4-98
connecting a modem	determining the trace status, 4-435
RS-232 operation, B-4	digit, 4-3
connecting your instrument to a printer or	displaying a trace, 4-433
plotter, 1-13	displaying the screen title, 4-425
connection an HP-GL plotter (RS-232	displaying the time and date, 4-424
operation), B-5	display line, 4-103
continuous sweep, 4-90	DISPOSE, 4-100
controlling the marker counter, 4-244	DIV, 4-101
controlling trace data with a computer, 3-2	divide, 4-101

DL, 4-103	fatal errors, 5-12
DN, 4-105	FB, 4-119
DONE, 4-106	FCALDATE, 4-121
dotted lines, 4-2	FFT, 4-122
down, 4-105	creating a trace window, 4-437
DSR	fft marker readout, 4-260
RS-232 handshaking line, B-2	finding the absolute value, 4-25
DTR	finding the maximum
RS-232 handshaking line, B-2	MXM, 4-279
· ,	finding the minimum value, 4-226
E	fixed
E1, 4-9	marker type, 4-269
E2, 4-9	FLATTOP filter
E3, 4-9	FFT, 4-123
E4, 4-9	FM gain, 4-126
EDITANNOT, 4-108	FMGAIN, 4-126
edit annotation, 4-108	FOFFSET, 4-127
EK, 4-109	force service request, 4-393
EM, 4-9	FORMAT, 4-129
enable knob, 4-109	format disk, 4-129
enable limit-line testing, 4-185	form feed
end-or-identify, 3-6	label function, 4-150
END statement, 3-12	free trigger mode, 4-426
enhancements	frequency
label function, 4-150	_ ·
	marker readout, 4-260
enter limit-line segment for frequency, 4-179	start frequency, 4-117
enter limit-line segment for sweep time, 4-182	frequency-amplitude correction factors
	number of, 4-37
enter parameter function, 4-110	frequency offset, 4-127
EOI, 3-6, 3-12	frequency units, 4-4
EP, 4-110	FS, 4-130
ERASE, 4-111	FSER, 4-131
error messages, 5-1	full span, 4-130
errors, non recoverable, 5-12	functional index, 4-1, 4-11ff
EX, 4-9	G
exchange, 4-457	
exchange trace A and trace B, 4-54	GRAT, 4-132
exchanging traces	graticule, 4-132
XCH, 4-458	н
excursion	
marker peak excursion, 4-258	handshaking connection
EXITANNOT, 4-112	RS-232 operation, B-2
exit annotation, 4-112	handshaking lines
EXP, 4-113	RS-232, B-1
exponent, 4-113	HANNING filter
external preamplifier gain, 4-299	FFT, 4-123
external trigger mode, 4-426	hardware error messages, 5-1
T7	harmonic number, 4-136
F	harmonic number lock, 4-137
FA, 4-116	HAVE, 4-133
fast Fourier transform, 4-122	HD, 4-135
creating a trace window, 4-437	Hewlett-Packard interface bus, A-1
marker readout, 4-260	HN, 4-136
fast marker, 4-118	HNLOCK, 4-137
FASTMRKR, 4-118	HNUNLK. 4-139

hold data entry, 4-135	KSC, 4-9
HP 9000 Series 200 technical computers, 1-3	KSE, 4-9
HP 9000 Series 300 technical computers, 1-5	KSG, 4-9
HP BASIC	KSH, 4-9
CLEAR command, 2-2	KSi, 4-9
CREATE command, 3-3	KSl, 4-9
DIM command, 3-5	KSm, 4-9
END command, 2-3	KSM, 4-9
ENTER, 3-6	KSn, 4-9
LOCAL command, 2-3	KSo, 4-9
REAL command, 2-5	KSO, 4-9
USING command, 3-6	KSp, 4-9
HP-IB interface, 1-1	KSZ, 4-9
HP-IB interface bus, A-1	1102, 10
HP Vectra personal computer	L
HP-IB interface, 1-7	L0, 4-9
· · · · · · · · · · · · · · · · · · ·	·
RS-232 interface, 1-9	last calibration date, 4-121
I	last key menu, 4-150
	LASTKEYMENU, 4-150
IB, 4-140	last span, 4-196
I-block format, 3-11	LF, 3-6, 4-151
IBM PC/AT and compatible computers, 1-11	LG, 4-152
ID, 4-141	LIMIAMPSCL, 4-153
identify, 4-141	LIMIDEL, 4-154
IFBW, 4-142	LIMIDISP, 4-155
impedance	LIMIFAIL, 4-157
INZ, 4-146	LIMIFRQSCL, 4-159
impedance units, 4-4	LIMIFT, 4-160
increasing the value	LIMIHI, 4-161
UP, 4-441	LIMILINE, 4-163
informational messages, 5-1	LIMILINESTA, 4-166
input B, 4-140	LIMILO, 4-168
input impedance, 4-146	LIMIMARGAMP, 4-169
instrument command, 4-3	LIMIMARGSTA, 4-170
instrument preset, 2-2, 4-147	LIMIMIRROR, 4-172
instrument state, 3-5	LIMIMODE, 4-174
•	LIMINUM, 4-176
INT, 4-144	
integer, 4-144	LIMIREL, 4-177
integer number range, 4-3	LIMISEG, 4-179
interface bus	LIMISEGT, 4-182
RS-232, B-1	LIMITEST, 4-185
intermediate frequency bandwidth, 4-142	limit line
inverse sweep time	entry mode, 4-174
marker readout, 4-260	limit-line amplitude scale, 4-153
inverse video	limit line display, 4-155
label function, 4-150	limit-line frequency scale, 4-159
INZ, 4-146	limit-line number, 4-176
IP, 2-2, 4-147	limit lines, 4-163
	enable limit-line testing, 4-185
K	enter limit-line segment for frequency,
knob	4-179
enabling knob with EP, 4-109	enter limit-line segment for sweep time,
KSA, 4-9	4-182
KSB, 4-9	limits failed, 4-157
KSc, 4-9	mirror limit line, 4-172
water way and w	TIME OF ASSISTED SEELE, T. E. F. G.

relative limit lines, 4-177	marker to center frequency, 4-238
limit-line state, 4-166	marker to reference level, 4-262
limit margin amplitude, 4-169	marker to span, 4-263
limit-margin state, 4-170	marker trace, 4-267
limits failed, 4-157	marker track, 4-268
LINCHK, 4-187	marker type, 4-269
linear, 4-188	amplitude, 4-269
linearity check, 4-187	delta, 4-269
linear scale, 4-190	fixed, 4-269
line-feed, 3-6	position, 4-269
line feed	•
label function, 4-150	marker zoom, 4-198
line trigger mode, 4-426	mass storage is, 4-278
LINFILL, 4-188	maximum, 4-279
·	maximum hold, 4-281
LN, 4-190	MC, 4-10
LOAD, 4-191	MDS, 3-9, 4-200
loading a file from the disk drive, 4-191	MDS command
LOG, 4-193	MKF programming example, 4-243
logarithm, 4-193	MDU, 4-202
logarithmic scale, 4-152	MEAN, 4-204
LOGSWEEPSPD, 4-197	MEANTH, 4-206
log sweep speed, 4-197	MEASALLSIGS, 4-208
log to linear conversion, 4-113	MEASAVG, 4-209
lower limit line, 4-168	MEASFREQ, 4-210
lsb length, 4-3	MEASPEAK, 4-211
LSB length, 3-10	MEASQPD, 4-212
LSPAN, 4-196	MEASRESULT, 4-213
M	MEASSIG, 4-215
M	MEASTIMEAVG, 4-216
M1, 4-10	MEASTIMEPK, 4-217
M2, 4-10	MEASTIMEQPD, 4-218
M3, 4-10	MEASURE, 4-219
M4, 4-198	measure all signals, 4-208
MA, 4-10	measure average, 4-209
Marker Amplitude, 4-233	measure frequency, 4-210
marker as the active function, 4-236	measurement data size, 3-9, 4-200
marker bandwidth, 4-237	measurement data units, 4-202
marker continue, 4-239	measurement units, 3-12, 4-94
marker counter, 4-244	range, 3-13
marker counter resolution, 4-245	measure mode, 4-219
marker delta, 4-240	measure peak, 4-211
marker frequency, 4-242	measure quasi-peak detector, 4-212
marker frequency output, 4-224	measure result, 4-213
marker minimum, 4-247	measure signal, 4-215
marker noise, 4-250	measure time average, 4-216
marker normal, 4-248	measure time peak, 4-217
marker off, 4-252	measure time quasi-peak detector, 4-218
marker pause, 4-255	measure with preselector peak, 4-221
marker peak, 4-257	MEASWITHPP, 4-221
marker peak excursion, 4-258	MERGE, 4-222
marker position, 4-253	merge two traces, 4-222
marker readout, 4-260	MF, 4-224
marker readout, 4-260	Mr, 4-224 M format, 3-12-14
marker step size, 4-264	MIN, 4-226
marker stop, 4-266	•
THE POOR TOOK TOOK	MINH, 4-228

minimum, 4-226	N
minimum hold, 4-228	natural exponent, 4-115
minimum position, 4-229	negative detection, 4-87
minimum trace value	non recoverable errors, 5-12
MKMIN, 4-247	normal detection, 4-87
MINPOS, 4-229	normalization
MIRROR, 4-231	
mirror image, 4-231	using AMBRI 4.33
mirror limit line, 4-172	using AMBPL, 4-33
mixer level, 4-270	normalized reference level, 4-282
MKA, 3-2, 4-233	NRL, 4-282
MKACT, 4-235	number, 4-3
MKACTV, 4-236	0
MKBW, 4-237	
MKCF, 4-238	01, 4-10
MKCONT, 4-239	02, 4-10
MKD, 4-240	03, 4-10
MKF, 3-2, 4-242	04, 4-10
MKFC, 4-244	OA, 4-284
MKFCR, 4-245	OL, 4-285
·	output active function value, 4-284
MKMIN, 4-247 MEN 4-249	output learn string, 4-285
MKN, 4-248 MKNOISE 4 250	output termination, 4-3
MKNOISE, 4-250	overload, 4-286
MKOFF, 4-252	over range for measurement units, 3-13
MKP, 4-253	OVLD, 4-286
MKPAUSE, 4-255	The state of the s
MKPK, 4-257	P
MKPK HI, 2-4	parameter units, 3-8
MKPX, 4-258	party-line bus structure, A-1
MKREAD, 4-260	PDA, 4-288
MKRL, 4-262	peak average detection, 4-87
MKSP, 4-263	PEAKS, 4-290
MKSS, 4-264	period
MKSTOP, 4-266	marker readout, 4-260
MKTRACE, 4-267	P format, 3-8
MKTRACK, 4-268	placing a marker
MKTYPE, 4-269	MKP, 4-253
ML, 4-270	placing a marker on a signal peak
MOD, 4-272	MKPK, 4-257
modulo, 4-272	PLOT, 4-293
MOV, 4-274	plotter units, 4-202
move, 4-274	plotting
moving the active marker between traces	HP-IB interface, 1-14
MKTRACE, 4-267	RS-232, 1-16
MPY, 4-276	position
msb length, 4-3	marker type, 4-269
MSB length, 3-10	positive and negative peaks detection, 4-87
MSI, 4-278	positive detection, 4-87
MINT TO ! O	power bandwidth, 4-310
MTO, 4-10	POWERON, 4-295
,	
MTO, 4-10	
MTO, 4-10 MT1, 4-10	power-on state, 4-295
MT0, 4-10 MT1, 4-10 multiply, 4-276	power-on state, 4-295 power up time, 4-312
MT0, 4-10 MT1, 4-10 multiply, 4-276 MXM, 4-279	power-on state, 4-295 power up time, 4-312 PP, 4-296
MT0, 4-10 MT1, 4-10 multiply, 4-276 MXM, 4-279	power-on state, 4-295 power up time, 4-312

preamplifier, 4-297	real number range, 4-3
preamplifier gain, 4-299	recall colors, 4-317
predefined function, 4-3	recalling with a prefix, 4-300
predefined variable, 4-4	recall state, 4-318
prefix, 4-300	recall trace, 4-319
PREFX, 4-300	receiver marker position, 4-321
preselector peak, 4-296	recommended path, 4-2
PRINT, 4-301	records, 3-6
print address, 4-302	reference level, 4-331
printer type, 4-305	marker to reference level, 4-262
printing	reference level offset, 4-335
HP-IB interface, 1-13	•
	reference-level position, 4-333
RS-232, 1-15	relative limit lines, 4-177
with a ThinkJet Printer (RS-232 only), B-3	remainder
print per page, 4-303	finding the remainder with MOD, 4-272
print resolution, 4-304	REMEASSIG, 4-323
PRNTADRS, 4-302	remeasure signal, 4-323
PRNTPPG, 4-303	repeating syntax element, 4-2
PRNTRES, 4-304	REPEAT UNTIL, 4-324
PRNTTYPE, 4-305	report definition, 4-336
probability distribution of amplitude, 4-288	request to send
problems, 1-18	RS-232 handshaking line, B-1
programming guidelines, 2-8	reserved words, 4-2
protect, 4-307	reset reference level, 4-326
PROTECT, 4-307	RESETRL, 4-326
protect state, 4-308	resolution bandwidth, 4-315
protocol	returning or storing trace values, 4-428
RS-232 protocol, B-2	returning the instrument to its former state,
PSTATE, 4-308	3-7
PURGE, 4-309	returning trace A data to the controller
purge file, 4-309	TA, 4-412
PWRBW , 4-310	returning trace B data to the controller
PWRUPTIME, 4-312	TA, 4-414
I WIGHTIME, 4-012	•
Q	returning trace data
	changing the trace data format, 4-416
QPGAIN, 4-313	REV, 4-327
quasi-peak detector, 4-49	revision, 4-327
quasi-peak gain, 4-313	RF filter section serial number, 4-131
R	RFIN, 4-328
	RFINLK, 4-330
R1, 4-10	RF input lock, 4-330
R2, 4-10	RF input signal, 4-328
R3, 4-10	RL, 4-331
R4, 4-10	RLPOS, 4-333
range, 4-314	RMS, 4-334
RANGE, 4-314	ROFFSET, 4-335
ratio	root mean square value, 4-334
setting the video bandwidth ratio, 4-449	rosenfell algorithm, 4-87
RB, 4-315	RPTDEF, 4-336
RC, 4-10	RQS, 4-337
RCLC, 4-317	RS-232
RCLS, 4-318	3-wire connection, B-3
RCLT, 4-319	baud rate, B-2
RCVRMRKR, 4-321	connecting a modem, B-4
reading trace data, 3-2	connecting an HP-GL plotter. B-5
	UU

connecting a ThinkJet printer, B-3 data lines, B-1	setting the time and date, 4-423 setting the trace operations to preset values
handshaking connection for personal	4-434
computer, B-2	
	setting the video bandwidth
handshaking lines, B-1	VB, 4-447
protocol, B-2	setting the video bandwidth ratio, 4-449
setting the baud rate, B-5	show set up, 4-356
RS-232 interface, 1-1	SHOWSETUP, 4-356
RS-232 interface bus, B-1	SIGADD, 4-357
RTS	SIGDEL, 4-358
RS-232 handshaking line, B-1	SIGDLTAVIEW, 4-359
S	SIGGRAPH, 4-361
	SIGLEN, 4-362
S1, 4-10	SIGLIST, 4-363
S2, 4-10	SIGMARK, 4-364
sample detection, 4-87	signal add, 4-357
SAVEC, 4-339	signal delete, 4-358
save colors, 4-339	signal delta view, 4-359
SAVES, 4-340	signal graph, 4-361
save state, 4-340	signal list, 4-363
SAVET, 4-341	signal list length, 4-362
save trace, 4-341	signal mark, 4-364
saving and recalling instrument states, 3-5	signal position, 4-365
saving trace data, 3-3	signal result, 4-366
saving with a prefix, 4-300	signal sort, 4-367
scaling factor, 4-115, 4-194	SIGNAL TRACK
screen title	MKTRACK, 4-268
TITLE, 4-425	signal unmark, 4-369
secondary keywords, 4-2	SIGPOS, 4-365
SEGDEL, 4-343	SIGRESULT, 4-366
segment delete, 4-343	SIGSORT, 4-367
segment entry for frequency limit lines,	SIGUNMARK, 4-369
4-345	single sweep, 4-372
segment entry for sweep time limit lines,	single-sweep mode, 2-3
4-348	SMOOTH, 4-370
select frequency or time limit line, 4-160	smooth trace, 4-370
selecting a trace window for FFT, 4-437	SNGLS, 2-3, 4-372
SENTER, 4-345	source attenuator, 4-381
SENTERT, 4-348	source leveling control, 4-380
SER, 4-351	source power, 4-388
serial number, 4-351	- '
service request mask, 4-337	source power-level step size, 4-384
SETC, 4-352	source power offset, 4-383
·	source power sweep, 4-386
set colors, 4-352	source tracking, 4-390
set date, 4-354	source tracking peak, 4-392
SETDATE, 4-354	SP, 2-4, 4-373
set time, 4-355	span, 2-4, 4-373
SETTIME, 4-355	marker to span, 4-263
setting the average video bandwidth	span zoom, 4-376
AVBW, 4-50	SPEAKER, 4-375
setting the baud rate, B-5	special numbers and characters, 4-2
setting the instrument trigger mode, 4-427	specifying the frequency of the marker
setting the marker counter resolution, 4-245	MKF, 4-242
setting the real-time clock, 4-423	SPZOOM, 4-376
setting the threshold level, 4-421	SQLCH, 4-377

SQR, 4-378	TDF, 3-8, 4-416
square root, 4-378	TDF command
squelch, 4-377	MKF programming example, 4-243
SRCALC, 4-380	test program, 1-2
SRCAT, 4-381	TH, 4-421
SRCPOFS, 4-383	ThinkJet Printer mode switch settings, B-4
SRCPSTP, 4-384	ThinkJet RS-232 switch settings, B-4
SRCPSWP, 4-386	threshold, 4-421
SRCPWR, 4-388	time and date
SRCTK, 4-390	displaying the time and date, 4-424
SRCTKPK, 4-392	time date, 4-423
SRQ, 4-393	TIMEDATE, 4-423
SS, 4-396	time display, 4-424
ST, 4-398	TIMEDSP, 4-424
standard baud rates, 4-56	time units, 4-4
start frequency, 4-116	TITLE, 4-425
status bits	TM, 4-426
clearing, 4-80	TRA, 3-2, 4-428
status byte query, 4-400	trace A minus trace B, 4-29
status of a trace	trace A minus trace B plus display line, 4-32
TRSTAT, 4-435	trace A plus trace B, 4-39
STB, 4-400	trace B exchange trace C, 4-64
step size	trace B minus display line, 4-62
decreasing by the step size with DN, 4-105	trace data format, 4-416
marker step size, 4-264	binary, 3-5
stop frequency, 4-119	TDF, 2-7
STOR, 4-401	trace data formats, 3-8
store, 4-401	trace data input and output, 4-428
SUB, 4-404	trace data transfers, 3-8
subtract, 4-404	trace define, 4-431
SUM, 4-406	trace display, 4-433
sum of squared trace amplitudes, 4-408	trace element, 4-4
sum of trace amplitudes, 4-406	•
SUMSQR, 4-408	trace math, 3-12 trace mean, 4-204
SV, 4-10	·
Sweep Couple, 4-410	trace mean above threshold, 4-206
sweep couple, 4-410 sweep time, 4-398	trace memory, 4-430
	trace preset, 4-434
marker readout, 4-260 SWPCPL, 4-410	trace range, 4-4
•	trace registers
syntax elements, 4-2, 4-3-4 T	determining the total number of trace registers available, 4-430
	trace status, 4-435
T0, 4-10	trace window, 4-437
T1, 4-10	tracking the signal
T2, 4-10	MKTRACK, 4-268
T3, 4-10	transducer conversion units, 4-459
T4, 4-10	transfer A, 4-412
T7, 4-10	transfer B, 4-414
T8, 4-10	transferring trace A data, 4-412
TA, 4-412	transferring trace B data, 4-414
table definition, 4-415	transfer trace B to trace C, 4-63
take sweep, 4-436	TRA/TRB/TRC, 4-428
taking a measurement sweep, 4-436	TRB, 4-428
TB, 4-414	TRC, 4-428
TBLDEF, 4-415	TRCMEM, 4-430

TRDEF, 4-431	vertical tab
TRDSP, 4-433	label function, 4-150
triggering the instrument, 4-427	video average, 4-446
trigger mode, 4-426	video bandwidth, 4-447
TRPRST, 4-434	video bandwidth ratio, 4-449
TRSTAT, 4-435	video trigger mode, 4-426
TS, 2-3, 4-436	VIEW, 4-450
turning off markers	viewing a trace
MKOFF, 4-252	VIEW, 4-450
TWNDOW, 4-437	·
two's complement, 4-39	$\mathbf{W}$
type of marker	WAIT, 4-451
changing the type, 4-269	window next, 4-452
	window off, 4-453
U	window on, 4-454
UDKDEFINE, 4-438	windows commands
UDKSET, 4-439	WINNEXT, 4-452
underlining	WINOFF, 4-453
label function, 4-150	WINON, 4-454
UNIFORM filter	WINZOOM, 4-456
FFT, 4-123	ZMKCNTR, 4-460
units, 4-4	ZMKPKNL, 4-462
unlock harmonic number, 4-139	ZMKPKNR, 4-463
unrange, 4-440	ZMKSPAN, 4-464
UNRANGE, 4-440	window zoom, 4-456
UNTIL, 4-324	WINNEXT, 4-452
UP, 4-441	WINOFF, 4-453
upper limit line, 4-161	WINON, 4-454
user-created error messages, 5-1	WINZOOM, 4-456
user-defined function, 4-4	writing your first program, 2-2
user-defined key, 4-438	
user-defined key set, 4-439	X
user-defined trace, 4-4	XCH, 4-457
user-defined variable, 4-4, 4-442	XUNITS, 4-459
$\mathbf{v}$	Z
VARDEF, 4-442	ZMKCNTR, 4-460
variable definition, 4-442	ZMKPKNL, 4-462
variables, 2-5	ZMKPKNR, 4-463
VARIANCE, 4-444	ZMKSPAN, 4-464
variance of trace amplitudes, 4-444	zone marker at center frequency, 4-460
VAVG, 4-446	zone marker for next left peak, 4-462
VB, 4-447	zone marker for next right peak, 4-463
VBR, 4-449	zone marker span, 4-464
·	water marker spear, a roa