

Record: Local date _____, Local time _____, (FM1, S/C A) _____, (FM2, S/C B) _____,
UTC date _____, UTC time _____, Initials _____, Temperature _____ °C, Rel. humidity _____ %.

List SEP sensors attached: LET _____, HET _____, SIT _____, SEPT-E _____ and SEPT-NS _____.

Describe test set-up configuration: _____

1.0 INTRODUCTION

1.1 TEST NAME: LET Comprehensive Performance Test

1.2 RESPONSIBLE SUBSYSTEM/INSTRUMENT LEAD: Branislav Kecman

1.3 AUTHOR: Branislav Kecman
(626) 395-4264, kecman@srl.caltech.edu

1.4 DATE CREATED: October 4, 2004
Rev A January 19, 2005 Checksum update and edit
Rev B April 4, 2005 Checksum update and edit

2.0 DESCRIPTION

2.1 PROCEDURE DESCRIPTION:

The procedure verifies comprehensive performance of the Low Energy Telescope (LET) sensor as part of Solar Energetic Particles (SEP) instrument suite before and after the following activities: SEP bench and environmental tests, SEP integration with the IMPACT suite, IMPACT suite integration with the STEREO spacecraft, S/C environmental tests, pre-launch operations and in flight. It exercises many aspects of LET operational modes and provides reliable means for their tracking over relatively long time period implied above.

2.2 PROCEDURE OUTLINE AND DOCUMENT REFERENCE NUMBER:

- 2.2.1 SEP Power On STEREO-CIT-031.A
- 2.2.2 SEP_Central Aliveness Test STEREO-CIT-034.A
- 2.2.3 Normal Mode (LET Aliveness Test) STEREO-CIT-024.A
- 2.2.4 ADC Only Mode *
- 2.2.5 Quiet Mode *
- 2.2.6 Threshold Mode *
- 2.2.7 LET Heater Mode *
- 2.2.8 SEP Power Off STEREO-CIT-032.A

2.3 TEST DURATION: 1 hour (maximum expected time).

3.0 INSTRUCTIONS FOR USE

- Obtain a double-sided hard copy of this procedure for record keeping during the test.
- Refer to SEP GSE User's Manual on how to log in and set up GSE computers and run GSE software.
- In this procedure all displays for data verification are based on a Linux PC, either desktop or laptop, which is commonly referred to as SEP GSE.
- To command LET go to SEP Command Center window on SEP GSE. Select ASCII Command option and enable LET-CMD button. Type LET command in CAPITAL letters. Verify spelling before hitting the RETURN key.
- Verify checksums and command responses in SEP Command Echo Monitor window on SEP GSE.
- Monitor LET operation on GSE displays as instructed by the procedure.

3.1 TEST SETUP REQUIREMENTS:

LET shall be installed on its bracket atop SEP Central Electronics box and set up on one of the following: environmental test fixture, clean flow-bench or STEREO spacecraft. LET data shall go to SEP GSE either directly or via IMPACT GSE. Both GSEs shall be in their monitoring mode and mutually communicating before the test begins.

Boil-off LN₂ purge shall be continuously supplied to LET except during T/V test. Monitor flow daily. LET sensor shall be double-bagged in Ilumalloy bagging material before being taken out of cleanroom.

3.2 PARAMETERS REQUIRED:

In order to test LET operational heater at any given temperature the heater control parameter (Set Point) needs to be adjusted so that ambient temperature appears cold enough for the controller to start the heating. This parameter is featured in Section 2.2.7.

3.3 CRITICAL ACTIVITIES:

DO NOT send commands until LET representative conducting the procedure gives verbal OK.

In vacuum DO NOT power on SEP within the first 24 hours of reaching stable pressure of 10⁻⁶ torr. In case of a vacuum loss LET power shall be immediately shut off via automatic relay.

3.4 SPECIAL CONSTRAINTS OR ACTIVITIES:

LET apertures shall be protected by their red tag covers at all times except during environmental tests. DO NOT touch exposed aperture windows and make sure nothing accidentally hits them while the covers are removed.

LET sensor weighs 0.85kg and sits on top of SEP Main Assembly which makes it top-heavy. Special care must be taken during stand-alone testing to firmly attach SEP Main Assembly to the mounting surface in order to prevent accidental tipping.

3.5 RECORDING REQUIREMENTS:

Prior to the execution of this procedure SEP GSE software shall be running, data logging enabled and pertinent LET data windows and displays open on SEP GSE.

Test conductor shall follow the procedure steps and fill in the blanks on a hard copy of this procedure and snap GSE display windows as instructed by the procedure.

Hard copies shall be filed in the CPT section of a three-ring binder titled "LET Functional Tests".

LET data shall be stored on SEP GSE and backed up immediately on another Linux PC.

BEGINNING OF EXECUTIVE PORTION

_____ UTC 2.2.1 SEP Power On STEREO-CIT-031.A

If SEP power is on and LET has already booted, skip this procedure and go directly to 2.2.3. _____ (√ if so)

_____ UTC 1a. Be sure that either lab P/S or IMPACT GSE or S/C power is properly connected to SEP. Click on the preferred dice icon (FM1, S/C Ahead) _____ or (FM2, S/C Behind) _____ on SEP GSE to start the corresponding software and establish proper data recording channel on GSE.

Enable data logging _____ (√ if OK), open all SEP GSE displays/windows of interest _____ (√ if OK) and get ready to synchronize switching of SEP power and enabling of IDPU I/F clock within 5 seconds after power is turned on in order to capture SEP Central boot checksums. _____ (√ if OK and ready to continue)

_____ UTC 1b. Verify SEP Central checksums after booting (10-15 seconds following the power on).

On SEP Central FM1 unit verify these:

B0B	_____	1018	_____	93831D	_____	(√ if OK)
1582	_____	1918	_____	51400A	_____	
191D	_____	1A37	_____	9019	_____	
2412	_____	4E38	_____	F6EF2	_____	
RAM	F4C232	_____				
PROM0	F52F4B	_____				
PROM1	F52F4B	_____				
BOTH	EA5E96	_____				

On SEP Central FM2 unit verify these:

B0B	_____	1018	_____	93831D	_____	(√ if OK)
1582	_____	1918	_____	51400A	_____	
191D	_____	1A37	_____	9019	_____	
2412	_____	4E38	_____	F6EF2	_____	
RAM	F4C232	_____				
PROM0	425E6F	_____				
PROM1	1923DA	_____				
BOTH	5B8249	_____				

_____ UTC 1c. Verify SEP main +28V supply current _____ A

(It can vary depending on how many SEP sensors are attached to SEP Central: for LET alone 0.188A, for LET/HET FM1 0.196A, for LET/HET FM2 0.191A, for complete SEP 0.252A. If operating at cold, the operational heaters will turn on/off periodically and draw a predictable amount of extra current. If SEPT is attached, its operational heaters will cycle on/off until Step 1f is executed.)

_____ UTC 1d. Verify SEP main +28V supply voltage _____ V (28V)

1e. The following command returns address at the end of FORTH dictionary in SEP Central memory:

_____ UTC SEP> HERE . (Note there is a space between E and the dot) _____ (20024)

1f. The following command turns on bias voltages, enables SEPT PDFE circuits and SEPT operational heater control, and boots SIT, HET and LET sensors in that order. Command responses consist of boot messages and checksums. It takes about 60 seconds to execute if all four sensors are attached:

____ UTC SEP> ALLON1 (for FM1, S/C A) ____ or SEP> ALLON2 (for FM2, S/C B) ____ (√ echo)

Verify that SIT has booted and SIT> prompt was shown ____ (√ if OK)

Verify that HET has booted and HET> prompt was shown ____ (√ if OK)

Verify that LET has booted and LET> prompt was shown ____ (√ if OK)

____ UTC 1g. After LET has booted verify SEP main +28V supply current ____ A (It can vary depending on how many SEP sensors are attached to SEP Central: for LET alone 0.215A, for LET/HET FM1 0.228A, for LET/HET FM2 0.226A, for complete SEP 0.307A. If operating at cold, the operational heaters will turn on/off periodically and draw a predictable amount of extra current.)

____ UTC 1h. Verify LET checksums. On LET FM1 unit verify these: (√ if OK)
AF3 ____ 1000 ____ 9197FF ____
10FC ____ 12DC ____ 990383 ____
12E6 ____ 23FC ____ E2FAC3 ____
4876 ____ 937F ____ F5487F ____
937F ____ B428 ____ 1ABF06 ____
1D9DCA ____

On LET FM2 unit verify these: (√ if OK)
AF3 ____ 1000 ____ 9197FF ____
10FC ____ 12DC ____ 990383 ____
12E6 ____ 23FC ____ E2E5CD ____
4876 ____ 937F ____ F5487F ____
937F ____ B428 ____ 1ABF06 ____
1D88D4 ____

1i. The following command sets various firmware flags in their proper state:
____ UTC SEP> INITRCHK ____ (√ echo)

____ UTC 1j. If there are no anomalies above, SEP Power On procedure is complete. Record its total running time and any observations or anomalies here: _____

_____ UTC 2.2.2 SEP_Central Aliveness Test

STEREO-CIT-034.A

2a. Open all SEP displays on SEP GSE.

_____ (√ if OK and ready to continue)

_____ UTC 2b. Verify SEP main +28V supply current

_____ A

(It can vary depending on how many SEP sensors are attached to SEP Central: for LET alone 0.215A, for LET/HET FM1 0.228A, for LET/HET FM2 0.226A, for complete SEP 0.307A. If operating at cold, the operational heaters will turn on/off periodically and draw a predictable amount of extra current.)

_____ UTC 2c. Verify SEP main +28V supply voltage

_____ V (28V)

2d. The following command returns elapsed time in hours/minutes/seconds/sub-seconds since the last booting.

_____ UTC SEP> TIME. (Note there is no space between E and the dot) _____ (record)

2e. Verify that SEP Central section of SEP Housekeeping display (bottom portion) has no indication of yellow/red limit violations for voltages and temperatures monitored. _____ (√ if OK)

Record SEP Central HK anomalies here: _____

2f. Verify that two bias voltage monitors are showing approx. -120V and +330V. _____ (√ if OK)

2g. Snap SEP GSE HK page display and file it at the back of this procedure. _____ (√ if OK)

2h. Compare HK page display with a reference sample. Confirm there are no discrepancies. _____ (√ if OK)

2i. Observe and verify that all sensors' CCSDS packets are flowing regularly on a minute by minute basis:

- SIT 12 science packets/minute _____ (√ if OK)
- HET 6 science packets/minute _____ (√ if OK)
- LET 16 science packets/minute _____ (√ if OK)
- SEPT-E 1 science packet/minute _____ (√ if OK)
- SEPT-NS 1 science packet/minute _____ (√ if OK)
- Beacon data 1 science packet/minute _____ (√ if OK)

2j. Verify that SEP Unknown CCSDS Packet window is empty. _____ (√ if OK)

If not, record how many packets there are and their APID: _____

_____ UTC 2k. If there are no anomalies above, SEP_Central Aliveness Test procedure is complete.

Record its total running time and any observations or anomalies here: _____

_____ UTC 2.2.3 Normal Mode (LET Aliveness Test)

STEREO-CIT-024.A

3a. Open all LET displays on SEP GSE. Use Single Sample for rate displays and arrange them on the same workspace screen. In SEP Command Center window select LET_CMD button to prepare for sending commands to LET. _____ (✓ if OK and ready to continue)

_____ UTC 3b. Record SEP main +28V supply current _____ A

3c. If SEP power was just turned on, this step is unnecessary because LET starts up in Normal Mode. Skip this step and go to 3d. _____ (✓ if so)
If LET was previously in some other mode, the following command will put it in Normal Mode by enabling slow ADC and Livetime stimulus pulsing:

_____ UTC LET> NORMAL _____ (✓ echo)

3d. The following command returns address at the end of FORTH dictionary in LET memory.
_____ UTC LET> HERE . (Note there is a space between E and the dot) _____ (46120)

3e. The following command returns elapsed time in hours/minutes/seconds/sub-seconds since the last booting:
_____ UTC LET> TIME. (Note there's no space between E and the dot) _____ (record)

3f. Verify that LET section of SEP Housekeeping display (lower middle portion) has no indication of yellow/red limit violations for leakage currents and temperatures monitored. _____ (✓ if OK)
Record LET HK anomalies here: _____

3g. Verify that four LET temperature monitors are showing similar values within 1°C. _____ (✓ if OK)

3h. If 2e skipped, snap SEP GSE HK page display and file it at the back of this procedure. _____ (✓ if OK)

3i. Compare HK page display with a reference sample. Confirm there are no discrepancies. _____ (✓ if OK)

3j. Verify that 16 LET CCSDS packets/minute with APID 580 are flowing regularly (check either LET CCSDS Packet or LET Payload Telemetry Packet window). _____ (✓ if OK)

3k. Verify that Unprocessed LET Science Packet window is empty. _____ (✓ if OK)
If not, record how many packets there are and their APID: _____

3l. Snap LET page displays on SEP GSE and file them at the back of this procedure. _____ (✓ if OK)

3m. Compare LET page displays with reference samples. Check for stim box rates, single detector rates and event totals by priority. Confirm there are no discrepancies. _____ (✓ if OK)

_____ UTC 3n. If there are no anomalies above, LET Aliveness Test procedure is complete.
Record its total running time and any observations or anomalies here: _____

_____ UTC 2.2.4 ADC Only Mode (minimum running time ~10 minutes)

4a. The following command puts LET in ADC Only Mode by disabling Livetime stimulus pulse and adjusting ADC pulse rate in order to read out events from all 32 DAC levels per each ADC:

_____ UTC LET> ADCMODE _____ (√ echo)

_____ UTC 4b. Wait at least 2 minutes for new telemetry, then open 2-D plots of L1 vs. L2 and L1 vs. L3 for both A and B sides of the telescope. Use log-log scale and "dither". _____ (√ if OK)

4c. Monitor single detector rates and event totals by priority. Snap LET page displays, label and file them at the back of this procedure. Compare 2-D plots, event and rate page displays with reference samples. _____ (√)

4d. Fit and analyze data off-line. Person(s) responsible for the analysis _____. Analysis results will be available: date _____, location _____.

_____ UTC 4e. If there are no anomalies above, ADC Only Mode procedure is complete. Record its total running time and any observations or anomalies here: _____

_____ UTC 2.2.5 Quiet Mode (minimum running time ~5 minutes)

5a. The following command puts LET in Quiet Mode by disabling ADC and Livetime stimulus pulse in order to check for noisy detectors:

_____ UTC LET> QUIET _____ (√ echo)

_____ UTC 5b. Wait at least 2 minutes for new telemetry, then snap LET page displays, label and file them at the back of this procedure. Compare rate page displays with reference samples. Confirm there are no discrepancies and no noisy detectors. _____ (√ if OK)

_____ UTC 5c. If there are no anomalies above, Quiet Mode procedure is complete. Record its total running time and any observations or anomalies here: _____

_____ UTC 2.2.6 Threshold Mode (minimum running time ~10 minutes)

6a. The following command puts LET in Threshold Mode by disabling Livetime stimulus pulse and running ADC pulser using a table of low DAC levels designed to bracket the ADC thresholds:

_____ UTC LET> THRMODE _____ (√ echo)

_____ UTC 6b. Wait at least 2 minutes for new telemetry, then use the same 2-D plots of L1 vs. L2 and L1 vs. L3 for both A and B sides of the telescope like in 5b. _____ (√ if OK)

6c. Monitor single detector rates in both 1-min Single Sample and Running Total accumulation display. Snap LET page displays, label and file them at the back of this procedure. Compare 2-D plots, event and rate page displays with reference samples. _____ (√ if OK)

6d. Fit and analyze data off-line. Person(s) responsible for the analysis _____.

Analysis results will be available: date _____, location _____.

6e. The following command puts LET back in Normal Mode:

_____ UTC LET> NORMAL _____ (✓ echo)

_____ UTC 6f. If there are no anomalies above, Threshold Mode procedure is complete.

Record its total running time and any observations or anomalies here: _____

_____ UTC 2.2.7 LET Heater Mode (minimum running time ~5 minutes)

_____ UTC 7a. Record SEP main +28V supply current _____ A

_____ UTC 7b. Verify SEP main +28V supply voltage _____ V (28V)

7c. The following command artificially raises LET operational heater control set point in order to enable the heater verification at room temperature.

_____ UTC LET> 50 TEMPGOAL ! _____ (✓ echo)

7d. Wait one minute for the command to take effect, then watch for periodic increase in SEP main current that amounts to 0.030A (30mA) @ 28V on LET FM1, or 0.022A (22mA) @ 28V on LET FM2. Note that this predicted current increment is different if SEP main supply voltage is other than 28V.

_____ UTC 7e. Record the periodic peak value of SEP main +28V supply current _____ A

7f. Subtract 7a from 7e and record the result _____ A

The increment should agree with the amount predicted in 7d _____ (✓ if OK)

7g. The following command restores LET operational heater control set point to flight value (-10 °C):

_____ UTC LET> 157 TEMPGOAL ! _____ (✓ echo)

7h. Wait one minute for the command to take effect.

_____ UTC 7i. Record SEP main +28V supply current _____ A

If voltage is same as in 7b, the current should go back to the same value as in 7a _____ (✓ if OK)

_____ UTC 7j. If there are no anomalies above, LET Heater Mode procedure is complete.

Record its total running time and any observations or anomalies here: _____

____ UTC 2.2.8 SEP Power Off STEREO-CIT-032.A

____ UTC 8a. Verify SEP main +28V supply current _____ A
(It can vary depending on how many SEP sensors are attached to SEP Central: for LET alone 0.215A, for LET/HET FM1 0.228A, for LET/HET FM2 0.226A, for complete SEP 0.307A. If operating at cold, the operational heaters will turn on/off periodically and draw a predictable amount of extra current.)

____ UTC 8b. Verify SEP main +28V supply voltage _____ V (28V)

8c. If SEP is not operating in vacuum skip this step and go to 8e. _____ (✓ if OK)

If SEP is operating in vacuum and SIT HVPS is turned on, the following command will bring the HVPS down gradually:

____ UTC SIT> hvpsoff _____ (✓ echo)

____ UTC 8d. Wait 30 seconds and record SEP main +28V supply current _____ A

____ UTC 8e. Turn off SEP main +28V supply _____ (✓ if OK)

____ UTC 8f. Verify SEP main +28V supply current is zero _____ A (0A)

____ UTC 8g. If there are no anomalies above, SEP Power Off procedure is complete.
Record its total running time and any observations or anomalies here: _____

____ UTC LET Comprehensive Performance Test procedure is complete.

END OF EXECUTIVE PORTION

Record the total running time and any observations or anomalies here: _____

