



TS-CV-DC

CERN
CH-1211 Geneva 23
Switzerland

TS/CV Detector Cooling Project Document No./MP5 No

127.50/FCUL-00009

EDMS Document No.

452100

TECHNICAL FOLDER

CMS TRACKER PORTABLE COOLING UNIT MP5: FCUL-00009



General description and functionalities

This portable cooling unit runs a mixture of water and ethylene glycol, cooled down by a scroll compressor refrigerating unit.

The maximum cooling power is 4.5 kW @ -25°C, corresponding to a total flow rate of 1.1 m³/h, for a nominal pressure of 5 bar (~1kW @ -20°C on the distribution lines).

Three distribution lines serve the user circuits.


<p>Prepared by : Stephane Berry Florian Corbaz Paola Tropea TS/CV - paola.tropea@cern.ch</p>	<p>Checked by :</p>	
---	----------------------------	--

1. USER MANUAL

1.1 GENERAL RECOMMENDATIONS

The cooling plant shall be operated only after all the installation procedure is finished. After connecting the cooling plant to the cooling loops to be served, verify the tightness of the connections. (Put the cooling unit in Stand-by mode and let the vacuum pump stabilize the system pressures).

If big modifications have been done on the circuit, please test the system in pressure as well (1.5 times the work pressure for 24 hours).



1.1.1 DESCRIPTION OF THE CONTROL INTERFACE

Main power: switches on/off the electrical power of the cooling unit

Temperature regulator: it is used to set the temperature of functioning and to set-up the control parameters (PID)

Storage tank pressure: it gives info on the pressure measure into the tank

Outlet tank pressure: it gives info on the pressure measured at the distribution lines outlet form the cooling unit

Output pressure set-point: it acts on the pump inverter (1 turn = about 1 bar)

Control: it is used to switch the cooling unit between the stop/stand-by/run status, to read the alarms and to re-boot the system.

1.2 STARTING PROCEDURE



Before starting the cooling unit, the user must check:

- the connections to the user pipes are tight (3 valves on the distribution lines serve the three lines to the panels of the environmental chamber in bldg. 186)
- the electrical power is on
- the cooling plant is in the "OFF" mode (PLC screen)
- the correct set temperature is set on the Temperature regulator (see §5.2.1 for details)
- no alarms or warning appear on the PLC screen
- that the pump inverter (Output pressure set-point) is turned on the minimum value (turn counter clock wise until it stops)
- that the dry air flushing is activated (manual valve on the back side of the cooling rack)

N.B.: for the actual installation, some checks have to be done also on the environmental chamber:

- open the distribution circuit valves
- open the dry air distribution into the cold box (flow rate of 5 to 10 m³/h)

After the checks, these steps shall be followed:

- change the PLC status in STAND-BY (push the + sign on the PLC)
- wait for about 20 minutes and check regularly that the pressure in the tank is stable at about 700 mbara (check that the "storage tank pressure" is at about -0.3)
- Open the distribution valves (if they were closed)
- Wait until the pressure is stable again
- Start the cooling plant : change the PLC status in RUN (push the + sign on the PLC)
- Raise the pressure by mean of the inverter (knob of the "outlet pressure set-point" to be turned clock wise) up to an outlet vale of 2 bar (check on the "outlet tank pressure" manometer)

1.2.1 SET OF THE DISTIRBUTION TEMPERATURE



To change the temperature at the distribution line:

- push the "*" on the temperature regulator
- wait for the actual temperature set point to be shown keeping the button pushed
- adjust the set-point by using the flashes (always keeping the "*" button pushed)
- Release all buttons

PLEASE NOTE THAT THE PARAMETERS OF THE REGULATOR HAVE BEEN SET FOR AN OPTIMAL USE OF THE COOLING PLANT AT -20°C. IN CASE YOU NEED BIG CHANGES IN THE DISTRIBUTION TEMPERATURE, PLEASE FORESEE AN INTERVENTION FOR THE REGULATOR PARAMETER TUNING

1.3 ALARM LIST & ACTIONS

Alarm	Signal generator	Action
Low pressure on fridge unit	Pressure switch	Call for intervention (possible leak into the fridge circuit)
High pressure on fridge unit	Pressure sitch	Call for intervention (possible leak into the fridge circuit)
Low liquid level	Level meter	Check for liquid leaks, eventually fill the tank (if during the filling of the circuits)
Regulator alarm ($T > T_{set} + 60^{\circ}\text{C}$)	Regulator	Call for intervention – leave the plant in stand-by mode
Overheating	Thermostat du chauffage	Call for intervention – leave the plant in stand-by mode
High pressure in the tank	Pressure switch HP on tank	Re-start the plant in stand-by mode and verify the tightness
Vacuum pump : pumping time longer than 10 min	Pressure switch LP on tank	Check for leaks on the return line
Power failure	PLC	Run the start up procedure

Call for intervention: Paola Tropea tel 164999

1.4 STOP PROCEDURE

To stop the cooling unit:

- Lower down the pump pressure (turn the "output pressure set-point" knob counter clock wise until it stops and pressure on the "outlet tank pressure" manometer is 0)
- Change the status in STAND-BY (push the - sign on the PLC)
- Change the status in STOP (push the - sign on the PLC)
- Close the distribution valves

2. TEST

2.1 PERFORMANCE TESTS IN THE LABORATORY

The parameters listed in §4.5 have been established after testing of performances in the TS/CV/DC laboratory, by Stephane Berry and Paola Tropea.

A dummy load of 6 kW has been used to evaluate the cooling unit performances.

The set point temperature for the actual parameters of the temperature regulator is -20°C. At this temperature, the cooling power of the plant is 1kW.

2.2 PERFORMANCE TESTS ON THE USER INSTALLATION (CMS ENVIRONMENTAL CHAMBER IN BLDG. 186 – AUGUST 04)

The three lines serving the cold box panels are connected and filled. The cold box is flushed in a continuous way by dry air. The ambient temperature varies between 20 and 28°C during the tests.

The performances of the cooling unit listed in the table below correspond to these particular ambient condition and hydraulic connection. In particular, Test A has been performed with an average ambient temperature of 26°C, and Test B has been performed with an average ambient temperature of 22 °C.

In the following tables, "T measured" corresponds to the temperature measured downstream the heat exchanger by the PT100 used as feedback signal for the electrical heater.


The "electrical power" corresponds to the percentage of the electrical heater which is used to maintain the set-temperature and gives the order of magnitude of the cooling power of the cooling unit which is available at that temperature for other heat than that produced by the empty environmental chamber flushed with dry air.

Table 1: TEST A

TIME hh:mm	Cooling Plant				Environmental Chamber		
	T set point °C	T measured °C	El. power % of 4.5 kW	El. power kW	T1 °C	T2 °C	RH %
10:50	0	-1.6			11.8	9.8	29
14:00	-5	-4.9			6.8	4.4	20
17:10	-10	-10	45	2.0	2.5	-0.1	20
20:00	-15	-15.1	20	0.9	-2.1	-5.1	--
8:00	-10	-10	53	2.4	0.8	-1.4	20
11:00	-20	-20	2	0.1	-8.2	-5.4	--

Table 2: TEST B

Time	Ambient	Cooling Plant				Environmental Chamber		
	T	T set-point	T measured	El. power	El. power	T1	T2	RH
HH:MM	°C	°C	°C	% of 4.5 kW	kW	°C	°C	%
9:21			23.2			24.3	24.6	41
9:30		0						
15:35	23.2	0	-2.6	98	4.41	7.6	5.8	20
15:36	23.2	-5						
8:30	20.1	-5	-5.0	86	3.87	4.5	2.5	20
10:10	20.0	-5	-5.0	88	3.96	4.4	2.1	20
10:11	20.0	-10						
12:25	23.0	-10	-9.9	52	2.34	1.9	-0.9	20
14:30	24.0	-10	-10.0	50	2.25	1.6	-1.1	1
14:40	24.0	-15						
18:00	22.0	-15	-15.0	26	1.17	-2.4	-5.4	-
18:05	22.0	-20						
19:05	22.0	-20	-19.8	0	0.00	-4	-7.2	-
18:55	23	-20	-20.1	2	0.09	-5.7	-8.9	-
8:37	20	-20	-20.1	6	0.27	-6.7	-9.6	-



3. MAINTENANCE

Preventive maintenance must be foreseen for some of the equipments of the cooling unit.

The table below shows an indicative maintenance procedure list:

Equipment	Condition	Action	Spare
Pump	After 1 year	Check of the shaft seal (presse etoupe) – ev. Change	Shaft seal (to be bought)
Filter	After 1 year	Clean the filter	-
Connections	After 1 year	Check the tightness of the connections	-