



INSTALLATION MANUAL


Packaged water-cooled water chillers



EWWD120MBYNN EWWD180MBYNN EWWD240MBYNN EWWD280MBYNN EWWD360MBYNN EWWD500MBYNN EWWD520MBYNN EWWD520MBYNN







E - DECLARATION-OF-CONFORMITY
E - KONFORMITÀTSERKLÄRUNG
E - DECLARATION-DE-CONFORMITE
E - CONFORMITEITSVERKLARING ភុគុគុគុ

 $\dot{\Theta}\dot{\Theta}\dot{\Theta}\dot{\Theta}$

DECLARACION-DE-CONFORMIDAD DICHIARAZIONE-DI-CONFORMITA ΔΗΛΩΣΗ ΣΥΜΜΟΡΦΩΣΗΣ

CE - DECLARAÇÃO-DE-CONFORMIDADE CE - 3ARBJIEHÍNE-O-COOTBETCTBUN CE - OPFYLDELSESERKLÆRING CE - FORSÁKRAN-OM-ÖVERENSTÄMMELSE

CE - ERKLÆRING OM-SAMSVAR CE - ILMOITUŞ-YHDENMUKAISUUDESTA CE - PROHLÁŠENÍ-O-SHODĚ

CE - IZJAVA-O-USKLAĐENOSTI CE - MEGFELELŐSÉGI-NYILATKOZAT CE - DEKLARACJA-ZGODNOŚCI CE - DECLARAŢIE-DE-CONFORMITATE

CE - IZJAVA O SKLADNOSTI CE - VASTAVUSDEKLARATSIOON CE - ДЕКЛАРАЦИЯ-3A-CЪOTBETCTBИE

CE - ATTIKTIES-DEKLARACIJA CE - ATBILSTĪBAS-DEKLARĀCIJA CE - VYHLÁSENIE-ZHODY CE - UYUMLULUK-BİLDİRİSİ

Daikin Europe N.V

declares under its sole responsibility that the air conditioning models to which this declar ation relates:

erklärt auf seine alleinige Verantwortung daß die Modelle der Klimageräte für die diese Erklärung bestimmt ist:

03 🕞 déclare sous sa seule responsabilité que les appareils d'air conditionné visés par la présente déclar ation:

05 (E) declara baja su única responsabilidad que los modelos de aire acondicionado a los cuales hace referencia la declaración:

📵 δηλώνει με αποκλειστική της ευθύνη ότι τα μοντέλα των κλιμαπιστικών συσκευών στα οποία αναφέρεται η παρούσα δήλωση: 6

declara sob sua exclusiva responsabilidade que os modelos de ar condicionado a que esta declaração se refere.

🝩 ЗАЯВЛЯВТ МСКЛЮЧИТЕЛЬНО ТОД СВОЮ ОТВЕТ СТВЕННОСТЬ, ЧТО МОДЕЛИ КОНДИЦИОНЕРОВ ВОЗДУХА, К КОТОРЫМ ОТНОСИТСЯ НАСТОЯЩЕВ ЗАЯВЛЕНИВ:

11 💿 deklarerar i egenskap av huvudansvarig, att luftkonditioneringsmodellerna som berörs av denna deklaration innebär att: 10
 erklærer under eneansvar, at klimaanlægmodellerne, som denne deklaration vedrører:

12 (x) erklærer et fullstendig ansvar for at de luftkondisjoneringsmodeller som berøres av denne deklarasjon innebærer at:

18 ® declară pe proprie răspundere că aparatele de aer condiționat la care se referă această declarație:

22 🖅 visiška savo atsakomybe skelbia, kad oro kondicionavimo prietaisu modeliai, kuriems vra taikoma ši deklaracija: 17 🖭 deklaruje na własną i wyłączną odpowiedzialność, że modele klimatyzatorów, których dotyczy niniejsza deklaracja: 16 (F.) teljes felelőssége tudatában kijelenti, hogy a klímaberendezés modellek, melyekre e nyilatkozat vonatkozik: 13 🐵 ilmoittaa yksinomaan omalla vastuullaan, että tämän ilmoituksen tarkoittamat ilmastointilaitteiden mallit: 15 🙉 izjavljuje pod isključivo vlastitom odgovornošću da su modeli klima uređaja na koje se ova izjava odnosi: 14 @ prohlašuje ve své plné odpovědnosti, že modely klimatizace, k nimž se toto prohlášení vztahuje: 04 🕮 verklaart hierbij op eigen exclusieve verantwoordelijkheid dat de airconditioning unts waarop deze verklaring betrekking heeft: 06 ① dichiara sotto sua responsabilità che i condizionatori modello a cui è riferita questa dichiarazione:

25 🙃 tamamen kendi sorumluluğunda olmak üzere bu bildirinin ilgili olduğu klima modellerinin aşağıdaki gibi olduğunu beyan eder: 23 🕑 ar pilnu atbidību apliecina, ka tālāk uzskaitīto modeļu gaisa kondicionētāji, uz kuriem attiecas šī deklarācija: 24 ® vyhlasuje na vlastnú zodpovednosť, že tieto klimatizačné modely, na ktoré sa vzťahuje toto vyhlásenie:

21 (віз декларира на своя отговорност, че моделите климатична инсталация, за които се отнася тази декларация

20 📾 kinnitab oma täielikul vastutusel, et käesoleva deklaratsiooni alla kuuluvad kliimaseadmete mudelid

19 🐽 z vso odgovornostjo izjavlja, da so modeli klimatskih naprav, na katere se izjava nanaša:

$\mathsf{EWWD}120\mathsf{MBYNN}^{***}, \mathsf{EWWD}180\mathsf{MBYNN}^{***}, \mathsf{EWWD}240\mathsf{MBYNN}^{***}, \mathsf{EWWD}280\mathsf{MBYNN}^{***}, \mathsf{EWWD}380\mathsf{MBYNN}^{***}, \mathsf{EWWD}440\mathsf{MBYNN}^{***}, \mathsf{EWWD}500\mathsf{MBYNN}^{***}, \mathsf{EWWD}520\mathsf{MBYNN}^{***}, \mathsf{EWWD}540\mathsf{MBYNN}^{***}, mathsf{EWWD}540\mathsf{MBYNN}^{***}, \mathsf{EWWD}540\mathsf{MBYNN}^{***}, \mathsf{EWWD}540\mathsf{MBYNN}^{***}, \mathsf{EWWD}540\mathsf{MBYN}^{**}, \mathsf{EWWD}540\mathsf{MBY$

acordo com as nossas instruções: Of are in conformity with the following standard(s) or other normative document(s), provided that these are used in accordance with our 02 der/den folgenden Norm(en) oder einem anderen Normdokument oder -dokumenten entspricht/entsprechen, unter der Voraussetzung,

03 sont conformes à lalaux norme(s) ou autre(s) document(s) normatif(s), pour autant qu'ils soient utilisés conformément à nos instructions: daß sie gemäß unseren Anweisungen eingesetzt werden:

04 conform de volgende norm(en) of één of meer andere bindende documenten zijn, op voorwaarde dat ze worden gebruikt overeenkomstig 05 están en conformidad con la(s) siguiente(s) norma(s) u otro(s) documento(s) normativo(s), siempre que sean utilizados de acuerdo con onze instructies:

06 sono conformi al(i) seguente(i) standard(s) o altro(i) documento(i) a carattere normativo, a patto che vengano usati in conformità alle nuestras instrucciones:

07 είναι σύμφωνα με το(α) ακόλουθο(α) πρότυπο(α) ή άλλο έγγραφο(α) κανονισμών, υπό την προϋπόθεση ότι χρησμοπαιούνται nostre istruzioni:

αήπφωνα με τις οδηγίες μας:

01 following the provisions of: EN60335-2-40

19 ob upoštevanju določb:

10 under iagttagelse af bestemmelserne i: 17 zgodnie z postanowieniami Dyrektyw: 11 enligt villkoren 16 követi a(z): 03 conformément aux stipulations des: 04 overeenkomstig de bepalingen van: 07 με τήρηση των διατάξεων των: 08 de acordo com o previsto em: 05 siguiendo las disposiciones de: 02 gemäß den Vorschriften der: 06 secondo le prescrizioni per:

23 ievērojot prasības, kas noteiktas: 25 bunun koşullarına uygun olarak: 22 laikantis nuostatu, pateikiamu: 21 следвайки клаузите на: 24 održiavajúc ustanovenia: 20 vastavalt nõuetele: 12 gitt i henhold til bestemmelsene i: 14 za dodržení ustanovení předpisu: noudattaen määräyksiä: 15 prema odredbama:

positivamente da «B» secondo il Certificato «C».

** delineato nel File Tecnico di Costruzione «D» e giudicato 06 * delineato nel File Tecnico di Costruzione <A> e giudicato 01 * as set out in the Technical Construction File < > and judged positively by according to the Certificate <C>.

18 în urma prevederilor:

09 в соответствии с положениями:

wie in der Technischen Konstruktionsakte < A> aufgeführt und von ** as set out in the Technical Construction File <D> and judged positively by <E> (Applied module <F>) according to the Certificate <G>. ž

positivamente da <E> (Modulo <F> applicato) secondo i

Certificato <G>

07* όπως προσδιορίζεται στο Αρχείο Τεχνικής Κατασκεμής ΑΦ και κρίνεται θετικά από το «Β» σύμφωνα με το Πιστοποιητικό «Ο» " όπως προσδιορίζετα στο Αρχείο Τεχνικής Κατασκεμής «Δ» και " όπως προσδιορίζετα στο Αρχείο Τεχνικής Κατασκεμής «Δ» και B. positiv ausgezeichnet gemäß Zertifikat <C>.
 ** wie in der Technischen Konstruktionsakte <D> aufgeführt und von 03 * tel que stipulé dans le Fichier de Construction Technique <A> et <E (Angewandtes Modul <F>) positiv ausgezeichnet gemäß

jugé positivement par «B» conformément au Certificat «C». ** tel que siguilé dans le Fichier de Construction Technique «D» et jugé positivement par <E> (Module appliqué <F>) conformément au Certificat <G>.

04* zoals vermeld in het Technisch Constructiedossier < A> en in orde ** zoals vermeld in het Technisch Constructiedossier < D> en in orde bevonden door <E> (Toegepaste module <F>) overeenkomstig bevonden door overeenkomstig Certificaat <C>. Certificaat < G>.

35* tal como se expone en el Archivo de Construcción Tecnica «A» y juzgado positivamente por «B» según el Certificado «C».
** tal como se expone en el Archivo de Construcción Técnica «D» y juzgado positivamente por <E> (Modulo aplicado <F>) según el Certificado <G>. \$

08 estão em conformidade com a(s) seguinte(s) norma(s) ou outro(s) documento(s) normativo(s), desde que estes sejam utilizados de

09 соответствуют следующим стандартам или другим нормативным документам, при условии их использования согласно нашим инструкциям:

10 overholder følgende standard(er) eller andet/andre retningsgivende dokument(er), forudsat at disse anvendes i henhold til vore 11 respektive utrustning är utförd i överensstämmelse med och följer följande standard(er), eller andra normgivande dokument, under instrukser:

12 respektive utstyr er i overensstemmelse med følgende standard(er) eller andre normgivende dokument(er), under forutssetning av at förutsättning att användning sker i överensstämmelse med våra instruktioner: disse brukes i henhold til våre instrukser:

15 u skladu sa slijedećim standardom(ima) ili drugim normativnim dokumentom(ima), uz uvjet da se oni koriste u skladu s našim uputama: 14 za předpokladu, že jsou využívány v souladu s našími pokyny, odpovídají následujícím normám nebo normatívním dokumentům: mukaisesti:

17 spełniają wymogi następujących norm i innych dokumentów normalizacyjnych, pod warunkiem że używane są zgodnie z naszymi 16 megfelelnek az alábbi szabvány(ok)nak vagy egyéb irányadó dokumentum(ok)nak, ha azokat előírás szerint használják: instrukciami 18 sunt în conformitate cu următorul (următoarele) standard(e) sau att(e) document(e) normativ(e), cu condiția ca acestea să fie utilizate în

21 съответстват на следните стандарти или други нормативни документи, при условие, че се използват сълласно нашите 20 on vastavuses järgmis(t)e standardi(te)ga või teiste normatiivsete dokumentidega, kui neid kasutatakse vastavalt meie juhenditele: 19 skladni z naslednjimi standardi in drugimi normativi, pod pogojem, da se uporabljajo v skladu z našimi navodili: conformitate cu instrucțiunile noastre

24 sú v zhode s nasledovnou(ými) normou(ami) alebo iným(í) normatívnym(í) dokumentom(ami), za predpokladu, že sa používajú v súlade 22 attinka žemiau nurodytus standartus ir (arba) kitus norminius dokumentus su sąlyga, kad yra naudojami pagal mūsų nurodymus: 23tad. ja lietoti atbilstoši ražotāja norādījumiem, atbilst sekojošiem standartiem un citiem normatīviem dokumentiem. инструкции: 13 vastaavat seuraavien standardien ja muiden ohjeellisten dokumenttien vaatimuksia edellyttäen, että niitä käytetään ohjeidemme

25 Değiştirilmiş halleriyle Yönetmelikler.

16 irányelv(ek) és módosításaik rendelkezéseit. 18 Directivelor, cu amendamentele respective.

07 Οδηγιών, όπως έχουν τροποποιηθεί. 08 Directivas, conforme alteração em.

09 Директив со всеми поправками.

16 * a(z) <A> műszaki konstrukciós dokumentáció alapján, a(z) igazolta a megfelelést a(z) <C> tanúsítvány szerint.
** a(z) <D> műszaki korstrukciós dokumentáció alapján, a(z) <E>

igazolta a megfelelést (alkalmazott modul: <F>), a(z) <G>

tanúsítvány szerint.

15 Smjernice, kako je izmijenjeno. 17 z późniejszymi poprawkami.

14 v platném znění.

03 Directives, telles que modifiées. 04 Richtijnen, zoals geamendeerd. 05 Directivas, según lo enmendado. 06 Direttive, come da modifica.

02 Direktiven, gemäß Änderung.

01 Directives, as amended.

24 Smernice, v platnom znení

21 Директиви, с техните изменения. 23 Direktīvās un to papildinājumos.

13 Direktivejä, sellaisina kuin ne ovat muutettuina.

12 Direktiver, med foretatte endringer 10 Direktiver, med senere ændringer. 11 Direktiv, med företagna ändringar.

19 Direktive z vsemi spremembami. 20 Direktiivid koos muudatustega. 22 Direktyvose su papildymais.

25 ürünün, talimatlarımıza göre kullanılması koşuluyla aşağı daki standartlar ve norm belirten belgelerle uyumludur: s našim návodom:

> Pressure Equipment 97/23/EEC ** Electromagnetic Compatibility 89/336/EEC Machinery Safety 98/37/EEC Low Voltage 73/23/EEC

i enlighet med den Tekniska Konstruktionsfilen <D> som positivt Konstruktionsfilen <A> som positivt intygas av vilket också 11 * utrustningen är utförd i enlighet med den Tekniska framgar av Certifikat <C>.

12 * som det fremkommer i den Tekniske Konstruksjonsfillen <A> og som det fremkommer i den Tekniske Konstruksjonsfilen <D> og intygats av <E> (Fastsatt modul <F>) vilket också framgår av gjennom positiv bedømmelse av ifølge Sertifikat <C>.

22 * kaip nurodyta Techninėje konstrukcijos byloje < As ir patvirtinta < Bspagal pažymėjimą < Cs ** kaip nurodyta Techninėje konstrukcijos byloje <D> ir patvirtinta <E>

17* goodnie z archiwahią dokumantacją konstrukcyjną <4>, pozylywną opinią <4D i Świadectwem <C> zgodnie z archiwalną dokumentacją konstrukcyjną <D- i pozylywną z godnie z archiwalną dokumentacją konstrukcyjną <D- i pozylywną

opinią <E> (Zastosowany moduł <F>) zgodnie ze

оценено положително от <Е> (Приложен модул <F>) съгласно

Сертификат <G>.

21 * както е заложено в Акта за техническа конструкция < A> и ** както е заложено в Акта за техническа конструкция <D> и оценено положително от **** съгласно **Сертификат <C>**.

> gjennom positiv bedømmelse av <E> (Arvendt modul <F>) ifølge Sertifikat <G>.

> > κρίνεται θετικά από το <Ε> (Χρησιμοποιούμενη υπομονάδα <F>)

σύμφωνα με το **Πιστοποιητικό «G».** 08 * tal como estabelecido no Ficheiro Técnico de Construção **<A>** e

com o parecer positivo de **** de acordo com o **Certificado <C>.**** tal como estabelecido no Ficheiro Técnico de Construção **<D>** e

com o parecer positivo de <E> (Módulo aplicado <F>) de acordo

hyvæksynyt (Sovellettu moduli <F>) Sertifikaatin <G> mukaisesti.
14* jak bylo uvedeno v souboru technické konstrukce <A> a pozitivně 13 * jotka on esitetty Teknisessä Asiakirjassa <A> ja jotka on ** jotka on esitetty Teknisessä Asiakirjassa <D> ja jotka <E> on hyväksynyt Sertifikaatin <C> mukaisesti.

zjištáno «B» v souladu s osvádčením «C».

** jak bylo uvedeno v souboru technické konstrukce «D» a pozitívně zjišténo «E» (použitý modul «F») v souladu s osvědčením «G».

15 * kako je izloženo u Datoteci o tehničkoj konstrukciji < 4> i pozitivno kako je izloženo u Datoteci o tehničkoj konstrukciji <D> i pozitivno ocijenjeno od strane <E> (Primijenjen modul <F>) prema ocijenjeno od strane prema Certifikatu <C>.

> модуль **<-**F>) согласно **Сви детельству <G>** som anført i den Tekniske Konstruktionsfil **<A>** og positivt vurderet ** som anført i den Tekniske Konstruktionsfil <D> og positivt vurderet

₽

af i henhold til Certifikat <C>.

af <E> (Anvendt modul <F>) i henhold til Certifikat <G>.

соответствии с положительным решением <Б> (Прикладной

соответствии с положительным решением <В> согласно как указано в Досье технического толкования «D» и в

как указано в Досье технического толкования < А> и в

com o Certificado <G>. Свидетельству <С>.

skladu s certifikatom <C>.

** kot je določeno v tehnični mapi <D> in odobreno s strani <E> (Uporabljen modul <F>) v skladu s certifikatom <G>. 20 * nagu on näidatud tehnilises dokumentatsioonis <A> ja heaks

nagu on näidatud tehnilises dokumentatsioonis <D> ja heaks kiidetud järgi vastavalt sertifikaadile <C>.

didetud <E> järgi (lisamoodul <F>) vastavalt sertifikaadile <G>.

24 * ako je to stanovené v Súbore technickej konštrukcie < A> a kladne posúdené < B> podľa Certifikátu < C> . ** ako je to stanovené v Súbore technickej konštrukcie <D> a kladne posúdené <E> (Aplikovaný modul <F>) podla Certifikátu <G>. 25 * <A> Teknik Yapi Dosyasnda belirtildúği gibi ve <C> sertifikasına göre **<B**- tarafından olumlu olarak değerlendirilmiştir. **<D**> Teknik Yapı Dosyasında belirtildiği gibi ve **<G> sertifikasına** göre **<E**> tarafından olumlu olarak (Uygulanan modül **<F>**) 19 * kot je določeno v tehnični mapi <A> in odobreno s strani v

pozitīvajam lēmumam (piekritīgā sadaļa: <F>), ko apliecina

sertifikāts <G>.

apreciate pozitiv de <E> (Modul aplicat <F>) în conformitate cu 18 * conform celor stabilite în Dosarul tehnic de construcție <A> și apreciate pozitiv de **** în conformitate cu **Certificatul <C>**.

** conform celor stabilite în Dosarul tehnic de construcție **<D>** și

Certificatul <G>.

pozitīvajam lēmumam ko apliecina sertifīkāts <C>.
** kā noteikts tehniskajā dokumentācijā <D>, atbilstoši <E> 23 * kā noteikts tehniskajā dokumentācijā <A>, atbilstoši

(taikomas modulis <F>) pagal pažymėjimą <G>.

71801-KRQ/ECM97-4240 AIB Vinçotte (NB0026) Daikin.TCFP.002 DAIKIN.TCF.013 52846/01/12/01 KEMA I ô ĝ ٩ ê ပ္စ ŵ ŕ

> Ostend, 1st of August 2005 Director Quality Assurance

Jiro Tomita

Zandvoordestraat 300, B-8400 Oostende, Belgium EUROPE

DAIKIN

CONTENTS Page
Introduction 1 Technical specifications 1 Electrical specifications 1 Options and features 1 Standard supplied accessories 2
Operation range
Main components
Selection of location
Inspecting and handling the unit2
Unpacking and placing the unit3
Important information regarding the refrigerant used3
Preparing, checking and connecting the water circuit3
Water charge, flow and quality4
Piping insulation
Discharge from pressure relief devices5
Field wiring
Before starting
Customization in the service menu
How to continue

Thank you for purchasing this Daikin air conditioner.



READ THIS MANUAL ATTENTIVELY BEFORE STARTING UP THE UNIT. DO NOT THROW IT AWAY. KEEP IT IN YOUR FILES FOR FUTURE REFERENCE.

IMPROPER INSTALLATION OR ATTACHMENT OF EQUIPMENT OR ACCESSORIES COULD RESULT IN ELECTRIC SHOCK, SHORT-CIRCUIT, LEAKS, FIRE OR OTHER DAMAGE TO THE EQUIPMENT. BE SURE ONLY TO USE ACCESSORIES MADE BY DAIKIN WHICH ARE SPECIFICALLY DESIGNED FOR USE WITH THE EQUIPMENT AND HAVE THEM INSTALLED BY A PROFESSIONAL.

IF UNSURE OF INSTALLATION PROCEDURES OR USE, ALWAYS CONTACT YOUR DAIKIN DEALER FOR ADVICE AND INFORMATION.

INTRODUCTION

The Daikin EWWD-MBYNN packaged water-cooled water chillers are designed for indoor installation and used for cooling applications only. The units are available in 9 standard sizes with nominal cooling capacities ranging from 120 to 540 kW.

The EWWD units can be combined with Daikin fan coil units or air handling units for air conditioning purposes. They can also be used for supplying chilled water for process cooling.

The present installation manual describes the procedures for unpacking, installing and connecting the EWWD units.

Technical specifications(1)

Model EWWD		120	180	240
Dimensions HxWxD	(mm)	1	014x2672x930)
Weight				
machine weight	(kg)	1000	1273	1527
operation weight	(kg)	1032	1318	1588
Connections				
chilled water inlet/outlet ⁽¹⁾	(inch)	3" OD (76 mm OD)	3" (88.9	mm OD)
condenser water inlet/outlet ⁽¹⁾	(inch)	2-1/2"	3" (88.9	mm OD)

Model EWWD		280	360	440
Dimensions HxWxD	(mm)	1014x2672 x930	2000x26	672x930
Weight				
machine weight	(kg)	1613	2546	2800
operation weight	(kg)	1693	2636	2902
Connections				
chilled water inlet/outlet ⁽¹⁾	(inch)	3	" (88.9 mm OD))
condenser water inlet/outlet ⁽¹⁾	(inch)	3	8" (88.9 mm OE))

Model EWWD		500	520	540
Dimensions HxWxD	(mm)		2000x2672x89	В
Weight				
machine weight	(kg)	3034	3150	3346
operation weight	(kg)	3156	3281	3485
Connections				
chilled water inlet/outlet ⁽¹⁾	(inch)		3" (88.9 mm OE	0)
condenser water inlet/outlet ⁽¹⁾	(inch)		3" (88.9 mm OE))

⁽¹⁾ Victaulic® coupling

Electrical specifications(1)

Model EWWD		120~540
Power circuit		
Phase		3~
Frequency	(Hz)	50
Voltage	(V)	400
Voltage tolerance	(%)	±10

Options and features(1)

Options

- Suction stop valve
- Ampere and voltmeter
- Main isolator switch
- Dual pressure relief valve on the condenser
- Low noise operation
- BMS-Connection (MODBUS/J-BUS, BACNET, LON)

Features

- Glycol application for leaving evaporator water down to -10°C
- Daikin Integrated Chiller Network (DICN)
- Liquid line solenoid valve
- Sight glass with moisture indication
- Voltage free contacts
 - · general operation/pumpcontact
 - alarm
 - operation circuit 1
 - operation circuit 2 (only for EWWD360~540)


⁽¹⁾ Refer to the operation manual or engineering data book for the complete list of specifications, options and features.

- Changeable voltage free contacts
 - · 100% unit signal
 - · second evaporator pump
 - · condenser pump
 - · cooling/heating reversing valve
- Changeable remote inputs
 - · remote start/stop
 - dual setpoint
 - enable/disable capacity limitation⁽²⁾
 - · remote cooling/heating
- Changeable analog input
 - setpoint signal (stand alone unit or slave 1 unit in a DICN system)
 0/1 V, 0/10 V, 0/20 mA or 4/20 mA
 - evaporator outlet water sensor of a DICN system (only on master unit)
- Multiple language selection
- Schedule timer
- Floating setpoint

Standard supplied accessories

■ Filter kit for installation in front of the evaporator water inlet.

OPERATION RANGE





Leaving water temperature condenser Leaving water temperature evaporator Standard operation range Range for pull down operation

MAIN COMPONENTS

(refer to the outlook diagram supplied with the unit)

- 1 Compressor
- 2 Evaporator
- 3 Condenser
- 4 Switchbox
- 5 Compressor switchbox
- 6 Air purge condenser
- 7 Water drain condenser
- 8 Charge valve
- 9 Safety valve
- 10 High pressure switch
- 11 Drier
- 12 Chilled water in
- 13 Chilled water out
- 14 Condenser water out
- 15 Condenser water in
- 16 Entering water temperature sensor (R3T)
- 17 Leaving water temperature sensor (R4T)
 - (2) Can be used for night set back and/or peak power limitation: A kWh-gauge is connected to a voltage free contact. If the contact is enabled, circuit 1/2 will be limited to a preset capacity step.

- 18 Discharge stopvalve
- 19 Condenser entering water temperature sensor
- 20 Digital display controller
- 21 Emergency Stop (S5E)
- 22 Power supply intake
- 23 Field wiring intake24 Eyebolts for lifting
- 25 Transportbeam
- 26 Ballvalve liquid pipe
- 27 Main isolator switch (optional S13S)
- 28 Filter
- 29 Flowswitch

SELECTION OF LOCATION

This is a class A product. In a domestic environment this product may cause radio interference in which case the user may be required to take adequate measures.


The units are designed for indoor installation and should be installed in a location that meets the following requirements:

- The foundation is strong enough to support the weight of the unit and the floor is flat to prevent vibration and noise generation.
- 2. The space around the unit is adequate for servicing.
- 3. There is no danger of fire due to leakage of inflammable gas.
- Select the location of the unit in such a way that the sound generated by the unit does not disturb anyone.
- Ensure that water cannot cause any damage to the location in case it drips out of the unit.

NOTE Pull-down operation is restricted to one hour maximum.

INSPECTING AND HANDLING THE UNIT

At delivery, the unit should be checked and any damage should be reported immediately to the carrier claims agent.



When handling the unit, take into account the following:

- 1 Lift the unit preferably with a crane and belts in accordance with the instructions on the unit. The length of the ropes (1) to be used for lifting are 4 m minimum each.
- 2 The unit is shipped with wooden beams (2) under it, these have to be removed before installation.


NOTE

Try to reduce the drilling in the unit to a minimum. If drilling is impreventable, remove the iron filling thoroughly in order to prevent surface rust!

UNPACKING AND PLACING THE UNIT

- Remove the wooden beams from the unit.
- 2 Install vibration mountings in case of an installation where noise and vibration might be an impediment.
- 3 Set the unit on a solid and level foundation.

The unit should be installed on a solid base. It is recommended to fix the unit on a concrete base with anchor bolts.



- Anchor bolt
- 2 Washer
- 3 Rubber plate
- 4 Row cork or rubber sheet
- 5 Ground
- 6 Concrete floor
- 7 Ditch
 - Fix anchor bolts into the concrete foundation. When finally fixing
 the unit by means of these anchor bolts, make sure that the
 washers for channel DIN434, and both field supplied rubber
 plates and field supplied raw cork or rubber sheets for better
 vibration protection, are installed as indicated.
- The concrete foundation should approximately be 100 mm higher than the floor level for ease of plumbing work and better drain.

		Anchor bo	olt
Model	Α	Size	Qty
EWWD120+180	300	M20x200	4
EWWD240+280	350	M20x200	4
EWWD360~540	350	M20x270	4

Make certain that the foundation surface is even and flat.



- The measurement tabulated is based on the fact the base is made in the ground or on a concrete floor. In case the base is made on a rigid floor, it is possible to include thickness of concrete floor in that of the base.
- In case a base is made on concrete floor, make sure to provide a ditch as shown. It is important to extract drainage regardless of whether a base is made in the ground or on the concrete floor (ditchsewerage).
- Ingredient ratio of the concrete is: cement 1, sand 2 and gravel 3. Insert iron bars of Ø10 at every interval of 300 mm. The edge of the concrete base should be planed.

IMPORTANT INFORMATION REGARDING THE REFRIGERANT USED

This product contains fluorinated greenhouse gases covered by the Kyoto Protocol. Do not vent gases into the atmosphere.

Refrigerant type: R134a GWP⁽¹⁾ value: 1300

(1) GWP = global warming potential

The refrigerant quantity is indicated on the unit name plate.

PREPARING, CHECKING AND CONNECTING THE WATER CIRCUIT


The units are equipped with a water inlet and water outlet for connection to a chilled water circuit. This circuit must be provided by a licensed technician and must comply with all relevant European and national regulations.



If air or dirt gets in the water circuit, problems may occur. Therefore, always take into account the following when connecting the water circuit:

- 1. Use clean pipes only.
- 2. Hold the pipe end downwards when removing burrs.
- 3. Cover the pipe end when inserting it through a wall so that no dust and dirt enter
- 1 Preparing the unit for connection to the water circuit

A box containing Victaulic® couplings and a filter is delivered with the unit.



- 1 Water inlet of the evaporator
- 2 Flowswitch
- 3 Inlet water sensor
- Water inlet pipe containing the flowswitch and the water inlet temperature sensor
- 5 Victaulic® coupling
- 6 Counter pipe
- 7 Field water piping circuit
- 8 Filter
- 9 Filter end cap

As not to damage the parts of the units during transport, the water inlet pipe with the flowswitch and the water inlet temperature sensor and the water outlet pipe with the outlet water temperature sensor, are not factory mounted.

■ Connecting the water inlet pipe containing the flowswitch and inlet water temperature sensor: (not for EWWD120)

The water inlet pipe containing the flowswitch and inlet water temperature sensor is mounted on the side of the water inlet of the evaporator(s) and is pre-insulated.


Cut the tie wraps and fix the pipe with the supplied Victaulic® couplings to the evaporator inlet(s).

Connecting the water outlet pipe containing the outlet water temperature sensor: (not for EWWD120)

The water outlet pipe containing the outlet water temperature sensor is mounted on the side of the water outlet of the evaporator and is pre-insulated.

Cut the tie wraps and fix the pipe(s) with the supplied Victaulic® couplings to the evaporator outlet(s).

After installation of the water inlet and outlet pipes and as a general rule for other units, it is recommended to check the insertion depth of the water temperature sensors into



the connection pipes prior to operation (see figure).




- The filter kit supplied with the unit must be installed in front of the evaporator water inlet by means of the supplied Victaulic® couplings as shown in the figure. The filter has holes of diameter 1.0 mm and secures the evaporator against clogging.
- Improper installation of the supplied filter will result in severe damage of the equipment (freezing of the evaporator)

A field supplied blow down port for flushing fluid and accumulated material from inside the filter can be connected on the filter end cap.

- Connecting the counter pipes Weld the supplied counter pipes to the ends of the water circuit and connect to the unit with the provided Victaulic® couplings.
- 2 Drain taps must be provided at all low points of the system to permit complete drainage of the circuit during maintenance or in case of shut down. The drain plug is provided to drain the condenser. When doing this, also remove the air plugs (refer to the outlook diagram).
- 3 Air vents must be provided at all high points of the system. The vents should be located at points which are easily accessible for servicing.
- 4 Shut-off valves should be provided at the unit so that normal servicing can be accomplished without draining the system.
- 5 Vibration eliminators in all water piping connected to the chiller are recommended to avoid straining the piping and transmitting vibration and noise.
- 6 For units in a DICN configuration with common leaving water control, be sure to foresee an insertion hole for the additional water temperature sensor. Sensor and sensor holder are optional parts.

The insertion hole shall be 1/4" GAS female thread and should be located in the mixed waterflow of the chillers.

Make sure that the sensortip is in the waterflow and that you have a length of straight pipe (L) of at least 10x the pipe diameter (A) before the sensor.



Choose the position of insertion in a way that the cable length of the sensor (12 m) is long enough to be attached to the master PCB

WATER CHARGE, FLOW AND QUALITY

To assure proper operation of the unit, the water flow through the evaporator must be within the operation range as specified in the table below and a minimum water volume is required in the system.

	Minimum water flow	Maximum water flow
EWWD120	175 l/min	700 l/min
EWWD180	265 l/min	1070 l/min
EWWD240	350 l/min	1400 l/min
EWWD280	400 l/min	1600 l/min
EWWD360	525 l/min	2100 l/min
EWWD440	625 l/min	2500 l/min
EWWD500	700 l/min	2800 l/min
EWWD520	750 l/min	3000 l/min
EWWD540	800 l/min	3200 l/min

The minimum water volume v [I] in the system must fullfill the criteria below:

$v>(Q/2)xt/(Cx\Delta T)$

- Q highest cooling capacity of the unit in lowest capacity step within the range of application (kW)
- t antirecycling timer of unit (AREC)/2(s)=300 s
- C specific heat capacity of the fluidum (kJ/kg°C)=4.186 kJ/kg°C for water
- ΔT $\,$ temperature difference between starting and stopping of the compressor.

 $\Delta T = a + 2b + c$

(for designation of a, b and c, refer to the operation manual)

NOTE

For units in a DICN configuration, the minimum required water volume in the system must equal the biggest required minimum volume of every individual chiller in the system.

The water quality must be in accordance with the specifications listed in the table below.

		circulating water	supply water	tendency if out of criteria
Items to be controlle	ed			
рН	at 25°C	6.8~8.0	6.8~8.0	corrosion+ scale
Electrical conductivity	[mS/m] at 25°C	<40	<30	corrosion+ scale
Chloride ion	[mg Cl ⁻ /l]	<50	<50	corrosion
Sulfate ion	[mg SO ₄ ²⁻ /l]	<50	<50	corrosion
M-alkalinity (pH4.8)	[mg CaCO ₃ /l]	<50	<50	scale
Total hardness	[mg CaCO ₃ /l]	<70	<70	scale
Calcium hardness	[mg CaCO ₃ /l]	<50	<50	scale
Silica ion	[mg SiO ₂ /l]	<30	<30	scale
Items to be referred	to			
Iron	[mg Fe/l]	<1.0	<0.3	corrosion+ scale
Copper	[mg Cu/l]	<1.0	<0.1	corrosion
Sulfide ion	[mg S ²⁻ /l]	not detectable	not detectable	corrosion
Ammonium ion	[mg NH ₄ /l]	<1.0	<0.1	corrosion
Remaining chloride	[mg Cl/l]	< 0.3	< 0.3	corrosion
Free carbide	[mg CO ₂ /I]	<4.0	<4.0	corrosion
Stability index		_	_	corrosion+ scale



The water pressure should not exceed the maximum working pressure of 10 bar.

NOTE

Provide adequate safeguards in the water circuit to make sure that the water pressure will never exceed the maximum allowable working pressure.

PIPING INSULATION

The complete water circuit, inclusive all piping, must be insulated to prevent condensation and reduction of the cooling capacity.

Protect the water piping against water freezing during winter period (e.g. by using a glycol solution or heatertape).

DISCHARGE FROM PRESSURE RELIEF DEVICES

Discharge of the refrigerant into installation area has to be in accordance with local regulations. If required it is possible to connect a 1" pipe to each pressure relief valve on the condenser.

Cross section and lenght of the discharge line must comply with local codes.

FIELD WIRING



All field wiring and components must be installed by a licensed electrician and must comply with relevant European and national regulations.

The field wiring must be carried out in accordance with the wiring diagram supplied with the unit and the instructions given below.

Be sure to use a dedicated power circuit. Never use a power supply shared by another appliance.



Verify on the wiring diagram all electrical actions mentioned below, in order to understand the operation of the unit more deeply.

Parts table

F1,2,3U	Main fuses for the unit
H1,4P	Indication lamp general operation
H2,5P	Indication lamp alarm
H3,6P	Indication lamp operation compressor
L1,2,3	Main supply terminals
PE	Main earth terminal
S6S	Changeable input 1
S8L	Flowswitch
S9L	Contact that closes if the pump is working
S10S	Changeable input 2
S11S	Changeable input 3
S12S	Changeable input 4
S13S	Main isolator switch
	Field wiring

Power circuit and cable requirements

- 1 The electrical power supply to the unit should be arranged so that it can be switched on or off independently of the electrical supply to other items of the plant and equipment in general.
- 2 A power circuit must be provided for connection of the unit. This circuit must be protected with the required safety devices, i.e. a circuit breaker, a slow blow fuse on each phase and an earth leak detector. Recommended fuses are mentioned on the wiring diagram supplied with the unit.

For a system with chillers in a DICN configuration, be sure to provide a separate power circuit for every chiller.



Switch off the main isolator switch before making any connections (switch off the circuit breaker, remove or switch off the fuses).

Connection of the watercooled water chiller power supply

1 Using the appropriate cable, connect the power circuit to the L1, L2 and L3 terminals of the unit.

In case the option "main isolator switch" is installed on the unit, the power circuit must be connected to the terminals 2, 4 and 6 of the main isolator switch.

2 Connect the earth conductor (yellow/green) to the earthing terminal PE.

Interconnection cables



A pump interlock contact must be installed **in series** with the contact of the flowswitch(es) to prevent the unit from operating without water flow. A terminal is provided in the switch box for the electrical connection of the interlock contact.

For units in a DICN configuration, every chiller can either have an individual circulation pump or 1 pump can discharge water in a distributor that leads water to several chillers.

In both cases, all units must be equipped with an interlock contact!

NOTE

Normally the unit will not operate if there is no flow thanks to the standard installed flowswitch.

But as to have a double safety, you **must** install the pump interlock contact in series with the contact of the flowswitch.

Operating the unit without flow will result in very severe damage to the unit (freezing of the evaporator)

■ Voltage free contacts

The controller is provided with some voltage free contacts to indicate the status of the unit. These voltage free contacts can be wired as described on the wiring diagram. The maximum allowable current is 4 A.

Remote inputs

Besides the voltage free contacts, there are also possibilities to install remote inputs. They can be installed as shown on the wiring diagram.

For units in DICN configuration, note the following:

- · Switch for remote on/off:
 - Units with status NORMAL or STANDBY will be controlled by the remote on/off switch connected to the chiller defined as MASTER. Units with status DISCONNECT ON/OFF are controlled by the switch connected to them.
 - See also operation manual: "Selecting local or remote on/off control"
- Remote dual setpoint switch:
 - The remote dual setpoint switch should only be connected to the chiller defined as MASTER.

However in case the master drops out because of e.g. a power supply failure, it might be interesting to have the dual temperature switch installed to the other units as well.

Connection and setup of a DICN system

(See Annex I, "Installation examples for a DICN configuration" on page 9)

For a system with chillers in a DICN configuration, the chillers have to be connected as shown in the figure below.



Make the connection as shown on the wiring diagram using an AWG20/22 shielded cable, made up of a twisted pair plus shield.

Pay attention to the polarity! TX+ on one chiller must be connected to TX+ on another chiller. The same for TX- and GND.


Setting the adresses on the digital controller

Set the addresses on the PCB by means of DIP-switches according to the drawing below:

PCB address

Any unit can be master, slave 1, slave 2, slave 3...

Where to find the DIP-switches of the digital controller



Important

Be sure to attach — in case of common leaving water control — the optional temperature sensor.

Cable for remote digital controller

See remote digital controller in the operation manual.

- A remote digital controller can be connected to the PCB inside the unit by means of a 6-ray cable and a connector located on the rear side of the remote digital controller in case you prefer to operate the unit from a distance. You are allowed to use a cable of up to 600 metres (EWWD120~280) or 300 metres (EWWD360~540). Specifications of the cable: 6-ray telephone cable with a maximum cable resistance of 0.1 Ω/m.
- 2 For units in a DICN configuration, the digital controllers of the units can be installed remotely at a distance of up to 50 metres by using a 6-ray telephone cable with a maximum cable resistance of 0.1 Ω /m.

Setting the adresses on the remote digital controller


When a remote digital controller is used, the adress has to be set by means of DIP-switches according to the drawing below:

Master Slave 1 Slave 2 Slave 3

123456 123456 123456 0FF 0FF 0FF

Any unit can be master, slave 1, slave 2, slave 3...

Where to find the DIP-switches of the remote digital controller






Remote digital

controller address

To avoid damage to the controllers liquid crystals during winter time, do not shut off the main power supply.

Setting the adresses on the EEV drivers

When EEV drivers are used, the adresses has to be set by means of DIP-switches according to the drawing below:



Any unit can be master, slave 1, slave 2, slave 3...

Where to find the DIP-switches of the EEV drivers



BEFORE STARTING



The unit should not be started, not even for a very short period of time, before the following pre-commissioning checklist is filled out completely.

tick ✓ when checked	standard steps to go through before starting the unit
_ 1	Check for external damage
2	Open all shut-off valves indicated by a red label: "OPEN THIS VALVE BEFORE OPERATION". (Open the liquid line, discharge and suction (if provided) stop valves completely.)
3	Install mainfuses , earth leak detector and mainswitch . Recommended fuses: aM according to IEC standard 269-2. Refer to the wiring diagram for size.
4	Supply the main voltage and check if it is within the allowable ±10% limits of the nameplate rating. The electrical main power supply should be arranged so, that it can be switched on or off independently of the electrical supply to other items of the plant and equipment in general. Refer to the wiring diagram, terminals L1, L2 and L3.
_ 5	Supply water to the evaporator and verify if waterflow is within the limits as given in the table under "Water charge, flow and quality" on page 4.
6	The piping must be completely purged . See also chapter "Preparing, checking and connecting the water circuit" on page 3.
7	Connect the pump contact(s) in series with the contact of the flowswitch(es), so that the unit can only come in operation when the waterpumps are running and the water flow is sufficient. For DICN configurations, every chiller shall have its own flowswitch and shall be interlocked with the pump from which it gets the flow.
8	Check the oil level in the compressors.
9	Install the filter kit(s) supplied with the unit in front of the evaporator(s) water inlet.
10	Check that all the water sensors are correctly fixed into the heat exchanger (see also the sticker attached to the heat exchanger).

NOTE

- It is necessary to read the operation manual delivered with the unit before operating the unit. It will contribute to understand the operation of the unit and its electronic controller.
- Close all switch box doors after installation of the unit.

I do confirm having executed and checked all the above mentioned items.

Date

Sign

KEEP FOR FUTURE REFERENCE

CUSTOMIZATION IN THE SERVICE MENU



All customized settings must be done by a licensed technician.

To change a setting in the service menu:

- 1 Enter the usersettings menu as indicated in the operation manual and press the

 key to go to the last screen to enter the service menu (this is only possible if the unit is off).
- Press (a) to confirm the password and enter the service menu.
- 4 Go to the screen which contains the parameter to be modified by using the (*) and (*) keys.
- 5 Position the cursor behind the parameter to be modified using the key.
- 7 Press to confirm the modification. When the modification has been confirmed, the cursor switches to the next parameter which can now be configured.
- 8 Place the cursor in the top left corner of the screen when you are finished changing the parameters on this screen.
- 9 Repeat from instruction 4 onwards to modify other parameters.

Setting of the minimum outlet water temperature

It is possible to change the minimum outlet water temperature (MIN_OUTWATER) in the service menu. Before lowering the minimum outlet water temperature:

- Make sure that sufficient glycol is added to the water system according to the table.
- Make sure that the low pressure safety is lowered according to the table.

	minim	um outlet wa	ter (MIN. O	UTWATER)
	2°C	0°C	-5°C	–10°C
Weight of ethylene glycol (%) 10	20	30	40
Weight of propylene glycol (%	5) 15	25	35	40
Low pressure setting (ba	r) 0.8	0.6	0.2	0.2



Improper setting of the minimum outlet water temperature can result in severe damage of the equipment.

Defining a unit in a setup of a DICN system

Change the setting of MS OPTION to Y on each unit.

Setting the password for safety reset

To avoid resetting of safeties by unqualified persons, the user password is asked by default when resetting a sefety.

This password however can be changed to SERVICE PASSWORD or to NONE.

NOTE

Since inadequate resetting of safeties can damage the machine, it is advised to keep the default setting of USER PASSWORD.

Setting of compressor running hours

When the displayed running hours do not comply with the actual running hours of the compressor it is possible to change the running hours to comply.

Defining of the changeable digital/analog inputs and outputs

Besides locked inputs and outputs there are a number of changeable inputs and outputs of which the function can be chosen from several possibilities.

Possible functions for changeable digital inputs are:

- NONE: no function is appointed to the changeable digital input.
- STATUS: no function is appointed to the changeable digital input, but the input status can be read in the "input/output" menu.
- DUAL SETPOINT: to switch between setpoints.
- REMOTE ON/OFF: to remotely switch the unit on or off.
- CAP. LIM 1/2/3/4: to limit the capacity of the unit to the entered values.
- REMOTE COOL/HEAT: to remotely switch the unit between cooling and heating.

Possible functions for the changeable digital output are:

- NONE (OPEN): no function is appointed to the changeable digital
- 1 (CLOSED): no function is appointed to the changeable digital output, but the output is closed.
- REV. VALUE (C/H): can be used to steer a cooling/heating reversing valve.
- 2ND EVAP PUMP: can be used to steer a second evaporator amua.
- CONDENSER PUMP: can be used to steer the condenser pump.
- 100% CAPACITY: indicates when the unit is working at 100%.

Possible configurations for the changeable analog input are:

- NONE: no function is appointed to the changeable analog input.
- SETP.SIGN. 0/10:
- SETP.SIGN. 0/100:
- SETP.SIGN.0/20mA:
- SETP.SIGN.4/20mA:

This allows the user to define a setpoint in function of an analog input as mentioned above. Refer to "Defining the setpoint signal setting" on page 8.

MS OUTL WATER E: to control the leaving water temperature of a DICN system.

Defining the setpoint signal setting

The setpoint signal is used to change the setpoint by an external analog input signal on a stand alone unit or on Slave 1 in a DICN system.

Example


in setpoints menu

INLSETP1 E: 12.0°C INLSETP2 E: 12.0°C OUTLSETP1 E: 07.0°C OUTLSETP2 E: 07.0°C

in service menu

_÷ CHANG.INP/OUTPUTS AI1:SETP.SIGN: 0/1V MAX SETP.DIF: 5.0°C

Remark: MAX SETP. DIFF is only available when input SETP.SIGN (0/1V, 0/10V, 0/20mA or 4/20mA) is selected.



Result

Display in readout menu

at 0 V \rightarrow 12.0°C

INLSETP1 E: 12.0°C

at 1 V \rightarrow 12.0°C + 5.0°C = 17.0°C INLSETP1 E: 17.0°C

Setting of the probe offset

It is possible to enter a correction value for certain measured temperatures (inlet water evaporator temperature and mixed outlet water evaporator temperature). This in order to correct a possible measurement fault. The default value of the probe offset, is equal to 0.

Steering the pump manually

There is the possibility to turn the pump on or off manually. This means that when the unit is off the pump can also be turned on at any time to check the pump.

Defining the BMS settings

The BMS parameters allowing communication between the unit and the supervisory system can be modified with the BMS SETTINGS and the BMSBOARD SETTINGS screen of the service menu. The BMS parameters are:

BMS SETTINGS screen:

- BMS CONTROL ALLOWED: if set to Y (yes), the unit can be commanded and configured from a supervisory system. If set to N (no), the supervisory system can only read out values but cannot modify them.
- BMS ADDR.PCB: used to address the PCB.
- PROTOCOL: indicates the communication protocol. If the optional gateway is used to connect the units to a supervisory system, the protocol is CAREL.

BMSBOARD SETTINGS screen:

- SER. BOARD: indicates the type of serial connection. The default is set to RS485.
- BAUD RATE: indicates the speed of communication. The default setting of 19200 bes must be used when the optional gateway is connected.

Defining the thermostat settings

Defining the thermostat settings for inlet and outlet water temperature of a, b and c can only be set in the service menu.

_÷STEPL SERVICE MENU A:0.8 B:0.5 C:0.2°C INLDIFF:0.5°C

To define the thermostat settings of the inlet and outlet water temperature.

How to continue

After installation and connection of the packaged water-cooled water chiller, the complete system should be checked and tested as described in "Checks before initial start-up" in the operation manual supplied with the unit.

Fill out the brief operation instructions form and fix it visibly near the operating site of the refrigeration system.

Installation examples for a DICN configuration

INTRODUCTION

This annex introduces 3 installation examples to help you set up your Daikin Integrated Chiller Network or DICN configuration.

Defining a unit in a setup of a DICN system

Change the setting of MS OPTION to Y on each unit.

EXAMPLES

Field wiring and wiring parts table



All field wiring and components must be installed by a licensed electrician and must comply with relevant European and national regulations.

The field wiring must be carried out in accordance with the wiring diagram supplied with the unit and instructions given below

Be sure to use a dedicated power circuit. Never use a power supply shared by another appliance.

All customized settings must be done by a licensed technician.

	Field wiring
	Earth wiring
•	Terminal on the unit
F1~F20	Fuses
K1P~K4P	Pump contact (S9L on main wiring diagram)
L1,L2,L3,N	Main supply terminals
M1P~M5P	Pump motor
	Sensor for common leaving water in a DICN system (EKCLWS)
R8T	Sensor for common leaving water in a DICN
R8T	Sensor for common leaving water in a DICN system (EKCLWS)
R9T	Sensor for common leaving water in a DICN system (EKCLWS)
R8T R9T S1S S6S (M,S3)	Sensor for common leaving water in a DICN system (EKCLWS)Sensor for secondary circuitManual switch for pump of master unit

Example 1: Single ring system with 1 pump

Figure 1 shows the system configuration, field wiring and terminals for field wiring of this example.

Purpose

Purpose of this system is to deliver a constant water flow at a constant temperature to a particular load. One unit, slave 3 (S3), is kept as a standby unit.

Setup

- The system is controlled on leaving water temperature. It is required to install the additional sensor R8T (EKCLWS) in the mixed water outlet and to connect it to the PCB of the master unit.
- The pump keeps running as long as 1 of the units is ON. After switching OFF all units, the pump runs for a time indicated by the PUMPLAG setting.
- Slave 3 (S3) is configured to operate when its remote start/stop switch S6S (S3) is pushed by the operator.
- Slave 1 (S1), slave 2 (S2) and the master unit (M) are switched ON or OFF using the remote start/stop switch S6S (M) which is connected to the master unit.
- The setpoint can be switched from 0UTLETSETP1 to 0UTLETSETP2 using the dual setpoint selection switch S10S which is connected to the master unit.

NOTE

K*P can also be a 24 V DC or 230 V AC contactor.



The additional sensor R8T (EKCLWS) must be connected directly to the PCB of the master unit.

Parameter settings of the units

Usersettings menu:

	Slave 3	Slave 2	Slave 1	Master
MODE:	DISCONNECT ON/OFF	NORMAL	NORMAL	NORMAL
PUMP ON IF:	UNIT ON	UNIT ON	UNIT ON	UNIT ON

Changeable inputs/outputs must be defined as follows:

Service setting menu:

	Slave 3	Slave 2	Slave 1	Master
Terminal 76-78 S10S DI1	NONE	NONE	NONE	DUAL SETPOINT
Terminal 76-79 S6S DI2	REMOTE ON/OFF	NONE	NONE	REMOTE ON∕OFF
Terminal 76-85 DI3	NONE	NONE	NONE	NONE
Terminal 76-86 DI4	NONE	NONE	NONE	NONE
Terminal 8T+8T- R8T Al1	NONE	NONE	NONE	MS OUTL WATER E

Remark

Slave 3 can be configured to start up automatically if:

- 1 of the other units is in alarm or;
- all other units are running on full capacity and the setpoint is not reached yet.

To have your slave 3 unit act this way, set its mode to STANDBY. In this case, S6S (S3) has no function.

Example 2: Single ring system with separate pumps

Figure 2 shows the system configuration, field wiring and terminals for field wiring of this example.

Purpose

Purpose of this system is to deliver a constant water flow at a constant temperature to a particular load. One unit, slave 3 (S3), is kept as a standby unit.

Setup

- The system is controlled on leaving water temperature. It is required to install the additional sensor R8T (EKCLWS) in the mixed water outlet and to connect it to the PCB of the master unit.
- Pump 1, pump 2 and pump 3 keep running as long as the master unit, slave 1 or slave 2 are ON. Pump 4 only starts running if slave 3 is switched ON. After switching OFF the units, the pump runs for a time indicated by the PUMPLAG setting.
- Slave 3 (S3) is configured to operate when its remote start/stop switch S6S (S3) is pushed by the operator.
- Slave 1 (S1), slave 2 (S2) and the master unit (M) are switched ON or OFF using the remote start/stop switch S6S (M) which is connected to the master unit.
- The setpoint can be switched from OUTLETSETP1 to OUTLETSETP2 using the dual setpoint selection switch S10S which is connected to the master unit.

NOTE

K*P can also be a 24 V DC or 230 V AC contactor.



■ The additional sensor R8T (EKCLWS) must be connected directly to the PCB of the master unit.

Parameter settings of the units

Usersettings menu:

	Slave 3	Slave 2	Slave 1	Master
MODE:	DISCONNECT ON/OFF	NORMAL	NORMAL	NORMAL
PUMP ON IF:	UNIT ON	UNIT ON	UNIT ON	UNIT ON

Changeable inputs/outputs must be defined as follows:

Service setting menu:

	Slave 3	Slave 2	Slave 1	Master
Terminal 76-78 S10S DI1	NONE	NONE	NONE	DUAL SETPOINT
Terminal 76-79 S6S DI2	REMOTE ON/OFF	NONE	NONE	REMOTE ON∕OFF
Terminal 76-85 DI3	NONE	NONE	NONE	NONE
Terminal 76-86 DI4	NONE	NONE	NONE	NONE
Terminal 8T+8T- R8T Al1	NONE	NONE	NONE	MS OUTL WATER E

Remark

Slave 3 can be configured to start up automatically if:

- 1 of the other units is in alarm or;
- all other units are running on full capacity and the setpoint is not reached yet.

To have your slave 3 unit act this way, set its mode to STANDBY. In this case, S6S (S3) has no function.

Example 3: Double ring system with several pumps

Figure 3 shows the system configuration, field wiring and terminals for field wiring of this example.

Purpose

Purpose of this system is to keep a buffer at a constant temperature and to feed a load from this buffer. One unit, slave 3 (S3), is kept as a standby unit.

Setup

- The system is controlled on entering water temperature.
- The pumps of the slave units only run when their compressor is running (energy saving). the pump runs for a time indicated by the PUMPLAG setting.
- The pump of the master unit must run continuously so as to sense the correct temperature.
- Slave 3 (S3) is configured to operate when its remote start/stop switch S6S (S3) is pushed by the operator.
- Slave 1 (S1), slave 2 (S2) and the master unit (M) are switched ON or OFF using the remote start/stop switch S6S (M) which is connected to the master unit.
- The setpoint can be switched from INLETSETP1 to INLETSETP2 using the dual setpoint selection switch S10S which is connected to the master unit.

NOTE K*P can also be a 24 V DC or 230 V AC contactor.



Parameter settings of the units

Usersettings menu:

	Slave 3	Slave 2	Slave 1	Master
MODE:	DISCONNECT ON/OFF	NORMAL	NORMAL	NORMAL
PUMP ON IF:	COMPR ON	COMPR ON	COMPR ON	COMPR ON

Changeable inputs/outputs must be defined as follows:

Service setting menu:

	Slave 3	Slave 2	Slave 1	Master
Terminal 76-78 S10S DI1	NONE	NONE	NONE	DUAL SETPOINT
Terminal 76-79 S6S DI2	REMOTE ON/OFF	NONE	NONE	REMOTE ON∕OFF
Terminal 76-85 DI3	NONE	NONE	NONE	NONE
Terminal 76-86 DI4	NONE	NONE	NONE	NONE
Terminal 8T+8T- R8T Al1	NONE	NONE	NONE	NONE


Remark


Slave 3 can be configured to start up automatically if:


- 1 of the other units is in alarm or;
- all other units are running on full capacity and the setpoint is not reached yet.

To have your slave 3 unit act this way, set its mode to STANDBY. In this case, S6S (S3) has no function.

Notes









Equipment supplier :		Service department : Phone :		
Phone:				
	EQUIPMENT	Γ TECHNICAL DATA		
Model :	OPE	Power supply (V/Ph/Hz/A) :		
then controlled by the Digital Shut-down by switching off th	Display Controlle	of the power circuit. The operation of the water chiller is ler. I the circuit breaker of the power circuit.		
WARNINGS Emergency shut down	n : Switch off	f the circuit breaker located on		
Air inlet and outlet	: Always kee	eep the air inlet and outlet free to obtain the maximum apacity and to prevent damage to the installation.		
Refrigerant charge	: Use refrige	gerant R134a only.		
First aid	: In case of	f injuries or accidents immediately inform:		
	➤ Company	y management : Phone		
	➤ Emergend	cy physician : Phone		



