





**Monogram™**

## ZKD910BF/SF/WF – GE Monogram 27" Warming Drawer


### Single Oven Installation (in inches)



### Warming Drawer Dimensions (in inches)



### Double Oven Installation (in inches)



**Note:** Additional clearance between cutouts may be required. Check to be sure that oven supports above the Warming Drawer location do not obstruct the required interior 23-1/2" depth and 9-1/4" height.

**Specification Revised 1/08**  
130714



Listed by  
Underwriters  
Laboratories


For answers to your Monogram®, GE Profile™ or GE appliance questions, visit our website at [GEAppliances.com](http://GEAppliances.com) or call GE Answer Center® service, 800.626.2000.



Monogram™

## ZKD910BF/SF/WF – GE Monogram 27" Warming Drawer

### Undercounter Installation (in inches)



**Note:** When installing warming drawer with a cooktop, allow a 2" minimum from cooktop burner box bottom to top of cut-out.

#### Important Installation Note:

Must provide anti-tip brace at the back of the cabinet and at the top of the cutout.

#### Optional Accessories:


**ZXD27B** – 3/4" wood panel trim kit

**\*Note:** When installing the warming drawer below a cooktop, a solid barrier must be installed at 1" from the lowest point of the bottom of cooktop burner box to the top of cutout. Use any solid material such as 1/4" thick plywood. Allow at least 1/4" air gap between the barrier and the top of the warming drawer. See label on top of the warming drawer for approved cooktop models.

- When installed, the front face of the drawer will be nearly flush with adjacent cabinetry doors.
- Drawer overlaps will conceal cut edges on all sides of the opening. The rough opening for the drawer must be:
  - Depth 23-1/2" min. from inside back to front of cabinet frame.
  - Width 25-1/2" for 27" wide models, 28-1/2" for 30" wide models.
  - Height 9-1/4"
- 5" min. above floor or 1" above toekick. 23-1/4" from floor to bottom of cutout is recommended for under countertop installation.

#### Side to Side Installation:

Install two warming drawers in separate cutouts. Allow 2" min. between cutouts.



Side to Side Installation

#### Installation below a cooktop:

Warming drawers are approved for installation below only certain specified cooktop models. See the label attached to the top of the warming drawer for approved models. A solid barrier and air gap between cooktop and warming drawer is required. See Note above.

#### Installation below a cabinet drawer:

The warming drawer may be installed beneath a cabinet drawer. In this installation, a solid barrier should be installed above the warming drawer to block access. Use any solid material such as 1/4" thick plywood. Allow at least 1/4" air gap between the barrier and the top of the warming drawer. Observe the 5" min. above the floor or 1" above the toekick minimum installation height.

**Note:** If you are installing in frameless cabinets, it may be necessary to install 1/2" wide cleats to accept drawer mounting screws. See drawer to find exact locations of mounting screws.

#### Specification Revised 1/08

130714




Listed by  
Underwriters  
Laboratories

For answers to your Monogram®, GE Profile™ or GE appliance questions, visit our website at [GEAppliances.com](http://GEAppliances.com) or call GE Answer Center® service, 800.626.2000.



**Monogram™**

## ZKD910BF/SF/WF – GE Monogram 27" Warming Drawer



### Features and Benefits

- 1.92 cu. ft. Capacity
- Variable Temperature Control – Proof (80)/ Low (140)/Med (170)/High (210)
- Variable Humidity Control – Crisp to Moist
- Half Rack
- “On” Signal Light
- On/Off Rocker Switch
- Removable Stainless Steel Pan
- Full Extension Ball Bearing Glides
- Hidden Controls Provide Flush Installation Appearance
- Variable Installation Options
- Pan Set Included
- Model ZKD910WFWW – White on white
- Model ZKD910BFBB – Black on black
- Model ZKD910SFSS – Stainless steel