

EViews 7 User's Guide I

EViews 7 User's Guide I

Copyright © 1994–2009 Quantitative Micro Software, LLC

All Rights Reserved

Printed in the United States of America

ISBN: 978-1-880411-40-7

This software product, including program code and manual, is copyrighted, and all rights are reserved by Quantitative Micro Software, LLC. The distribution and sale of this product are intended for the use of the original purchaser only. Except as permitted under the United States Copyright Act of 1976, no part of this product may be reproduced or distributed in any form or by any means, or stored in a database or retrieval system, without the prior written permission of Quantitative Micro Software.

Disclaimer

The authors and Quantitative Micro Software assume no responsibility for any errors that may appear in this manual or the EViews program. The user assumes all responsibility for the selection of the program to achieve intended results, and for the installation, use, and results obtained from the program.

Trademarks

Windows, Excel, and Access are registered trademarks of Microsoft Corporation. PostScript is a trademark of Adobe Corporation. X11.2 and X12-ARIMA Version 0.2.7 are seasonal adjustment programs developed by the U. S. Census Bureau. Tramo/Seats is copyright by Agustin Maravall and Victor Gomez. Info-ZIP is provided by the persons listed in the infozip_license.txt file. Please refer to this file in the EViews directory for more information on Info-ZIP. Zlib was written by Jean-loup Gailly and Mark Adler. More information on zlib can be found in the zlib_license.txt file in the EViews directory. All other product names mentioned in this manual may be trademarks or registered trademarks of their respective companies.

Quantitative Micro Software, LLC

4521 Campus Drive, #336, Irvine CA, 92612-2621

Telephone: (949) 856-3368

Fax: (949) 856-2044

e-mail: sales@eviews.com

web: www.eviews.com

April 2, 2010

Table of Contents

EViews7 USER'S GUIDE 1

PREFACE	1
PART I. EViews FUNDAMENTALS	3
CHAPTER 1. INTRODUCTION	
What is EViews?	5
Installing and Running EViews	5
The EViews Window	6
Breaking or Canceling in EViews	10
Closing EViews	10
Where to Go For Help	10
EViews Updates	11
CHAPTER 2. A DEMONSTRATION	
Getting Data into EViews	13
Examining the Data	16
Estimating a Regression Model	21
Specification and Hypothesis Tests	23
Modifying the Equation	25
Forecasting from an Estimated Equation	27
Additional Testing	31
CHAPTER 3. WORKFILE BASICS	
What is a Workfile?	33
Creating a Workfile	34
The Workfile Window	49
Saving a Workfile	53
Loading a Workfile	56
Multi-page Workfiles	56
Addendum: File Dialog Features	65
CHAPTER 4. OBJECT BASICS	
What is an Object?	67
Basic Object Operations	71

The Object Window	..73
Working with Objects	..75
CHAPTER 5. BASIC DATA HANDLING	
Data Objects	..81
Samples	..91
Sample Objects	..99
Importing Data	..101
Exporting Data	..110
Reading EViews Data using Other Applications	..112
Frequency Conversion	..116
Importing ASCII Text Files	..122
CHAPTER 6. WORKING WITH DATA	1
Numeric Expressions	..131
Series	..141
Auto-series	..145
Groups	..150
Scalars	..154
CHAPTER 7. WORKING WITH DATA (ADVANCED)	155
Auto-Updating Series	..155
Alpha Series	..160
Date Series	..166
Value Maps	..169
CHAPTER 8. SERIES LINKS	
Basic Link Concepts	..183
Creating a Link	..197
Working with Links	..207
CHAPTER 9. ADVANCED WORKFILES	2
Structuring a Workfile	..213
Resizing a Workfile	..238
Appending to a Workfile	241
Contracting a Workfile	..244
Copying from a Workfile	244
Reshaping a Workfile	..248
Sorting a Workfile	..265

Exporting from a Workfile	2	65
References		266
CHAPTER 10. EViews DATABASES		
Database Overview		267
Database Basics		268
Working with Objects in Databases		272
Database Auto-Series		279
The Database Registry		281
Querying the Database		283
Object Aliases and Illegal Names		291
Maintaining the Database	2	93
Foreign Format Databases	2	95
Working with DRIPRO Links		306
PART II. BASIC DATA ANALYSIS		313
CHAPTER 11. SERIES		315
Series Views Overview		315
Spreadsheet		316
Graph		316
Descriptive Statistics & Tests		316
One-Way Tabulation		332
Correlogram		333
Long-run Variance		336
Unit Root Test		336
Variance Ratio Test		337
BDS Independence Test	3	37
Label		337
Properties		338
Series Procs Overview		339
Generate by Equation		339
Generate by Classification		339
Resample		344
Interpolate		346
Seasonal Adjustment		349
Exponential Smoothing		364
Hodrick-Prescott Filter		369

Frequency (Band-Pass) Filter	3	71
Whiten Data		374
Distribution Plot Data		374
References		375
CHAPTER 12. GROUPS.	9.	
Group Views Overview	3	79
Group Members		379
Spreadsheet		380
Dated Data Table		383
Graph		391
Descriptive Statistics		391
Covariance Analysis		392
N-Way Tabulation		404
Tests of Equality		408
Principal Components		409
Correlograms		422
Cross Correlations and Correlograms		422
Long-run Covariance		422
Unit Root Test		428
Cointegration Test		428
Granger Causality		428
Label		429
Group Procedures Overview		430
References		433
CHAPTER 13. GRAPHING DATA		
Quick Start		436
Graphing a Series		439
Graphing Multiple Series (Groups)		448
Basic Customization		459
Graph Types		479
References		522
CHAPTER 14. CATEGORICAL GRAPHS.		5
Illustrative Examples		523
Specifying Factors		540

PART III. CUSTOMIZING OUTPUT.	555
CHAPTER 15. GRAPH OBJECTS.	
Creating Graph Objects	557
Combining Graphs	562
Customizing Graphs	562
Modifying Multiple Graphs	582
Printing Graphs	585
Copying Graphs to the Clipboard	586
Saving Graphs to a File	586
Graph Commands	587
CHAPTER 16. TABLE AND TEXT OBJECTS.	
Table Objects	589
Text Objects	598
CHAPTER 17. SPOOL OBJECTS.	
Creating a Spool	601
Managing the Spool	602
Customizing the Spool	613
Editing Objects in a Spool	616
Printing a Spool	619
Saving a Spool	620
APPENDIX A. GLOBAL OPTIONS.	
The Options Menu	621
Print Setup	637
INDEX.	641

EVIEWS 7 USER'S GUIDE II 1

PREFACE.	1
PART IV. BASIC SINGLE-EQUATION ANALYSIS.	3
CHAPTER 18. BASIC REGRESSION ANALYSIS.	
Equation Objects	5
Specifying an Equation in EVIEWS	6
Estimating an Equation in EVIEWS	9

Equation Output	11
Working with Equations	17
Estimation Problems	21
References	22
CHAPTER 19. ADDITIONAL REGRESSION TOOLS	23
Special Equation Expressions	23
Robust Standard Errors	32
Weighted Least Squares	36
Nonlinear Least Squares	40
Stepwise Least Squares Regression	46
References	53
CHAPTER 20. INSTRUMENTAL VARIABLES AND GMM	55
Background	55
Two-stage Least Squares	55
Nonlinear Two-stage Least Squares	62
Limited Information Maximum Likelihood and K-Class Estimation	63
Generalized Method of Moments	67
IV Diagnostics and Tests	78
References	83
CHAPTER 21. TIME SERIES REGRESSION	8
Serial Correlation Theory	85
Testing for Serial Correlation	86
Estimating AR Models	89
ARIMA Theory	93
Estimating ARIMA Models	95
ARMA Equation Diagnostics	104
References	110
CHAPTER 22. FORECASTING FROM AN EQUATION	111
Forecasting from Equations in EViews	111
An Illustration	114
Forecast Basics	117
Forecasts with Lagged Dependent Variable	123
Forecasting with ARMA Errors	125
Forecasting from Equations with Expressions	130

Forecasting with Nonlinear and PDL Specifications	136
References	137
CHAPTER 23. SPECIFICATION AND DIAGNOSTIC TESTS.	138
Background	139
Coefficient Diagnostics	140
Residual Diagnostics	157
Stability Diagnostics	169
Applications	186
References	191
PART V. ADVANCED SINGLE-EQUATION ANALYSIS	193
CHAPTER 24. ARCH AND GARCH ESTIMATION	195
Basic ARCH Specifications	195
Estimating ARCH Models in EViews	198
Working with ARCH Models	205
Additional ARCH Models	208
Examples	213
References	216
CHAPTER 25. COINTEGRATING REGRESSION.	219
Background	219
Estimating a Cointegrating Regression	221
Testing for Cointegration	234
Working with an Equation	243
References	245
CHAPTER 26. DISCRETE AND LIMITED DEPENDENT VARIABLE MODELS.	247
Binary Dependent Variable Models	247
Ordered Dependent Variable Models	266
Censored Regression Models	273
Truncated Regression Models	283
Count Models	287
Technical Notes	296
References	298
CHAPTER 27. GENERALIZED LINEAR MODELS.	301
Overview	301

How to Estimate a GLM in EViews	303
Examples	307
Working with a GLM Equation	315
Technical Details	319
References	330
CHAPTER 28. QUANTILE REGRESSION.	331
Estimating Quantile Regression in EViews	331
Views and Procedures	336
Background	341
References	352
CHAPTER 29. THE LOG LIKELIHOOD (LOGL) OBJECT	355
Overview	355
Specification	357
Estimation	362
LogL Views	364
LogL Procs	364
Troubleshooting	367
Limitations	368
Examples	369
References	375
PART VI. ADVANCED UNIVARIATE ANALYSIS.	377
CHAPTER 30. UNIVARIATE TIME SERIES ANALYSIS	379
Unit Root Testing	379
Panel Unit Root Test	391
Variance Ratio Test	402
BDS Independence Test	411
References	415
PART VII. MULTIPLE EQUATION ANALYSIS.	417
CHAPTER 31. SYSTEM ESTIMATION	419
Background	419
System Estimation Methods	420
How to Create and Specify a System	422
Working With Systems	433

Technical Discussion	446
References	456
CHAPTER 32. VECTOR AUTOREGRESSION AND ERROR CORRECTION MODELS	459
Vector Autoregressions (VARs)	459
Estimating a VAR in EViews	460
VAR Estimation Output	461
Views and Procs of a VAR	462
Structural (Identified) VARs	471
Vector Error Correction (VEC) Models	478
A Note on Version Compatibility	484
References	484
CHAPTER 33. STATE SPACE MODELS AND THE KALMAN FILTER	487
Background	487
Specifying a State Space Model in EViews	492
Working with the State Space	503
Converting from Version 3 Sspace	509
Technical Discussion	509
References	510
CHAPTER 34. MODELS	
Overview	511
An Example Model	514
Building a Model	529
Working with the Model Structure	531
Specifying Scenarios	535
Using Add Factors	537
Solving the Model	539
Working with the Model Data	557
References	561
PART VIII. PANEL AND POOLED DATA	563
CHAPTER 35. POOLED TIME SERIES CROSS SECTION DATA	565
The Pool Workfile	565
The Pool Object	566
Pooled Data	569
Setting up a Pool Workfile	571

Working with Pooled Data	5	78
Pooled Estimation		586
References		613
CHAPTER 86. WORKING WITH PANEL DATA		613
Structuring a Panel Workfile		615
Panel Workfile Display		618
Panel Workfile Information	6	19
Working with Panel Data	6	23
Basic Panel Analysis		635
References		645
CHAPTER 87. PANEL ESTIMATION		645
Estimating a Panel Equation	6	47
Panel Estimation Examples	6	54
Panel Equation Testing		668
Estimation Background		676
References		681
PART IX. ADVANCED MULTIVARIATE ANALYSIS		683
CHAPTER 88. COINTEGRATION TESTING		683
Johansen Cointegration Test	6	85
Single-Equation Cointegration Tests		694
Panel Cointegration Testing		698
References		703
CHAPTER 89. FACTOR ANALYSIS		703
Creating a Factor Object		706
Rotating Factors		712
Estimating Scores		713
Factor Views		716
Factor Procedures		720
Factor Data Members		721
An Example		721
Background		736
References		748

APPENDIX B. ESTIMATION AND SOLUTION OPTIONS	75
Setting Estimation Options	751
Optimization Algorithms	755
Nonlinear Equation Solution Methods	759
References	761
APPENDIX C. GRADIENTS AND DERIVATIVES	
Gradients	763
Derivatives	766
References	770
APPENDIX D. INFORMATION CRITERIA	
Definitions	771
Using Information Criteria as a Guide to Model Selection	773
References	773
APPENDIX E. LONG-RUN COVARIANCE ESTIMATION	77
Technical Discussion	775
Kernel Function Properties	785
References	785
INDEX	787

Preface

The EViews documentation is divided into four volumes.

The first two User's Guide volumes provide basic documentation on using EViews. User's Guide I, describes EViews fundamentals and describes using EViews to perform basic data analysis and display results. The second volume, User's Guide II offers a description of EViews' more advanced statistical and estimation features.

The remaining volumes document the use of commands and programming in EViews. The Command and Programming Reference offers details on specific commands and functions, while the Object Reference documents the commands for working with views and procedures of objects in EViews.

The material in the User's Guide II may be divided into three distinct parts:

- [Part I. "EViews Fundamentals," beginning on page 3](#) introduces you to the basics of using EViews. In addition to a discussion of basic Windows operations, we explain how to use EViews to work with your data.
- [Part II. "Basic Data Analysis," beginning on page 313](#) describes the use of EViews to perform basic analysis of data and to draw graphs and display tables describing the results of analysis of your data.
- [Part III. "Customizing Output," beginning on page 555](#) documents the graph object, table and text objects, and the spool object, all of which are used to produce presentation output.

You need not read the manuals from cover-to-cover in order to use EViews. Once you gain a basic familiarity with the program you should be able to perform most operations without consulting the documentation. We do recommend, however, that you glance at most of [Part I. "EViews Fundamentals"](#) to gain familiarity with the basic concepts and operation of the program.

Part I. EViews Fundamentals

The following chapters document the fundamentals of working with EViews:

- [Chapter 1. "Introduction"](#) describes the basics of installing EViews and offers basic information to get you started (including tips on places to look for help).
- [Chapter 2. "A Demonstration"](#) guides you through a typical EViews session, introducing you to the basics of working with EViews.
- [Chapter 3. "Workfile Basics"](#) describes working with workfiles (the containers for your data in EViews).
- [Chapter 4. "Object Basics"](#) provides an overview of EViews objects, which are the building blocks for all analysis in EViews.
- [Chapter 5. "Basic Data Handling"](#) and [Chapter 6. "Working with Data"](#) provide background on the basics of working with numeric data. We describe methods of getting your data into EViews, manipulating and managing your data held in series and group objects, and exporting your data into spreadsheets, text files and other Windows applications.

We recommend that you browse through most of the material in the above sections before beginning serious work with EViews.

The remaining material is somewhat more advanced and may be ignored until needed:

- [Chapter 7. "Working with Data \(Advanced\),"](#) [Chapter 8. "Series Links,"](#) and [Chapter 9. "Advanced Workfiles"](#) describe advanced tools for working with numeric data, and tools for working with different kinds of data (alphanumeric and date series, irregular and panel workfiles).
- [Chapter 10. "EViews Databases"](#) describes the EViews database features and advanced data handling features.

This material is relevant only if you wish to work with the advanced tools.

Chapter 1. Introduction

What is EViews?

EViews provides sophisticated data analysis, regression, and forecasting tools on Windows-based computers. With EViews you can quickly develop a statistical relation from your data and then use the relation to forecast future values of the data. Areas where EViews can be useful include: scientific data analysis and evaluation, financial analysis, macroeconomic forecasting, simulation, sales forecasting, and cost analysis.

EViews is a new version of a set of tools for manipulating time series data originally developed in the Time Series Processor software for large computers. The immediate predecessor of EViews was MicroTSP, first released in 1981. Though EViews was developed by economists and most of its uses are in economics, there is nothing in its design that limits its usefulness to economic time series. Even quite large cross-section projects can be handled in EViews.

EViews provides convenient visual ways to enter data series from the keyboard or from disk files, to create new series from existing ones, to display and print series, and to carry out statistical analysis of the relationships among series.

EViews takes advantage of the visual features of modern Windows software. You can use your mouse to guide the operation with standard Windows menus and dialogs. Results appear in windows and can be manipulated with standard Windows techniques.

Alternatively, you may use EViews' powerful command and batch processing language. You can enter and edit commands in the command window. You can create and store the commands in programs that document your research project for later execution.


Installing and Running EViews

Your copy of EViews is distributed on a single CD-ROM. Installation is straightforward—simply insert your CD-ROM disc into a drive, wait briefly while the disc spins-up and the setup program launches, and then simply follow the prompts. If the disc does not spin-up, navigate to the drive using Windows Explorer, then click on the Setup icon.

We have also provided detailed installation instructions in a separate sheet and in the EViews 7 Getting Started booklet, one of which you should have received with your EViews package. If you did not receive either the sheet or booklet, please contact our office.

The EViews Window

If the program is installed correctly, you should see the EViews window when you launch the program.



You should familiarize yourself with the following main areas in the EViews window.


The Title Bar

The title bar, labeled EViews, is at the very top of the main window. When EViews is the active program in Windows, the title bar has a color and intensity that differs from the other windows (generally it is darker). When another program is active, the EViews title bar will be lighter. If another program is active, EViews may be made active by clicking anywhere in the EViews window or by using ALT-TAB to cycle between applications until the EViews window is active.

The Main Menu

Just below the title bar is the main menu. If you move the cursor to an entry in the main menu and click on the left mouse button, a drop-down menu will appear. Clicking on an entry in the drop-down menu selects the highlighted item.

For example, here we click on the Object entry in the main menu to reveal a drop-down menu. Notice that some of the items in the drop-down menu are listed in black and others are in gray. In menus, black items may be executed while the gray items are not available. In this example, you cannot create a New Object or Store an object, but you can Print and View Options. We will explain this behavior in our discussion of “[The Object Window](#)” on page 73.




The Command Window

Below the menu bar is an area called the command window. EViews commands may be typed in this window. The command is executed as soon as you hit ENTER.

The vertical bar in the command window is called the insertion point. It shows where the letters that you type on the keyboard will be placed. As with standard word processors, if you

have typed something in the command area, you can move the insertion point by pointing to the new location and clicking the mouse. If the insertion point is not visible or your key-strokes are not appearing in the window, it probably means that the command window is not active (not receiving keyboard focus); simply click anywhere in the command window to tell EViews that you wish to enter commands.



To toggle between the active window and the command window, press F5.

See “[Window Behavior](#)” on page 622 of User’s Guide for a discussion of focus settings which affect the use of the command window.


Command Editing

The command window supports Windows cut-and-paste so that you can easily move text between the command window, other EViews text windows, and other Windows programs. The contents of the command area may also be saved directly into a text file for later use: make certain that the command window is active by clicking anywhere in the window, and then select File/Save As... from the main menu.

If you have entered more commands than will fit in your command window, EViews turns the window into a standard scrollable window. Simply use the scroll bar or up and down arrows on the right-hand side of the window to see various parts of the list of previously executed commands. You may move the insertion point to previously executed commands, edit the existing command, and then press ENTER to execute the edited version of the command.

Alternately, to display a list of previous commands in the order in which they were entered, press the Control key and the UP arrow (CTRL+UP). The last command will be entered into the command window. Holding down the CTRL key and pressing UP repeatedly will display the next prior commands. Repeat until the desired command is recalled.

To examine a history of the last 30 commands, press the Control Key and the J key (CTRL+J). In the popup window you may use the UP and DOWN arrows to select the desired command and then press the ENTER key to add it to the command window, or simply double click on the command. To close the history window without selecting a command, click elsewhere in the command window or press the Escape (ESC) key.



To execute the retrieved command, simply press ENTER again. You may first edit the command if you wish to do so.


You may find that the default size of the command window is too large or small for your needs. You can resize the command window by placing the cursor at the bottom of the com-

mand window, holding down the mouse button and dragging the window up or down. Release the mouse button when the command window is the desired size.

Undocking the Command Window

You may drag the command window to anywhere inside the EViews frame. Press F4 to toggle docking, or click on the command window, depress the right-mouse button and select Toggle Command Docking .


When undocked, the command window toolbar contains buttons for displaying commands in the list, and for redocking.



The Status Line

At the very bottom of the window is a status line which is divided into several sections.

The left section will sometimes contain status messages sent to you by EViews. These status messages can be cleared manually by clicking on the box at the far left of the status line.



The next section shows the default directory that EViews will use to look for data and programs. The last two sections display the names of the default database and workfile. In later chapters, we will show you how to change both defaults.

The Work Area

The area in the middle of the window is the work area where EViews will display the various object windows that it creates. Think of these windows as similar to the sheets of paper you might place on your desk as you work. The windows will overlap each other with the foremost window being in focus or active. Only the active window has a darkened titlebar.

When a window is partly covered, you can bring it to the top by clicking on its titlebar or on a visible portion of the window. You can also cycle through the displayed windows by pressing the F6 or CTRL-TAB keys.

Alternatively, you may select a window by clicking on the Window menu item, and selecting the desired name.

You can move a window by clicking on its title bar and dragging the window to a new location. You can change the size of a window by clicking on any corner and dragging the corner to a new location.

Breaking or Canceling in EViews

EViews follows the Windows standard in using the ESC key as the break key. If you wish to cancel the current task or ongoing operation, simply press ESC.

Closing EViews

There are a number of ways to close EViews. You can always select File/Exit from the main menu, or you can press ALT-F4. Alternatively, you can click on the close box in the upper right-hand corner of the EViews window, or double click on the EViews icon in the upper left-hand corner of the window. If necessary, EViews will warn you and provide you with the opportunity to save any unsaved work.

Where to Go For Help

The Student Version Manual

The remainder of this Student Version manual walks you through a detailed demonstration of the basic operation of your EViews student version—taking you from importing data from an Excel spreadsheet, to running a regression and performing hypothesis tests. We also provide a discussion of basics of working with EViews workfiles and objects.

The EViews Manuals

This User's Guide describes how to use EViews to carry out your research. The earlier chapters deal with basic operations, the middle chapters cover basic econometric methods, and the later chapters describe more advanced methods.

Though we have tried to be complete, it is not possible to document every aspect of EViews. There are almost always several ways to do the same thing in EViews, and we cannot describe them all. In fact, one of the strengths of the program is that you will undoubtedly discover alternative, and perhaps more efficient, ways to get your work done.

Most of the User's Guide explains the visual approach to using EViews. It describes how you can use your mouse to perform operations in EViews. To keep the explanations simple, we do not tell you about alternative ways to get your work done. For example, we will not remind you about the ALT- keyboard alternatives to using the mouse.

When we get to the discussion of the substantive statistical methods available in EViews, we will provide some technical information about the methods, and references to econometrics textbooks and other sources for additional information.

The Help System

Almost all of the EViews documentation may be viewed from within EViews by using the help system. To access the EViews help system simply go to the main menu and select Help.

In addition, the Help system will contain updates to the documentation that were made after the manuals went to press.

The EViews Forum

To supplement the information provided in the manuals and the help system, we encourage you to visit the EViews Forum where you can find answers to common questions about installing, using, and getting the most out of EViews. The Forum is an ideal place to ask questions of and share information with other EViews users. The forum address is:

<http://forums.eviews.com> .

EViews Updates

QMS occasionally releases patches to the EViews program, and we strongly recommend that you keep your copy of EViews as up-to-date as possible.

EViews includes an automatic updating feature that can check for new updates every day, and install any update that may be available. The automatic update feature can be disabled from the Options/EViews Auto-Update from Web item in your main

EViews menu. You can also manually check for updates from within EViews at any time by selecting Check now... under the EViews Auto-Update from Web menu item, or by selecting EViews Update from the Help menu.

You may also check for updates to the EViews program or for updates to supplementary components such as the EViews documentation or sample data and programs manually by visiting the Download section of the EViews website (www.eviews.com).

Chapter 2. A Demonstration

In this chapter, we provide a demonstration of some basic features of EViews. The demonstration is meant to be a brief introduction to EViews; not a comprehensive description of the program. A full description of the program begins in [Chapter 4. “Object Basics,” on page 67.](#)

This demo takes you through the following steps:

- getting data into EViews from an Excel spreadsheet
- examining your data and performing simple statistical analyses
- using regression analysis to model and forecast a statistical relationship
- performing specification and hypothesis testing
- plotting results

Getting Data into EViews


The first step in most projects will be to read your data into an EViews workfile. EViews provides sophisticated tools for reading from a variety of common data formats, making it extremely easy to get started.

Before we describe the process of reading a foreign data file, note that the data for this demonstration have been included in both Excel spreadsheet and EViews workfile formats in your EViews installation directory (“\Example Files\EV7 Manual Data\Chapter 2 - A Demonstration”).

If you wish to skip the discussion of opening foreign files, going directly to the analysis part of the demonstration, you may load the EViews workfile by selecting File/Open/Foreign Data as Workfile... and opening “Demo.WF1”, or by navigating to the directory and drag-and-dropping “Demo.WF1” onto your open EViews application window or icon.


The easiest way to read the data from Excel file “Demo.XLS” is to drag-and-drop the file into an open EViews application window. You may also drag-and-drop the file onto the EViews icon. In the latter case, Windows will first start the EViews application and will then open the demonstration Excel workfile.

Alternately, you may use the File/Open/EViews workfile... dialog, selecting Files of type Excel and selecting the desired file.



When EViews opens “Demo.XLS”, it determines that the file is in Excel file format, analyzes the contents, and opens the Excel Read wizard.

The first page of the wizard includes a preview of the data found in the spreadsheet. In most cases, you need not worry about any of the options on this page. In more complicated cases, you may use the options on this page to provide a custom range of cells to read, or to select a different sheet in the workbook.




The second page of the wizard contains various options for reading the Excel data. These options are set at the most likely choices given the EViews analysis of the contents of your workbook. In most cases, you should simply click on Finish to accept the default settings. In other cases where the preview window does not correctly display the desired data, you may click on Next and

adjust the options that appear on the second page of the wizard. In our example, the data appear to be correct, so we simply click on Finish to accept the default settings.

When you accept the settings, EViews automatically creates a workfile that is sized to hold the data, and imports the series into the workfile. The workfile ranges from 1952 quarter 1 to 1996 quarter 4, and contains five series (GDP, M1, OBS, PR, and RS) that you have read from the Excel file. There are also two objects, the coefficient vector C and the series RESID, that are found in all EViews workfiles.

In addition, EViews opens the imported data in a spreadsheet view, allowing you to perform an initial examination of your data. You should compare the spreadsheet views with the Excel worksheet to ensure that the data have been read correctly. You can use the scroll bars and scroll arrows on the right side of the window to view and verify the remainder of the data.



You may wish to click on Name in the group toolbar to provide a name for your UNTITLED group. Enter the name ORIGINAL, and click on OK to accept the name.

Once you are satisfied that the data are correct, you should save the workfile by clicking on the Save button in the workfile window. A saved dialog will open, prompting you for a workfile name and location. You should enter "Demo2.WF1", and then click OK. A second dialog may be displayed prompting you to set storage options. Click OK to accept the defaults. EViews will save the workfile in the specified directory with the name


“Demo2.WF1”. A saved workfile may be opened later by selecting File/Open/Workfile.... from the main menu.

Examining the Data

Now that you have your data in an EViews workfile, you may use basic EViews tools to examine the data in your series and groups in a variety of ways.

First, we examine the characteristics of individual series. To see the contents of the M1 series, simply double click on the M1 icon in the workfile window, or select Quick/Show... in the main menu, enter m1, and click on OK.

EViews will open the M1 series object and will display the default spreadsheet view of the series. Note the description of the contents of the series (“Series: M1”) in the upper leftmost corner of the series window toolbar, indicating that you are working with the M1 series.




The screenshot shows the EViews window for the M1 series. The title bar reads "Series: M1 Workfile: DEMO::DEMO1". The toolbar includes buttons for View, Proc, Object, Properties, Print, Name, Freeze, Default, and Sort. The main area displays a spreadsheet with the following data:

M1	
Last updated: 08/13/09 - 18:36	
Imported from 'C:\EViews\data\Demo.xls'	
1952Q1	126.537
1952Q2	127.506
1952Q3	129.385
1952Q4	128.512
1953Q1	130.587
1953Q2	130.341
1953Q3	

You will use the entries in the View and Proc menus to examine various characteristics of the series. Simply click on the buttons on the toolbar to access these menu entries, or equivalently, select View or Proc from the main menu.


To compute, for example, a table of basic descriptive statistics for M1, simply click on the View button, then select Descriptive Statistics & Tests/ Stats Table. EViews will compute descriptive statistics for M1 and change the series view to display a table of results.



The screenshot shows the EViews window for the M1 series with the View menu open. The title bar reads "Series: M1 Workfile: DEMO::DEMO1". The toolbar includes buttons for View, Proc, Object, Properties, Print, Name, Freeze, Sample, Genr, and Sheet. The main area displays a table of descriptive statistics for the M1 series:

M1	
Mean	445.0064
Median	298.3990
Maximum	1219.420
Minimum	126.5370
Std. Dev.	344.8315
Skewness	0.997776
Kurtosis	2.687096
Jarque-Bera	30.60101
Probability	0.000000
Sum	80101.16
Sum Sq. Dev.	21284672
Observations	180

Similarly, to examine a line graph of the series, simply select View/Graph... to bring up the Graph Options dialog, and select Line & Symbol from the list of graph types on the left-hand side. EViews will change the M1 series window to display a line graph of the data in the M1 series.



At this point, you may wish to explore the contents of the View and Proc menus in the M1 series window to see the various tools for examining and working with series data. You may always return to the spreadsheet view of your series by selecting View/Spreadsheet from the toolbar or main menu.


Since our ultimate goal is to perform regression analysis with our data expressed in natural logarithms, we may instead wish to work with the log of M1. Fortunately, EViews allows you to work with expressions involving series as easily as you work with the series themselves. To open a series containing this expression, select Quick/Show... from the main menu, enter the text for the expression, $\log(m1)$, and click OK. EViews will open a series window for containing LOG(M1). Note that the titlebar for the series shows that we are working with the desired expression.

The figure shows the spreadsheet view of a series named 'LOG(M1)'. The titlebar indicates the series is 'LOG(M1)' and the workfile is 'DEMO::DEMO1'. The toolbar includes buttons for View, Proc, Object, Properties, Print, Name, Freeze, Default, Sort, and Edit. The spreadsheet displays the following data:


LOG(M1)	
Last updated: 08/13/09 - 18:42	
Formula: log(m1)	
1952Q1	4.840535
1952Q2	4.848163
1952Q3	4.862792
1952Q4	4.856022
1953Q1	4.872040
1953Q2	4.870154
1953Q3	4.878162
1953Q4	4.866696
1954Q1	4.868864
1954Q2	

You may work with this auto-series in exactly the same way you worked with M1 above. For example, clicking on View in the series toolbar and selecting Descriptive Statistics &

Tests/Histogram and Stats displays a view containing a histogram and descriptive statistics for LOG(M1):



Alternately, we may display a smoothed version of the histogram by selecting View/Graph..., choosing Distribution from the list on the left and Kernel Density from the drop-down on the right, and clicking on OK to accept the default options:




Suppose that you wish to examine multiple series or series expressions. To do so, you will need to construct a group object that contains the series of interest.

Earlier, you worked with an EViews created group object containing all of the series read from your Excel file. Here, we will construct a group object containing expressions involving a subset of those series. We wish to create a group object containing the logarithms of the series M1 and GDP, the level of RS, and the first difference of the logarithm of the series PR. Simply select Quick/Show... from the main EViews menu, and enter the list of expressions and series names:

$\log(m1)$ $\log(gdp)$ rs $dlog(pr)$


Click on OK to accept the input. EViews will open a group window containing a spreadsheet view of the series and expressions of interest.




View	Proc	Object	Print	Name	Freeze	Default	Sort	Transpose	Edit+/-	Smp
obs		LOG(M1)		LOG(GDP)		RS		DLOG(PR)		
1952Q1		4.840535		4.475915		1.640000		NA		
1952Q2		4.848163		4.478756		1.677667		0.003066		
1952Q3		4.862792		4.495634		1.828667		0.010099		
1952Q4		4.856022		4.531255		1.923667		0.005317		
1953Q1		4.872040		4.549922		2.047333		-0.000965		
1953Q2		4.870154		4.559650		2.202667		0.001950		
1953Q3		4.878162		4.558341		2.021667		0.003922		
1953Q4		4.866696		4.545155		1.486333		0.002406		
1954Q1		4.868864		4.544092		1.083667		0.003414		
1954Q2		4.878132		4.545420		0.814333		0.002085		
1954Q3		4.902508		4.568603		0.869667		0.002207		
1954Q4		4.898719		4.578454		1.036333		0.000405		
1955Q1		4.915687		4.612394		1.256333		0.005996		
1955Q2		4.916112		4.633029		1.614333		0.003031		
1955Q3										

As with the series object, you will use the View and Proc menus of the group to examine various characteristics of the group of series. Simply click on the buttons on the toolbar to access these menu entries or select View or Proc from the main menu to call up the relevant entries. Note that the entries for a group object will differ from those for a series object since the kinds of operations you may perform with multiple series differ from the types of operations available when working with a single series.

For example, you may select View/Graph... from the group object toolbar, and then select Line & Symbol from the list on the left side of the dialog to display a single graph containing line plots of each of the series in the group:



Alternately, you may select View/Graph... and choose Multiple graphs from the Multiple series drop-down on the right side of the dialog to display the same information, but with each series expression plotted in an individual graph:




Likewise, you may select View/Descriptive Stats/Individual Samples to display a table of descriptive statistics computed for each of the series in the group:

The figure shows a screenshot of the 'Descriptive Statistics' window in EViews. It displays a table of statistics for four series: LOG(M1), LOG(GDP), RS, and DLOG(PR). The table includes measures of central tendency (Mean, Median, Maximum, Minimum), dispersion (Std. Dev., Kurtosis), and normality tests (Jarque-Bera, Probability). The number of observations for LOG(M1), LOG(GDP), and RS is 180, while for DLOG(PR) it is 179. The table also shows summary statistics like Sum and Sum Sq. Dev. for each series.

	LOG(M1)	LOG(GDP)	RS	DLOG(PR)
Mean	5.811220	5.991505	5.412928	0.009645
Median	5.698431	5.925009	5.057500	0.008295
Maximum	7.106131	7.574674	15.08733	0.030557
Minimum	4.840535	4.475915	0.814333	-0.000965
Std. Dev.	0.754650	1.002533	2.908939	0.006206
Skewness	0.323130	0.062361	0.986782	0.909753
Kurtosis	1.694566	1.562971	4.049883	3.466402
Jarque-Bera	15.91357	15.60457	37.47907	26.31399
Probability	0.000350	0.000409	0.000000	0.000002
Sum	1046.020	1078.471	974.3270	1.726530
Sum Sq. Dev.	101.9398	179.9079	1514.685	0.008855
Observations	180	180	180	179

Note that the number of observations used for computing descriptive statistics for DLOG(PR) is one less than the number used to compute the statistics for the other expressions. By electing to compute our statistics using “Individual Samples”, we informed EViews that we wished to use the series specific samples in each computation, so that the loss of an observation in DLOG(PR) to differencing should not affect the samples used in calculations for the remaining expressions.

We may instead choose to use “Common Samples” so that observations are only used if the data are available for all of the series in the group. Click on View/Covariance Analysis... and select the Correlation checkbox to display the correlation matrix of the four series for the 179 common observations:



	LOG(M1)	LOG(GDP)	RS	DLOG(PR)
LOG(M1)	1.000000	0.992173	0.469921	0.191597
LOG(GDP)	0.992173	1.000000	0.554978	0.267920
RS	0.469921	0.554978	1.000000	0.681349
DLOG(PR)	0.191597	0.267920	0.681349	1.000000

Once again, we suggest that you may wish to explore the contents of the View and Proc menus for this group to see the various tools for examining and working with sets of series. You can always return to the spreadsheet view of the group by selecting View/Spreadsheet.


Estimating a Regression Model

We now estimate a regression model for M1 using data over the period from 1952Q1–1992Q4 and use this estimated regression to construct forecasts over the period 1993Q1–2003Q4. The model specification is given by:

$$\log M1_t = b_1 + b_2 \log GDP_t + b_3 RS_t + b_4 \log PR_t + e_t \quad (2.1)$$

where $\log(M1)$ is the logarithm of the money supply, $\log(GDP)$ is the log of income, RS is the short term interest rate, and $\log PR$ is the log first difference of the price level (the approximate rate of inflation).

To estimate the model, we will create an equation object. Select Quick from the main menu and choose Estimate Equation... to open the estimation dialog. Enter the following equation specification:



Here we list the expression for the dependent variable, followed by the expressions for each of the regressors, separated by spaces. The built-in series name C stands for the constant in the regression.


The dialog is initialized to estimate the equation using the LS - Least Squares method for the sample 1952Q1 1996Q4. You should change text in the Sample edit box to “1952Q1 1992Q4” to estimate the equation for the subsample of observations.

Click OK to estimate the equation using least squares and to display the regression results:

Dependent Variable: LOG(M1)
Method: Least Squares
Date: 08/18/09 Time: 14:14
Sample (adjusted): 1952Q2 1992Q4
Included observations: 163 after adjustments


Variable	Coefficient	Std. Error	t-Statistic	Prob.
C	1.312383	0.032199	40.75850	0.0000
LOG(GDP)	0.772035	0.006537	118.1092	0.0000
RS	-0.020686	0.002516	-8.221196	0.0000
DLOG(PR)	-2.572204	0.942556	-2.728967	0.0071
R-squared	0.993274	Mean dependent var	5.692279	
Adjusted R-squared	0.993147	S.D. dependent var	0.670253	
S.E. of regression	0.055485	Akaike info criterion	-2.921176	
Sum squared resid	0.489494	Schwarz criterion	-2.845256	
Log likelihood	242.0759	Hannan-Quinn criter.	-2.890354	
F-statistic	7826.904	Durbin-Watson stat	0.140967	
Prob(F-statistic)	0.000000			

Note that the equation is estimated from 1952Q2 to 1992Q4 since one observation is dropped from the beginning of the estimation sample to account for the DLOG difference term. The estimated coefficients are statistically significant, with t-statistic values well in excess of 2. The overall regression fit, as measured by the R^2 value, indicates a very tight fit. You can select View/Actual, Fitted, Residual/Actual, Fitted, Residual Graph in the equation toolbar to display a graph of the actual and fitted values for the dependent variable, along with the residuals:



Specification and Hypothesis Tests

We can use the estimated equation to perform hypothesis tests on the coefficients of the model. For example, to test the hypothesis that the coefficient on the price term is equal to 2, we will perform a Wald test. First, determine the coefficient of interest by selecting View/Representations from the equation toolbar:



Note that the coefficients are assigned in the order that the variables appear in the specification so that the coefficient for the PR term is labeled C(4). To test the restriction on C(4) you should select View/Coefficient Diagnostics/Wald Test–Coefficient Restrictions..., and enter the restriction "C(4)=2". EViews will report the results of the Wald test:

Wald Test:			
Equation: UNTITLED			
Null Hypothesis: C(4)=2			
Test Statistic	Value	df	Probability
t-statistic	-4.850856	159	0.0000
F-statistic	23.53081	(1, 159)	0.0000
Chi-square	23.53081	1	0.0000
Null Hypothesis Summary:			
Normalized Restriction (= 0)	Value	Std. Err.	
-2 + C(4)	-4.572204	0.942556	

Restrictions are linear in coefficients.

The low probability values indicate that the null hypothesis that C(4)=2 is strongly rejected.

We should, however, be somewhat cautious of accepting this result without additional analysis. The low value of the Durbin-Watson statistic reported above is indicative of the presence of serial correlation in the residuals of the estimated equation. If uncorrected, serial correlation in the residuals will lead to incorrect estimates of the standard errors, and invalid statistical inference for the coefficients of the equation.

The Durbin-Watson statistic can be difficult to interpret. To perform a more general Breusch-Godfrey test for serial correlation in the residuals, select View/Residual Diagnostics/Serial Correlation LM Test... from the equation toolbar, and specify an order of serial correlation to test against. Entering "1" yields a test against first-order serial correlation:

Breusch-Godfrey Serial Correlation LM Test:

F-statistic	813.0060	Prob. F(1,158)	0.0000
Obs*R-squared	136.4770	Prob. Chi-Square(1)	0.0000

Test Equation:

Dependent Variable: RESID

Method: Least Squares

Date: 08/18/09 Time: 14:10

Sample: 1952Q2 1992Q4

Included observations: 163

Presample missing value lagged residuals set to zero.

Variable	Coefficient	Std. Error	t-Statistic	Prob.
C	-0.006355	0.013031	-0.487683	0.6265
LOG(GDP)	0.000997	0.002645	0.376929	0.7067
RS	-0.000567	0.001018	-0.556748	0.5785
DLOG(PR)	0.404143	0.381676	1.058864	0.2913
RESID(-1)	0.920306	0.032276	28.51326	0.0000
R-squared	0.837282	Mean dependent var	1.23E-15	
Adjusted R-squared	0.833163	S.D. dependent var	0.054969	
S.E. of regression	0.022452	Akaike info criterion	-4.724644	
Sum squared resid	0.079649	Schwarz criterion	-4.629744	
Log likelihood	390.0585	Hannan-Quinn criter.	-4.686116	
F-statistic	203.2515	Durbin-Watson stat	1.770965	
Prob(F-statistic)	0.000000			

The top part of the output presents the test statistics and associated probability values. The test regression used to carry out the test is reported below the statistics.

The statistic labeled "Obs*R-squared" is the LM test statistic for the null hypothesis of no serial correlation. The (effectively) zero probability value strongly indicates the presence of serial correlation in the residuals.

Modifying the Equation

The test results suggest that we need to modify our original specification to take account of the serial correlation.

One approach is to include lags of the independent variables. To add variables to the existing equation, click on the Estimate button in the equation toolbar and edit the specification to include lags for each of the original explanatory variables:


```
log(m1) c log(gdp) rs dlog(pr) log(m1(-1)) log(gdp(-1)) rs(-1)
dlog(pr(-1))
```

Note that lags are specified by including a negative number, enclosed in parentheses, following the series name. Click on OK to estimate the new specification and to display the results:

Dependent Variable: LOG(M1)
 Method: Least Squares
 Date: 08/18/09 Time: 14:19
 Sample (adjusted): 1952Q3 1992Q4
 Included observations: 162 after adjustments

Variable	Coefficient	Std. Error	t-Statistic	Prob.
C	0.071297	0.028248	2.523949	0.0126
LOG(GDP)	0.320338	0.118186	2.710453	0.0075
RS	-0.005222	0.001469	-3.554801	0.0005
DLOG(PR)	0.038615	0.341619	0.113036	0.9101
LOG(M1(-1))	0.926640	0.020319	45.60375	0.0000
LOG(GDP(-1))	-0.257364	0.123264	-2.087910	0.0385
RS(-1)	0.002604	0.001574	1.654429	0.1001
DLOG(PR(-1))	-0.071650	0.347403	-0.206246	0.8369
R-squared	0.999604	Mean dependent var	5.697490	
Adjusted R-squared	0.999586	S.D. dependent var	0.669011	
S.E. of regression	0.013611	Akaike info criterion	-5.707729	
Sum squared resid	0.028531	Schwarz criterion	-5.555255	
Log likelihood	470.3261	Hannan-Quinn criter.	-5.645823	
F-statistic	55543.30	Durbin-Watson stat	2.393764	
Prob(F-statistic)	0.000000			

Note that EViews has automatically adjusted the estimation sample to accommodate the additional lagged variables. We will save this equation in the workfile for later use. Press the Name button in the toolbar and name the equation EQLAGS.



The EQLAGS equation object will be placed in the workfile.

One common method of accounting for serial correlation is to include autoregressive (AR) and/or moving average (MA) terms in the equation. To estimate the model with an AR(1)

error specification, you should make a copy of the EQLAGS equation by clicking Object/ Copy Object... in the EQLAGS window. EViews will create a new untitled equation containing all of the information from the previous equation. Press Estimate on the toolbar of the copy and modify the specification to read

$\log(m1) \text{ c } \log(gdp) \text{ rs } d\log(pr) \text{ ar}(1)$

This specification removes the lagged terms, replacing them with an AR(1) specification:

$$\log M1_t = b_1 + b_2 \log GDP_t + b_3 RS_t + b_4 \log PR_t + u_t \quad (2.2)$$

$$u_t = r u_{t-1} + e_t$$

Click OK to accept the new specification. EViews will estimate the equation and will report the estimation results, including the estimated first-order autoregressive coefficient of the error term:

Dependent Variable: LOG(M1)				
Method: Least Squares				
Date: 08/18/09 Time: 14:12				
Sample (adjusted): 1952Q3 1992Q4				
Included observations: 162 after adjustments				
Convergence achieved after 32 iterations				
Variable	Coefficient	Std. Error	t-Statistic	Prob.
C	1.050341	0.328260	3.199724	0.0017
LOG(GDP)	0.794928	0.049324	16.11633	0.0000
RS	-0.007395	0.001457	-5.075118	0.0000
DLOG(PR)	-0.008020	0.348689	-0.023002	0.9817
AR(1)	0.968109	0.018189	53.22359	0.0000
R-squared	0.999526	Mean dependent var	5.697490	
Adjusted R-squared	0.999514	S.D. dependent var	0.669011	
S.E. of regression	0.014751	Akaike info criterion	-5.564584	
Sum squared resid	0.034164	Schwarz criterion	-5.469288	
Log likelihood	455.7313	Hannan-Quinn criter.	-5.525892	
F-statistic	82748.93	Durbin-Watson stat	2.164283	
Prob(F-statistic)	0.000000			
Inverted AR Roots	.97			

The fit of the AR(1) model is roughly comparable to the lag model, but its somewhat higher values for both the Akaike and the Schwarz information criteria indicate that the previous lag model may be preferred. Accordingly, we will work with the lag model in EQLAGS for the remainder of the demonstration.

Forecasting from an Estimated Equation


We have been working with a subset of our data, so that we may compare forecasts based upon this model with the actual data for the post-estimation sample 1993Q1–1996Q4.

Click on the Forecast button in the EQLAGS equation toolbar to open the forecast dialog:

The screenshot shows the 'Forecast' dialog box in EViews. The 'Forecast equation' is 'EQLAGS'. Under 'Series to forecast', 'LOG(M1)' is selected. In the 'Series names' section, 'Forecast name' is 'm1_f' and 'S.E. (optional)' is 'm1_se'. The 'Method' section has 'Dynamic forecast' selected, with 'Coef uncertainty in S.E. calc' checked. The 'Forecast sample' is '1993q1 1996q4'. The 'Output' section has both 'Forecast graph' and 'Forecast evaluation' checked. The 'Insert actuals for out-of-sample observations' checkbox is also checked. 'OK' and 'Cancel' buttons are at the bottom.


We set the forecast sample to 1993Q1–1996Q4 and provide names for both the forecasts and forecast standard errors so both will be saved as series in the workfile. The forecasted values will be saved in M1_F and the forecast standard errors will be saved in M1_SE.

Note also that we have elected to forecast the log of M1, not the level, and that we request both graphical and forecast evaluation output. The Dynamic option constructs the forecast for the sample period using only information available at the beginning of 1993Q1. When you click OK, EViews displays both a graph of the forecasts, and statistics evaluating the quality of the fit to the actual data:



Alternately, we may also choose to examine forecasts of the level of M1. Click on the Forecast button in the EQLAGS toolbar to open the forecast dialog, and select M1 under the

Series to forecast option. Enter a new name to hold the forecasts, say M1LEVEL_F, and click OK. EViews will present a graph of the forecast of the level of M1, along with the asymmetric confidence intervals for this forecast:




The series that the forecast procedure generates are ordinary EViews series that you may work with in the usual ways. For example, we may use the forecasted series for $\text{LOG}(M1)$ and the standard errors of the forecast to plot actuals against forecasted values with (approximate) 95% confidence intervals for the forecasts.

We will first create a new group object containing these values. Select Quick/Show... from the main menu, and enter the expressions:


$m1\_f + 2 * m1\_se$ $m1\_f - 2 * m1\_se$ $\log(m1)$

to create a group containing the confidence intervals for the forecast of $\text{LOG}(M1)$ and the actual values of $\text{LOG}(M1)$:




There are three expressions in the dialog. The first two represent the upper and lower bounds of the (approximate) 95% forecast interval as computed by evaluating the values of the point forecasts plus and minus two times the standard errors. The last expression represents the actual values of the dependent variable.

When you click OK, EViews opens an untitled group window containing a spreadsheet view of the data. Before plotting the data, we will change the sample of observations so that we only plot data for the forecast sample. Select Quick/Sample... or click on the Sample button in the group toolbar, and change the sample to include only the forecast period:



To plot the data for the forecast period, select View/Graph... from the group window and choose Line & Symbol from the list on the left of the Graph Options dialog:




The actual values of $\log(M1)$ are within the forecast interval for most of the forecast period, but fall below the lower bound of the 95% confidence interval beginning in 1996:1.

For an alternate view of these data, you can select View/Graph... and Error Bar from the list in the dialog, which displays the graph as follows:

This graph shows clearly that the forecasts of LOG(M1) over-predict the actual values in the last four quarters of the forecast period.

Additional Testing

Note that the above specification has been selected for illustration purposes only. Indeed, performing various specification tests on EQLAGS suggests that there may be a number of problems with the existing specification.



For one, there is quite a bit of serial correlation remaining even after estimating the lag specification. A test of serial correlation in the EQLAGS equation (by selecting View/Residual Diagnostics/Serial Correlation LM Test... , and entering “1” for the number of lags) rejects the null hypothesis of no serial correlation in the reformulated equation. The top portion of the output is:

Breusch-Godfrey Serial Correlation LM Test:

F-statistic	7.880369	Prob. F(1,153)	0.0056
Obs*R-squared	7.935212	Prob. Chi-Square(1)	0.0048

Moreover, there is strong evidence of autoregressive conditional heteroskedasticity (ARCH) in the residuals. Select View/Residual Diagnostics/Heteroskedasticity Tests... to bring up the Heteroskedasticity Tests dialog. Then select ARCH from the listbox and accept the default of “1”. The top portion of the ARCH test results shows that the data suggest the presence of ARCH in the residuals:

Heteroskedasticity Test: ARCH

F-statistic	11.21965	Prob. F(1,159)	0.0010
Obs*R-squared	10.61196	Prob. Chi-Square(1)	0.0011

In addition to serial correlation and ARCH, there is an even more fundamental problem with the above specification since, as the graph `sattest`, LOG(M1) exhibits a pronounced upward trend, suggesting that we should perform a unit root in this series. The presence of a unit root will indicate the need for further analysis.

We once again display the LOG(M1) series window by clicking on Window and selecting the LOG(M1) series window from the menu. If the series window for LOG(M1) is not

present (if you previously closed the window), you may again open a new window by selecting Quick/Show... , entering “log(m1)”, and clicking OK.

Before computing the test statistic, we will reset the workfile sample to all of the observations by clicking on Quick/Sample... and entering “@all” in the dialog.

Next, to perform an Augmented Dickey-Fuller (ADF) test for nonstationarity of this series, select View/Unit Root Test... and click on OK to accept the default options. EViews will perform an ADF test and display the test results. The top portion of the output reads:

Null Hypothesis: LOG(M1) has a unit root
Exogenous: Constant
Lag Length: 0 (Automatic - based on SIC, maxlag=13)

		t-Statistic	Prob.*
Augmented Dickey-Fuller test statistic		3.797182	1.0000
Test critical values:	1% level	-3.470679	
	5% level	-2.879155	
	10% level	-2.576241	

*MacKinnon (1996) one-sided p-values.

EViews performs the ADF test statistic with the number of lagged difference terms in the test equation (here, four) determined by automatic selection. The ADF test statistic value has a probability value of 0.9911, providing little evidence that we may reject the null hypothesis of a unit root.

If a unit root were present in our data, we may wish to adopt more sophisticated statistical models. These techniques are discussed in [Chapter 21. “Time Series Regression,”](#) [Chapter 25. “Cointegrating Regression,”](#) and [Chapter 32. “Vector Autoregression and Error Correction Models”](#) (all in User’s Guide I) which deal with basic time series, cointegrating regression models, and vector error correction specifications, respectively).

Chapter 3. Workfile Basics

Managing the variety of tasks associated with your work can be a complex and time-consuming process. Fortunately, EViews' innovative design takes much of the effort out of organizing your work, allowing you to concentrate on the substance of your project. EViews provides sophisticated features that allow you to work with various types of data in an intuitive and convenient fashion.

Before describing these features, we begin by outlining the basic concepts underlying the EViews approach to working with datasets using workfiles, and describing simple methods to get you started on creating and working with workfiles in EViews.

What is a Workfile?

At a basic level, a workfile is simply a container for EViews objects (see [Chapter 4. "Object Basics," on page 67](#)). Most of your work in EViews will involve objects that are contained in a workfile, so your first step in any project will be to create a new workfile or to load an existing workfile into memory.

Every workfile contains one or more workfile pages, each with its own objects. A workfile page may be thought of as a subworkfile or subdirectory that allows you to organize the data within the workfile.

For most purposes, you may treat a workfile page as though it were a workfile (just as a subdirectory is also a directory) since there is often no practical distinction between the two. Indeed, in the most common setting where a workfile contains only a single page, the two are completely synonymous. Where there is no possibility of confusion, we will use the terms "workfile" and "workfile page" interchangeably.

Workfiles and Datasets

While workfiles and workfile pages are designed to hold a variety of EViews objects, such as equations, graphs, and matrices, their primary purpose is to hold the contents of datasets. A dataset is defined here as a data rectangle, consisting of a set of observations on one or more variables—for example, a time series of observations on the variables GDP, investment, and interest rates, or perhaps a random sample of observations containing individual incomes and tax liabilities.

Key to the notion of a dataset is the idea that each observation in the dataset has a unique identifier, or ID. Identifiers usually contain important information about the observation, such as a date, a name, or perhaps an identifying code. For example, annual time series data typically use year identifiers ("1990", "1991", ...), while cross-

sectional state data generally use state names or abbreviations (“AL”, “AK”, ..., “WY”). More complicated identifiers are associated with longitudinal data, where one typically uses both an individual ID and a date ID to identify each observation.

Observation IDs are often, but not always, included as a part of the dataset. Annual datasets, for example, usually include a variable containing the year associated with each observation. Similarly, large cross-sectional survey data typically include an interview number used to identify individuals.

In other cases, observation IDs are not provided in the dataset, but external information is available. You may know, for example, that the 21 otherwise unidentified observations in a dataset are for consecutive years beginning in 1990 and continuing to 2010.

In the rare case where there is no additional identifying information, one may simply use a set of default integer identifiers that enumerate the observations in the dataset (“1”, “2”, “3”, ...).

Since the primary purpose of every workfile page is to hold the contents of a single dataset, each page must contain information about observation identifiers. Once identifier information is provided, the workfile page provides context for working with observations in the associated dataset, allowing you to use dates, handle lags, or work with longitudinal data structures.

Creating a Workfile

There are several ways to create and set up a new workfile. The first task you will face in setting up a workfile (or workfile page) is to specify the structure of your workfile. We focus here on three distinct approaches:

First, you may simply describe the structure of your workfile ([“Creating a Workfile by Describing its Structure” on page 35](#)). EViews will create a new workfile for you to enter or import your data).

Describing the workfile is the simplest method, requiring only that you answer a few simple questions—it works best when the identifiers follow a simple pattern that is easily described (for example, “annual data from 1950 to 2000” or “quarterly data from 1970Q1 to 2002Q4”). This approach must be employed if you plan to enter data into EViews by typing or copy-and-pasting data.

In the second approach, you simply open and read data from a foreign data source ([“Creating a Workfile by Reading from a Foreign Data Source” on page 39](#)). EViews will analyze the data source, create a workfile, and then automatically import your data.

The final approach, which should be reserved for more complex settings, involves two distinct steps. In the first, you create a new workfile using one of the first two approaches (by

describing the structure of the workfile, or by opening and reading from a foreign data source). Next, you will structure the workfile, by instructing EViews to construct unique identifiers, in some cases using values of variables contained in the dataset.

We begin by describing the first two methods. The third approach, involving the more complicated task of structuring a workfile, will be taken up in [“Structuring a Workfile” on page 213](#)

Creating a Workfile by Describing its Structure

To describe the structure of your workfile, you will need to provide EViews with external information about your observations and their associated identifiers. For example, you might tell EViews that your dataset consists of a time series of observations for each quarter from 1990Q1 to 2003Q4, or that you have information for every day from the beginning of 1997 to the end of 2001. At the very least, you might indicate that you have a dataset with 500 observations and no additional identifier information.

To create a new workfile, select File/New/Workfile... from the main menu to open the Workfile Create dialog.

On the left side of the dialog is a combo box for describing the underlying structure of your dataset. You will choose between the Dated - regular frequency, the Unstructured, and the Balanced Panel settings. Generally speaking, you should use Dated - regular frequency if you have a simple time series dataset, for a simple panel dataset you should use Balanced Panel, and in all other cases, you should select Unstructured. Additional detail to aid you in making a selection is provided in the description of each category.

Describing a Dated Regular Frequency Workfile

When you select Dated - regular frequency, EViews will prompt you to select a frequency for your data. You may choose between the standard EViews supported date frequencies (Multi-year, Annual, Semi-annual, Quarterly, Monthly, Bimonthly, Fortnight, Ten-day, Weekly, Daily - 5 day week, Daily - 7 day week, Daily - custom week, Intraday), and a special frequency (Integer date) which is a generalization of a simple enumeration.

Workfile Create

Workfile structure type: Dated - regular frequency

Irregular Dated and Panel workfiles may be made from Unstructured workfiles by later specifying date and/or other identifier series.

Date specification:

Frequency: Annual

Start date: 1980

End date: 2002

Workfile names (optional):

WF:

Page:

OK Cancel

In selecting a frequency, you set intervals between observations in your data (whether they are annual, semi-annual, quarterly, monthly, weekly, etc.), which allows EViews to use all available calendar information to organize and manage your data. For example, when moving between daily and weekly or annual data, EViews knows that some years contain days in each of 53 weeks, and that some years have 366 days, and will use this information when working with your data.

As the name suggests, regular frequency data arrive at regular intervals, defined by the specified frequency (e.g., monthly). In contrast, irregular frequency data do not arrive in regular intervals. An important example of irregular data is found in stock and bond prices where the presence of holidays and other market closures ensures that data are observed only irregularly, and not in a regular 5-day daily frequency. Standard macroeconomic data such as quarterly GDP or monthly housing starts are examples of regular data.

EViews also prompts you to enter a Start date and End date for your workfile. For Daily - custom week or Intraday, you will also need to enter Day and/or Time information as described below. When you click on OK, EViews will create a regular frequency workfile with the specified number of observations and the associated identifiers.

Suppose, for example, that you wish to create a quarterly workfile that begins with the first quarter of 1970 and ends in the last quarter of 2020.

- First, select Dated - regular frequency for the workfile structure, and then choose the Quarterly frequency.
- Next, enter the Start date and End date. There are a number of ways to fill in the dates. EViews will use the largest set of observations consistent with those dates, so if you enter “1970” and “2020”, your quarterly workfile will begin in the first quarter of 1970, and end in the last quarter of 2020. Entering the date pair “Mar 1970” and “Nov 2020”, or the start-end pair “3/2/1970” and “11/15/2020” would have generated a workfile with the same structure, since the implicit start and end quarters are the same in all three cases.

This latter example illustrates a fundamental principle regarding the use of date information in EViews. Once you specify a date frequency for a workfile, EViews will use all available calendar information when interpreting date information. For example, given a quarterly frequency workfile, EViews knows that the date “3/2/1990” is in the first quarter of 1990 (see [“Dates” on page 82](#) of the Command and Programming Reference for details).

For some choices of frequency, you will be prompted for additional information. If, for example, you select the Daily - custom week frequency, the dialog will prompt you to provide a range for the days of the week in your custom week. You should use the Intraweek/Intraday range combo boxes to define the start and end of the week. Here, we indicate that we want to define a custom 4-day (Monday-Thursday) week.

If you choose the Intraday frequency you will be prompted to provide additional information about the structure of your observed days. You must provide information about the frequency of observations within the day, the days of the week for which you observe data, and the time, and the time range of observations within a day.

The intraday settings are best illustrated through a simple example. To create an hourly workfile that begins at 8AM Monday and ends at 5PM Friday for every day in 2005, you should also specify the Day and Time parameters.

- Select Dated - regular frequency for the workfile structure, and then choose the Intraday frequency. Select Hour from the dropdown that appears.
- Enter the Start date and End date. In this case, this will be 2005 for both fields.
- After selecting an Intraday frequency, the Intraweek/Intraday range options were enabled at the bottom of the dialog. Select 1-Mon through 5-Fri from the Days dropdowns and 8:00:00 through 17:00:00 from the Time dropdowns.

Note that the workfile created will have ten observations per day, the first at 8 a.m. and the last at 5 p.m. Though you may have intended to create a workfile to record nine hours of data, specifying an end time of 17:00:00 defines the period from 5 p.m. to 6 p.m., adding an extra hour to the day specification. This may be desirable for recording discrete measurements on the hour from 8 a.m. to 5 p.m., but if you wish to measure the hours as intervals (from 8 a.m. to 9 a.m., 9 a.m. to 10 a.m., ..., and 4 p.m. to 5 p.m.), with one observation for each interval, you should specify an end time of 16:00:00, or 4 p.m. An end time of 16:00:00 defines the last interval as 4 p.m. to 5 p.m. (see ["Specifying Start and End Times," on page 225](#) for a thorough discussion of how start and end times are defined).

Lastly, you may optionally provide a name to be given to your workfile and a name to be given to the workfile page.

After creating a workfile, you can see EViews' interpretation of your workfile specification by looking at the Workfile structure dialog. Select Proc/Structure/Resize Current Page... or click on the Range area at the top of the new workfile to bring up the Workfile structure dialog (see [“Applying a Structure to a Workfile,” on page 223](#) for detailed discussion of structuring a workfile and the settings in this dialog).

For the previous example, you may take note of two things in the dialog. First, the Start date is displayed as “1/03/2005 08:00”, which corresponds to 8 a.m. this is the first Monday in 2005. Similarly, the End date is “12/30/2005 17:00”, the last Friday in 2005. Second, notice that the time in the End date field is different from the time displayed in the Time end field. This illustrates that because the End date is specified in hours, an end time of 17:00 defines the period from 5 p.m. to 6 p.m. Alternately, the Time field denotes the last second that is part of the specification, 17:59:59.

Describing an Unstructured Workfile

Unstructured data are simply data which use the default integer identifiers. You should choose the Unstructured type if your data are not a Dated - regular frequency or Balanced Panel (i.e., you wish to create an undated workfile that uses the default identifiers or you will eventually define an advanced structure your data).

When you select this structure in the combo box, the remainder of the dialog will change, displaying a single field prompting you for the number of observations. Enter the number of observations, and click on OK to proceed. In the example depicted here, EViews will create a 500 observation workfile containing integer identifiers ranging from 1 to 500.

In many cases, the integer identifiers will be sufficient for you to work with your data. In more complicated settings, you may wish to further refine your identifiers. We describe this process in [“Applying a Structure to a Workfile” on page 223](#).

Describing a Balanced Panel Workfile

The Balanced Panel entry provides a simple method of describing a regular frequency panel data structure. Panel data is the term that we use to refer to data containing observations with both a group (cross-section) and time (within-group) identifiers.

This entry may be used when you wish to create a balanced structure in which every cross-section follows the same regular frequency with the same date observations. Only the barest outlines of the procedure are provided here since a proper discussion requires a full description of panel data and the creation of the advanced workfile structures. Panel data and structured workfiles are discussed at length in “Structuring a Workfile” on page 213.

To create a balanced panel, select Balanced Panel in the combo box, specify the desired Frequency, and enter the Start date and End date, and Number of cross sections. You may optionally name the workfile and the workfile page. Click on OK. EViews will create a balanced panel workfile of the given frequency, using the specified start and end dates and number of cross-sections.

The screenshot shows the 'Workfile Create' dialog box. It has two main sections: 'Workfile structure type' and 'Panel specification'. Under 'Workfile structure type', 'Balanced Panel' is selected. Below this, a note states: 'Irregular Dated and Panel workfiles may be made from Unstructured workfiles by later specifying date and/or other identifier series.' The 'Panel specification' section includes a 'Frequency' dropdown set to 'Quarterly', and text boxes for 'Start date' (1970), 'End date' (2020), and 'Number of cross sections' (200). At the bottom, there is a 'Workfile names (optional)' section with 'WF' and 'Page' text boxes; 'Page' is set to 'Quarterly'. 'OK' and 'Cancel' buttons are at the bottom right.

Here, EViews creates a 200 cross-section, regular frequency, quarterly panel workfile with observations beginning in 1970Q1 and ending in 2020Q4.

Unbalanced panel workfiles or workfiles involving more complex panel structures should be created by first defining an unstructured workfile, and then applying a panel workfile structure.

Creating a Workfile by Reading from a Foreign Data Source

A second method of creating an EViews workfile is to open a foreign (non-EViews format) data source and to read the data into a new EViews workfile.

One way to read foreign data into a new workfile is to copy the foreign data source to the Windows clipboard, right click on the gray area in your EViews window, and select Paste as new Workfile. EViews will automatically create a new workfile containing the contents of the clipboard. Such an approach, while convenient, is only practical for small amounts of data.

Alternately, you may open a foreign data source as an EViews workfile. There are two ways to proceed. First, you may select File/Open/Foreign Data as Workfile..., to bring up the standard file Open dialog. Clicking on the Files of type combo box brings up a list of the file types that EViews currently supports for opening a workfile. Select a file type to narrow the list of files in the dialog, then choose the file you wish to open.

EViews offers drag-and-drop support for the file open operation. Simply select the file you wish to open in Windows, then drag-and-drop the file on the gray area in your EViews window.

Whichever your approach, EViews will open the specified foreign data as an EViews workfile.

If you select a time series database file (e.g., Aremos TSD, GiveWin/Pc-Give, Rats 4x, Rats Portable, TSP Portable), EViews will create a new, regular frequency workfile containing the contents of the entire file. If there are mixed frequencies in the database, EViews will select the lowest frequency, and convert all of the series to that frequency using the default conversion settings (we emphasize here that all of these database formats may also be opened as databases by selecting **File/Open/Database...** and filling out the dialogs, allowing for additional control over the series to be read, the new workfile frequency, and any frequency conversion).

If you choose one of the remaining source types, EViews will create a new unstructured workfile. First, EViews will open a series of dialogs prompting you to describe and select data to be read. The data will be read into the new workfile, which will be resized to fit. If possible, EViews will attempt to structure the workfile using information in the file. If this is not possible but you still wish to apply a specific workfile structure with these data, you will have to define a structured workfile using the advanced workfile structure tools (see [“Structuring a Workfile” on page 213](#)).


The import as workfile interface is available for Microsoft Access files, Gauss Dataset files, ODBC Dsn files, ODBC Query files, SAS Transports, native SPSS files (using the SPSS Input/output .DLL that should be installed on your system), SPSS Portable files, Stata files, Excel files, raw ASCII or binary files, or ODBC Databases and queries (using an ODBC driver already present on your system).

An Illustration

Perhaps the most common form of foreign datafiles are Excel files, followed by text files (ASCII). We offer examples of reading Excel, ASCII, and Stata files to illustrate the basic process of creating a new workfile (or a workfile page) by opening a foreign source file.


The easiest way to specify the foreign file to be opened is to drag-and-drop the file into background area of the main EViews window.

Here we have dragged an Excel file onto the EViews desktop. A plus (“+”) sign will appear when the file is over an appropriate area. Drop the file and EViews will proceed with the foreign file open process, first opening the selected file, validating its type, then displaying a tabbed dialog allowing you to select the specific data that you wish to read into your new workfile. If you wish to read all of your data using the default settings, click on OK to proceed. Otherwise you may use each of the tabs to change the read behavior.



Alternately, you may specify the foreign file using the File/Open/Foreign Data as Workfile... dialog, first navigate to the appropriate directory and select the Files of type entry to match the file you wish to open. In this example, we see the if we select Stata files (*.dta) the dialog displays a list of Stata files that may be opened.

Double-click on the name to select and open the file, or enter the filename in the dialog and click on Open to accept the selection. Note that the Open dialog displayed here is the one for the Windows XP operating system. The dialog may look different in other versions of Windows.



If you have chosen an Excel file, the first dialog that will open is Step 1 of the Spreadsheet Read dialog. This page lets you select which data in the Excel file you wish to read into EViews. You can choose from either one of the Pre-defined range options (a list of Excel ranges that EViews has automatically selected), or you can specify a Custom range , and enter

Spreadsheet Read - Step 1 of 2

Cell Range

☒ Predefined range
academic salaries by discipline

☐ Custom range
academic salaries by discipline!\$A\$

Sheet: academic salaries by disc

Start cell: \$A\$1

End cell: \$F\$29

discipline	nonacadsal	pctfemale	pctnonad	pctunemp	salary
Dentistry	40005	15.7	99.4	0.1	44214
Medicine	50005	25.5	96	0.2	43160
Law	30518	34	99.3	0.5	40670
Agriculture	31063	12.9	43.4	0.8	36879
Engineering	35133	4.6	65.5	0.5	35694
Geology	33602	13.5	58.1	0.3	33206
Chemistry	32489	16.2	61.9	1.1	33069
Physics	33434	7.2	40.7	1.2	32925
Life Sciences	30500	29.8	27.4	1.4	32605

Cancel < Back Next > Finish

the Sheet name and the Start Cell and End Cell of the data. The bottom half of this dialog presents a preview of the incoming data, based upon the range you have selected. In this example we have opened the file "academic salaries by discipline.XLS". Here the predefined range chosen by EViews is exactly the data we wish to read in.

If you are happy with the way the previewed data looks, you can click Finish , and EViews will open up a new workfile containing the Excel data. For further adjustments to the data import, you can click Next rather than Finish and open up Step 2 of the Spreadsheet Read dialog.

The Column headers section of Step 2 allows you to specify the number of header lines (lines containing information about each column of the data, such as column names or descriptions, rather than the data itself) contained in the Excel file, and tell EViews a little bit about what information is stored in the header lines, using the Header type drop-down box.

Spreadsheet Read - Step 2 of 2

Column headers

Header lines: 1

Header type: Names only

Clear Edited Column Info

Text representing NA: #N/A

Column info

Click in preview to select column for editing

Name: discipline

Description:

Data type: Character

discipline	nonacadsal	pctfemale	pctnonac	pctunemp	salary
Dentistry	40005	15.7	99.4	0.1	44214
Medicine	50005	25.5	96	0.2	43160
Law	30518	34	99.3	0.5	40670
Agriculture	31063	12.9	43.4	0.8	36879
Engineering	35133	4.6	65.5	0.5	35694
Geology	33602	13.5	58.1	0.3	33206
Chemistry	32489	16.2	61.9	1.1	33069
Physics	33434	7.2	40.7	1.2	32925

Cancel < Back Next > Finish

If the data in your Excel file has special coding for missing values, you can set the Text representing NA box to whatever value your data uses.

EViews will fill out the Column info box automatically, based upon your choices in the Column headers box, and by analyzing the data in your file. If you would like to change the name, description or data type (Character, Number or Date) of a specific column, select that column in the preview box at the bottom of the dialog, and then change the information.

Once you are happy with the way the data looks in the preview window you can click Finish to bring the data into a new EViews workfile.

If you have chosen an ASCII text file, EViews will open Step 1 of the ASCII Read dialog. This page lets you specify column and row information for your file. Generally EViews will analyze your file and fill this data in correctly, meaning you can just click Finish. If EViews has not analyzed your data correctly, you can make changes during the three steps of the ASCII Read dialog.

ASCII Read - Step 1 of 3

Please examine the preview window below.
If the rows and columns appear to be correct, click on the Finish button to read your data into EViews.
To adjust the column breaks, choose a column type from the list on the right, then click Next to continue.
To adjust the row breaks, click on the following button.

Column specification

☒ Delimiter characters between values
☐ Fixed width fields
☐ An explicit format (to be provided)

Start of data/header

Skip lines: 0

Show row options

discipline	nonacadsal	pctfemale	pcntnonac	pctunemp	salary
Dentistry	40005	15.7	99.4	0.1	44214
Medicine	50005	25.5	96.0	0.2	43160
Law	30518	34.0	99.3	0.5	40670
Agriculture	31063	12.9	43.4	0.8	36879
Engineering	35133	4.6	65.5	0.5	35694
Geology	33602	13.5	58.1	0.3	33206
Chemistry	32489	16.2	61.9	1.1	33069
Physics	33434	7.2	40.7	1.2	32925
Life Sciences	30500	29.8	27.4	1.4	32605

Cancel < Back Next > Finish

If your text file has lines of text at the start of the file that come before the actual columns of data (such as text explaining what the data is, or where it came from), you should tell EViews to skip these lines as part of the data read in the Start of data/header box.

Most text files containing data will have a row of text for each observation, and EViews, by default, will read in the data assuming this is the case. For more complicated structures, you should press the Show row options button, which will then display a set of options that allow you to specify how each row of your file is formatted.

The Column specification box lets you specify how each column of data is separated from each other. The most common method of separating columns in a text file is through the use of a delimiter character, such as a comma or space or a tab, between each column. A second form of separation is through fixed width columns - each column has the same number of characters in it for every row. If your data has a fixed width, you should select Fixed width fields. If your text file uses neither delimiters nor fixed widths, you should select An explicit format (to be provided).

Step 2 of the ASCII Read dialog will change depending upon the choices you made in the Column specification box during Step 1. If you chose Delimiter characters between values, Step 2 lets you specify information about the delimiters.

You can either choose from one of the preset Standard delimiters, or specify a Custom delimiter. You can also choose how EViews treats delimiters that are part of text enclosed in quotes using the Other options box.

ASCII Read - Step 2 of 3

Delimiters

☒ Standard delimiter: 2 or more spaces

☐ Custom delimiters: Enter list of delimiters - Use 'T' for tab and 'A' for all alpha

☐ Treat consecutive delimiters as one

Other options

☒ Don't split quoted fields

Quote character(s): " or '

	discipline	nonacadsal	pcnt female	pcntnonac	pctunemp
1-	Dentistry	40005	15.7	99.4	0.1
2-	Medicine	50005	25.5	96.0	0.2
3-	Law	30518	34.0	99.3	0.5
4-	Agriculture	31063	12.9	43.4	0.8
5-	Engineering	35133	4.6	65.5	0.5
6-	Geology	33602	13.5	58.1	0.3
7-	Chemistry	32489	16.2	61.9	1.1
8-	Physics	33434	7.2	40.7	1.2


Buttons: Cancel, < Back, Next >, Finish

If you chose Fixed width fields as your column separator, Step 2 will let you specify the width of each column. If you chose An explicit format, Step 2 lets you specify the format string.

Step 3 of the ASCII Read dialog is exactly the same as Step 2 of the Spreadsheet Read dialog, explained above, and lets you set information regarding the data columns of your file.

If you had chosen a Stata file (or other file containing predefined variable information) to be read, the Table read specification dialog will open, letting you select which variables to read.

The Select variables tab of the dialog should be used to choose the series data to be included. The upper list box shows the names of the variables that can be read into EViews series, along with the variable data type, and if available, a description of the data. The variables are first listed in the order in which they appear in the file. You may choose to sort the data by clicking on the header for the column. The display will be toggled between three states: the original order, sorted (ascending), and sorted (descending). In the latter two cases, EViews will display a small arrow on the header column indicating the sort type. Here, the data are sorted by variable name in ascending order.




When the dialog first opens, all variables are selected for reading. You can change the current state of any variable by checking or unchecking the corresponding checkbox. The number of variables selected is displayed at the bottom right of the list.

There may be times when checking and unchecking individual variables is inconvenient (e.g., when there are thousands of variable names). The bottom portion of the dialog provides you with a control that allows you to select or unselect variables by name. Simply enter the names of variables using wildcard characters if desired, choose the types of interest, and click on the appropriate button.

For example, entering "A* B?" in the selection edit box, selecting only the Numeric checkbox, and clicking on Unselect will uncheck all numeric series beginning with the letter "A" and all numeric series with two character names beginning in "B". To select only series beginning with the letter "A ", enter "*" and click on Unselect, then enter "A*" and click on Select.

When opening datasets that contain value labels, EViews will display a second tabbed dialog page labeled Select maps, which controls the importing of value maps. On this page, you will specify how you wish EViews to handle these value labels. You should bear in mind that when opening datasets which do not contain value labels, EViews will not display the value map tab.

The upper portion of the dialog contains a combo box where you specify which labels to read. You may choose between the default Attached to selected series, None, All, or Selected from list.




The selections should be self-explanatory—Attached to selected series will only load maps that are used by the series that you have selected for inclusion; Selected from list (depicted) displays a map selection list in which you may check and uncheck individual label names along with a control to facilitate selecting and deselecting labels by name.

Lastly, the Filter obs page brings up an observation filter specification where you may enter a condition on your data that must be met for a given observation to be read.

When reading the dataset, EViews will discard any observation that does not meet the specified criteria. Here we tell EViews that we only wish to keep observations where AGE>10.

Once you have specified the characteristics of your table read, click on OK to begin the procedure.

EViews will open the foreign dataset, validate the type, create a workfile, read the selected data, and if possible, apply a workfile structure. When the procedure is completed, EViews will display an untitled group containing the series, and will display relevant information in the status line. In this example, EViews will report that after applying the observation filter it has retained 636 of the 1534 observations in the original dataset.




The Workfile Window

Probably the most important windows in EViews are those for workfiles. Since open workfiles contain the EViews objects that you are working with, it is the workfile window that provides you with access to all of your data. Roughly speaking, the workfile window provides you with a directory for the objects in a given workfile or workfile page. When open, the workfile window also provides you with access to tools for working with workfiles and their pages.

Workfile Directory Display

The standard workfile window view will look something like this:



In the title bar of the workfile window you will see the “ Workfile ” designation followed by the workfile name. If the workfile has been saved to disk, you will see the name and the full disk path. Here, the name of the workfile is “TESTFILE”, and it is located in the “C:\EIEWS\DATA” directory on disk. If the workfile has not been saved, it will be designated “UNTITLED”.

Just below the titlebar is a button bar that provides you with easy access to useful workfile operations. Note that the buttons are simply shortcuts to items that may be accessed from the main EViews menu. For example, the clicking on the Fetch button is equivalent to selecting Object/Fetch from DB... from the main menu.

Below the toolbar are two lines of status information where EViews displays the range (and optionally, the structure) of the workfile, the current sample of the workfile (the range of observations that are to be used in calculations and statistical operations), and the display filter (rule used in choosing a subset of objects to display in the workfile window). You may change the range, sample, and filter by double clicking on these labels and entering the relevant information in the dialog boxes.


Lastly, in the main portion of the window, you will see the contents of your workfile page in the workfile directory. In normal display mode, all named objects are listed in the directory, sorted by name, with an icon showing the object type. The different types of objects and their icons are described in detail in [“Object Types” on page 69](#). You may also show a subset of the objects in your work file page, as described below.

It is worth keeping in mind that the workfile window is a specific example of an object window. Object windows are discussed in [“The Object Window” on page 73](#).

Workfile Directory Display Options

You may choose **View/Name Display** in the workfile toolbar to specify whether EViews should use upper or lower case letters when it displays the workfile directory. The default is lower case.

You can change the default workfile display to show additional information about your objects. If you select **View/Details+/-**, or click on the **Details +/-** button on the toolbar, EViews will toggle between the standard workfile display format, and a display which provides additional information about the date the object was created or updated, as well as the label information that you may have attached to the object.




Filtering the Workfile Directory Display

When working with workfiles containing a large number of objects, it may become difficult to locate specific objects in the workfile directory display. You can solve this problem by using the workfile display filter to instruct EViews to display only a subset of objects in the workfile window. This subset can be defined on the basis of object name as well as object type.

Select **View/Display Filter...** or double click on the Filter description in the workfile window. The following dialog box will appear:

There are two parts to this dialog. In the edit field (blank space) of this dialog, you may place one or several name descriptions that include the standard wildcard characters:

"*" (match any number of characters) and "?" (match any single character). Below the edit field are a series of check boxes corresponding to various types of EViews objects.



EViews will display only objects of the specified types whose names match those in the edit field list.

The default string is “*”, which will display all objects of the specified types. However, if you enter the string:

x*

only objects with names beginning with X will be displayed in the workfile window. Entering:

x?y

displays all objects that begin with the letter X, followed by any single character and then ending with the letter Y. If you enter:

x* y* *z

all objects with names beginning with X or Y and all objects with names ending in Z will be displayed. Similarly, the more complicated expression:

??y* *z*

tells EViews to display all objects that begin with any two characters followed by a Y and any or no characters, and all objects that contain the letter Z. Wildcards may also be used in more general settings—a complete description of the use of wildcards in EViews is provided in [Appendix A. “Wildcards,” on page 559](#) of the Command and Programming Reference


When you specify a display filter, the Filter description in the workfile window changes to reflect your request. EViews always displays the current string used in matching names. Additionally, if you have chosen to display a subset of EViews object types, a “—” will be displayed in the Display Filter description at the top of the workfile window.

Workfile Summary View

In place of the directory display, you can display a summary view for your workfile. If you select this view, the display will change to provide a description of the current workfile structure, along with a list of the types and numbers of the various objects in each of the pages of the workfile.

To select the summary view, click on View/Statistics in the main workfile menu or toolbar. Here we see the display for a first page of a two page workfile.


To return to the directory display view, select View/Workfile Directory.



Object	Count	Data Points
series	6	2952
coef	1	750
vector	2	469
matrix	1	1392
sample	1	
equation	1	
graph	2	
table	1	
model	1	
system	1	
var	1	
sspace	1	
group	1	
Total	20	5563

Saving a Workfile

You should name and save your workfile for future use. Push the Save button on the workfile toolbar to save a copy of the workfile on disk. You can also save a file using the File/Save As... or File/Save... choices from the main menu. EViews will display the Windows common file dialog.



You can specify the target directory in the upper file menu labeled **Save in**. You can navigate between directories in the standard Windows fashion—click once on the down arrow to access a directory tree; double clicking on a directory name in the display area gives you a list of all the files and subdirectories in that directory. Once you have worked your way to the right directory, type the name you want to give the workfile in the **File name** field and push the **Save** button.

Alternatively, you could just type the full Windows path information and name in the **File name** edit field.

In most cases, you will save your data as an EViews workfile. By default, EViews will save your data in this format, using the specified name and the extension “.WF1”. You may, of course, choose to save the data in your workfile in a foreign data format by selecting a different format in the combo box. We explore the subject of saving foreign formats below in [“Exporting from a Workfile” on page 265](#).

Saving Updated Workfiles

You may save modified or updated versions of your named workfile using the **Save** button on the workfile toolbar, or by selecting **File/Save...** from the main menu. Selecting **Save** will update the existing workfile stored on disk. You may also use **File/Save As...** to save the workfile with a new name. If the file you save to already exists, EViews will ask you whether you want to update the version on disk.

When you overwrite a workfile on disk, EViews will usually keep a backup copy of the overwritten file. The backup copy will have the same name as the file, but with the first


character in the extension changed to ~. For example, if you have a workfile named “Mydata.WF1”, the backup file will be named “Mydata.~f1”. The existence of these backup files will prove useful if you accidentally overwrite or delete the current version of the workfile file, or if the current version becomes damaged.

If you wish to turn on or off the creation of these backup copies you should set the desired global options by selecting Options/Workfile Storage Defaults..., and selecting the desired settings.

Workfile Save Options

By default, when you click on the Save button, EViews will display a dialog showing the current global default options for storing the data in your workfile.

Your first choice is whether to save your series data in either Single precision or Double precision. Single precision will create smaller files on disk, but saves the data with fewer digits of accuracy (7 versus 16).



You may also choose to save your data in compressed or non-compressed form. If you select Use compression, EViews will analyze the contents of your series, choose an optimal (lossless) storage precision for each series, and will apply compression algorithms, all to reduce the size of the workfile on disk. The storage savings may be considerable, especially for large datasets containing lots of integer and 0, 1 variables. We caution however, that a compressed workfile is not backward compatible, and will not be readable by versions prior to EViews 5.

There is also a checkbox for showing the options dialog on each save operation. By default, the dialog will be displayed every time you save a workfile. Unchecking the Prompt on each Save option instructs EViews to hide this dialog on subsequent saves. If you later wish to change the save settings or wish to display the dialog on saves, you must update your global settings by selecting Options/General Options... from the main EViews menu and going to the Data storage/Workfile save portion of the dialog.

Note that, with the exception of compressed workfiles, workfiles saved in EViews 7 may be read by previous versions of EViews. Objects such as valmaps or alpha series that are not supported by early versions will, however, be dropped when read by those versions of EViews. You should take great caution when saving workfiles using older versions of EViews as you will lose any deleted objects (see “[Workfile Compatibility](#)” in Getting Started).

Note also that only the first page of a multi-page workfile will be read by versions prior to EViews 5; all other pages will be dropped. You may save individual pages of a multi-page workfile to separate workfiles so that they may be read by versions that do not support multiple pages; see [“Saving a Workfile Page” on page 65](#)

Loading a Workfile

You can use File/Open/EViews Workfile... to load into memory a previously saved workfile. You may also drag-and-drop the workfile onto your EViews workspace. You will typically save a workfile containing all of your data and results at the end of the day, and later load the workfile to pick up where you left off.

When you select File/Open/EViews Workfile... you will see a standard Windows file dialog. Simply navigate to the appropriate directory and double click on the name of the workfile to load it into RAM. The workfile window will open and all of the objects in the workfile will immediately be available.

For convenience, EViews keeps a record of the most recently used files at the bottom of the File menu. Select an entry and it will be opened in EViews.

The current version of EViews can read workfiles from all previous versions of EViews. Due to changes in the program, however, some objects may be modified when they are read into the current version.

Multi-page Workfiles

While a great many of your workfiles will probably contain a single page, you may find it useful to organize your data into multiple workfile pages. Multi-page workfiles are primarily designed for situations in which you must work with multiple datasets.

For example, you may have both quarterly and monthly data that you wish to analyze. The multi-page workfile allows you to hold both sets of data in their native frequency, and to perform automatic frequency conversion as necessary. Organizing your data in this fashion allows you to switch instantly between performing your analysis at the monthly and the quarterly level.


Likewise, you may have a panel dataset on individuals that you wish to use along with a cross-sectional dataset on state level variables. By creating a workfile with a separate page for the individual level data, and a separate page for the state level data, you can move back and forth between the individual and the state level analyses, or you can link data between the two to perform dynamic match merging.

Creating a Workfile Page

There are several ways to create a new workfile page.

Creating a Page by Describing its Structure

First, you may describe the structure of the workfile page. This method follows the approach outlined in [“Creating a Workfile by Describing its Structure” on page 35](#). Simply call up the new page menu by clicking on the tab labeled New Page and selecting Specify by Frequency/Range... , and EViews will display the familiar Workfile Create dialog. Simply describe the structure of your workfile page as you would for a new workfile, and enter OK.



EViews will create a new workfile page with the specified structure and the new page will be given a default name and designated as the active workfile page. The default name will be constructed from the next available name for the given workfile structure. For example, if you create a regular frequency annual page, EViews will attempt to name the page ANNUAL, ANNUAL1, and so forth. The active page is noted visually by the tab selection at the bottom of the workfile window. With the exception of a few page-specific operations, you may generally treat the active page as if it were a standard workfile.

Creating a Workfile Page Using Identifiers

The second approach creates a new page using the unique values of one or more identifier series. Click on the New Page tab and select Specify by Identifier Series... EViews will open a dialog for creating a new page using one or more identifier series.

At the top of the dialog is a combo box labeled Method that you may use to select between the various ways of using identifiers to specify a new page.

You may choose between creating the page using:

- (1) the unique ID values from the current workfile page, (2) the union of unique ID values from multiple pages, (3) the intersection of unique ID values from multiple pages, (4) and (5) the cross of the unique values of two ID series, (6) the cross of a single ID series with a date range.

As you change the selected method, the dialog will change to provide you with different options for specifying identifiers.

Unique values of ID series from one page

The easiest way to create a new page from identifiers is to use the unique values in one or more series in the current workfile page.

If you select Unique values of ID series from one page in the Method combo, EViews will prompt you for one or more identifier series which you should enter in the Cross-section ID series and Date series edit fields.

EViews will take the set of series and will identify the unique values in the specified Sample. Note that when multiple identifiers are specified, the unique values are defined over the values in the set of ID series, not over each individual series.

The new page will contain identifier series containing the unique values, and EViews will structure the workfile using this information. If Date ID series were provided in the original dialog, EViews will restructure the result as a dated workfile page.


Suppose, for example, that we begin with a workfile page UNDATED that contains 471 observations on 157 firms observed for 3 years. There is a series FCODE identifying the firm, and a series YEAR representing the year.

We first wish to create a new workfile page containing 157 observations representing the unique values of FCODE. Simply enter FCODE in the Cross-section ID series, set the sample to “@ALL”, name the new page “UNDATED1”, and click on OK.

Value	Count	Percent	Cumulative Count	Cumulative Percent
410032	3	0.64	3	0.64
410440	3	0.64	6	1.27
410495	3	0.64	9	1.91
410500	3	0.64	12	2.55
410501	3	0.64	15	3.18
410509	3	0.64	18	3.82
410513	3	0.64	21	4.46
410517	3	0.64	24	5.10
410518	3	0.64	27	5.73
410521	3	0.64	30	6.37

EViews will create a new structured (undated - with identifier series) workfile page UNDATED1 containing 157 observations. The new page will contain a series FCODE with the 157 unique values found in the original series FCODE, and the workfile will be structured using this series.

Similarly, we may choose to create a new page using the series YEAR, which identifies the year that the firm was observed. There are three distinct values for YEAR in the original workfile page ("1987," "1988," "1989"). Click on the New Page tab and select Specify by Identifier Series... from the menu, and Unique values of ID series from one page in the Method combo. Enter "YEAR" in the Date ID series field, and click on OK to create a new annual page with range 1987–1989. Note that EViews will structure the result as a dated workfile page.



Union of common ID series from multiple pages

In some cases, you may wish to create your new page using unique ID values taken from more than one workfile page.

If you select Union of common ID series from multiple pages, EViews will find, for each source page, a set of unique ID values, and will create the new workfile page using the union of these values. Simply enter the list of identifiers in the Cross-section ID series and Date series and edit fields, and a list of pages in which the common identifiers may be found. When you click on OK, EViews will first make certain that each of the identifier series is found in each page, then will create the new workfile page using the union of the observed ID values.

We may extend our earlier example where there are three distinct values for YEAR in the original page ("1987," "1988," "1989"). To make things more interesting, suppose there is a second page in the workfile, ANNUAL, containing annual data for the years 1985–1988 and that this page also contains a series YEAR with those values ("1985," "1986," "1987," "1988").

Since we want to exploit the fact that YEAR contains date information, we create a page using the union of IDs by selecting Union of common ID series from multiple pages , entering YEAR in the Date series field, and then entering “UNDATED” and “ANNUAL” in the page field. When you click on OK, EViews will create a 5 observation, regular annual frequency workfile page for 1987–1989, formed by taking the union of the unique values in the YEAR series in the UNDATED panel page, and the YEAR series in the ANNUAL page.

Intersection of common ID series from multiple pages

In other cases, you may wish to create your new page using common unique ID values taken from more than one workfile page. If you select Intersection of common ID series from multiple pages , EViews will take the specified set of series and will identify the unique values in the specified Sample. The intersection of these sets of unique values across the pages will then be used to create a new workfile page.

In our extended YEAR example, we have two pages: UNDATED, with 471 observations and 3 distinct YEAR values (“1987,” “1988,” and “1989”); and the ANNUAL workfile page containing annual data for four years from 1985–1988, with corresponding values for the series YEAR.

The screenshot shows the 'Workfile Page Create by ID' dialog box. It has two main sections: 'Identifier series' and 'Sample'. In the 'Identifier series' section, the 'Method' dropdown is set to 'Intersection of common ID series from multiple pages'. Below it, 'Cross ID series' is a text field containing 'year'. 'Date ID series' is an empty text field. 'Multiple pages' is a text field containing 'undated annual'. In the 'Sample' section, there is a text field containing '@all'. To the right of the 'Sample' section is a 'Names (optional)' section with 'WF' set to 'JTRAIN' and 'Page' as an empty text field. At the bottom are 'OK' and 'Cancel' buttons.

Suppose that we enter YEAR in the Date ID field, and tell EViews to examine the intersection of values in the Multiple pages UNDATED and ANNUAL. EViews will create a new workfile page containing the intersection of the unique values of the YEAR series across pages (“1987,” “1988”). Since YEAR was specified as a date ID, the page will be structured as a dated annual page.

Cross of two ID series

There are two choices if you wish to create a page by taking the cross of the unique values from two ID series: Cross of two non-date ID series creates an undated panel page using the unique values of the two identifiers, while Cross of one date and one non-date ID series uses the additional specification of a date ID to allow for the structuring of a dated panel page.

Suppose for example, that you wish to create a page by crossing the 187 unique FCODE values in the UNDATED page with the 4 unique YEAR values in the ANNUAL page (“1985,”

“1986,” “1987,” “1988”). Since the YEAR values may be used to create a dated panel, we select Cross of one date and one non-date ID from our Method combo.

Since we wish to use YEAR to date structure our result, we enter “FCODE” and “UNDATED” in the Cross ID series and Cross page fields, and we enter “YEAR” and “ANNUAL” in the Date ID series and Date page fields.

When you click on OK, EVIEWS will create a new page by crossing the unique values of the two ID series.

The resulting workfile will be an annual dated panel for 1985–1988, with FCODE as the cross-section identifier.

It is worth noting that had we had entered the same information in the Cross of two non-date ID dialog, the result would be an undated panel with two identifier series.

Cross of ID Series with a date range

In our example of crossing a date ID series with a non-date ID, we were fortunate to have an annual page to use in constructing the date ID. In some cases, the dated page may not be immediately available, and will have to be created prior to performing the crossing operation.

In cases where the page is not available, but where we wish to cross our non-date ID series with a regular frequency range, we may skip the intermediate page creation by selecting the Cross of ID series with a date range method.

Here, instead of specifying a date ID series and page, we need only specify a page frequency, start, and end dates. In this example, the resulting annual panel page is identical to the page specified by crossing FCODE with the YEAR series from the ANNUAL page.


The screenshot shows a dialog box titled "Workfile Page Create by ID". It contains several input fields and buttons. Under the "Identifier series" section, the "Method" is set to "Cross of ID series with a date range", "Freq" is "Annual", "ID series" is "focde", "ID page" is "undated", "Start date" is "1985", and "End date" is "1988". Under the "Sample" section, the text "@all" is entered. Under the "Names (optional)" section, "WF" is "JTRAIN" and "Page" is empty. At the bottom are "OK" and "Cancel" buttons.

While specifying a frequency and range is more convenient than specifying a date ID and page, this method is obviously more restrictive since it does not allow for irregular dated data. In these latter cases, you must explicitly specify your date ID series and page.

Creating a Page by Copying from the Current Page

You may also create a new workfile page by copying data from the current page. Click on New Page or click on Proc in the main workfile menu, and select Copy/Extract from Current Page and either By Link to New Page... or By Value to New Page or Workfile... . EViews will open a dialog prompting you to specify the objects and data that you wish to copy to a new page. See ["Copying from a Workfile" on page 244](#) for a complete discussion.


Alternately, you may simply drag-and-drop a group of selected series from the current workfile page onto the New Page tab on the bottom of the workfile window.



Creating a Page by Loading a Workfile or Data Source

The next method for creating a new page is to load an existing workfile or data source. Call up the new page menu by clicking on New Page and selecting Load Workfile Page... or by selecting Proc/Load Workfile Page... from the main workfile menu. EViews will present you with the File Open dialog, prompting you to select your file.

More directly, you may drag an existing workfile, workfile page, or foreign data file directly onto the New Page tab on the bottom of your workfile window. You can even copy a page from one workfile to another by dragging the page tab from the source workfile and dropping onto the New Page in the other workfile.



If you select an existing EViews workfile, EViews will add a page corresponding to each page in the source workfile. If you load a workfile with a single page named QUARTERLY, EViews will attempt to load the entire workfile in the new page. If your workfile contains multiple pages, each page of the workfile will be loaded into a new and separate page. The active page will be the newest page.

If you select a foreign data source as described in ["Creating a Workfile by Reading from a Foreign Data Source" on page 39](#), EViews will load the data into a single newly created page in the workfile. This method is exactly the same as that used when creating a new workfile except that the results are placed in a new workfile page.

Creating a Page by Pasting from the Clipboard

You may create a new workfile page by pasting the contents of the Windows Clipboard. This method is particularly useful for copying and pasting data from another application such as Microsoft Word, Excel, or your favorite web browser.

Simply copy the data you wish to use in creating your page, then click on New Page and select Paste from Clipboard as Page. EViews will first analyze the contents of the clipboard. EViews then creates a page to hold the data and then will read the data into series in the page.


Note that while EViews can correctly analyze a wide range of data representations, the results may not be as expected in more complex settings.

Working With Workfile Pages

While workfile pages may generally be thought of simply as workfiles, there are certain operations that are page-specific or fundamental to multi-page workfiles.

Setting the Active Workfile Page

To select the active workfile page, simply click on the visible tab for the desired page in the workfile window. The active page is noted visually by the tab selection at the bottom of the workfile window.



If the desired page is not visible, you may click on the small right and left arrows in the bottom left-hand corner of the workfile window to scroll the page tab display until the desired page is visible, then click on the tab.

You should note that it is possible to hide existing page tabs. If a page appears to be missing, for example if New Page is the only visible tab, the remaining tabs are probably hidden. You should click on the left arrow located in the bottom right of the workfile window until your page tabs are visible.

Renaming a Workfile Page

EViews will give your workfile pages a default name corresponding to the workfile structure. You may wish to rename these pages to something more informative. Simply click on the tab for the page you wish to rename and right-mouse-button click to open the workfile page menu. Select Rename Workfile Page... from the menu and enter the page name.

Alternatively, you may select Proc/Rename Current Page... from the main workfile menu to call up the dialog.

Workfile page names must satisfy the same naming restrictions as EViews objects. Notably, the page names must not contain spaces or other delimiters.

Deleting a Workfile Page

To delete a workfile page, right mouse click on the page tab and select Delete Workfile Page, or with the page active, click on the Proc menu and select Delete Current Page.

Saving a Workfile Page

If you wish to save the active workfile page as an individual workfile, click on the page tab, right mouse click to open the workfile page menu and select Save Workfile Page... to open the SaveAs dialog. Alternatively, you may select Proc/Save Current Page... from the main workfile menu to access the dialog.

Saving a page as an individual workfile is quite useful when you wish to load a single page into several workfiles, or if you wish to use the page in a previous version of EViews. Once saved on disk, it is the same as any other single-page EViews workfile.

Reordering Workfile Pages

You may change the order of your workfile pages by dragging the tab for a page at the bottom of the workfile window, and dropping it on top of the tab for the page it should follow. Note the difference in behavior between dragging a tab within a workfile and dragging across workfiles. The first reorders the pages, while the second copies the contents of one page into another.

Addendum: File Dialog Features

There are additional features in the file open and save dialogs which you may find useful.

Set Default Directory


All EViews file dialogs begin with a display of the contents of the default directory. You can always identify the default directory from the listing on the EViews status line. The default directory is set initially to be the directory containing the EViews program, but it can be changed at any time.

You can change the default directory by using the File/Open... or the File/Save As... menu items, navigating to the new directory, and checking the Update Default Directory box in the dialog. If you then open or save a workfile, the default directory will change to the one you have selected. The default directory may also be set from the Options/File locations... dialog. See ["File Locations" on page 634](#) of User's Guide I

An alternative method for changing the default EViews directory is to use the `cd` command. Simply enter “CD” followed by the directory name in the command window (see [cd](#) for details).

File Operations

Since EViews uses a variant of the Windows common file dialog for all open and save operations, you may use the dialog to perform routine file operations such as renaming, copying, moving, and deleting files.



For example, to delete a file, click once on the file name to select the file, then right click once to call up the menu, and select **Delete**. Likewise, you may select a file, right-mouse click, and perform various file operations such as **Copy** or **Rename**.

Chapter 4. Object Basics

At the heart of the EViews design is the concept of an object. In brief, objects are collections of related information and operations that are bundled together into an easy-to-use unit. Virtually all of your work in EViews will involve using and manipulating various objects.

EViews holds all of its objects in object containers. You can think of object containers as filing cabinets or organizers for the various objects with which you are working. The most important object container in EViews is the workfile, which is described in [Chapter 3. "Workfile Basics," beginning on page 33.](#)

The remainder of this chapter describes basic techniques for working with objects in a workfile. While you may at first find the idea of objects to be a bit foreign, the basic concepts are easy to master and will form the foundation for your work in EViews. But don't feel that you have to understand all of the concepts the first time through. If you wish, you can begin working with EViews immediately, developing an intuitive understanding of objects and workfiles as you go.

Subsequent chapters will provide a more detailed description of working with the various types of objects and other types of object containers.

Note that the current discussion focuses on interactive methods for working with objects. If you feel more comfortable using commands, [Chapter 1. "Object and Command Basics," beginning on page 3](#) of the Command and Programming Reference offers command equivalents for the operations described in this chapter.

What is an Object?

Information in EViews is stored in objects. Each object consists of a collection of information related to a particular area of analysis. For example, a series object is a collection of information related to a set of observations on a particular variable. An equation object is a collection of information related to the relationship between a collection of variables.

Note that an object need not contain only one type of information. For example, an estimated equation object contains not only the coefficients obtained from estimation of the equation, but also a description of the specification, the variance-covariance matrix of the coefficient estimates, and a variety of statistics associated with the estimates.

Associated with each type of object is a set of views and procedures which can be used with the information contained in the object. This association of views and procedures with the type of data contained in the object is what we term the object oriented design of EViews.

The object oriented design simplifies your work in EViews by organizing information as you work. For example, since an equation object contains all of the information relevant to an

estimated relationship, you can move freely between a variety of equation specifications simply by working with different equation objects. You can examine results, perform hypothesis and specification tests, or generate forecasts at any time. Managing your work is simplified since only a single object is used to work with an entire collection of data and results.

This brief discussion provides only the barest introduction to the use of objects. The remainder of this section will provide a more general description of EViews objects. Subsequent chapters will discuss series, equations, and other object types in considerable detail.

Object Data

Each object contains various types of information. For example, series, matrix, vector, and scalar objects, all contain mostly numeric information. In contrast, equations and systems contain complete information about the specification of the equation or system, and the estimation results, as well as references to the underlying data used to construct the estimates. Graphs and tables contain numeric, text, and formatting information.

Since objects contain various kinds of data, you will want to work with different objects in different ways. For example, you might wish to compute summary statistics for the observations in a series, or you may want to perform forecasts based upon the results of an equation. EViews understands these differences and provides you with custom tools, called views and procedures, for working with an object's data.

Object Views

There is more than one way to examine the data in an object. Views are tabular and graphical windows that provide various ways of looking at the data in an object.

For example, a series object has a spreadsheet view, which shows the raw data, a line graph view, a bar graph view, a histogram-and-statistics view, and a correlogram view. Other views of a series include distributional plots, QQ-plots, and kernel density plots. Series views also allow you to compute simple hypothesis tests and statistics for various subgroups of your sample.

An equation object has a representation view showing the equation specification, an output view containing estimation results, an actual-fitted-residual view containing plots of fitted values and residuals, a covariance view containing the estimated coefficient covariance matrix, and various views for specification and parameter tests.

Views of an object are displayed in the object's window. Only one window can be opened for each object and each window displays only a single view of the object at a time. You can change views of an object using the View menu located in the object window's toolbar or the EViews main menu.

Perhaps the most important thing to remember about views is that views normally do not change data outside the object. Indeed, in most cases, changing views only changes the display format for the data, and not the data in the object itself.

Object Procedures

Most EViews objects also have procedures or procs. Like views, procedures often display tables or graphs in the object's window. Unlike views, however, procedures alter data, either in the object itself or in another object.

Many procedures create new objects. For example, a series object contains procedures for smoothing or seasonally adjusting time series data and creating a new series containing the smoothed or adjusted data. Equation objects contain procedures for generating new series containing the residuals, fitted values, or forecasts from the estimated equation.

You select procedures from the Proc menu on the object's toolbar or from the EViews main menu.

Object Types

The most common objects in EViews are series and equation objects. There are, however, a number of different types of objects, each of which serves a unique function. Most objects are represented by a unique icon which is displayed in the object container (workfile or database) window. The basic object icons are given by:

Alpha	Matrix	Spool	Text
 Coef	 Model	 Sspace	 Valmap
Equation	Pool	String	Var
 Factor	 Rowvector	 Svector	 Vector
Graph	Sample	Sym	
 Group	 Scalar	 System	
Logl	Series	Table	

Despite the fact that they are also objects, object containers do not have icons since they cannot be placed in other object containers—thus, workfiles and databases do not have icons since they cannot be placed in other workfiles or databases.

Note also that there are special icons that correspond to special versions of the objects:

Auto-updating Series



Group data and definitions (in databases)

Undefined Link

If you set a series object to be auto-updating (see [“Auto-Updating Series” on page 155](#)), EViews will use the special icon to indicate that the series depends upon a formula. In contrast, an auto-updating alpha series (which we imagine to be less common) uses the original alpha icon, with an orange color to indicate the presence of a formula.

When group data are stored in databases, you will be given the option of storing the group definition (list of series names) alone, or both the group definition and the series contained in the group (see [“Store, Fetch, and Copy of Group Objects” on page 277](#)). If the latter are stored, the standard group icon will be modified, with the “+” indicating the additional presence of the series data.


Lastly, a link object (see [“Series Links” on page 183](#)), is always in one of three states, depending upon the definition contained in the link. If the link is to a numeric source series, the link object is displayed using a series icon, since it may be used as though it were an ordinary series, with a distinctive pink color used to indicate that the object depends on linked data. If the link is to an alpha source series, the link will show up as an alpha series icon, again in pink. If, however, the link object is unable to locate the source series, EViews will display the “?” icon indicating that the series type is unknown.

Basic Object Operations

Creating Objects

To create an object, you must first make certain that you have an open workfile container and that its window is active. Next, select Object/New Object... from the main menu. Until you have created or loaded a workfile, this selection is unavailable. After you click on the Object/New Object... menu entry, you will see the New Object dialog box.

You can click on the type of object you want, optionally provide a name for the object, and then click on OK. For some object types, a second dialog box will open prompting you to describe your object in more detail. For most objects, however, the object window will open immediately.



For example, if you select Equation, you will see a dialog box prompting you for additional information. Alternatively, if you click on Series and then select OK, you will see an object window (series window) displaying the sp readsheet view of an UNTITLED series.

We will discuss object windows in greater detail in [“The Object Window” on page 73](#).


Objects can also be created by applying procedures to other objects or by freezing an object view (see [“Freezing Objects” on page 78](#)).

Selecting Objects

Creating a new object will not always be necessary. Instead, you may want to

work with an existing object. One of the fundamental operations in EViews is selecting one or more objects from the workfile directory.

The easiest way to select objects is to point-and-click, using the standard Windows conventions for selecting contiguous or multiple items if necessary. Keep in mind that if you are



selecting a large number of items, you may find it useful to use the display filter before beginning to select items.

In addition, the **View** button in the workfile toolbar provides convenient selection shortcuts:

- **Select All** selects all of the objects in the workfile with the exception of the C coefficient vector and the RESID series.
- **Deselect All** eliminates any existing selections.

Note that all of the selected objects will be highlighted.

Opening Objects

Once you have selected your object or objects, you will want to open your selection, or create a new object containing the selected objects. You can do so by double clicking anywhere in the highlighted area.

If you double click on a single selected object, you will open an object window.

If you select multiple graphs or series and double click, a pop-up menu appears, giving you the option of creating and opening new objects (group, equation, VAR, graph) or displaying each of the selected objects in its own window.

(You may also select **View/Open Selected** or right-mouse click and select **Open** to access menus for opening the multiple objects.)

Note that if you select multiple graphs and double click or select **View/Open Selected/One Window**, all of the graphs will be merged into a single graph and displayed in a single window.

Other multiple item selections are not valid, and will either issue an error or will simply not respond when you double click.

When you open an object, EViews will display the current view. In general, the current view of an object is the view that was displayed the last time the object was opened (if an object has never been opened, EViews will use a default view). The exception to this general rule is for those views that require significant computational time. In this latter case, the current view will revert to the default.

Showing Objects

An alternative method of selecting and opening objects is to “show” the item. Click on the **Show** button on the toolbar, or select **Quick/Show...** from the menu and type in the object name or names.

Showing an object works exactly as if you first selected the object or objects, and then opened your selection. If you enter a single object name in the dialog box, EViews will open

the object as if you double clicked on the object name. If you enter multiple names, EViews will always open a single window to display results, creating a new object if necessary.

The Show button can also be used to display functions of series, also known as auto-series. All of the rules for auto-series that are outlined in ["Database Auto-Series" on page 279](#) will apply.


The Object Window

We have been using the term object window somewhat loosely in the previous discussion of the process of creating and opening objects. Object windows are the windows that are displayed when you open an object or object container. An object's window will contain either a view of the object, or the results of an object procedure.

One of the more important features of EViews is that you can display object windows for a number of items at the same time. Managing these object windows is similar to the task of managing pieces of paper on your desk.

Components of the Object Window

Let's look again at a typical object window:



Here, we see the equation window for OLS_RESULTS. First, notice that this is a standard window which can be closed, resized, minimized, maximized, and scrolled both vertically and horizontally. As in other Windows applications, you can make an object window active by clicking once on the titlebar, or anywhere in its window. Making an object window

active is equivalent to saying that you want to work with that object. Active windows may be identified by the darkened titlebar.

Second, note that the titlebar of the object window identifies the object type, name, and object container (in this case, the BONDS workfile or the OLS_RESULTS equation). If the object is itself an object container, the container information is replaced by directory information.

Lastly, at the top of the window there is a toolbar containing a number of buttons that provide easy access to frequently used menu items. These toolbars will vary across objects—the series object will have a different toolbar from an equation or a group or a VAR object.

There are several buttons that are found on all object toolbars:

- The View button lets you change the view that is displayed in the object window. The available choices will differ, depending upon the object type.
- The Proc button provides access to a menu of procedures that are available for the object.
- The Object button lets you manage your objects. You can store the object on disk, name, delete, copy, or print the object.
- The Print button lets you print the current view of the object (the window contents).
- The Name button allows you to name or rename the object.
- The Freeze button creates a new object graph, table, or text object out of the current view.


Menus and the Object Toolbar

As we have seen, the toolbar provides a shortcut to frequently accessed menu commands. There are a couple of subtle, but important, points associated with this relationship that deserve special emphasis:

- Since the toolbar simply provides a shortcut to menu items, you can always find the toolbar commands in the menus.
- This fact turns out to be quite useful if your window is not large enough to display all of the buttons on the toolbar. You can either enlarge the window so that all of the buttons are displayed, or you can access the command directly from the menu.
- The toolbar and menu both change with the object type. In particular, the contents of the View menu and the Proc menu will always change to reflect the type of object (series, equation, group, etc.) that is active.

The toolbars and menus differ across objects. For example, the View and Proc drop-down menus differ for every object type. When the active window is displaying a series window, the menus provide access to series views and series procedures. Alternatively, when the

active window is a group window, clicking on View or Proc in the main menu provides access to the different set of items associated with group objects.



The figure above illustrates the relationship between the View toolbar button and the View menu when the series window is the active window. In the left side of the illustration, we see a portion of the EViews main window, as it appears, after you click on View in the main menu (note that the RC series window is the active window). On the right, we see a depiction of the series window as it appears after you click on the View button in the series toolbar. Since the two operations are identical, the two drop-down menus are identical.

In contrast to the View and Proc menus, the Object menu does not, in general, vary across objects. An exception occurs, however, when an object container window (i.e., a workfile or database window) is active. In this case, clicking on Object in the toolbar, or selecting Object from the menu provides access to menu items for manipulating the objects in the container.


Working with Objects

Naming Objects

Objects may be named or unnamed. When you give an object a name, the name will appear in the directory of the workfile, and the object will be saved as part of the workfile when the workfile is saved.

You must name an object if you wish to keep its results. If you do not name an object, it will be called “UNTITLED”. Unnamed objects are not saved with the workfile, so they are deleted when the workfile is closed and removed from memory.

To rename an object, first open the object window by double clicking on its icon, or by clicking on Show on the workfile toolbar, and entering the object name. Next, click on the Name button on the object window, and enter the name (up to 24 characters), and optionally, a display name to be used when labeling the object in tables and graphs. If no display name is provided, EViews will use the object name.



You can also rename an object from the workfile window by selecting Object/Rename Selected... and then specifying the new object name. This method saves you from first having to open the object.

The following names are reserved and cannot be used as object names: “ABS”, “ACOS”, “AND”, “AR”, “ASIN”, “C”, “CON”, “CNORM”, “COEF”, “COS”, “D”, “DLOG”, “DNORM”, “ELSE”, “ENDIF”, “EXP”, “LOG”, “LOGIT”, “LPT1”, “LPT2”, “MA”, “NA”, “NOT”, “NRND”, “OR”, “PDL”, “RESID”, “RND”, “S AR”, “SIN”, “SMA”, “SQR”, and “THEN”.

EViews accepts both capital and lower case letters in the names you give to your series and other objects, but does not distinguish between names based on case. Its messages to you will follow normal capitalization rules. For example, “SALES”, “sales”, and “sAles” are all the same object in EViews. For the sake of uniformity, we have written all examples of input using names in lower case, but you should feel free to use capital letters instead.

Despite the fact that names are not case sensitive, when you enter text information in an object, such as a plot legend or label information, your capitalization will be preserved.


By default, EViews allows only one untitled object of a given type (one series, one equation, etc.). If you create a new untitled object of an existing type, you will be prompted to name the original object, and if you do not provide one, EViews will replace the original untitled object with the new object. The original object will not be saved. If you prefer, you can instruct EViews to retain all untitled objects during a session but you must still name the ones you want to save with the workfile. See [“Window Behavior” on page 622](#).

Labeling Objects

In addition to the display name described above, EViews objects have label fields where you can provide extended annotation and commentary. To view these fields, select View/Label from the object window:

This is the label view of an unmodified object. By default, every time you modify the object, EViews automatically appends the modification in the History field at the bottom of the label view.

You can edit any of the fields, except the Last Update field. Simply click in the field cell that you want to edit. All fields, except the Remarks and History fields, contain only one line. The Remarks and History fields can contain multiple lines. Press ENTER to add a new line to these two fields.



These annotated fields are most useful when you want to search for an object stored in an EViews database. Any text that is in the fields is searchable in an EViews database; see ["Querying the Database" on page 283](#) for further discussion.

Copying Objects

There are two distinct methods of duplicating the information in an object: copying and freezing.

If you select Object/Copy from the menu, EViews will create a new untitled object containing an exact copy of the original object. By exact copy, we mean that the new object duplicates all the features of the original (except for the name). It contains all of the views and procedures of the original object and can be used in future analyses just like the original object.

You may also copy an object from the workfile window. Simply highlight the object and click on Object/Copy Selected... or right mouse click and select Object/Copy..., then specify the destination name for the object.

We mention here that Copy is a very general and powerful operation with many additional features and uses. For example, you can copy objects across both workfiles and databases using wildcards and patterns. See ["Copying Objects" on page 275](#) for details on these additional features.

Copy-and-Pasting Objects

The standard EViews copy command makes a copy of the object in the same workfile. When two workfiles are in memory at the same time, you may copy objects between them using copy-and-paste.

Highlight the objects you wish to copy in the source workfile. Then select **Edit/Copy** from the main menu.

Select the destination workfile by clicking on its titlebar. Then select either **Edit/Paste** or **Edit/Paste Special...** from the main menu or simply **Paste** or **Paste Special...** following a right mouse click.

Edit/Paste will perform the default paste operation. For most objects, this involves simply copying over the entire object and its contents. In other cases, the default paste operation is more involved. For example, when copy-and-pasting series between source and destination workfiles that are of different frequency, frequency conversion will be performed, if possible, using the default series settings (see [“Frequency Conversion” on page 116](#) for additional details). EViews will place named copies of all of the highlighted objects in the destination workfile, prompting you to replace existing objects with the same name.

If you elect to **Paste Special...**, EViews will open a dialog prompting you for any relevant paste options. For example, when pasting series, you may use the dialog to override the default series settings for frequency conversion, to perform special match merging by creating links ([“Series Links” on page 183](#)). In other settings, **Paste Special...** will simply prompt you to rename the objects in the destination workfile.

Freezing Objects

The second method of copying information from an object is to freeze a view of the object. If you click **Object/Freeze Output** or press the **Freeze** button on the object's toolbar, a table or graph object is created that duplicates the current view of the original object.

Before you press **Freeze**, you are looking at a view of an object in the object window. Freezing the view makes a copy of the view and turns it into an independent object that will remain even if you delete the original object. A frozen view does not necessarily show what is currently in the original object, but rather shows a snapshot of the object at the moment you pushed the button. For example, if you freeze a spreadsheet view of a series, you will see a view of a new table object; if you freeze a graphical view of a series, you will see a view of a new graph object.

Frozen graphs are a bit more sophisticated than other frozen objects. While frozen tables do not change when the workfile sample or data change, you may select if and when a frozen graph should update as the sample or its underlying data change. You may treat a frozen graph as a snapshot of the data at the time it was frozen, or update it at will. For a complete discussion of graph updating, see [“Freezing a Graph View” on page 558](#).

The primary feature of freezing an object is that the tables and graphs created by freezing may be edited for presentations or reports. Many options for customization are only available for frozen objects or may be deleted when the object is refreshed, so you should be sure to freeze an object before customizing it.

Deleting Objects

To delete an object or objects from your workfile, select the object or objects in the workfile directory. When you have selected everything you want to delete, click **Delete** or **Object/Delete Selected** on the workfile toolbar. EViews will prompt you to make certain that you wish to delete the objects.


Printing Objects

To print the currently displayed view of an object, push the **Print** button on the object window toolbar. You can also choose **File/Print** or **Object/Print** on the main EViews menu bar.

EViews will open a **Print** dialog containing the default print settings for the type of output you are printing. Here, we see the dialog for printing text information; the dialog for printing from a graph will differ slightly.

The default settings for printer type, output redirection, orientation, and text size may be set in the **Print Setup...** dialog (see [“Print Setup” on page 637](#)) or they may be overridden in the current print dialog.

For example, the print commands normally send a view or procedure output to the current Windows printer. You may specify instead that the output should be saved in the workfile as a table or graph, spooled to an RTF or ASCII text file on disk, or sent to a spool object. Simply click on **Redirect**, then select the output type from the list.



Storing Objects

EViews provides three ways to save your data on disk. You have already seen how to save entire workfiles, where all of the objects in the workfile are saved together in a single file with the .WF1 extension. You may also store individual objects in their own data bank files. They may then be fetched into other workfiles.

We will defer a full discussion of storing objects to data banks and databases until [Chapter 10. “EViews Databases,” on page 267](#). For now, note that when you are working with an object, you can place it in a data bank or database file by clicking on the **Object/Store to DB...** button on the object's toolbar or menu. EViews will prompt you for additional information.

You can store several objects, by selecting them in the workfile window and then pressing the Object/Store selected to DB... button on the workfile toolbar or menu.

Fetching Objects

You can fetch previously stored items from a data bank or database. One of the common methods of working with data is to create a workfile and then fetch previously stored data into the workfile as needed.

To fetch objects into a workfile, select Object/Fetch from DB... from the workfile menu or toolbar. You will see a dialog box prompting you for additional information for the fetch: objects to be fetched, directory and database location, as applicable.

See [“Fetching Objects from the Database” on page 273](#) for details on the advanced features of the fetch procedure.

Updating Objects

Updating works like fetching objects, but requires that the objects be present in the workfile. To update objects in the workfile, select them from the workfile window, and click on Object/Update from DB... from the workfile menu or toolbar. The Fetch dialog will open, but with the objects to be fetched already filled in. Simply specify the directory and database location and click OK.

The selected objects will be replaced by their counterparts in the data bank or database.

See [“Fetching Objects from the Database” on page 273](#) and [“Database Auto-Series” on page 279](#) for additional details.

Copy-and-Paste Object Information

You can copy the list of object information displayed in a workfile or database window to the Windows clipboard and paste the list to other program files such as word processing files or spreadsheet files. Simply highlight the objects in the workfile directory window, select Edit/Copy (or click anywhere in the highlighted area, with the right mouse button, and select Copy). Then move to the application (word processor or spreadsheet) where you want to paste the list, and select Edit/Paste.

If only object names and icons are displayed in the window, EViews will copy a single line containing the highlighted names to the clipboard, with each name separated by a space. If the window contains additional information, either because View/Display Comments (Label+/-) has been chosen in a workfile window or a query has been carried out in a database window, each name will be placed in a separate line along with the additional information.

Note that if you copy-and-paste the list of objects into another EViews workfile, the objects themselves will be copied.

Chapter 5. Basic Data Handling

The process of entering, reading, editing, manipulating, and generating data forms the foundation of most data analyses. Accordingly, much of your time in EViews will probably be spent working with data. EViews provides you with a sophisticated set of data manipulation tools that make these tasks as simple and straightforward as possible.

This chapter describes the fundamentals of working with data in EViews. There are three cornerstones of data handling in EViews: the two most common data objects, series and groups, and the use of samples which define the set of observations in the workfile that we wish to use in analysis.

We begin our discussion of data handling with a brief description of series, groups, and samples, and then discuss the use of these objects in basic input, output, and editing of data. Lastly, we describe the basics of frequency conversion.

In [Chapter 6. “Working with Data,” on page 131](#), we discuss the basics of EViews’ powerful language for generating and manipulating the data held in series and groups. Subsequent chapters describe additional techniques and objects for working with data.

Data Objects

The actual numeric values that make up your data will generally be held in one or more of EViews’ data objects (series, groups, matrices, vectors, and scalars). For most users, series and groups will by far be the most important objects, so they will be the primary focus of our discussion. Matrices, vectors, and scalars are discussed at greater length in [Chapter 8. “Matrix Language,” on page 159](#) in the Command and Programming Reference

The following discussion is intended to provide only a brief introduction to the basics of series and groups. Our goal is to describe the fundamentals of data handling in EViews. An in-depth discussion of series and group objects follows in subsequent chapters.

Series

An EViews series contains a set of observations on a numeric variable. Associated with each observation in the series is a date or observation label. For series in regularly dated workfiles, the observations are presumed to be observed regularly over time. For undated data, the observations are not assumed to follow any particular frequency.


Note that the series object may only be used to hold numeric data. If you wish to work with alphanumeric data, you should employ alpha series. See [“Alpha Series” on page 160](#) for discussion.

Creating a series

One method of creating a numeric series is to select **Object/New Object...** from the menu, and then to select **Series**. You may, at this time, provide a name for the series, or you can let the new series be untitled. Click on **OK**.

EViews will open a spreadsheet view of the new series object. All of the observations in the series will be assigned the missing value code "NA". You may then edit or use expressions to assign values for the series.

You may also use the **New Object** dialog to create alpha series. Alpha series are discussed in greater detail in ["Alpha Series" on page 160](#)



A second method of creating a series is to generate the series using mathematical expressions. Click on **Quick/Generate Series...** in the main EViews menu, and enter an expression defining the series. We will discuss this method in depth in the next chapter.

Lastly, you may create the numeric or alpha series by entering `aseries` or `alpha` command in the command window. Entering an expression of the form:

```
series series_name= series_expr
```

creates a series with the name `series_name` and assigns the expression to each observation. Alternately:

```
alpha alpha_name= alpha_expr
```

creates an alpha series object and assigns the `alpha_expr` to each observation.

You may leave out the right-hand side assignment portion of the commands; in this case, the series or alpha will be initialized to missing values (NA and blank strings, respectively).

Changing the Spreadsheet Display

EViews provides you with extensive ability to customize your series spreadsheet display.


Column Widths

To resize the width of a column, simply move your mouse over the column separator until the icon changes, then drag the column to its desired width. The new width will be remembered the next time you open the series and will be used when the series is displayed in a group spreadsheet.


Display Type

The series display type, which is listed in the combo box in the series toolbar, determines how the series spreadsheet window shows your data.

The Default method shows data in either raw (underlying data) form or, if a value map is attached to the series, shows the mapped values. Alternatively, you may use the Raw Data to show only the underlying data. See “Value Maps” on page 169 for a description of the use of value maps.



You may also use the display type setting to show transformations of the data. You may, for example, set the display method to Differenced, in order to have EViews display the first-differences of your data.




Changing the display of your series values does not alter the underlying values in the series, it only modifies the values shown in the spreadsheet (the series header, located above the labels, will also change to indicate the transformation). Note, however, that if you edit the values of your series while displayed in transformed mode, EViews will change the underlying values of the series accordingly. Changing the display and editing data in transformed mode is a convenient method of inputting data that arrive as changes or other transformed values.

Display Formats

You may customize the way that numbers or characters in your series are displayed in the spreadsheet by setting the series display properties. To display the dialog, click on Properties in the series toolbar, or right mouse click and select the Display Format... entry in the menu to display the first tab of the dialog.

EViews will open the Properties dialog with the Display tab selected. You should use this dialog to change the default column width and justification for the series, and to choose from a large list of numeric display formats.

You may, for example, elect to change the display of numbers to show additional digits, to separate thousands with a comma, or to display numbers as fractions. The last four items in the Numeric display combo box provide options for the formatting of date number.



Similarly, you may elect to change the series justification by selecting Auto, Left, Center, or Right. Note that Auto justification will set justification to right for numeric series, and left for alpha series.

You may also use this dialog to change the column width (note that column widths in spreadsheets may also be changed interactively by dragging the column headers).

Once you click on OK, EViews will accept the current settings and change the spreadsheet display to reflect your choices. In addition, these display settings will be used whenever the series spreadsheet is displayed or as the default settings when the series is used in a group spreadsheet display.

Note that when you apply a display format, you may find that a portion of the contents of a cell are not visible, when, for example, the column widths are too small to show the entire cell. Alternately, you may have a numeric cell for which the current display format only shows a portion of the full precision value.


In these cases, it may be useful to examine the actual contents of a table cell. To do so, simply select the table cell. The unformatted contents of the cell will appear in the status line at the bottom of the EViews window.

Narrow versus Wide

The narrow display displays the observations for the series in a single column, with date labels in the margin. The typical series spreadsheet display will use this display format.

The wide display arranges the observations from left to right and top to bottom, with the label for the first observation in the row displayed in the margin. For dated workfiles, EViews will, if possible, arrange the data in a form which matches the frequency of the data. Thus, semi-annual data will be displayed with two observations per row, quarterly data will contain four observations per row, and 5-day daily data will contain five observations in each row.

You can change the display to show the observations in your series in multiple columns by clicking on the Wide +/- button on the spreadsheet view toolbar (you may need to resize the series window to make this button visible). For example, toggling the Wide +/- button switches the display between the wide display (as depicted), and the narrow (single column) display.



This wide display format is useful when you wish to arrange observations for a particular season in each of the columns.

Observation Numbers

If you wish to modify the observation labels to include an observation number, right-click and select **ObsID +/-**. Selecting **ObsID +/-** switches the display between showing a label that includes the observation label and one which does not. This feature is useful if you wish to identify the observation number of a particular observation.

Sample Subset Display

By default, all observations in the workfile are displayed, even those observations not in the current sample. By pressing **Smpl +/-** you can toggle between showing all observations in the workfile, and showing only those observations included in the current sample.

There are two features that you should keep in mind as you toggle between the various display settings:

- If you choose to display only the observations in the current sample, EViews will switch to single column display.
- If you switch to wide display, EViews automatically turns off the display filter so that all observations in the workfile are displayed.

One consequence of this behavior is that if you begin with a narrow display of observations in the current sample, click on **Wide +/-** to switch to wide display, and then press the **Wide +/-** button again, EViews will provide a narrow display of all of the observations in

the workfile. To return to the original narrow display of the current sample, you will need to press the **Smpl +/-** button again.


Editing a series

You can edit individual values of the data in a series.

First, open the spreadsheet view of the series. If the series window display does not show the spreadsheet view, click on the **Sheet** button, or select **View/Spreadsheet**, to change the default view.

Next, make certain that the spreadsheet window is in edit mode. EViews provides you with the option of protecting the data in your series by turning off the ability to edit from the spreadsheet window. You can use the **Edit +/-** button on the toolbar to toggle between edit mode and protected mode.

Here we see a series spreadsheet window in edit mode. Notice the presence of the edit window just beneath the series toolbar containing the value of RC in 1953M01, and the box around the selected cell in the spreadsheet; neither are present in protected mode.



To change the value for an observation, select the cell, type in the value, and press ENTER. For example, to change the value of RC in 1953M01, simply click on the cell containing the value, type the new value in the edit window, and press ENTER.

When editing series values, you should pay particular attention to the series display format, which tells you the units in which your series are displayed. Here, we see that the series values are displayed in **Default** mode so that you are editing the underlying series values (or their value mapped equivalents). Alternately, if the series were displayed in **Differenced** mode, then the edited values correspond to the first differences of the series.


Note that some cells in the spreadsheet are protected. For example, you may not edit the observation labels, or the "Last update" series label. If you select one of the protected cells, EViews will display a message in the edit window telling you that the cell cannot be edited.

When you have finished editing, you should protect yourself from inadvertently changing values of your data by clicking on Edit +/- to turn off edit mode.

Inserting and Deleting Observations in a Series

You can also insert and delete observations in the series. First, click on the cell where you want the new observation to appear. Next, right click and select Insert obs... or Delete obs... from the menu. You will see a dialog asking how many observations you wish to insert or delete at the current position.

If you choose to insert a single observation, EViews will insert a missing value at the appropriate position and push all of the observations down so that the last observation will be lost from the workfile. If you wish to preserve this observation, you will have to expand the workfile before inserting observations. If you choose to delete an observation, all of the remaining observations will move up, so that you will have a missing value at the end of the workfile range.



Sorting a series

The data in a series may be displayed sorted by observation or by the values in the series.

From the spreadsheet view of a series (see [“Editing a series,” on page 87](#)), you can sort by pressing the Sort button on the button bar or by pressing the right-mouse button and selecting Sort from the menu. To sort by series value, the entire series must be selected. To select the series, simply press the column header directly above the series values. Similarly, to sort by observation, the observation column must be selected.

If only a subset of the entire data series or observation series is selected, the Sort menu item will not be available.

Groups

When working with multiple series, you will often want to create a group object to help you manage your data. A group is a list of series names (and potentially, mathematical expressions) that provides simultaneous access to all of the elements in the list.

With a group, you can refer to sets of variables using a single name. Thus, a set of variables may be analyzed, graphed, or printed using the group object, rather than each one of the individual series. Therefore, groups are often used in place of entering a lengthy list of names. Once a group is defined, you can use the group name in many places to refer to all of the series contained in the group.


You will also create groups of series when you wish to analyze or examine multiple series at the same time. For example, groups are used in computing correlation matrices, testing for cointegration and estimating a VAR or VEC, and graphing series against one another.

Creating Groups

There are several ways to create a group. Perhaps the easiest method is to select **Object/New Object...** from the main menu or workfile toolbar, click on **Group**, and if desired, name the object.

You should enter the names of the series to be included in the group, separated by spaces, and then click OK. A group window will open showing a spreadsheet view of the group.

You may have noticed that the dialog allows you to use group names and series expressions. If you include a group name, all of the series in the named group will be included in the new group. For example, suppose that the group GR1 contains the series X, Y, and Z, and you create a new group GR2, which contains GR1 and the series A and B. Then GR2 will contain X, Y, Z, A and B. Bear in mind that only the series contained in GR1, not GR1 itself, are included in GR2; if you later add series to GR1, they will not be added to GR2.



Series expressions will be discussed in greater depth later. For now, it suffices to note that series expressions are mathematical expressions that may involve one or more series (e.g. "7/2" or "3*X*Y/Z"). EViews will automatically evaluate the expressions for each observation and display the results as if they were an ordinary series. Users of spreadsheet programs will be familiar with this type of automatic recalculation.

Here, for example, is a spreadsheet view of an untitled group containing the series RC, a series expression for the lag of RG, $RG(-1)$, and a series expression involving RC and RG.

Notice here the Default setting for the group spreadsheet display indicates that the series RC and $RG(-1)$ are displayed using the original values, spreadsheet types, and formats set in the original series (see "Display Formats" on page 83). A newly created group always uses the Default display

obs	RC	RG(-1)	2*RC/RG
1953M01	3.510000	NA	NA
1953M02	3.530000	0.000000	NA
1953M03	3.570000	0.000000	NA
1953M04	3.650000	0.000000	2.579505
1953M05	3.780000	2.830000	2.478689
1953M06	3.860000	3.050000	2.482315
1953M07	3.860000	3.110000	2.634812
1953M08	3.850000	2.930000	2.610169
1953M09	3.880000	2.950000	2.703833
1953M10	3.820000	2.870000	2.872180
1953M11	3.750000	2.660000	2.798507
1953M12	3.740000	2.680000	2.888031
1954M01			

setting, regardless of the settings in the original series, but the group does adopt the original series cell formatting. You may temporarily override the display setting by selecting a group display format. For example, to use the display settings of the original series, you should select **Series Spec** to display differences of all of the series in the group, select **Differenced**.

An equivalent method of creating a group is to select **Quick/Show...**, or to click on the **Show** button on the workfile toolbar, and then to enter the list of series, groups and series expressions to be included in the group. This method differs from using **Object/New Object...** only in that it does not allow you to name the object at the time it is created.

You can also create an empty group that maybe used for entering new data from the keyboard or pasting data copied from another Windows program. These methods are described in detail in [“Entering Data” on page 101](#) and [“Copying-and-Pasting” on page 103](#)

Editing in a Group

Editing data in a group is similar to editing data in a series. Open the group window, and click on **Sheet**, if necessary, to display the spreadsheet view. If the group spreadsheet is in protected mode, click on **Edit +/-** to enable edit mode, then select a cell to edit, enter the new value, and press ENTER. The new number should appear in the spreadsheet.

Since groups are simply references to series, editing the series within a group changes the values in the original series.


As with series spreadsheet views, you may click on **Smpl +/-** to toggle between showing all of the observations in the workfile and showing only those observations in the current sample. Unlike the series window, the group window always shows series in a single column.

Note that while groups inherit many of the series display formats when they are created, to reduce confusion, groups do not initially show transformed values of the series. If you wish to edit a series in a group in transformed form, you must explicitly set a transformation type for the group display.

Adding to or Modifying a Group

You can add to or modify an existing group by clicking on **View/Group Members** and then editing the list of names. Clicking on the **UpdateGroup** accepts your edits (see [“Group Members” on page 379](#) for details).

Alternately, you can drag-and-drop series into the **Group Members** or **Spreadsheet** views of the group. EViews will automatically add the series to the group.



Samples

One of the most important concepts in EViews is the sample of observations. The sample is the set (often a subset) of observations in the workfile to be included in data display and in performing statistical procedures. Samples may be specified using ranges of observations and "if conditions" that observations must satisfy to be included.


For example, you can tell EViews that you want to work with observations from 1953M1 to 1970M12 and 1995M1 to 1996M12. Or you may want to work with data from 1953M1 to 1958M12 where observations in the RC series exceed 3.6.

The remainder of this discussion describes the basics of using samples in non-panel workfiles. For a discussion of panel samples, see ["Panel Samples," beginning on page 624](#) of User's Guide II

The Workfile Sample

When you create a workfile, the workfile sample or global sample is set initially to be the entire range of the workfile. The workfile sample tells EViews what set of observations you wish to use for subsequent operations. Unless you want to work with a different set of observations, you will not need to reset the workfile sample.

You can always determine the current workfile sample of observations by looking at the top of your workfile window.



Here the BONDS workfile consists of 528 observations from January 1953 to December 1996. The current workfile sample uses a subset of those observations, consisting of the 45 observations between 1953M01 and 1958M12 for which the value of the RC series exceeds 3.6.


Changing the Sample

There are four ways to set the workfile sample: you may click on the Sample button in the workfile toolbar, you may double click on the sample string display in the workfile window, you can select Proc/Set Sample... from the main workfile menu, or you may enter a `smpl` command in the command window. If you use one of the interactive methods, EViews will open the Sample dialog prompting you for input.

Date Pairs

In the upper edit field you will enter one or more pairs of dates (or observation numbers). Each pair identifies a starting and ending observation for a range to be included in the sample.

For example, if, in an annual workfile, you entered the string "1950 1980 1990 1995", EViews will use observations for 1950 through 1980 and observations for 1990 through 1995 in subsequent operations; observations from 1981 through 1989 will be excluded. For undated data, the date pairs correspond to observation identifiers such as "1 50" for the first 50 observations.



You may enter your date pairs in a frequency other than that of the workfile. Dates used for the starts of date pairs are rounded down to the first instance of the corresponding date in the workfile frequency, while dates used for the ends of date pairs are rounded up to the last instance of the corresponding date in the workfile frequency. For example, the date pair "1990m1 2002q3" in an annual workfile will be rounded to "1990 2002", while the date pair "1/30/2003 7/20/2004" in a quarterly workfile will be rounded to "2003q1 2004q3".

For intraday data, the sample may be further specified by including a time after the start and end dates. For example, given an hourly workfile, entering "1/3/2000 10AM 12/30/2000 2PM" will limit the start time to 10AM on 1/3/2000 and to 2PM on 12/30/2000.

EViews provides special keywords that may make entering sample date pairs easier. First, you can use the keyword "@ALL", to refer to the entire workfile range. In the workfile above, entering "@ALL" in the dialog is equivalent to entering "1953M1 1996M12". Furthermore, you may use "@FIRST" and "@LAST" to refer to the first and last observation in the workfile. Thus, the three sample specifications for the above workfile:

@all

@first 1996m12

1953m1 @last

are identical.

Note that when interpreting sample specifications involving days, EViews will, if necessary, use the global defaults ("[Date Representation](#)" on [page 629](#)) to determine the correct ordering of days, months, and years. For example, the order of the months and days is ambiguous in the date pair:

1/3/91 7/5/95

so EViews will use the default date settings to determine the desired ordering. We caution you, however, that using the default settings to disambiguate dates in samples is not generally a good idea since a given pair may be interpreted in different ways at different times if your settings change.

Alternately, you may use the IEEE standard format, "YYYY-MM-DD", which uses a four-digit year, followed by a dash, a two-digit month, a second dash, and a two-digit day. The presence of a dash in the format means that you must enclose the date in quotes for EViews to accept this format. For example:

"1991-01-03" "1995-07-05"

will always be interpreted as January 3, 1991 and July 5, 1995. See "[Free-format Conversion Details](#)" on [page 102](#) in the Command and Programming Reference for related discussion.

Sample IF conditions

The lower part of the sample dialog allows you to add conditions to the sample specification. The sample is the intersection of the set of observations defined by the range pairs in the upper window and the set of observations defined by the "if" conditions in the lower window. For example, if you enter:

Upper window: 1980 1993

Lower window: incm > 5000

the sample includes observations for 1980 through 1993 where the series INCM is greater than 5000.

Similarly, if you enter:

Upper window: 1958q1 1998q4

Lower window: gdp > gdp(-1)

all observations from the first quarter of 1958 to the last quarter of 1998, where GDP has risen from the previous quarter, will be included.

The “or” and “and” operators allow for the construction of more complex expressions. For example, suppose you now wanted to include in your analysis only those individuals whose income exceeds 5000 dollars peryear and who have at least 13 years of education. Then you can enter:

Upper window: @all

Lower window: income > 5000 and educ >= 13

Multiple range pairs and “if” conditions may also be specified:

Upper window: 50 100 200 250

Lower window: income >= 4000 and educ > 12

includes undated workfile observations 50 through 100 and 200 through 250, where the series INCOME is greater than or equal to 4000 and the series EDUC is greater than 12.

You can create even more elaborate selection rules by including EViews built-in functions:

Upper window: 1958m1 1998m1

Lower window: (ed>=6 and ed<=13) or earn<@mean(earn)

includes all observations where the value of the variable ED falls between 6 and 13, or where the value of the variable EARN is lower than its mean. Note that you may use parentheses to group the conditions and operators when there is potential ambiguity in the order of evaluation.

It is possible that one of the comparisons used in the conditioning statement will generate a missing value. For example, if an observation on INCM is missing, then the comparison INCM>5000 is not defined for that observation. EViews will treat such missing values as though the condition were false, and the observation will not be included in the sample.

Sample Commands

You may find it easier to set your workfile sample from the command window—instead of using the dialog, you may set the active sample using the `smpl` command. Simply click on the command window to make it active, and type the keyword “SMPL”, followed by the sample string:

`smpl 1955m1 1958m12 if rc>3.6`

and then press ENTER (notice, in the example above, the use of the keyword "IF" to separate the two parts of the sample specification). You should see the sample change in the workfile window.

Samples for Intraday data

When your data is specified in a frequency higher than a day, you may use IF conditions to set the sample to include specific hours over multiple days. Four functions in EViews facilitate this: @hour, @minute, @second, and @hourf.

Suppose you have minute data over all 24 hours and would like to set the sample to only include 9:30AM to 2:30PM. This can be accomplished using the @hourf command, which returns the observation time as a floating point hour:

```
smpl if @hourf>=9.5 and @hourf<=14.5
```

To select only observations that appear on the half hour, use the @minute command:

```
smpl if @minute=0 or @minute=30
```

To select only observations that are on Mondays at 10AM:

```
smpl if @weekday=1 and @hourf=10
```

Sample Offsets

Sample range elements may contain mathematical expressions to create date offsets. This feature can be particularly useful in setting up a fixed width window of observations. For example, in the regular frequency monthly workfile above, the sample string:

```
1953m1 1953m1+11
```

defines a sample that includes the 12 observations in the calendar year beginning in 1953M1.

While EViews expects date offsets that are integer values, there is nothing to stop you from adding or subtracting non-integer values—EViews will automatically convert the number to an integer. You should be warned, however, that the conversion behavior is not guaranteed to be well-defined. If you must use non-integer values, you are strongly encouraged to use the @round, @floor or @ceil functions to enforce the desired behavior.

The offsets are perhaps most useful when combined with the special keywords to trim observations from the beginning or end of the sample. For example, to drop the first observation in your sample, you may use the sample statement:

```
smpl @first+1 @last
```

Accordingly, the following commands generate a series containing cumulative sums of the series X in XSUM:

```
smpl @first @first
```

```
series xsum = x
smpl @first+1 @last
xsum = xsum(-1) + x
```

(see [“Basic Assignment” on page 142](#)). The first two commands initialize the cumulative sum for the first observation in each cross-section. The last two commands accumulate the sum of values of X over the remaining observations.

Similarly, if you wish to estimate your equation on a subsample of data and then perform cross-validation on the last 20 observations, you may use the sample defined by,

```
smpl @first @last-20
```

to perform your estimation, and the sample,

```
smpl @last-19 @last
```

to perform your forecast evaluation.

While the use of sample offsets is generally straightforward, there are a number of important subtleties to note when working with irregularly dated data and other advanced workfile structures ([“Advanced Workfiles” on page 213](#)). To understand the nuances involved, note that there are three basic steps in the handling of date offsets.

First, dates used for the starts of date pairs are rounded down to the first instance of the corresponding date in the workfile regular frequency, while dates used for the ends of date pairs are rounded up to the last instance of the corresponding date in the regular frequency. If date pairs are specified in the workfile frequency (e.g., the pair “1990 2000” is used in an annual workfile), this step has no effect.

Next, EViews examines the workfile frequency date pair to determine whether the sample dates fall within the range of the observed dates in the workfile, or whether they fall outside the observed date range. The behavior of sample offsets differs in the two cases.

For simplicity of discussion, assume first that both dates fall within the range of observed dates in the workfile. In this case:

- EViews identifies base observations consisting of the earliest and latest workfile observations falling within the date pair range.
- Offsets to the date pair are then applied to the base observations by moving through the workfile observations. If, for example, the offset for the first element of a date pair is “+1”, then the sample is adjusted so that it begins with the observation following the base start observation. Similarly, if the offset for the last element of a date pair is “-2”, then the sample is adjusted to end two observations prior to the base end observation.

Next, we assume that both dates fall outside the range of observed workfile dates. In this setting:

- EViews applies offsets to the date pair outside of the workfile range using the regular frequency until the earliest and latest workfile dates are reached. The base observations are then set to the earliest and latest workfile observations.
- Any remaining offsets are applied to the base observations by moving through the workfile observations, as in the earlier case.

The remaining two cases, where one element of the pair falls within, and the other element falls outside the workfile date range, follow immediately.

It is worth pointing out that the difference in behavior is not arbitrary. It follows from the fact that within the date range of the data, EViews is able to use the workfile structure to identify an irregular calendar, but since there is no corresponding information for the dates beyond the range of the workfile, EViews is forced to use the regular frequency calendar.

A few examples will help to illustrate the basic concepts. Suppose for example, that we have an irregular dated annual workfile with observations for the years “1991,” “1994,” “1995,” “1997,” “2000,” and “2002”:

YEAR	
Last updated: 02/03/04 - 10:10	
1991	1991
1994	1994
1995	1995
1997	1997
2000	2000
2002	2002

The sample statement:

```
smpl 1993m8+1 2002q2-2
```


is processed in several steps. First, the date “1993m8” is rounded to the previous regular frequency date, “1993,” and the date “2002q2” is rounded up to the last instance of the regular frequency date “2002”; thus, we have the equivalent sample statement:

```
smpl 1993+1 2002-2
```

Next, we find the base observations in the workfile corresponding to the base sample pair (“1993 2002”). The “1994” and the “2002” observations are the earliest and latest, respectively, that fall in the range.

Lastly, we apply the offsets to the remaining observations.

The offsets for the start and end will drop one observation (“1994”) from the beginning and two observations (“2002” and “2000”) from the end of the sample, leaving two observations (“1995,” “1997”) in the sample.



Consider instead the sample statement:


smpl 1995-1 2004-4

In this case, no rounding is necessary since the dates are specified in the workfile frequency.

For the start of the date pair, we note that the observation for “1995” corresponds to the start date. Computing the offset “-1” simply adds the “1994” observation.

For the end of the date pair, we note that “2004” is beyond the last observation in the workfile, “2002”.

We begin by computing offsets to “2004” using the regular frequency calendar, until we reach the highest



date in the workfile, so that we “drop” the two observations “2004” and “2003”. The remaining two offsets, which use the observed dates, drop the observations for “2002” and “2000”. The resulting sample includes the observations “1994,” “1995,” and “1997”.


Sample Objects

As you have seen, it is possible to develop quite elaborate selection rules for the workfile sample. However, it can become quite cumbersome and time-consuming to re-enter these rules if you change samples frequently. Fortunately, EViews provides you with a method of saving sample information in an object which can then be referred to by name. If you work with many well-defined subsets of your data, you will soon find sample objects to be indispensable.

Creating a Sample Object

To create a sample object, select **Object/New Object...** from the main menu or the workfile toolbar. When the New Object dialog appears, select **Sample** and, optionally provide a name. If you do not provide a name, EViews will automatically assign one for you (sample objects may not be untitled). Click on **OK** and EViews will open the sample object specification dialog:

Here is a partially filled-in sample object dialog for **SMPL1**. Notice that while this dialog looks very similar to the one we described above for setting the sample, there are minor cosmetic differences: the name of the sample object appears in the title bar, and there is a check box for setting the workfile sample equal to this sample object.



These cosmetic differences reflect the two distinct purposes of the dialog: (1) to define the sample object, and (2) to set the workfile sample. Since EViews separates the act of defining the sample object from the act of setting the workfile sample, you can define the object without changing the workfile sample, and vice versa.

To define the sample object, you should fill out this dialog as described before and click on **OK**. The sample object now appears in the workfile directory with a double-arrow icon.

To declare a sample object using a command, simply issue the sample declaration, followed by the name to be given to the sample object, and then the sample string:

```
sample mysample 1955m1 1958m12 if rc>3.6
```

EViews will create the sample object **MYSAMPLE** which will use observations between 1955:01 and 1958:12, where the value of the **RC** series is greater than 3.6.

Using a Sample Object

You may use a previously defined sample object directly to set the workfile sample. Simply open a sample object by double clicking on the name or icon. This will reopen the sample dialog. If you wish to change the sample object, you may edit the sample specification; otherwise, simply click the `Set workfile sample` check box and click on OK.

Or, you may set the workfile sample using the sample object, by entering the `smpl` command, followed by the sample object name. For example, the command:

```
smpl mysample
```

will set the workfile sample according to the rules contained in the sample object MYSAMPLE.

For many purposes, you may also use a named sample object as though it were an ordinary EViews series containing the values 1 and 0, for observations that are and are not included, respectively. Thus, if SMP2 is a named sample object, you may use it as though it were a series in any EViews expressions (see [Series Expressions](#) on page 133). For example:

```
y1*(smp2=0) + 3*y2*(smp2=1)
```

is a valid EViews expression, evaluating to the value of $3 \cdot Y_2$ if an observation is in SMP2, and Y_1 , otherwise.

You may also, for example, create a new series that is equal to a sample object, and then examine the values of the series to see which observations do and do not satisfy the sample criterion.

Additionally, one important consequence of this treatment of sample objects is that you may use sample objects in the construction of other sample objects. For example, if you create a sample object FEMALE containing observations for individuals who are females,

```
sample female @all if gender="female"
```

and a second sample object HIGHINC if INCOME is greater than 25000:

```
sample highinc @all if income>25000
```

You may set the sample to observations where individuals are low income females using:

```
smpl @all if female and not highinc
```

where we use the NOT keyword to take the complement of the observations in HIGHINC. To create a sample object HIGHFEMALE using this sample, use the command:

```
sample highfemale @all if female and not highinc
```

Alternatively, we could have used the equivalent expression

```
sample highfemale @all if female and highinc=0
```

More generally, we may use any expression involving sample objects and the keywords “AND”, “OR”, and “NOT”, as in

```
smpl 1950 1980 if female or not highinc
```

which sets the sample to those observations from 1950 to 1980 that are also in the sample FEMALE, but not in the sample HIGHINC.

Importing Data

The data for your project may be available in a variety of forms. The data may be in a machine readable spreadsheet or ~~txt~~ file that you created yourself or downloaded from the Internet, or perhaps they are in book or photocopy form.

There are a number of ways to read such data into EViews. Earlier, we described workfile creation tools that allow you to open data from foreign sources into a new workfile ([“Creating a Workfile by Reading from a Foreign Data Source” on page 39](#)). This is most likely the easiest way to move data from foreign files and database sources such as ODBC into EViews and we recommend it as your first approach, but you should note that these tools are expressly designed for creating new workfiles.

Alternatively, you may wish to import data into an existing workfile, perhaps into existing series in the workfile—you may, for example, wish to read a portion of an Excel file into a subset of observations in a series or group of series. We term the reading of data into existing workfiles and/or series *importing series data* to distinguish it from the creation of entirely new workfiles and series.


There are several methods for importing series data into EViews. In the remainder of this discussion, we outline the basics of data import from spreadsheet, text file, or printed formats, into series and group objects. Note that we omit, for the moment, discussion of importing data into EViews matrix, vector and pool objects, and discussion of EViews and foreign databases:

- Matrix and vector import tools are discussed briefly in [“Matrix Object Import” on page 108](#)
- Pool import is described in [“Importing Pooled Data” on page 572](#) of User’s Guide II
- EViews databases are the subject of [Chapter 10. “EViews Databases,” beginning on page 267](#)


Entering Data

For small datasets in printed form, you may wish to enter the data by typing at the keyboard.

- Your first step is to open a temporary spreadsheet window in which you will enter the data. Choose Quick/Empty Group (Edit Series) from the main menu to open an untitled group window:



- The next step is to create and name the series. First click once on the up arrow in the scroll bar to display the second obs label on the left-hand column. The row of cells next to the second obs label is where you will enter and edit series names.
Click once in the cell next to the second obs label, and enter your first series name. Here we have typed “income” in the edit window (the name in the cell changes as we type in the edit window). Press RETURN. If you enter the name of an existing series, the series data will be brought into the group.
- EViews will prompt you to specify a series type for the column. You may select a numeric series, numeric series containing date values, or an alpha series. When you click on OK, EViews will create a numeric or alpha series and will apply formatting information that will aid you in viewing your data.
- You should repeat this procedure in subsequent columns for each additional series. If you decide you want to rename one of your series, simply select the cell containing the series name, edit the name in the edit window, and then press RETURN. EViews will prompt you to confirm the series rename.



- To enter the data, click on the appropriate cell and type the number or text. Pressing RETURN after entering the cell value will move you to the next cell. If you prefer, you can use the cursor keys to navigate the spreadsheet.
- When you are finished entering data, close the group window. If you wish, you can first name the untitled group by clicking on the Name button. Otherwise, if you do not wish to keep the group, answer Yes when EViews asks you to confirm the deletion.

Copying-and-Pasting


The Windows clipboard is a handy way to move small amounts of data within EViews and between EViews and other software applications. It is a natural tool for importing these types of data from Excel and other Windows applications that support Windows copy-and-paste.

Copying from Windows Applications

The following discussion involves an example using an Excel spreadsheet, but the basic principles apply for other Windows applications.

Suppose you have bond yield and interest rate data in an Excel spreadsheet that you would like to bring into EViews.

Open the spreadsheet in Excel. Your first step is to highlight the cells to be imported into EViews. Since the column headings YIELD and INTEREST will be used as EViews variable names, you should highlight them as well. Since EViews understands dated data, and we are going to create a monthly workfile, you do not need to copy the date column. Instead, click on the column label B and drag to the column label C. The two columns of the spreadsheet will be highlighted.




	A	B	C	D	E	F	G
1	obs	yield	interest				
2	1953M01	3.51	0				
3	1953M02	3.53	0				
4	1953M03	3.57	0				
5	1953M04	3.65	2.83				
6	1953M05	3.78	3.05				
7	1953M06	3.86	3.11				
8	1953M07	3.86	2.93				
9	1953M08	3.85	2.95				
10	1953M09	3.88	2.87				

Select **Edit/Copy** to copy the highlighted data to the clipboard.

Pasting into New Series

Start EViews and create a new, or load an existing, monthly workfile containing the dates in the Excel spreadsheet (in our example, 1953:1 through 1994:11). Make certain that the sample is set to include the same observations that you have copied onto the clipboard.




	A	B	C	D	E	F
1	obs	yield	interest			
2	1953M01	3.51	0			
3	1953M02	3.53	0			
4	1953M03	3.57	0			
5	1953M04	3.65	2.83			
6	1953M05	3.78	3.05			
7	1953M06	3.86	3.11			
8	1953M07	3.86	2.93			
9	1953M08	3.85	2.95			
10	1953M09	3.88	2.87			
11	1953M10	3.82	2.66			

Select **Quick/Empty Group (Edit Series)** . Note that the spreadsheet opens in edit mode so there is no need to click the **Edit +/-** button.

Here, we have created a monthly workfile with a range from 1953:1 to 1999:12. The first row of the EViews spreadsheet is labeled 1953:01 Since we are pasting in the series names as well, you should click on the up arrow in the scroll bar to make room for the series names.

Place the cursor in the upper-left cell, just to the right of the second obs label. Then select **Edit/Paste** from the main menu (not **Edit +/-** in the toolbar). The group spreadsheet will now contain the data from the clipboard.

EViews automatically analyzes the data on the clipboard to determine the most likely series type. If, for example, your series contains text that can always be interpreted as a number, EViews will create a numeric series. Here, the numeric series **YIELD** and **INTEREST** have been created in the workfile.



obs	YIELD	INTEREST
obs	YIELD	INTEREST
1953M01	3.510000	0.000000
1953M02	3.530000	0.000000
1953M03	3.570000	0.000000
1953M04	3.650000	2.830000
1953M05	3.780000	3.050000
1953M06	3.860000	3.110000
1953M07	3.860000	2.930000
1953M08	3.850000	2.950000
1953M09	3.880000	2.870000
1953M10	3.820000	2.660000
1953M11	3.750000	2.680000
1953M12	3.710000	2.580000

If the numbers in the series may all be interpreted as date values, or if the data are all string representations of dates, EViews will create a numeric series formatted to display dates.

If you paste a name corresponding to an object that already exists in the workfile, EViews will find the next available name by appending an integer to the series name. For example, if **SER** already exists in the workfile, pasting the name “**SER**” will create a series **SER01**.

You may now close the group window and delete the untitled group without losing the two series.

Pasting into Existing Series

You can import data from the clipboard into an existing EViews series or group spreadsheet by using Edit/Paste in the same fashion. There are only a few additional issues to consider:

- To paste several series, you will first open a group window containing the existing series. The easiest way to do this is to click on Show, and then type the series names in the order they appear on the clipboard. Alternatively, you can create an untitled group by selecting the first series, holding down the Ctrl-key and click select each subsequent series (in order), and then double clicking to open.
- Make certain that the group window is showing the sample range that corresponds to the data on the clipboard.
- Next, make certain that the group window is in edit mode. If not in edit mode, press the Edit +/- button to toggle to edit mode. Place the cursor in the target cell, and select Edit/Paste from the main menu.
- Finally, click on Edit +/- to return to protected mode.
- If you are pasting into a single series you will need to make certain that the series window is in edit mode, and that the series is viewed in a single column. If the series is in multiple columns, push on the Wide +/- button. Then Edit/Paste the data as usual, and click on Edit +/- to protect the data.

Importing Data from a Spreadsheet or Text File

Important note: Since the original EViews 7 manuals went to press, we have added a set of easy-to-use interactive import tools to EViews 7. See [“Importing Data” on page 5](#) of the supplemental document “Readme.PDF” for details on the new features.

With the exception of cases where the source file contains transposed data (i.e., data arranged by row rather than by column), you should find the new tools to be superior to those documented here.

You can also read data directly from files created by other programs into a workfile. Perhaps the easiest way to bring data from a foreign file into an existing workfile is to first open the foreign data as a new workfile ([“Creating a Workfile by Reading from a Foreign Data Source” on page 39](#)), and then copy the data into your existing file. However, some data in standard ASCII form or in either Lotus (.WKS, .WK1, or .WK3) or Excel (.XLS or .XLSX) spreadsheet formats may be directly imported into a workfile.


First, make certain that you have an open workfile to receive the contents of the data import and that the workfile window is active.

Next, click on Proc/Import/Read Text-Lotus-Excel... You will see a standard File Open dialog box asking you to specify the type and name of the file. Select a file type, navigate to the directory containing the file, and double click on the name. Alternatively, type in the name of the file that you wish to read (with full path information, if appropriate); if possible, EViews will automatically set the file type, otherwise it will treat the file as an ASCII file. Click on Open.

EViews will open a dialog prompting you for additional information about the import procedure. The dialog will differ greatly depending on whether the source file is a spreadsheet or an ASCII file.

Spreadsheet Import

The title bar of the dialog will identify the type of file that you have asked EViews to read. Here is the dialog for importing an Excel 5 (or later versions of Excel) spreadsheet:



You will see slightly different versions of this dialog depending on whether you are reading a Lotus or an Excel 4 (and earlier) file. Now fill in the dialog:

- First, you need to tell EViews whether the data are ordered by observation or by series. By observation means that all of the data for the first observation are followed by all of the data for the second observation, etc. By series means that all of the data for the first variable are followed by all data for the second variable, etc. Another

interpretation for “by observation” is that variables are arranged in columns while “by series” implies that all of the observations for a variable are in a single row.

Our Excel example above (“Copying from Windows Applications” on page 103) is organized by observation since each series is in a separate column. If the Excel data for YIELD and INTEREST were each contained in a single row as depicted

	A	B	C	D	E	F	G
1	obs	1953:01	1953:02	1953:03	1953:04	1953:05	1953:06
2	yield	3.51	3.53	3.57	3.65	3.78	3.86
3	interest	0	0	0	2.83	3.05	3.11
4							
5							
6							
7							
8							
9							
10							

here, then the data should be read by series.

- Next, tell EViews the location of the beginning cell (upper left-hand corner) of your actual data, not including any label or date information. In both examples above, the upper left-hand cell is B2.
- In the edit box in the middle of the dialog, enter the names to be assigned to the series you will be importing. EViews reads spreadsheet data in contiguous blocks, so you should provide a name for each column or row (depending on the orientation of the data), even if you only wish to read selected columns or rows. To read a column or row into an alpha series, you should enter the tag “\$” following the series name (e.g., “NAME \$ INCOME CONSUMP”).
- Alternatively, if the names that you wish to use for your series are contained in the file, you can simply provide the number of series to be read. The names must be adjacent to your data. If the data are organized by row and the starting cell is B2, then the names must be in column A, beginning at cell A2. If the data are organized by column beginning in B2, then the names must be in row 1, starting in cell B1. If, in the course of reading the data, EViews encounters an invalid cell name, it will automatically assign the next unused name with the prefix SER, followed by a number (e.g., SER01, SER02, etc.).
- Lastly, you should tell EViews the sample of data that you wish to import. EViews begins with the first observation in the file and assigns it to the first date in the sample for each variable. Each successive observation in the file is associated with successive observations in the sample. Thus, in an annual workfile, if you enter the sample:

1971 1975 1990 1991

in the import dialog, the first five observations will be assigned to the dates 1971–1975, and the sixth and seventh observations will be assigned to the dates 1990–1991. The data in the intermediate period will be unaffected by the importing procedure.

You should be warned that if you read into a sample which has more observations than are present in your input file, observations for which there are no corresponding inputs will be assigned missing values. For example, if you read into the sample defined as “1971 1990”, and there are only 10 observations in the input file, the observations from 1981 to 1990 will be assigned missing values.

When the dialog is first displayed, EViews enters the current workfile sample in the edit box by default. You should edit this string to reflect the desired sample. To make it easier to set the sample, EViews provides you with three push-buttons which change the string in the edit box to commonly used values:

1. Current sample sets the dialog string to the current workfile sample.
 2. Workfile range sets the dialog string to the entire range of the workfile.
 3. To end of range sets the dialog string to all observations from the beginning of the current sample to the end of the workfile range.
- If you are reading data from an Excel 5 workbook file, there will be an additional edit box where you can enter the name of the sheet containing your data. If you do not enter a name, EViews will read from the topmost sheet in the Excel workbook.
 - When the dialog is completely filled out, simply click OK and EViews will read your file, creating series and assigning values as requested.

ASCII Import

If you choose to read from an ASCII file, EViews will open an ASCII Text Import dialog. Fill out the dialog to read from the specified file.

The dialog box for ASCII file import is considerably more complicated than the corresponding spreadsheet dialog. While unfortunate, this complexity is necessary since there is no standard format for ASCII files. EViews provides you with a range of options to handle various types of ASCII files.


ASCII file importing is explained in considerable detail in [“Importing ASCII Text Files,” beginning on page 122](#)

Matrix Object Import

The preceding discussion focused on importing data into series or group objects. Similar tools are available for importing data directly into a matrix object from spreadsheet or from ASCII text files.

To import data from a file into a matrix object, you must first open the correctly sized matrix object, and select Proc/Import Data (ASCII, .XLS, .WK?)... . After you select your file, EViews will open an import dialog.

Here, we depict the dialog for importing from an Excel spreadsheet. The corresponding ASCII dialog has many more options, since ASCII file reading is more complicated. Note that both the import and export dialogs differ little from the series import dialogs described above.



The differences reflect the different nature of series and matrix input and output. For example, dialog options for series names and the sample are omitted since they do not apply to matrices.

In reading from a file, EViews first fills the matrix with NAs, puts the first data element in the (1,1) element of the matrix, and then continues reading the data by row or column according to the specified settings for Data order. If this option is set as Original, EViews will read by row, filling the first row from left to right, and then continuing on to the next row. If the ordering is set as Transpose, EViews will read by column, reading the first column from top to bottom and then continuing on to the next column. In either case, the data read from the file are placed into the matrix by row.

ASCII files provide you with the option of reading your file as a rectangle. If your ASCII file is laid out as a rectangle, the contents of the rectangle will be placed in the matrix beginning at the (1,1) element of the matrix. For example, if you have a 3 × 3 matrix X in EViews, and read from the ASCII file containing:

```
1 2 3 4
5 6 7 8
9 10 11 12
```

using the File laid out as rectangle option, the matrix X will contain the corresponding rectangular portion of the ASCII file:

```
1 2 3
5 6 7
9 10 11
```


If you do not select the rectangular read option, EViews fills the matrix element-by-element, reading from the file line-by-line. Then X will contain:

```
1 2 3
4 5 6
7 8 9
```

Exporting Data

EViews provides you with a number of methods for getting data from EViews into other applications.

The easiest way to save series data is to use the save your workfile page as a foreign file. Simply select File/Save As from the main EViews menu, choose your file type and provide a name, then fill out the dialogs. EViews will prompt you to specify the variables and object you wish to save. You will notice that the identifier series are listed first in the top portion of the dialog, with @date selected and @enddate unselected by default. You may also specify the sample of observations to be written, and for some output formats, the valmaps to be written.



(See ["Creating a Workfile by Reading from a Foreign Data Source"](#) on page 39 for a discussion of the dialog controls.)

For most applications, this method of saving data to a foreign format will be more than sufficient. The remainder of this section discusses alternate methods that support other object types and may offer additional control over the export operation. If, for example, you wish to export data in a matrix, you will need to use one of the methods described below.

Copying and Pasting

You can click and drag in a spreadsheet view or table of statistical results to highlight the cells you want to copy. Then click Edit/Copy... in the main menu to put the data into the

clipboard. You will see a dialog box asking whether to copy the numbers with the precision showing on your screen (formatted copy) or to copy the numbers at full precision (unformatted copy).

As a shortcut, you can highlight entire rows or columns of cells by clicking on the gray border that surrounds the spreadsheet. Dragging across the border selects multiple rows or columns. To copy several adjacent series from the spreadsheet, drag across their names in the top border. All of their data will be highlighted. Then click **Edit/Copy...** to put the data into the clipboard.

Once the data are on the clipboard, switch to the target application, highlight the cells to which the data is to be copied and select **Edit/Paste**.

When pasting to a spreadsheet view or a table in EViews, if the paste cell range is larger than the copy range, the data will be repeated to fill the entire paste range. However, this will only occur if the paste range is proportional to copy range. Ranges are considered proportional when the paste range is a multiple of the copy range. For example, if a 3 by 1 area (3 rows by 1 column) is copied, the paste range must be at least 3 by 1. Proportional paste ranges could include 3 by 2, 6 by 1, 6 by 2, etc.

Exporting to a Spreadsheet or Text File

First, click on **Proc/Export/Write Text-Lotus-Excel...** from the workfile toolbar or main menu, then enter the name and type of the output file in the **SaveAs** dialog. As you fill out the **SaveAs** dialog, keep in mind the following behavior:

- If you enter a file name with an extension, EViews will use the file extension to identify the file type. Files with common spreadsheet extensions (".XLS", ".WK3", ".WK1", and ".WKS") will be saved to the appropriate spreadsheet type. All others will be saved as ASCII files.
- If you do not enter an extension, EViews will use the file type selected in the combo box to determine the output type. Spreadsheet files will have the appropriate extensions appended to the name. ASCII files will be saved using the name provided in the dialog, without an extension. EViews will not append extensions to ASCII files unless you explicitly include one in the file name.
- Note that EViews cannot, at present, write into an existing file. The file that you select will, if necessary, be replaced.

Once you have specified the output file, click **OK** to open the export dialog.

Tip: if you highlight the series you wish to export before beginning the export procedure, the series names will be used to fill out the export dialog.

Spreadsheet Export

The dialogs for spreadsheet export are virtually identical to the dialogs for spreadsheet import. You should determine the orientation of your data, the series to export, and the sample of observations to be written.

Additionally, EViews provides you with checkboxes for determining whether to include the series names and/or the series dates in the spreadsheet. If you choose to write one or both to the spreadsheet, make certain that the starting cell for your data leaves the necessary room along the borders for the information. If the necessary room is not available, EViews will ignore the option—for example, if you choose to write your data beginning in cell A1, EViews will not write the names or dates.

ASCII Export

The ASCII export dialog is quite similar to the spreadsheet export dialog, but it contains a few additional options:

- You can change the text string to be used for writing missing values. Simply enter the text string in the edit field.
- EViews provides you with the option of separating data values with a tab, a space, or a comma. Click on the desired radio button.

We caution that if you attempt to write your data by series, EViews will write all of the observations for a series on a single line. If you have a reasonably long series of observations, these data may overflow the line-length of other programs.

Matrix Object Export

Exporting data from a matrix object simply reverses the matrix import ([“Matrix Object Import” on page 108](#)). To write the contents of the matrix to a file, select Proc/Export Data (ASCII, .XLS, .WK?)... from the matrix toolbar and fill in the dialog as appropriate.

Reading EViews Data using Other Applications

The EViews OLEDB driver provides an easy way for OLEDB-aware clients or custom programs to read data stored in EViews workfiles (WF1) and EViews databases (EDB).

We also provide an EViews Microsoft Excel Add-in that allows users to fetch and link to EViews data located in workfiles and databases. The Add-in offers an easy-to-use interface to OLEDB for reading EViews data from within Excel.

The following discussion offers only a brief overview of the OLEDB driver and the Excel Add-in. For additional details, see the Using the EViews OLEDB Driver and The EViews Microsoft Excel Add-in whitepapers, both available in your EViews documentation directory or from our website www.eviews.com.

The Excel Add-in


The EViews Excel Add-in offers a simple interface for fetching and linking from within Microsoft Excel (2000 and later) to series and matrix objects stored in EViews workfiles and databases.

Installation of the EViews Excel Add-in is an option during the normal EViews installation procedure. Note that use of the Add-in requires that EViews be installed with a valid serial number. If you have already installed EViews but have not yet installed the Add-in, please run your EViews installer, and select the EViews Excel Add-in option.


Once installed, you'll need to activate the Add-in from within Microsoft Excel (see your Excel documentation or the The EViews Microsoft Excel Add-in for details).

The following Excel 2007 instructions illustrate use of the EViews Add-in to retrieve data:


- From the Add-ins ribbon, select the EViews dropdown from the Custom Toolbars section. Select Get Data to display the Get EViews Data popup dialog and click on Change source... to pick an existing workfile or database. If the specified source is a workfile, a Page dropdown will display all available pages; simply pick the page from which you wish to read. If the source is a database, the Freq dropdown will let you filter the series in the database by frequency.



- You may use the Types dropdown to change the default series object filter so that you only consider matrix objects.
- You may further filter objects by name and description by clicking on the **Filter...** button and entering restrictions in the dialog.



- You may select one or more series objects or a single matrix object and click on **Import** or **Import & Link** to continue. If you wish, you may instead click on **Add** to add selected items to the **Objects to import** list. Clicking on **Add All** adds all of the displayed items to the import list. You may also type in the name of the objects to import. Once your list is complete, click on **Import** or **Import & Link** to proceed. The import list approach is particularly useful if you wish to build-up a list of objects using various approaches or multiple filtered lists.
- The last step is to import or link the **EViews** data into Excel. On the resulting **Select Insert Point** popup, you should specify a destination cell in your Excel worksheet (you can click on a target cell to fill out the dialog). Click on **OK**.



At this point, the data should now be displayed in the specified worksheet. If we select **Import & Link** instead of **Import** in the first step, this data will automatically refresh itself every time the worksheet is opened. (Note: this worksheet must be saved in a trusted location to allow the data to refresh properly. See the Microsoft Excel documentation regarding "Trusted File Locations" for details.)


The OLEDB Driver

The **EViews** OLEDB driver is automatically installed and registered on your computer when you install **EViews**. Once installed, you may use OLEDB-aware clients or custom programs to read series, vector, and matrix objects directly from **EViews** workfiles and databases.


For additional details, see the [Using the EViews OLEDB Driver](#) whitepaper.

The following instructions for Excel 2007 illustrate the use of built-in OLEDB support to read EViews workfile data. (Note that [“The Excel Add-in,”](#) on page 113 describes a streamlined interface for performing the same operation.)


- From the Data ribbon, select From Other Sources in the Get External Data section. In the dropdown, select From Data Connection Wizard. In the Data Connection Wizard, select Other/Advanced in the listbox and click Next.




- In the Data Link Properties popup, select EViews OLE DB Provider and click Next.
- On the Connection tab, select an EViews workfile or database and click OK (not shown).



- Next, on the Data Connection Wizard popup, you should see a dropdown with all the available pages (if a workfile was selected) and in the grid below a list of readable series, vector, and matrix objects. Select one here and click Finish.



- On the Import Data popup, point to where you'd like to see the data in the worksheet and click OK.
- At this point, you should see the data (and any corresponding ID series data) appear in the specified worksheet



Frequency Conversion

Every series in EViews has an associated frequency. When a series is in a workfile, the series is stored at the frequency of the workfile. When a series is held in a database ([Chapter 10. “EViews Databases”](#)), it is stored at its own frequency. Since all series in the same workfile page must share a common frequency, moving a series from one workfile to another or from a database to a workfile page will cause the series being moved to be converted to the frequency of the workfile page into which it is being placed.

Performing Frequency Conversion

Frequency conversion is performed in EViews simply by copying or fetching a series with one frequency into a workfile of another frequency.

Copy-and-Paste

Suppose that you have two workfile pages (or a source database and a destination workfile page), where the source contains quarterly data on the series YQ, and the destination work-

file contains annual data. Note that you may copy between pages in the same workfile or between separate workfiles.

To convert YQ from a quarterly to annual frequency, you may copy-and-paste the series from the source quarterly work file to the annual workfile. Click on the YQ series in the quarterly workfile, press the right-mouse button and select Copy, navigate to the annual workfile, then right mouse button and select Paste or Paste Special...

If you select Paste, EViews will copy YQ to the annual page, using the default frequency conversion settings present in YQ to perform the conversion.

If you select Paste Special..., EViews will display a dialog offering you the opportunity to override the default frequency conversion settings. Before describing this dialog (["Overriding Default Conversion Methods" on page 121](#)), we provide a background on frequency conversion methods, and describe how default conversion methods are specified in EViews.

Drag-and-Drop

An alternative to copy-and-paste is to use drag-and-drop to copy files between workfile pages. Simply select the series to be copied then drag-and-drop them on the destination page tab. If you use the right-mouse button to select the series, dropping them on the new tab will bring up the Paste Special dialog.

You can even drag-and-drop a workfile page tab into a workfile window to copy all of the objects from one workfile page into another. Depending on the objects being copied and the frequencies of the workfiles, you may receive a series of prompts to assist in completing the paste properly.

Using Commands

You may use either the copy or fetch command to move series between workfiles or between a database and a workfile. EViews will perform frequency conversion if the frequencies of the source and destination do not match.

See [copy \(p. 216\)](#) and [fetch \(p. 243\)](#) in the Command and Programming Reference for details.

Frequency Conversion Methods

There are three types of frequency conversion: high frequency to low frequency conversion, low frequency to high frequency conversion, and frequency conversion between a dated and undated workfile.

EViews provides you with the ability to specify methods for all types of conversion. In addition, there are settings that control the handling of missing values when performing the conversion.

High Frequency to Low Frequency

If a numeric series being imported has a higher frequency than the workfile, you may choose between a number of different conversion methods:

- Average observations
- Sum observations
- First observation
- Last observation
- Maximum observation
- Minimum observation
- No down conversions

with the latter setting permitting you to disallow high to low conversions. In this case, EViews will generate an error if you attempt to convert from high to low frequency.

In addition, you may specify how EViews handles missing data when carrying out the calculations. You may elect to propagate NAs so that whenever a missing value appears in a calculation, the result for the corresponding period will be an NA. Alternatively, you may elect not to propagate NAs so that calculations will be performed ignoring the missing values (though if all values for a period are missing, the corresponding result will still be an NA).

Low Frequency to High Frequency

EViews also provides a number of different interpolation methods for dealing with the case where the series being brought into the workfile has a lower frequency than the workfile. Since observing a series at a lower frequency provides fundamentally less information than observing the same series at a higher frequency, it is generally not possible to recover the high frequency series from the low frequency data. Consequently, the results from EViews' interpolation methods should be considered to be suggestive rather than providing the true values of the underlying series.

EViews supports the following interpolation methods:

- Constant: Constant with sum or average matched to the source data.
- Quadratic: Local quadratic with sum or average matched to the source data.
- Linear: Linear with last observation matched to the source data.
- Cubic: Cubic spline with last observation matched to the source data.
- No conversion: Do not allow up conversion.

Using an interpolation method which matches the average means that the average of the interpolated points for each period is equal to the source datapoint for that period. Similarly

if the sum is matched, the interpolated points will sum to the source data point for the period, and if the last observation is matched, the last interpolated point will equal the source data point for the period.

For all methods, all relevant data from the low frequency series is used when forming the high frequency series, even if the destination observations are a subset of the observations available in the source.

The following describes the different methods in greater detail:

- Constant: match average, Constant: match sum —These two methods assign the same value to all observations in the high frequency series associated with a particular low frequency period. In one case, the value is chosen so that the average of the high frequency observation matches the low frequency observation (the value is simply repeated). In the other case, the value is chosen so that the sum of the high frequency observations matches the low frequency observation (the value is divided by the number of observations).
- Quadratic: match average, Quadratic: match sum —These two methods fit a local quadratic polynomial for each observation of the low frequency series, then use this polynomial to fill in all observations of the high frequency series associated with the period. The quadratic polynomial is formed by taking sets of three adjacent points from the source series and fitting a quadratic so that either the average or the sum of the high frequency points matches the low frequency data actually observed. For most points, one point before and one point after the period currently being interpolated are used to provide the three points. For end points, the two periods are both taken from the one side where data is available.

This method is a purely local method. The resulting interpolation curves are not constrained to be continuous at the boundaries between adjacent periods. Because of this, the method is better suited to situations where relatively few data points are being interpolated and the source data is fairly smooth.

- Linear: match last —This method assigns each value in the low frequency series to the last high frequency observation associated with the low frequency period, then places all intermediate points on straight lines connecting these points.
- Cubic: match last —This method assigns each value in the low frequency series to the last high frequency observation associated with the low frequency period, then places all intermediate points on a natural cubic spline connecting all the points.

A natural cubic spline is defined by the following properties:

1. Each segment of the curve is represented by a cubic polynomial.
2. Adjacent segments of the curve have the same level, first derivative and second derivative at the point where they meet.

3. The second derivative of the curve at the two global end points is equal to zero (this is the “natural” spline condition).

Cubic spline interpolation is a global interpolation method so that changing any one point (or adding an additional point) to the source series will affect all points in the interpolated series.

Undated Conversion

If you fetch or copy a series to or from an undated or unstructured workfile into or from a dated workfile, the data will be copied sequentially, beginning at the starting observation number of the undated or unstructured series (generally the first observation).

Panel Conversion


Performing frequency conversion when either the source or destination are panel workfile pages raises a number of additional issues. See [“Panel links with date matching” on page 191](#) and [“Panel frequency conversion” on page 195](#) for discussion of the general issues.

Specifying Default Conversion Methods

When performing frequency conversion of one or more series, EViews uses the default settings in each series to perform the conversion. These settings may be specified in each series using the Freq Convert tab of the Properties dialog. To access the dialog, click on the Properties button on the series toolbar and select the Freq Convert tab.

If the series default setting is set to EViews default, the series will take its frequency conversion setting from the EViews global options (see [“Frequency Conversion” on page 624](#) in [Appendix A. “Global Options”](#)). Here, the high to low conversion is set to Sum observations, overriding the global setting, while the low to high uses the EViews default global setting.

This two level default system allows you to set global default settings for frequency conversion that apply to all newly created series, while allowing you to override the default settings for specific series.



As an example of controlling frequency conversion using default settings, suppose you have daily data consisting of HIGH, LOW, and CLOSE series for a particular stock, from which you would like to construct a monthly workfile. If you use the default frequency conversion

methods, the monthly workfile will contain series which use the series defaults, which is not likely to be what you want. By setting the frequency conversion method of the HIGH series to Max observation, of the LOW series to Min observation, and of the CLOSE series to Last observation, you may use conversion to populate a monthly workfile with converted daily data that follow the desired behavior.


Overriding Default Conversion Methods

If you use copy-and-paste to copy one or more series between two workfiles, EViews will copy the series to the destination page, using the default frequency conversion settings present in the series to perform the conversion.

If, when pasting the series into the destination, you use Paste Special... in place of Paste, EViews will display a dialog offering you the opportunity to override the default frequency conversion settings.

You need not concern yourself with most of the settings in this dialog at the moment; the dialog is discussed in greater detail in [“Frequency conversion links” on page 203](#).

We note, however, that the dialog offers us the opportunity to change both the name of the pasted YQ series, and the frequency conversion method.



The “*” wildcard in the Pattern field is used to indicate that we will use the original name (wildcards are most useful when pasting multiple series). We may edit the field to provide a name or alternate wildcard pattern. For example, changing this setting to “*A” would copy the YQ series as YQA in the destination workfile.

Additionally, we note that the dialog allows us to use the frequency conversion method Specified in series or to select alternative methods.

If, instead of copy-and-paste, you are using either the `copy` or `fetch` command and you provide an option to set the conversion method, then EViews will use this method for all of the series listed in the command (see [copy \(p. 216\)](#) and [fetch \(p. 243\)](#) in the Command and Programming Reference for details).

Importing ASCII Text Files

To import an ASCII text file, click on Proc/Import/Read Text-Lotus-Excel... from the main menu or the workfile toolbar, and select the file in the File Open dialog. The ASCII Text Import dialog will be displayed.

You may notice that the dialog is more complicated than the corresponding spreadsheet dialog. Since there is no standard format for ASCII text files, we need to provide a variety of options to handle various types of files.

Preview - First 16K of file:

LABEL	P85	P75	RMT85	CS82	S582	S82	ME84	REV84	REG	CL
1	33	27	288	13	24	49	2135	2836	1	1
2	19	15	139	14	12	41	957	2035	1	1
3	26	20	196	12	14	41	1530	6030	1	1
4	19	15	159	12	19	41	1059	4704	1	1
5	56	52	536	20	27	61	3951	5183	1	1

Note that the preview window at the bottom of the dialog shows you the first 16K of your file. You can use this information to set the various formatting options in the dialog.

You must provide the following information:

- Names for series or Number of series if names in file. If the file does not contain series names, or if you do not want to use the names in the file, list the names of the series in the order they appear in the file, separated by spaces.

If the names of the series are located in the file before the start of the data you can tell EViews to use these names by entering a number representing the number of series to be read.

If possible, you should avoid using parentheses and mathematical symbols such as “*”, “+”, “-”, “/”, “^” in the series names in the file. If EViews tries to read the names from the file and encounters an invalid name, it will try to rename the series to a valid name by replacing invalid characters with underscores and numbers. For example, if the series is named “X(-3)” in the file, EViews will rename this series to “X__3_01”. If “X__3_01” is already a series name, then EViews will name the series “X__3_02”, and so forth.

If EViews cannot name your series, say, because the name is a reserved name, or because the name is used by an object that is not a series, the series will be named "SER01", "SER02", etc.

You should be very careful in naming your series and listing the names in the dialog. If the name in the list or in the file is the same as an existing series name in the workfile, the data in the existing series will be overwritten.

- Data order . You need to specify how the data are organized in your file. If your data are ordered by observation so that each series is in a column, select Columns . If your data are ordered by series so that all the data for the first series are in one row followed by all the data for the second series, and so on, select Rows .
- Import sample . You should specify the sample in which to place the data from the file. EViews fills out the dialog with the current workfile sample, but you can edit the sample string or use the sample reset buttons to change the input sample. The input sample only sets the sample for the import procedure, it does not alter the workfile sample.

EViews fills all of the observations in the current sample using the data in the input file. There are a couple of rules to keep in mind:

1. EViews assigns values to all observations in the input sample. Observations outside of the input sample will not be changed.
2. If there are too few values in the input file, EViews will assign NAs to the extra observations in the sample.
3. Once all of the data for the sample have been read, the remainder of the input file will be ignored.

In addition to the above information, you can use the following options to further control the way EViews reads in ASCII data.

EViews scans the first few lines of the source file and sets the default formatting options in the dialog based on what it finds. However, these settings are based on a limited number of lines and may not be appropriate. You may find that you need to reset these options.

Delimiters

Delimiters are the characters that your file uses to separate observations. You can specify multiple delimiters by selecting the appropriate entries. Tab, Comma, and Space are self-explanatory. The Alpha option treats any of the 26 characters from the alphabet as a delimiter.

For delimiters not listed in the option list, you can select the Custom option and specify the symbols you wish to treat as delimiters. For example, you can treat the slash "/" as a delimiter by selecting Custom and entering the character in the edit box. If you enter more than one character, each character will be treated as a delimiter. For example, if you enter double

slash “/” in the Custom field, then the single slash “/” will be treated as a delimiter, instead of the double slash “//”. The double slash will be interpreted as two delimiters.

EViews provides you with the option of treating multiple delimiter characters as a single delimiter. For example, if “,” is a delimiter and the option Treat multiple delimiters as one is selected, EViews will interpret “,,” as a single delimiter. If the option is turned off, EViews will view this string as two delimiters surrounding a missing value.

Rectangular File Layout Options

To treat the ASCII file as a rectangular file, select the File laid out as rectangle option in the upper right-hand portion of the dialog. If the file is rectangular, EViews reads the file as a set of lines, with each new line denoting a new observation or a new series, depending on whether you are reading by column or by row. If you turn off the rectangular option, EViews treats the whole file as one long string separated by delimiters and carriage returns.

Knowing that a file is rectangular simplifies ASCII reading since EViews knows how many values to expect on a given line. For files that are not rectangular, you will need to be precise about the number of series or observations that are in your file. For example, suppose that you have a non-rectangular file that is ordered in columns and you tell EViews that there are four series in the file. EViews will ignore new lines and will read a new observation after reading every four values.

If the file is rectangular, you can tell EViews to skip columns and/or rows.

For example, if you have a rectangular file and you type 3 in the Rows to skip field, EViews will skip the first three rows of the data file. Note that you can only skip the first few rows or columns; you cannot skip rows or columns in the middle of the file.

Series Headers

This option tells EViews how many “cells” to offset as series name headers before reading the data in the file. The way that cell offsets are counted differs depending on whether the file is in rectangular form or not.

For files in rectangular form, the offsets are given by rows (for data in columns) or by columns (for data in rows). For example, suppose your data file looks as follows:

There is a one line (row) gap between the series name line and the data for the first observation. In this case, you should set the series header offset as 2, one for the series name line and one for the gap. If there were no gap, then the correct offset would instead be 1.

For files not in rectangular form, the offsets are given by the number of cells separated by the delimiters. For example, suppose you have a data file that looks as follows:

The data are ordered in columns, but each observation is recorded in two lines, the first line for the first 10 series and the second line for the remaining 4 series.

It is instructive to examine what happens if you incorrectly read this file as a rectangular file with 14 series and a header offset of 2. EViews will look for the series names in the first line, will skip the second line, and will begin reading data starting with the third line, treating each line as one observation. The first 10 series names will be read correctly, but since EViews will be unable to find the remaining four names on the first line, the remaining series will be named SER01–SER04. The data will also be read incorrectly. For example, the first four observations for the series GR will be 215.9800, NA, 180.4800, and NA, since EViews treats each line as a new observation.

To read this data file properly, you should turn off the rectangle file option and set the header offset to 1. Then EViews will read, from left to right, the first 14 values that are separated by a delimiter or carriage return and take them as series names. This corresponds to the header offset of 1, where EViews looks to the number of series (in the upper left edit box) to determine how many cells to read per header offset. The next 14 observations are the first observations of the 14 series, and so on.

Miscellaneous Options

- Quote with single ' not " . The default behavior in EViews is to treat anything inside a pair of matching double quotes as one string, unless it is a number. This option treats anything inside a pair of matching single quotes as one string, instead of the double quotes. Since EViews does not support strings, the occurrence of a pair of matching double quotes will be treated as missing, unless the text inside the pair of double quotes may be interpreted as a number.
- Drop strings—don't make NA . Any input into a numeric series that is not a number or delimiter will, by default, be treated as a missing observation. For example, "10b" and "90:4" will both be treated as missing values (unless Alphabetic characters or ":" are treated as delimiters). The Drop strings option will skip these strings instead of treating them as NAs.

If you choose this option, the series names, which are strings, will also be skipped so that your series will be named using the EViews default names: "SER01", "SER02", and so on. If you wish to name your series, you should list the series names in the dialog.

Note that strings that are specified as missing observations in the Text for NA edit box will not be skipped and will be properly indicated as missing.

- Numbers in () are negative . By default, EViews treats parentheses as strings. However, if you choose this option, numbers in parentheses will be treated as negative numbers and will be read accordingly.
- Allow commas in numbers . By default, commas are treated as strings unless you specify them as a delimiter. For example, “1,000” will be read as either NA (unless you choose the drop string option, in which case it will be skipped) or as two observations, 1 and 0 (if the comma is a delimiter). However, if you choose to Allow commas in numbers , “1,000” will be read as the number 1000.
- Currency . This option allows you to specify a symbol for currency. For example, the default behavior treats “\$10” as a string (which will either be NA or skipped) unless you specify “\$” as a delimiter. If you enter “\$” in the Currency option field, then “\$10” will be read as the number 10.

The currency symbol can appear either at the beginning or end of a number but not in the middle. If you type more than one symbol in the field, each symbol will be treated as a currency code. Note that currency symbols are case sensitive. For example, if the Japanese yen is denoted by the “Y” prefix, you should enter “Y”, not “y”.

- Text for NA . This option allows you to specify a code for missing observations. The default is NA. You can use this option to read data files that use special values to indicate missing values, e.g., “.”, or “-99”.

You can specify only one code for missing observations. The entire Text for NA string will be treated as the missing value code.

Examples

In these examples, we demonstrate the ASCII import options using example data files downloaded from the Internet. The first example file looks as follows:

This is a cross-section data set, with seven series ordered in columns, each separated by a single space. Note that the B series takes string values, which will be replaced by NAs. If we type 7 series in the number of series field and use the default setting, EViews will correctly read the data.

By default, EViews checks the Treat multiple delimiters as one option even though the series are delimited by a single space. If you do not check this option, the last series BB will not be read. EViews will create a series named “SER01” and all data will be incorrectly

imported. This strange behavior is caused by an extra space in the very first column of the data file, before the 1st and 3rd observations of the X series. EViews treats the very first space as a delimiter and looks for the first series data before the first extra space, which is missing. Therefore the first series is named SER01 with data NA, 10, NA, 12 and all other series are incorrectly imported.

To handle this case, EViews automatically ignores the delimiter before the first column data if you choose both the Treat multiple delimiters as one and the File laid out as rectangle options.

The top of the second example file looks like:

This is a cross-section data set, ordered in columns, with missing values coded as “-999.0”. There are eight series, each separated by spaces. The first series is the ID name in strings.

If we use the EViews defaults, there will be problems reading this file. The spaces in the ID description will generate spurious NA values in each row, breaking the rectangular format of the file. For example, the first name will generate two NAs, since “African” is treated as one string, and “elephant” as another string.

You will need to use the Drop strings option to skip all of the strings in your data so that you don't generate NAs. Fill out the ASCII dialog as follows:

Note the following:

- Since we skip the first string series, we list only the remaining seven series names.
- There are no header lines in the file, so we set the offset to 0.

- If you are not sure whether the delimiter is a space or tab, mark both options. You should treat multiple delimiters as one.
- Text for NA should be entered exactly as it appears in the file. For this example, you should enter “-999.0 ”, not “ -999”.

The third example is a daily data file that looks as follows:

This file has 10 lines of data description, line 11 is the series name header, and the data begin in line 12. The data are ordered in columns in rectangular form with missing values coded as a “0”. To read these data, you can instruct EViews to skip the first 10 rows of the rectangular file, and read three series with the names in the file, and NAs coded as “0”.

The screenshot shows the 'ASCII Text Import' dialog box with the following settings:

- Name for series or Number if named in file:** 3
- Data order:** ☒ in Columns, ☐ in Rows
- Rectangular file layout:** ☒ File laid out as rectangle
 - Columns to skip: 0
 - Rows to skip: 10
 - Comment character:
- Series headers:** # of headers (including names) before data: 1
- Import sample:** 1/02/1989 12/31/1993
 - Reset sample to: ☐ Current sample, ☐ Workfile range, ☐ To end of range
- Delimiters:** ☒ Treat multiple delimiters as one
 - ☒ Tab, ☒ Comma, ☒ Space
 - ☐ Alpha (A-Z), ☐ Custom:
- Miscellaneous:**
 - ☐ Quote with single ' not "
 - ☐ Drop strings - don't make NA
 - ☐ Numbers in (..) are negative
 - ☐ Allow commas in numbers
 - Currency:
 - Text for NA: 0

The only problem with this method is that the DATE series will be filled with NAs since EViews treats the entry as a string (because of the “/” in the date entry). You can avoid this problem by identifying the slash as a delimiter using the Custom edit box. The first column will now be read as three distinct series since the two slashes are treated as delimiters. Therefore, we modify the option settings as follows:

The screenshot shows the 'ASCII Text Import' dialog box with the following settings:

- Name for series or Number if named in file:** month day year aaa baa
- Data order:** in Columns (selected)
- Rectangular file layout:**
 - ☒ File laid out as rectangle
 - Columns to skip: 0
 - Rows to skip: 11
 - Comment character:
- Series headers:** # of headers (including names) before data: 0
- Import sample:** 10/02/1989 12/31/1993
 - Reset sample to:
 - ☐ Current sample
 - ☐ Workfile range
 - ☐ To end of range
- Delimiters:**
 - ☒ Treat multiple delimiters as one
 - ☒ Tab
 - ☒ Comma
 - ☒ Space
 - ☐ Alpha (A-Z)
 - ☒ Custom: /
- Miscellaneous:**
 - ☐ Quote with single ' not "
 - ☐ Drop strings - don't make NA
 - ☐ Numbers in (...) are negative
 - ☐ Allow commas in numbers
 - Currency:
 - Text for NA: 0

Note the changes to the dialog entries:

- We now list five series names. We cannot use the file header since the line only contains three names.
- We skip 11 rows with no header offset since we want to skip the name header line.
- We specify the slash "/" as an additional delimiter in the Custom option field.

The month, day, and year will be read as separate series and can be used as a quick check of whether the data have been read correctly.

Chapter 6. Working with Data

In the following discussion, we describe EViews' powerful language for using numeric expressions and generating and manipulating the data in series and groups. We first describe the fundamental rules for working with mathematical expressions in EViews, and then describe how to use these expressions in working with series and group data.

More advanced tools for working with numeric data, and objects for working with different kinds of data are described in [Chapter 7. "Working with Data \(Advanced\)," beginning on page 155](#)

Numeric Expressions

One of the most powerful features of EViews is the ability to use and to process mathematical expressions. EViews contains an extensive library of built-in operators and functions that allow you to perform complicated mathematical operations on your data with just a few keystrokes. In addition to supporting standard mathematical and statistical operations, EViews provides a number of specialized functions for automatically handling the leads, lags and differences that are commonly found in time series data.

An EViews expression is a combination of numbers, series names, functions, and mathematical and relational operators. In practical terms, you will use expressions to describe all mathematical operations involving EViews objects.

As in other programs, you can use these expressions to calculate a new series from existing series, to describe a sample of observations, or to describe an equation for estimation or forecasting. However, EViews goes far beyond this simple use of expressions by allowing you to use expressions virtually anywhere you would use a series. We will have more on this important feature shortly, but first, we describe the basics of using expressions.

Operators

EViews expressions may include operators for the usual arithmetic operations. The operators for addition (+), subtraction (-), multiplication (*), division (/) and raising to a power (^) are used in standard fashion so that:

$$5 + 6 * 7.0 / 3$$
$$7 + 3e-2 / 10.2345 + 6 * 10^2 + 3e3$$
$$3^2 - 9$$

are all valid expressions. Notice that explicit numerical values may be written in integer, decimal, or scientific notation.

In the examples above, the first expression takes 5 and adds to it the product of 6 and 7.0 divided by 3 ($5 + 14 = 19$); the last expression takes 3 raised to the power 2 and subtracts 9 ($9 - 9 = 0$). These expressions use the order of evaluation outlined below.

The “-” and “+” operators are also used as the unary minus (negation) and unary plus operators. It follows that:

```
2-2
-2+2
2+++++++--2
2---2
```

all yield a value of 0.

EVIEWS follows the usual order in evaluating expressions from left to right, with operator precedence order as follows (from highest precedence to lowest):

- unary minus (-), unary plus (+)
- exponentiation (^)
- multiplication (*), division (/)
- addition (+), subtraction (-)
- comparison (< , > , <= , >= , =)
- and , or

The last two sets of operators are used in logical expressions.

To enforce a particular order of evaluation, you can use parentheses. As in standard mathematical analysis, terms which are enclosed in parentheses are treated as a subexpression and evaluated first, from the innermost to the outermost set of parentheses. We strongly recommend the use of parentheses when there is any possibility of ambiguity in your expression.

To take some simple examples,

- -1^2 , evaluates to $(-1)^2 = 1$ since the unary minus is evaluated prior to the power operator.
- $-1 + -2 * 3 + 4$, evaluates to $-1 + -6 + 4 = -3$. The unary minus is evaluated first, followed by the multiplication, and finally the addition.
- $(-1 + -2) * (3 + 4)$, evaluates to $-3 * 7 = -21$. The unary minuses are evaluated first, followed by the two additions, and then the multiplication.
- $3 * ((2 + 3) * (7 + 4) + 3)$, evaluates to $3 * (5 * 11 + 3) = 3 * 58 = 174$.

A full listing of operators is presented in [Chapter 10. “Operator and Function Reference,” on page 389](#) of the Command and Programming Reference

Series Expressions

Much of the power of EViews comes from the fact that expressions involving series operate on every observation, or element, of the series in the current sample. For example, the series expression:

$$2*y + 3$$

tells EViews to multiply every sample value of Y by 2 and then to add 3. We can also perform operations that work with multiple series. For example:

$$x/y + z$$

indicates that we wish to take every observation for X and divide it by the corresponding observation on Y, and add the corresponding observation for Z.

Series Functions

EViews contains an extensive library of built-in functions that operate on all of the elements of a series in the current sample. Some of the functions are “element functions” which return a value for each element of the series, while others are “summary functions” which return scalars, vectors or matrices, which may then be used in constructing new series or working in the matrix language (see [Chapter 8. “Matrix Language,” on page 159](#) of the Command and Programming Reference for a discussion of scalar, vector and matrix operations).

Most function names in EViews are preceded by the @sign. For example, @mean returns the average value of a series taken over the current sample, and @abs takes the absolute value of each observation in the current sample.

All element functions return NAs when any input value is missing or invalid, or if the result is undefined. Functions which return summary information generally exclude observations for which data in the current sample are missing. For example, the @mean function will compute the mean for those observations in the sample that are non-missing.

There is an extensive set of functions that you may use with series:

- A list of mathematical functions is presented in [Chapter 10. “Operator and Function Reference,” on page 389](#) of the Command and Programming Reference
- Workfile functions that provide information about observations identifiers or allow you to construct time trends are described in [Chapter 12. “Workfile Functions”](#) of the Command and Programming Reference
- Functions for working with strings and dates are documented in [“String Function Summary” on page 451](#) and [“Date Function Summary” on page 452](#) both in the Command and Programming Reference

The remainder of this chapter will provide additional information on some of these functions, then examples of expressions involving functions.

Series Elements

At times, you may wish to access a particular observation for a series. EViews provides you with a special function, `@elem`, which allows you to use a specific value of a series.

`@elem` takes two arguments: the first argument is the name of the series and the second is the date or observation identifier.

For example, suppose that you want to use the 1980Q3 value of the quarterly series `Y`, or observation 323 of the undated series `X`. Then the functions:

```
@elem(y, 1980Q3)
@elem(x, 323)
```

will return the values of the respective series in the respective periods.

Numeric Relational Operators

Relational comparisons may be used as part of a mathematical operation, as part of a sample statement, or as part of an if-condition in programs.

A numeric relational comparison is an expression which contains the “=” (equal), “>=” (greater than or equal), “<=” (less than or equal), “<>” (not equal), “>” (greater than), or “<” (less than) comparison operators. These expressions generally evaluate to TRUE or FALSE, returning a 1 or a 0, depending on the result of the comparison.

Comparisons involving strings are discussed in [“String Relational Operators,” beginning on page 67](#) of the Command and Programming Reference

Note that EViews also allows relational comparisons to take the value “missing” or NA, but for the moment, we will gloss over this point until our discussion of missing values (see [“Missing Values” on page 139](#)).

We have already seen examples of expressions using relational operators in our discussion of samples and sample objects. For example, we saw the sample condition:

```
incm > 5000
```

which allowed us to select observations meeting the specified condition. This is an example of a relational expression—it is TRUE for each observation on INCM that exceeds 5000; otherwise, it is FALSE.

As described above in the discussion of samples, you may use the “and” and “or” conjunction operators to build more complicated expressions involving relational comparisons:

```
(incm>5000 and educ>=13) or (incm>10000)
```


It is worth emphasizing the fact that EViews uses the number 1 to represent TRUE and 0 to represent FALSE. This internal representation means that you can create complicated expressions involving logical subexpressions. For example, you can use relational operators to recode your data:

$$0*(inc<100) + (inc\geq 100 \text{ and } inc<200) + 2*(inc\geq 200)$$

which yields 0 if INC<100, 1 if INC is greater than or equal to 100 and less than 200, and 2 for INC greater than or equal to 200.

The equality comparison operator “=” requires a bit more discussion, since the equal sign is used both in assigning values and in comparing values. We consider this issue in greater depth when we discuss creating and modifying series (see [“Series” on page 141](#)). For now, note that if used in an expression:

$$incm = 2000$$

evaluates to TRUE if INCOME is exactly 2000, and FALSE, otherwise.

Descriptive Statistics

Standard descriptive statistic functions are available in EViews. These include, but are not limited to functions to calculate the mean (`@mean`), the median (`@median`), the standard deviation (`@stdev`), the variance (`@var`) and covariance (`@cov`). The descriptive statistic functions all take an optional sample as an argument. For a full list of descriptive statistics functions, details on the use of samples, and some examples, see [“Descriptive Statistics,” on page 394](#) of the Command and Programming Reference

It should be noted that EViews offers two ways to calculate standard deviations, variances and covariances. The simple standard deviation function, `@stdev`, calculates the sample standard deviation, that is the square root of the sum-of-squares divided by $n - 1$. To calculate the population standard deviation, that is division by n , use the `@stdevp` function. Note for symmetry purposes there is also a `@stdevs` which performs the same calculation as `@stdev`.

The `@var` and `@cov` functions calculate the population variance and covariance respectively, i.e., they divide through by n . To calculate the sample variance or covariance use the `@vars` or `@covs` functions. Again, there are also `@varp` and `@covp` functions which do the same as `@var` or `@cov`.

Leads, Lags, Differences and Time Series Functions

It is easy to work with lags or leads of your series. Simply use the series name, followed by the lag or lead enclosed in parentheses. Lags are specified as negative numbers and leads as positive numbers so that,

$$income(-4)$$

is the fourth lag of the income series, while:

```
sales(2)
```

is the second lead of sales.

While EViews expects lead and lag arguments to be integers, there is nothing to stop you from putting non-integer values in the parentheses. EViews will automatically convert the number to an integer; you should be warned, however, that the conversion behavior is not guaranteed to be systematic. If you must use non-integer values, you are strongly encouraged to use the `@round`, `@floor`, or `@ceil` functions to control the lag or lead behavior.

In many places in EViews, you can specify a range of lead or lag terms. For example, when estimating equations, you can include expressions of the form:

```
income(-1 to -4)
```

to represent all of the INCOME lags from 1 to 4. Similarly, the expressions:

```
sales sales(-1) sales(-2) sales(-3) sales(-4)
```

```
sales(0 to -4)
```

```
sales(to -4)
```

are equivalent methods of specifying the level of SALES and all lags from 1 to 4.

The `@lag` function can also be used to specify lags. Thus the expressions:

```
@lag(sales,1)
```

```
sales(-1)
```

are equivalent. Note one useful function of `@lag` is that it will take the lag of everything within parenthesis. `@lag` can therefore be used to find the lag of an expression. Typing:

```
@lag((sales-income)/sales,4)
```

```
(sales(-4)-income(-4))/sales(-4)
```

yields identical results.

EViews also has several built-in functions for working with difference data in either levels or in logs. The “D” and “DLOG” functions will automatically evaluate the differences for you. For example, instead of taking differences explicitly,

```
income - income(-1)
```

```
log(income) - log(income(-1))
```

you may use the equivalent expressions,

```
d(income)
```

```
dlog(income)
```

You can take higher order differences by specifying the difference order. For example, the expressions:

```
d(income,4)
dlog(income,4)
```

represent the fourth-order differences of INCOME and log(INCOME).

If you wish to take seasonal differences, you should specify both the ordinary, and a seasonal difference term:

```
d(income,1,4)
dlog(income,1,4)
```

These commands produce first order differences with a seasonal difference at lag 4. If you want only the seasonal difference, specify the ordinary difference term to be 0:

```
d(income,0,4)
dlog(income,0,4)
```

Other time series functions provided by EViews include a number of percentage change type functions. The simplest of these, @pccalculates a simple one-period percentage change in a series. For example typing:

```
@pca(income)
```

calculates the annual percentage change in INCOME.

Two special types of time series functions, moving functions and cumulative functions are also available in EViews, and are described below.

Mathematical details of lags, leads, differences and percentage change functions are provided in [Chapter 10. "Operator and Function Reference," on page 389](#) of the Command and Programming Reference

Cumulative and Moving Statistic Functions

Cumulative and moving statistic functions provide information over a range, or "window" of observations. The cumulative functions come in two types, those that move forwards and those that move backwards. The forwards functions, which take the form @cum[stat] , have a window that starts at the start of the workfile (or if a sample is given in the function, from the start of the sample) up until the current observation.

The backwards functions, which take the form @cumb[stat] , start at the end of the workfile, or sample, and move backwards until the current observation.

Note for both type of cumulative function the length of the window is different for each observation. The cumulative functions may be thought of as perform "running total" type calculations. Missing values are not propagated in the cumulative functions, i.e., observations with a value equal to NA are simply skipped.

The moving statistic functions have a shorter, user specified, window length. They provide information on the n observations up to, and including, the current observation, where n is chosen by the user.

The moving functions come in two types, those that propagate missing values and those that do not. For the functions that do propagate missing values, which take the form `@movstatj`, if any of the observations within the window contain an NA the function will return NA. The functions that do not propagate, which take the form `@mstatj`, will simply skip any NA observations.

For more information on missing values see [“Missing Values” on page 139](#).

As an example, you could find out the maximum value of INCOME from the start of the workfile to each observation by typing:

```
show @cummax(income)
```

If the first, say, four observations of INCOME are 100, 120, 110, 140 then this command will show a series as 100, 120, 120, and 140 as the first four observations.

If you wanted to know at each observation the average of the previous 3 years (including the current year) SALES figures you could type:

```
show @movav(sales,3)
```

Note this is equal to:

```
show (sales + sales(-1) + sales(-2))/3
```

Note that the lag or lead operators can be used inside a moving statistic function to allow you to control the exact start and end point of your window. For example, if you wanted to know, at each observation, the sum of SALES from three years ago, two years ago and last year (i.e. the sum of SALES(-1), SALES(-2) and SALES(-3)) you could type:

```
show @movsum(sales(-1),3)
```

Further details and a complete list of cumulative functions can be found in [“Cumulative Statistical Functions” on page 397](#), and for moving functions in [“Moving Statistic Functions” on page 400](#) both in the Command and Programming Reference

Ranking Series

EViews has an `@ranks` function which will generate a series based upon the ranking of another series. Ranking can be either ascending or descending depending upon whether “a” or “d” is used as an option in the function. For example to create series, ARANK, which contains the ascending ranks of the observations in the series SALES you could type:

```
series arank = @ranks(sales,a)
```

and to create a series containing the descending ranks you could type:

```
series drank = @ranks(sales,d)
```

EViews provides a number of different ways of handling ties in the ranking. For more details see `@ranks` in [“Descriptive Statistics” on page 394](#) of the Command and Programming Reference

Missing Values

Occasionally, you will encounter data that are not available for some periods or observations, or you may attempt to perform mathematical operations where the results are undefined (e.g., division by zero, log of a negative number). EViews uses the code NA (not available) to represent these missing values.

For the most part, you need not worry about NAs. EViews will generate NAs for you when appropriate, and will automatically exclude observations with NAs from statistical calculations. For example, if you are estimating an equation, EViews will use the set of observations in the sample that have no missing values for the dependent and all of the independent variables.

There are, however, a few cases where you will need to work with NAs, so you should be aware of some of the underlying issues in the handling of NAs.

First, when you perform operations using multiple series, there may be alternative approaches for handling NAs. EViews will usually provide you with the option of casewise exclusion (common sample) or listwise exclusion (individual sample). With casewise exclusion, only those observations for which all of the series have non-missing data are used. This rule is always used, for example, in equation estimation. For listwise exclusion, EViews will use the maximum number of observations possible for each series, excluding observations separately for each series in the list of series. For example, when computing descriptive statistics for a group of series, you have the option to use a different sample for each series.

If you must work directly with NAs, just keep in mind that EViews NAs observe all of the rules of IEEE NaNs. This means that performing mathematical operations on NAs will generate missing values. Thus, each of the following expressions will generate missing values:

```
@log(-abs(x))
1/(x-x)
(-abs(x))^(1/3)
3*x + NA
exp(x*NA)
```

For the most part, comparisons involving NA values propagate NA values. For example, the commands:

```
series y = 3
```

```
series x = NA
series equal = (y = x)
series greater = (y > x)
```

will create series EQUAL and GREATER that contain NA values, since the comparison between observations in a series involving an NA yields an NA.

Note that this NA handling behavior differs from EViews 4 and earlier in which NAs were treated as ordinary values for purposes of equality (“=”) and inequality (“<”) testing. In these versions of EViews, the comparison operators “=” and “<” always returned a 0 or a 1. The change in behavior was deemed necessary to support the use of string missing values. In all versions of EViews, comparisons involving ordering (“>”, “<”, “<=”, “>=”) propagate NAs.

It is still possible to perform comparisons using the previous methods. One approach is to use the special functions `@eqna` and `@neqna` for performing equality and strict inequality comparisons without propagating NAs. For example, you may use the commands:

```
series equal1 = @eqna(x, y)
series nequal = @neqna(x, y)
```

so that NAs in either X or Y are treated as ordinary values for purposes of comparison. Using these two functions, EQUAL1 will be filled with the value 0, and NEQUAL will be filled with the value 1. Note that the `@eqna` and `@neqna` functions do not compare their arguments to NA, but rather facilitate the comparison of values so that the results are guaranteed to be 0 or 1. See also [“Version 4 Compatibility Mode” on page 123](#) of the Command and Programming Reference for settings that enable the previous behavior for element comparisons in programs.

To test whether individual observations in a series are NAs, you may use the `@isna` function. For example,

```
series isnaval = @isna(x)
```

will fill the series ISNAVAL with the value 1, since each observation in X is an NA.

There is one special case where direct comparison involving NAs does not propagate NAs. If you test equality or strict inequality against the literal NA value:

```
series equal2 = (x = NA)
series nequal2 = (y <> NA)
```

EViews will perform a special test against the NA value without propagating NA values. Note that these commands are equivalent to the comparisons involving the special functions:

```
series equal3 = @eqna(x, NA)
series nequal3 = @neqna(y, NA)
```

If used in a mathematical operation, a relational expression resulting in an NA is treated as an ordinary missing value. For example, for observations where the series X contains NAs, the mathematical expression

$$5*(x>3)$$

will yield NAs. However, if the relational expression is used as part of a sample or IF-statement, NA values are treated as FALSE.

smpl 1 1000 if x>y

smpl 1 1000 if x>y and not @isna(x) and not @isna(y)

are equivalent since the condition $x>3$ implicitly tests for NA values. One consequence of this behavior is that:

smpl 1 1000 if x<NA

will result in a sample with no observations since less-than tests involving NAs yield NAs.

Very early versions of EViews followed the IEEE rules for missing data with one important exception. In EViews 2 and earlier, multiplying any number by zero (including NAs) yielded a zero. In subsequent versions, the value NA times zero equals NA. Thus, an earlier recommended method of recoding (replacing) NA values in the series X no longer worked so that the command for replacing NA values with the values in Y:

$$x = (x <> na) * x + (x = na) * y$$

works in EViews 2, but does not work subsequent versions. The @nan function has been provided for this purpose.

$$x = @nan(x, y)$$

recodes NA values of X to take the values in the series Y. See [Operators](#) on page 390 of the Command and Programming Reference

Series

One of the primary uses of expressions is to generate new series from existing data or to modify the values in an existing series. Used in combination with samples, expressions allow you to perform sophisticated transformations of your data, saving the results in new or existing series objects.

The current discussion focuses on the basic numeric series object. Users who wish to work with alphanumeric or advanced series features should see [Chapter 7. "Working with Data \(Advanced\),"](#) on page 155 and [Chapter 8. "Series Links,"](#) on page 183

To create or modify a series, select Quick/Generate Series... or click on the Genr button on the workfile toolbar. EViews opens a window prompting you for additional information.

You should enter the assignment statement in the upper edit box, and the relevant sample period in the lower edit box.

The assignment statement is actually an implicit loop over observations. Beginning with the first observation in the sample, EViews will evaluate the assignment statement for each included observation.

Basic Assignment

You can type the series name, followed by an equal sign and then an expression. For every element of the sample, EViews will evaluate the expression on the right-hand side of the equality, and assign the value to the destination series on the left-hand side, creating the series if necessary.

For example, if there is no series named Y,

$$y = 2 * x + 37 * z$$

will first create the Y series and fill it with NAs. Then, for every observation in the current sample, EViews will fill each element of the Y series with the value of the expression. If Y does exist, EViews will only replace Y values in the current sample with the value of the expression. All observations not in the sample will be unchanged.

One special form of assignment occurs when the right-hand side of the assignment statement is a constant expression:

$$y = 3$$

$$y = 37 * 2 + 3$$

EViews will simply assign the value of the constant to all of the observations in the sample.

Using Samples

By modifying the sample of observations used in assignment, you can splice together series using multiple Genr commands. For example, if we enter three Genr commands with different samples: first


Upper window: `y = z`

Lower window: `@all if z <= 1 and z > -1`

followed by a Genr with,

Upper window: `y = -2 + 3 * z`

Lower window: `if z > 1`



and finally,

Upper window: $y = -.9 + .1*z$

Lower window: $\text{if } z \leq -1$

we can generate Y as a piecewise linear function of the series Z. Note that the “@ALL” is implicit in the latter two assignments.

While it is possible to perform these types of operations using loops and IF-statements (see [Chapter 6. “EViews Programming,” on page 105](#) of the Command and Programming Reference), we strongly urge you to use `genr` and sample statements where possible, since the latter approach is much more efficient.

Dynamic Assignment

Since EViews evaluates the assignment expression for each observation in the sample, you can perform dynamic assignment by using lagged values of the destination series on the right side of the equality. For example, suppose we have an annual workfile that ranges from 1945 to 1997. Then if we enter:

Upper window: $y = y + y(-1)$

Lower window: 1946 1997

EViews will replace the Y series with the cumulative sum of Y. We begin with 1946, since we do not want to transform the first value in the workfile. Then for each period, EViews will take the current value of Y and add it to the lagged value of Y. The assignment is dynamic because as we successively move on to the next period, the lagged value of Y contains the cumulative sum.

Note that this procedure destroys the original data. To create a new series with the cumulative sums, you will have to perform the assignment in two steps, first making a copy of the original series, and then performing the dynamic assignment.

Implicit Assignment

You can make an implicit assignment by putting a simple formula on the left-hand side of the equal sign. EViews will examine your expression and select, as the destination series, the first valid series name on the left-hand side of the equality. Then for every observation in the sample, EViews will assign values using the implicit relationship. For example, if you enter:

$\log(y) = x$

EViews will treat Y as the destination series, and evaluate $y = \exp(x)$ for every observation in the sample.

The following are examples of valid assignment statements where Y is the destination series:

```
1/y = z
log(y/x)/14.14 = z
log(@inv(y)*x) = z
2+y+3*z = 4*w
d(y) = nrnd
```

In general, EViews can solve for, or normalize, equations that use the following on the left-hand side of the equality: +, −, *, /, ^, log() , exp() , sqr() , d() , dlog() , @inv() .

Since Genr is not a general equation solver, there will be situations in which EViews cannot normalize your equation. You cannot, for example, use the assignment statement:

```
@tdist(y, 3) = x
```

since @tdist is not one of the functions that EViews knows how to invert. Similarly, EViews cannot solve for equations where the destination series appears more than once on the left side of the equality. For example, EViews cannot solve the equation:

```
x + 1/x = 5
```

In both cases, EViews will display the error message “Unable to normalize equation”.

Note that the destination series can appear on both sides of the equality. For example:

```
log(x) = x
```

is a legal assignment statement. EViews will normalize the expression and perform the assignment

```
x = exp(x)
```

so that X will be assigned the exponential of the original value of X. EViews will not solve for the values of X satisfying the equality “LOG(X) = X”.

Using the Command Window

You can create series and assign values from the command window. First, set the workfile sample using the `smpl` statement, then enter the assignment statement.

There are alternative forms for the assignment statement. First, if the series does not exist, you must use either the `series` or the `genr` keyword, followed by the assignment expression. The two statements:

```
series y = exp(x)
genr y = exp(x)
```

are equivalent methods of generating the series Y. Once the series has been created, subsequent assignment statements do not require the `series` or the `genr` keyword:

```
smpl @all
series y = exp(x)
```

```
smpl 1950 1990 if y>300
```

```
y = y/2
```

This set of commands first sets the series to equal $\text{EXP}(X)$ for all observations, then assigns the values $Y/2$ for the subset of observations from 1950 to 1990 if $Y > 300$.

Auto-series

Another important method of working with expressions is to use an expression in place of a series. EViews' powerful tools for expression handling allow you to substitute expressions virtually any place you would use a series—as a series object, as a group element, in equation specifications and estimation, and in models.

We term expressions that are used in place of series as **auto-series** since the transformations in the expressions are automatically calculated without an explicit assignment statement.

Auto-series are most useful when you wish to see the behavior of an expression involving one or more series, but do not want to keep the transformed series, or in cases where the underlying series data change frequently. Since the auto-series expressions are automatically recalculated whenever the underlying data change, they are never out-of-date.

See [“Auto-Updating Series” on page 155](#) for a more advanced method of handling series and expressions.

Creating Auto-series

It is easy to create and use an auto-series—anywhere you might use a series name, simply enter an EViews expression. For example, suppose that you wish to plot the log of CP against time for the period 1953M01 to 1958M12. There are two ways in which you might plot these values.

One way to plot these values is to generate an ordinary series, as described earlier in [“Basic Assignment” on page 142](#), and then to plot its values. To generate an ordinary series containing the log of CP, say with the name LOGCP, select **Quick/Generate series...** from the main menu, and enter,

```
logcp = log(cp)
```

or type the command,

```
series logcp = log(cp)
```

in the command window. EViews will evaluate the expression $\text{LOG}(\text{CP})$ for the current values of CP, and will place these values into the series LOGCP. To view a line graph view of the series, open the series LOGCP and select **View/Graph/Line**.

Note that the values of the ordinary series LOGCP will not change when CP is altered. If you wish to update the values in LOGCP to reflect subsequent changes in CP, you will need to issue another series or gener assignment statement.


Alternatively, you may create and use an auto-series by clicking on the Show button on the toolbar, or selecting Quick/Show... and entering the command,

log(cp)

or by typing


show log(cp)

in the command window . EViews will open a series window in spreadsheet view:



Note that in place of an actual series name, EViews substitutes the expression used to create the auto-series.

An auto-series may be treated as a standard series window so all of the series views and procedures are immediately available. To display a time series graph of the LOG(CP) auto-series, simply select View/Graph... from the series window toolbar and click OK to create a line graph:



All of the standard series views and procedures are also accessible from the menus.


Note that if the data in the CP series are altered, the auto-series will reflect these changes. Suppose, for example, that we take the first four years of the CP series, and multiply them by a factor of 10:

```
smpl 1953m01 1956m12
```

```
cp = cp*10
```

```
smpl 1953m01 1958m12
```

The auto-series graph will automatically change to reflect the new data:




In contrast, the values of the ordinary series LOGCP are not affected by the changes in the CP data.

Similarly, you may use an auto-series to compute a 12-period, backward-looking, geometric moving average of the updated CP data. The command:

```
show @exp(@movav(@log(cp),12))
```

will display the auto-series containing the geometric moving average. To view a line graph of the auto-series, select View/Graph... from the series window toolbar and click OK:



Naming an Auto-series

The auto-series is deleted from your computer memory when you close the series window containing the auto-series. For more permanent expression handling, you may convert the auto-series into an auto-updating series that will be kept in the workfile, by assigning a name to the auto-series.

Simply click on the Name button on the series toolbar, or select Object/Name... from the main menu, and provide a name. EViews will create an auto-updating series with that name in the workfile, and will assign the auto-series expression as the formula used in updating the series. For additional details, see [“Auto-Updating Series” on page 155](#)

Using Auto-series in Groups

One of the more useful ways of working with auto-series is to include them in a group. Simply create the group as usual, using an expression in place of a series name, as appropriate. For example, if you select Object/New Object.../Group , and enter:


```
cp @exp(@movav(@log(cp),12))
```

you will create a group containing two series: the ordinary series CP, and the auto-series representing the geometric moving average. We may then use the group object graphing routines to compare the original series with the smoothed series. Select View/Graph... from the group window toolbar and click OK:

[“Groups” on page 150](#) below describes other useful techniques for working with auto-series.

Using Auto-Series in Estimation

One method of using auto-series in estimation is to allow expressions as right-hand side variables. Thus, you could estimate an equation with $\log(x)$ or $\exp(x+z)$ as an explanatory variable.



EViews goes a step beyond this use of auto-series, by allowing you to use auto-series as the dependent variable in estimation. Thus, if you want to regress the log of Y on explanatory variables, you don't have to

create a new variable LOGY. Instead, you can use the expression $\log(y)$ as your dependent variable.

When you forecast using an equation with an auto-series dependent variable, EViews will, if possible, forecast the untransformed dependent variable and adjust the estimated confidence interval accordingly. For example, if the dependent variable is specified as $\log(y)$, EViews will allow you to forecast the level of Y, and will compute the asymmetric confidence interval. See [Chapter 22. “Forecasting from an Equation,” on page 111](#) of User’s Guide II for additional details.

Groups

EViews provides specialized tools for working with groups of series that are held in the form of a group object. In [“Importing Data” on page 101](#), we used groups to import data from spreadsheets into existing workfiles. Briefly, a group is a collection of one or more series identifiers or expressions. Note that a group does not contain the data in the individual series, only references to the data in the series.

To create a group, select **Object/New Object.../Group** and fill in the dialog with names of series and auto-series. Or you may select **Show** from the workfile toolbar and fill out the dialog. Alternatively, type the command `group` in the command window, followed by a name to be given to the group and then the series and auto-series names:

```
group macrolist gdp invest cons
```

creates the group MACROLIST containing the series GDP, INVEST and CONS. Similarly,

```
group altlist log(gdp) d(invest) cons/price
```

creates the group ALTLIST containing the log of the series GDP, the first difference of the series INVEST, and the CONS series divided by the PRICE series.

There are a few features of groups that are worth keeping in mind:

- A group is simply a list of series identifiers. It is not a copy of the data in the series. Thus, if you change the data for one of the series in the group, you will see the changes reflected in the group.
- If you delete a series from the workfile, the series identifier will be maintained in all groups. If you view the group spreadsheet, you will see a phantom series containing NA values. If you subsequently create or import the series, the series values will be restored in all groups.
- Renaming a series changes the reference in every group containing the series, so that the newly named series will still be a member of each group.
- There are many routines in EViews where you can use a group name in place of a list of series. If you wish, for example, to use X1, X2, and X3 as right-hand side variables

in a regression, you can instead create a group containing the series, and use the group in the regression.

We describe groups in greater detail in [Chapter 12. "Groups," on page 379](#).

Accessing Individual Series in a Group

Groups, like other EViews objects, contain their own views and procedures. For now, note that you can access the individual elements of a named group as individual series.

To refer the n -th series in the group, simply append "(n)" to the group name. For example, consider the MACROLIST group, defined above. The expression MACROLIST(1) may be used to refer to GDP and MACROLIST(2) to refer to INVEST.

You can work with MACROLIST(1) as though it were any other series in EViews. You can display the series by clicking on the Show button on the toolbar and entering MACROLIST(1). You can include GDP in another group directly or indirectly. A group which contains:

```
macrolist(1) macrolist(2)
```

will be identical to a group containing

```
gdp invest
```

We can also use the individual group members as part of expressions in generating new series:

```
series realgdp = macrolist(1)/price  
series y = 2*log(macrolist(3))
```

or in modifying the original series:

```
series macrolist(2) = macrolist(2)/price
```

Note that in this latter example the `series` keyword is required, despite the fact that the INVEST series already exists. This is true whenever you access a series as a member of a group.

Other tools allow you to retrieve the number of series in a group using the `@count` group data member:

```
scalar numgroup = macrolist.@count
```

To retrieve the names of each of the series, you may use the group data member `@series-name`. These tools are described in greater detail in ["Group" on page 224](#) of the Command and Programming Reference

Group Row Functions

EViews allows you to generate a series based upon the rows, or observations, in a group. The most simple of these is the `@columns` function which simply returns a series where every observation is equal to the number of series in a group. This function provides exactly the same information as the `@count` data member of a group. Thus the expression:

```
series numgroup = @columns(macrolist)
```

produces the same result as:

```
series numgroup = macrolist.@count
```

There are also functions that will calculate the mean of a group's rows (`@rmean`), their standard deviation (`@rstdev`) and variance (`@rvar`).

The `@rvalcount` function can be used to find how many times a specific value occurs within the rows of a group. For example:

```
series numvals = @valcount(macrolist,5)
```

will create a series where each row of that series will be the count of how many of the series within the MACROLIST group contain the value “5” for that particular row. Note that the value argument for this function can be a scalar or a series.

A full list of the group row functions can be found in [“Group Row Functions” on page 404](#) of the Command and Programming Reference

Creating a Group By Expanding a Series

The `@expand` function allows you to create a group of dummy variables by expanding out one or more series into individual categories. For example, if the series UNION contains values equal to either “union”, “non-union”, then using:

```
group g1 @expand(union)
```

will create a group, G1, with two series, the first series containing 1 where-ever union is equal to “union” and zero elsewhere, the second series containing 1 where-ever union is equal to “non-union” and zero elsewhere.

`@expand` may also be used on more than one series to give the cross-interaction of different series. Thus if you have a second series called MARRIED that contains either “married” or “single” then entering:

```
group g2 @expand(union,married)
```

will create a group, G2, with four series, the first containing 1 where-ever UNION is equal to “union” and MARRIED is equal to “married”, the second series containing a 1 where-ever UNION is equal to “union” and MARRIED is equal to “single”, and so on.

The @expand function can be used as part of a mathematical expression, so that a command of:

```
group g3 2*@expand(union)
```

will create a group where the first series contains a 2 where-ever UNION is equal to "union". Further,

```
group g4 log(income)*@expand(married)
```

creates a group where the first series is equal to the values of the log of INCOME where-ever MARRIED is equal to "married" and so on.

One of the most useful applications of the @expand function is when specifying an equation object, since it can be used to automatically create dummy variables.

See also ["Automatic Categorical Dummy Variables" on page 28](#) of User's Guide II for additional discussion.

An Illustration

Auto-series and group processing provides you with a powerful set of tools for working with series data. As we saw above, auto-series provide you with dynamic updating of expressions. If we use the auto-series expression:

```
log(y)
```

the result will be automatically updated whenever the contents of the series Y changes.

A potential drawback of using auto-series is that expressions may be quite lengthy. For example, the two expressions:

```
log(gdp)/price + d(invest) * (cons + invest)
12345.6789 * 3.14159 / cons^2 + dlog(gdp)
```

are not suited to use as auto-series if they are to be used repeatedly in other expressions.

You can employ group access to make this style of working with data practical. First, create groups containing the expressions:

```
group g1 log(gdp)/price+d(invest)*(cons+invest)
group g2 12345.6789*3.14159/cons^2+dlog(gdp)
```

If there are spaces in the expression, the entire contents should be enclosed in parentheses.

You can now refer to the auto-series as G1(1) and G2(1). You can go even further by combining the two auto-series into a single group:

```
group myseries g1(1) g2(1)
```

and then referring to the series as MYSERIES(1) and MYSERIES(2). If you wish to skip the intermediate step of defining the subgroups G1 and G2, make certain that there are no

spaces in the subexpression or that it is enclosed in parentheses. For example, the two expressions in the group `ALT SERIES`,

```
group altseries (log(gdp)/price) 3.141*cons/price
```

may be referred to as `ALT SERIES(1)` and `ALT SERIES(2)`.

Scalars

Scalar objects are different from series and groups in that they hold a single number instead of data for each observation in the sample. Scalars are created by commands of the form:

```
scalar scalar_name = number
```

where you assign a number to the scalar name. The number may be an expression or special functions that return a scalar.

To examine the contents of a scalar, you may enter the command `show`, followed by the name of the scalar. For example:

```
scalar logl1 = eq1.@logl  
show logl1
```

stores the log likelihood value of the equation object named `EQ1` in a scalar named `LOGL1`, and displays the scalar window.

Chapter 7. Working with Data (Advanced)

In addition to the basic tools for working with numeric data outlined in [Chapter 6. “Working with Data,”](#) EViews provides additional tools and objects for more advanced data handling, or for working with different kinds of data.

Auto-Updating Series

One of the most powerful features of EViews is the ability to use a series expression in place of an existing series. These expressions generate auto-series in which the expression is calculated when in use, and automatically recalculated whenever the underlying data change, so that the values are never out of date.

Auto-series are designed to be discarded after use. The resulting downside to auto-series is that they are quite transitory. You must, for example, enter the expression wherever it is used; for example, you must type “LOG(X)” every time you wish to use an auto-series for the logarithm of X. For a single use of a simple expression, this requirement may not be onerous, but for more complicated expressions used in multiple settings, repeatedly entering the expression quickly becomes tedious.

For more permanent series expression handling, EViews provides you with the ability to define a series or alpha object that uses a formula. The resulting auto-updating series is simply an EViews numeric series or alpha series that is defined, not by the values currently in the object, but rather by an expression that is used to compute the values. In most respects, an auto-updating series may simply be thought of as a named auto-series. Indeed, naming an auto-series is one way to create an auto-updating series.

The formula used to define an auto-series may contain any of the standard EViews series expressions, and may refer to series data in the current workfile page, or in EViews databases on disk. It is worth emphasizing that in contrast with link objects, which also provide dynamic updating capabilities, auto-updating series are designed to work with data in a single workfile page.


Auto-updating series appear in the workfile with a modified version of the series or alpha series icon, with the numeric series icon augmented by an “=” sign to show that it depends upon a formula.

Defining an Auto-Updating Series

Using the Dialog


To turn a series into an auto-updating series, you will assign an expression to the series and tell EViews to use this expression to determine the series values. Simply click on the Properties button on the series or alpha series toolbar, or select View/Properties... from the main menu, then select the Values tab.

There are three radio buttons which control the values that will be placed in the numeric or alpha series ([“Alpha Series,” beginning on page 160](#)). The default setting is either Numeric data or Alphanumeric (text) data (depending on the series type) in which the series is defined by the values currently in the series; this is the traditional way that one thinks of defining a numeric or alpha series.



If instead you select Formula, enter a valid series expression in the dialog box, and click on OK, EViews will treat the series as an auto-updating series and will evaluate the expression, putting the resulting values in the series. Auto-updating numeric series appear with a new icon in the workfile—a slightly modified version of the standard series icon, featuring the series line with an extra equal sign, all on an orange background.

In this example, we instruct EViews that the existing series LOGTAXRT should be an auto-updating series that contains the natural logarithm of the TAXRATE2 series. As with an auto-series expression, the values in LOGTAXRT will never be out of date since they will change to reflect changes in TAXRATE2. In contrast to an auto-series, however, LOGTAXRT is a permanent series in the workfile which may be used like any other series.



Alternately, you may create an auto-updating series that links to a series in a database by selecting Database link. In contrast to an auto-updating series based on a formula which updates whenever the underlying data change, an auto-updating series based on a database link will update only when the workfile is first loaded (you will be prompted for whether to refresh the data series or not) or when you manually update the links by clicking on Object/

Manage Links & Formulae... in the workfile window, selecting Database links within series & alphas and clicking on the Refresh Links - update data from source button. You may also update the link by selecting Update from DB... in the series Object menu.

You may, at any time, change an auto-updating series into an standard numeric series by bringing up the Values page of the Properties dialog, and clicking on the Numeric data setting. EViews will then define the series by its current values. In this way you may freeze the formula series values at their existing values, a procedure that is equivalent to performing a standard series assignment using the provided expression.

Note that once an expression is entered as a formula in a series, EViews will keep the definition even if you specify the series by value. Thus, you may take a series that has previously been frozen, and return it to auto-updating by selecting Formula definition.

Issuing a Command

To create an auto-updating series using commands, you should use the formula keyword, `frml`, followed by an assignment statement. The following example creates a series named `LOW` that uses a formula to compute values. The auto-updating series takes the value 1 if either `INC` is less than or equal to 5000 or `EDU` is less than 13, and takes the value 0 otherwise:

```
frml low = inc<=5000 or edu<13
```

`LOW` is now an auto-updating series that will be reevaluated whenever `INC` or `EDU` change.

You may also define auto-updating alpha series using the `frml` keyword. If `FIRST_NAME` and `LAST_NAME` are alpha series, then the declaration:

```
frml full_name = first_name + " " + last_name
```

creates an auto-updating alpha series, `FULL_NAME`.

The same syntax should be used when you wish to apply a formula to an existing series.

```
series z = rnd
```

```
frml z = (x+y)/2
```

makes `Z` an auto-updating series that contains the average of series `X` and `Y`. Note that the previous values of `Z` are replaced, and obviously lost. Similarly, we may first define an alpha series and then apply an updating formula:

```
alpha a = "initial value"
```

```
frml a = @upper(first_name)
```

You may not, however, apply an alpha series expression to a numeric series, or vice versa. Given the series `Z` and `A` defined above, the following two statements:

```
frml z = @upper(first_name)
```

```
frml a = (x+y)/2
```

will generate errors.

Note that once a numeric series or alpha series is defined to be auto-updating, its values may not be modified directly, since they are determined from the formula. Thus, if Z is an auto-updating series, the assignment command:

$$z = \log(x)$$

will generate an error since an auto-updating series may not be modified. To modify Z you must either issue a new `frml` assignment or you must first set the values of Z to their current values by turning off auto-updating, and then issue the assignment statement.

To reset the formula in Z, you may simply issue the command:

$$\text{frml } z = \log(x)$$

to replace the formula currently in the series.

To turn off auto-updating for a series, you may use the special expression “@CLEAR” in your `frml` assignment. When you turn off auto-updating, EViews freezes the numbers or strings in the series at their current values. Once the series is set to current values, it is treated as an ordinary series, and may be modified as desired. Thus, the commands:

$$\text{frml } z = @\text{clear}$$

$$z = \log(x)$$


are allowed since Z is converted into an ordinary series prior to performing the series assignment.

Alternately, you may convert a named auto-updating series into an ordinary series by selecting **Object/Manage Links & Formulae...** from the workfile window and using the dialog to break the links in the auto-updating series.

One particularly useful feature of auto-updating series is the ability to reference series in databases. The command:

$$\text{frml } \text{gdp} = \text{usdata}::\text{gdp}$$

creates a series in the workfile called GDP that gets its values from the series GDP in the database USDATA. Similarly:




```
frml lgdp = log(usdata::gdp)
```

creates an auto-updating series named LGDP that contains the log of the values of GDP in the database USDATA.

Series that reference data in databases may be refreshed each time a workfile is loaded from disk. Thus, it is possible to setup a workfile so that its data are current relative to a shared database.

Naming an Auto-Series

If you have previously opened a window containing an ordinary auto-series, you may convert the auto-series into an auto-updating series by assigning a name. To turn an auto-series into an auto-updating series, simply click on the Name button on the toolbar, or select Object/Name... from the main menu, and enter a name. EViews will assign the name to the series object, and will apply the auto-series definition as the formula to use for auto-updating.

Suppose, for example, that you have opened a series window containing an auto-series for the logarithm of the series CP by clicking on the Show button on the toolbar, or selecting Quick/Show... and entering "LOG(CP)". Then, simply click on the Name button in the auto-series toolbar, and assign a name to the temporary object to create an auto-updating series in the workfile.

Additional Issues

Auto-updating series are designed to calculate their values when in use, and automatically update values whenever the underlying data change. An auto-updating series will assign a value to every observation in the current workfile, irrespective of the current values of the workfile sample.

In most cases, there is no ambiguity in this operation. For example, if we have an auto-updating series containing the expression "LOG(CP)", we simply take each observation on CP in the workfile, evaluate the log of the value, and use this as the corresponding auto-updating series value.


However, in cases where the auto-updating series contains an expression involving descriptive statistics, there is ambiguity as to whether the sample used to calculate the values is the sample at the time the auto-updating series was created, the sample at the time the series is evaluated, the entire workfile range, or some other sample.

To resolve this ambiguity, EViews will enter the current workfile sample into the expression at the time the auto-updating series is defined. Thus, if you enter "@MEAN(CP)" as your auto-updating series expression, EViews will substitute an expression of the form "@MEAN(CP, smpl)" into the definition. If you wish to evaluate the descriptive statistics for a given sample, you should enter an explicit sample in your expression.

Alpha Series

An alpha series object contains a set of observations on alphanumeric string values. Alpha series should be used when you wish to work with variables that contain alphanumeric data, such as names, addresses, and other text. If any of these types of data were entered into an ordinary series, EViews will replace the string with the numeric missing value, NA.

You may, for example, have an alpha series that contains the two-character U.S. Postal Service abbreviations for the 50 states, D.C., and Puerto Rico. Here, we show the alpha series, STATE, that contains the appropriate 2-character string values. STATE will be identified in the workfile with the alpha series icon labeled “abc”, and by the designation Alpha in the titlebar of the alpha series window.



Similarly, alpha series may be used to hold identifying information such as the names and addresses of individuals, social security and telephone numbers, or classifying labels such as “male” and “female”, or “high”, “medium”, and “low”.

Declaring an Alpha Series

To create a new alpha series, you may select Object/New Object... from the main EViews window or workfile button bar, and then click on Series Alpha and optionally enter a name to be given to your alpha series. If you provide a name, EViews will create a new alpha series object in the workfile. If you do not supply a name, EViews will open an UNTITLED alpha series window.

Alternatively, you may type the keyword “ALPHA”, followed by an optional series name, in the command window. The command:

alpha


will create a new untitled alpha series and will display the series in an object window. Likewise:

alpha myseries

will create a new alpha series MYSERIES. To open the alpha series windows for MYSERIES or SETSERIES, simply double-click on the corresponding alpha series icon in the workfile window directory, or enter the command "SHOW MYSERIES".

In both of the cases described above, the alpha series will be initialized to contain missing values. For alpha series, the empty string (the null string, "") is used to designate a missing value. If you are declaring an alpha series using a command, you may combine the declaration with the assignment of the values in the series. We explore alpha series assignment in ["Assigning values to Alpha Series" on page 162](#)

For the most part, you need not worry about the lengths of string values in your alpha series since EViews will automatically resize your series as required, up to the limit specified in the global defaults. Beyond that point, EViews will truncate the values of the alpha series. To modify the truncation length,



select Options/General Options... from the main menu and go to the Series and Alphas/Alpha truncation page. Enter the desired length, and subsequent alpha series creation and assignment will use the new truncation length.


You should bear in mind that the strings in EViews alpha series are of fixed length so that the size of each observation is equal to the length of the longest string. If you have a series with all short strings with the exception of one very long string, the memory taken up by the series will be the number of observations times the longest string. In settings of this sort, efficiency suggests that you consider using value maps (["Value Maps" on page 169](#)) to encode the values of the long string.

Editing an Alpha Series

There is no difference between editing an ordinary numeric series and editing an alpha series. Make certain that the alpha series is in edit mode by verifying the existence of the edit field in the series window. If not, click on the Edit +/- button to enable edit mode.

To edit a specific value, click on the desired cell. The existing value in the cell will appear in the edit window for you to modify or delete.

Simply type the new value in the edit window. Once you have entered the desired value, move to a new cell by clicking or using the arrow keys, or press the return key. This action will accept the entered value and prepare you for editing the newly selected cell.



Note that when editing the values of an alpha series, EViews does not require you to delimit your strings. You may simply type the relevant value in the edit field. EViews will remove any leading and trailing spaces from the value that you enter; if you wish to retain those characters, enclose your string in double quotes. To enter the double quote character as a part of your string, you should escape the character with another double quote so that you enter two consecutive double quotes.

Assigning values to Alpha Series

You may assign values to an alpha series using string expressions. An alpha series assignment has the form:

```
alpha_name= string_expr
```

where `alpha_name` is the name of an existing alpha series and `string_expr` is any expression containing a combination of string literals, alpha series, and functions or operators that return strings (see [“Strings” on page 65](#) of the Command and Programming Reference for details). As with ordinary series, we may combine the declaration and assignment steps so that the commands:

```
alpha alpha_name= string_expr
```

or

```
genr alpha_name= string_expr
```

first create the alpha series `alpha_name` and then will assign the values using `string_expr`. In the latter command, EViews notes that the right-hand side expression is a string so that it knows to create an alpha series.

Alternatively, assuming that the alpha series exists, you may reassign the series values by clicking on Quick/Generate Series... in the main menu and entering the assignment and sample statements in the dialog. For example, if you enter the expression:

```
myalpha = string_expr
```

in the dialog, EViews will assign the values of the string_expr to the existing alpha series MYALPHA. Alternatively, you may enter the expression in the command line. In both cases, EViews will assign the corresponding values for all observations in the current workfile sample, overwriting the existing values.

Let us consider a simple example. Suppose that we have data on the company name (NAME), ticker symbol (SYMBOL), time of last trade (LAST_TIME), and closing price (LAST_TRADE) for each of the stocks in the Dow Jones Industrial Average on September 10, 2003.

Clicking on the icon for NAME, we can display the alpha series spreadsheet view. Note here that the default column width is not wide

NAME				
		Last updated: unknown		
1	ALCOA INC			
2	AMER EXPR...			
3	BOEING CO			
4	CITIGROUP			
5	CATERPILL...			
6	DU PONT CO			
7	WALT DISN...			
8	EASTMAN K...			
9	GENERAL E...			
10	GENERAL ...			
11				

enough to display the contents of every observation, a condition that is signaled by the trailing "..." in the display for several of the observations. We may increase the column width by dragging the column header separators (the lines separating the column headers located just below the name of the series), by clicking on the Properties button and entering a larger number in the width field, or by double clicking on the column header separator to adjust the column width to the minimum width that displays all of the observation values without truncation.


Suppose now that we wish to create an alpha series containing the name of each company followed by its ticker symbol (enclosed in parentheses). A simple assignment statement generates the desired series:

```
alpha namesymb = name + " (" + symbol + ")"
```

EViews will create a new alpha series NAMESYMB if one doesn't exist. Then, for every observation in the workfile sample, the contents of the alpha series NAME are concatenated with the literal strings for the parentheses, and the contents of the SYMBOL series.

Working with Alpha Series

Once created, an alpha series is used in two primary ways: (1) to generate numeric values and (2) to provide identifiers for the observations in the workfile.



NAMESYMB	
Last updated: 08/12/09 - 18:54	
Modified: 1 30 // namesymb = name + "(" + symbol + ")"	
1	ALCOA INC (AA)
2	AMER EXPRESS CO (AXP)
3	BOEING CO (BA)
4	CITIGROUP (C)
5	CATERPILLAR INC (CAT)
6	DU PONT CO (DD)
7	WALT DISNEY CO (DIS)
8	EASTMAN KODAK (EK)
9	GENERAL ELEC CO (GE)
10	GENERAL MOTORS (GM)
11	

Generating Numeric Values

By definition, an alpha series contains a string value for each observation. This means that if you use an alpha series in a setting requiring numeric input, all of the values of the alpha series will be treated as NAs. For example, if you attempt to compute the mean of the STATE alpha series or use the Dow company NAME in an equation regression specification, EViews will generate an error saying that there are an insufficient number of observations, since all of the numeric values are missing.

You may, however, use the string relational operators (see ["String Relational Operators" on page 67](#) of the Command and Programming Reference) to generate a series of numeric values. For the data from our Dow Jones example, the commands:

```
smpl @all
series wname = (@lower(@left(NAME, 1)) = "w")
```

generate the numeric series WNAME containing the value 1 if the company name begins with the letter "W", and 0 otherwise.

Similarly, the relational operators may be used when specifying a subsample. The command:

```
smpl @all if gender = "Male"
```

will restrict the workfile sample to include only observations where the string value in the alpha series GENDER is "Male".

You may also use the various functions described in ["String Information Functions" on page 70](#) of the Command and Programming Reference to generate numeric values.

Two examples are of particular importance. First, you may have an alpha series that contains string representations of numbers, such as “3.14159”. In order to use the strings as actual numbers, you must translate them into numbers, using either the string evaluation function `@val`.

Suppose, in our Dow Jones example, that we have the alpha series `CHANGE` containing information on the stock price change, expressed in both levels and percentages.

If we wish to extract only the levels information from the alpha series, the `@left` function may be used to extract the leftmost four characters of each string. The `@val` function may then be used to obtain the numeric value for each observation. Putting this together, the command:

```
series chgval = @val(@left(change, 4))
```


converts the leading four characters of the `CHANGE` series into numeric values, and places the results in the series `CHGVAL`.

Second, you may have an alpha series that contains a text representation of dates. Here, we have a series `DATES` that contains text representations of dates in “dd-Mon-YY” format (one or two-digit day, dash, three-character month abbreviation, dash, two-digit year). For example, “12-Jun-03” represents June 12, 2003.

To convert every element of this series into a numeric series containing date values, simply issue the command:


```
series dval = @dateval(dates)
```

The newly created series `DVAL` will contain date numbers associated with each of the string values in `DATES`.



The screenshot shows a window titled "Alpha: CHANGE" with a menu bar (View, Proc, Object, Properties, Print, Name, Freeze, Raw Data, Sort) and a toolbar. The main area displays a table with the title "CHANGE". The table has a header row with "Last updated: unknown". The data rows show stock price changes for 10 observations, with columns for index, level, and percentage change.

CHANGE		
Last updated: unknown		
1	0.65	(2.28%)
2	0.51	(1.12%)
3	0.71	(1.95%)
4	0.33	(0.75%)
5	0.40	(0.58%)
6	0.69	(1.55%)
7	0.58	(2.74%)
8	0.41	(1.45%)
9	0.13	(0.42%)
10		



The screenshot shows a window titled "Alpha: DATES" with a menu bar (View, Proc, Object, Properties, Print, Name, Freeze, Raw Data, Sort) and a toolbar. The main area displays a table with the title "DATES". The table has a header row with "Last updated: unknown". The data rows show dates in "dd-Mon-YY" format for 10 observations, with columns for index, date string, and date value.

DATES		
Last updated: unknown		
437	12-Jun-03	
438	13-Jun-03	
439	16-Jun-03	
440	17-Jun-03	
441	18-Jun-03	
442	19-Jun-03	
443	20-Jun-03	
444	23-Jun-03	
445	24-Jun-03	
446	25-Jun-03	
447	26-Jun-03	
448	27-Jun-03	
449	30-Jun-03	
450		

Additional Issues

The Spreadsheet View

By default, the alpha series spreadsheet will display your data left-justified, with a column width of approximately 12 characters. You may change the justification and column width settings by clicking on the Properties button in the toolbar, then selecting a new justification setting and entering a new column width. Alternatively, the column width may be changed by dragging the separator in the columnheader to the desired position, or by double-clicking on the separator to adjust the column width to the minimum width that displays all of the observation values without truncation.

Auto-series

You should note that like ordinary series, you may also work directly with a series expression that produces an alpha series. For example, if ALPHA1 is an alpha series, the command:

```
show @lower(alpha1)
```

will result in an alpha series containing the contents of ALPHA1 with the text converted to all lowercase characters.

Auto-series expressions involving alpha series may also evaluate to ordinary series. For example, if NUMER1 is a numeric series and ALPHA1 is an alpha series, you may enter:

```
show numer1+@len(alpha1)+(alpha1>"cat")
```

to open a series window containing the results of the operation. Note that the parentheses around the relational comparison are required for correct parsing of the expression.

Date Series

A date series is a standard EViews numeric series that contains valid date values (see [“Dates” on page 82](#) of the Command and Programming Reference). There is nothing that distinguishes a date series from any other numeric series, except for the fact that the values it contains may be interpreted as dates.

Creating a Date Series

There is nothing special about creating a date series. Any method of creating an EViews series may be used to create a numeric series that will be used as a date series.

Displaying a Date Series

The numeric values in a date series are generally of interest only when performing calendar operations. For most purposes, you will wish to see the values of your date series as date strings.

For example, the following series QDATES in our quarterly workfile is a numeric series containing valid date values for the start of each quarter. The numeric values of QDATES depicted here show the number of days since 1 January A.D. 1.

QDATES	
Last updated: 07/24/06 - 16:47	
Modified: 1990Q1 2005Q4 // qdates=dates	
1990Q1	726467.0
1990Q2	726557.0
1990Q3	726648.0
1990Q4	726740.0
1991Q1	726832.0
1991Q2	726922.0
1991Q3	727013.0
1991Q4	727105.0
1992Q1	727197.0
1992Q2	727288.0
1992Q3	727379.0
1992Q4	

Obviously, this is not the way that most people will wish to view their date series. Accordingly, EViews provides considerable control over the display of the date values in your series. To change the display, click on the Properties button in the series toolbar, or select View/Properties... from the main menu.

EViews will display a dialog prompting you to change the display properties of the series. While you may change a variety of display settings such as the column width, justification, and indentation, here, for the moment, we are more interested in setting the properties of the Numeric Display .


For a date series, there are four settings of interest in the Numeric Display combo box (Period, Day, Day-Time, and Time), with each corresponding to specific information that we wish to display in the series spreadsheet. For example, the Day selection allows you to display date information up to the day in various formats; with year, month, and day all included in the representation.

Let us consider our quarterly workfile example. Here we have selected Period and chosen a specific Date format entry ("YYYY[Q]Q"), which tells EViews that you wish to display the year, followed by the "Q" separator, and then the quarter number. Note also that when Period is selected, there is a Current Workfile setting in the Date format combo box which tells EViews to use the current workfile display settings.

The two checkboxes below the Date format combo box may be used to modify the selected date format. If you select Two digit year , EViews will only display the last two-dig-

its of the year (if the selected format is “YYYY[Q]Q”, the actual format used will be “YY[Q]Q”); if you select Day/month order, days will precede months in whichever format is selected (if you select “mm/dd/YYYY” as the format for a day display, EViews will use “dd/mm/YYYY”).


Applying this format to the QDATES series, the display changes to show the data in the new format:



The screenshot shows the EViews software interface for the QDATES series. The window title is "Series: QDATES Workfile: ITALY::Quarterly". The "View" tab is selected. The main display area shows a table of quarterly dates from 1990Q1 to 1992Q4. The dates are displayed in the format "YYYYQ1", "YYYYQ2", "YYYYQ3", and "YYYYQ4". The table has two columns, with the first column containing the dates and the second column being empty. The status bar at the bottom indicates "Last updated: 08/12/09 - 19:12" and "Modified: 1990Q1 2005Q4 // qdates=dates".

QDATES	
Last updated: 08/12/09 - 19:12	
Modified: 1990Q1 2005Q4 // qdates=dates	
1990Q1	
1990Q2	
1990Q3	
1990Q4	
1991Q1	
1991Q2	
1991Q3	
1991Q4	
1992Q1	
1992Q2	
1992Q3	
1992Q4	

If instead we select the Day display, and choose the “YYYY-MM-DD” format, the QDATES spreadsheet will show:



The screenshot shows the EViews software interface for the QDATES series, with the date format changed to "YYYY-MM-DD". The window title is "Series: QDATES Workfile: ITALY::Quarterly". The "View" tab is selected. The main display area shows a table of quarterly dates from 1990Q1 to 1992Q4. The dates are displayed in the format "YYYY-MM-DD". The table has two columns, with the first column containing the dates and the second column being empty. The status bar at the bottom indicates "Last updated: 08/12/09 - 19:13" and "Modified: 1990Q1 2005Q4 // qdates=dates".

QDATES	
Last updated: 08/12/09 - 19:13	
Modified: 1990Q1 2005Q4 // qdates=dates	
1990Q1	1990-01-01
1990Q2	1990-04-01
1990Q3	1990-07-01
1990Q4	1990-10-01
1991Q1	1991-01-01
1991Q2	1991-04-01
1991Q3	1991-07-01
1991Q4	1991-10-01
1992Q1	1992-01-01
1992Q2	1992-04-01
1992Q3	1992-07-01
1992Q4	

There is one essential fact to remember about the QDATES series. Despite the fact that we have changed the display to show a text representation of the date, QDATES still contains the underlying numeric date values. This is in contrast to using an alpha series to hold a text representation of the date.


If you wish to convert a (numeric) date series into an alpha series, you will need to use the @datestr function. If you wish to convert an alpha series into a numeric date series, you will need to use the @dateval function. See [“Translating between Date Strings and Date Numbers” on page 88](#) of the Command and Programming Reference for details.

Editing a Date Series

You may edit a date series either by either datenumbers, or if the series is displayed using a date format, by entering date strings directly.

Suppose, for example, that we have our date series from above and that we wish to change a value. If we are displaying the series with date formatting, we may enter a date string, which EViews will automatically convert into a date number.

For example, we may edit our QDATES series by entering a valid date string (“April 10, 1992”), which EViews will convert into a date number (727297.0), and then display as a date string (“1992-04-10”). See [“Free-format Conversion” on page 89](#) of the Command and Programming Reference for details on automatic translation of strings to date values.



Note, however, that if we were to enter the same string value in the series when the display is set to show numeric values, EViews will not attempt to interpret the string and will enter an NA in the series.

Value Maps

You may use the valmap object to create a value map (or map, for short) that assigns descriptive labels to values in numeric or alpha series. The practice of mapping observation values to labels allows you to hold your data in encoded or abbreviated form, while displaying the results using easy-to-interpret labels.

Perhaps the most common example of encoded data occurs when you have categorical identifiers that are given by integer values. For example, we may have a numeric series FEMALE containing a binary indicator for whether an individual is a female (1) or a male (0).

Numeric encodings of this type are commonly employed, since they allow one to work with the numeric values of FEMALE. One may, for example, compute the mean value of the FEMALE variable, which will provide the proportion of observations that are female.

On the other hand, numeric encoding of categorical data has the disadvantage that one must always translate from the numeric values to the underlying categorical data types. For example, a one-way tabulation of the FEMALE data produces the output:

The screenshot shows a software window titled "Series: FEMALE" with a menu bar (View, Proc, Object, Properties, Print, Name, Freeze, Default) and a toolbar. The main area displays a table with the following data:

FEMALE	
Last updated: 07/24/06 - 17:04	
Fred	0
George	0
Karen	1
Mark	0
Paula	1
Rebecca	1

Tabulation of FEMALE
Date: 09/30/03 Time: 11:36
Sample: 1 6
Included observations: 6
Number of categories: 2

Value	Count	Percent	Cumulative	Cumulative
			Count	Percent
0	3	50.00	3	50.00
1	3	50.00	6	100.00
Total	6	100.00	6	100.00


Interpretation of this output requires that the viewer remember that the FEMALE series is encoded so that the “0” value represents “Male” and the “1” represents “Female”. The example above would be easier to interpret if the first column showed the text representations of the categories in place of the numeric values.

Valmaps allow us to combine the benefits of descriptive text data values with the ease of working with a numeric encoding of the data. In cases where we define value maps for alphanumeric data, the associations allow us to use space saving abbreviations for the underlying data along with more descriptive labels to be used in presenting output.

Defining a Valmap

To create a valmap object, select Object/New Object.../ValMap from the main menu and optionally enter an object name, or enter the keyword “VALMAP” in the command line, followed by an optional name. EViews will open a valmap object.


You will enter your new mappings below the double line by typing or by copy-and-pasting. In the Value column, you should enter the values for which you wish to provide labels; in the Label column, you will enter the corresponding text label. Here, we define a valmap named FEMALEMAP in which the value 0 is mapped to the string “Male”, and the value 1 is mapped to the string “Female”.



The two special entries above the double line should be used to define mappings for blank strings and numeric missing values. The default mapping is to represent blank strings as themselves, and to represent numeric missing values with the text “NA”. You may change these defaults by entering the appropriate text in the Label column. For example, to change the representation of missing numeric values to, say, a period, simply type the “.” character in the appropriate cell.

We caution that when working with maps, EViews will look for exact equality between the value in a series and the value in the valmap. Such an equality comparison is subject to the usual issues associated with comparing floating point numbers. To mitigate these issues and to facilitate mapping large numbers of values, EViews allows you to define value maps using intervals.

To map an interval, simply enter a range of values in the Value column and the associated label in the Label column. You may use round and square parentheses, to denote open (“(”, “)”) or closed (“[”, “]”) interval endpoints, and the special values “-INF” and “INF” to represent minus and plus infinity.



Using interval mapping, we require only three entries to map all of the negative values to the string “negative”, the positive values to the string “positive”, and the value 0 to the string “zero”. Note that the first interval

in our example, “[−inf, 0)”, is mathematically incorrect since the lower bound should not be closed, but EViews allows the closed interval syntax in this case since there is no possibility of confusion.


While the primary use for valmaps will be to map numeric series values, there is nothing stopping you from defining labels corresponding to alpha series values (note that value and label matching is case sensitive). One important application of string value mapping is to expand abbreviations. For example, one might wish to map the U.S. Postal Service state abbreviations to full state names.

Since valmaps may be used with both numeric and alpha series, the text entries in the Value column may generally be used to match both numeric and alphanumeric values. For example, if you enter the text “0” as your value, EViews treats the entry as representing either a numeric 0 or the string value “0”. Similarly, entering the text string “[0,1]” will match both numeric values in the interval, as well as the string value “[0,1]”.

There is one exception to this dual interpretation. You may, in the process of defining a given valmap, provide an entry that conflicts with a previous entry. EViews will automatically identify the conflict, and will convert the latter entry into a string-only valmap entry.

For example, if the first line of your valmap maps 0 to “Zero”, a line that maps 0 to “New Zero”, or one that maps “[0, 1]” to “Unit interval” conflicts with the existing entry. In the latter cases, the conflicting maps will be treated as text maps. Such a map is identified by enclosing the entry with quotation marks. Here, EViews has automatically added the enclosing quotation marks to indicate that the latter two label entries will only be interpreted as string maps, and not as numeric maps.

Once you have defined your mappings, click on the Update button on the toolbar to validate the object. EViews will examine your valmap and will remove entries with values that are exact duplicates. In this example, the last entry, which maps the string “0” to the value “New Zero” will be removed since it conflicts with the first line. The second entry will be




retained since it is not an exact duplicate of any other entry. It will, however, be interpreted only as a string since the numeric interpretation would lead to multiple mappings for the value 0.

Assigning a Valmap to a Series

To use a valmap, you need to instruct EViews to display the values of the map in place of the underlying data. Before working with a valmap, you should be certain that you have updated and validated your valmap by pressing the Update button on the valmap toolbar.

First, you must assign the value map to your series by modifying the series properties. Open the series window and select View/ Properties... or click on the Properties button in the series toolbar to open the properties dialog. Click on the Value Map tab to display the value map name edit field.

If the edit field is blank, a value map has not been associated with this series. To assign a valmap, simply enter the name of a valmap object in the edit field and click on OK.



EViews will validate the entry and apply the specified map to the series. Note that to be valid, the valmap must exist in the same workfile page as the series to which it is assigned.


Using the Valmap Tools

EViews provides a small set of object-specific views and procedures that will aid you in working with valmaps.

Sorting Valmap Entries

You may add your valmap entries in any order without changing the behavior of the map. However, when viewing the contents of the map, you may find it useful to see the entries in sorted order.

To sort the contents of your map, click on Proc/Sort... from the main valmap menu. EViews provides you with the choice of sorting by the value column using numeric order (Value - Numeric), sorting by the value column using text order (Value - Text) or sorting by the label column (Label).



In the first two cases, we sort by the values in the first column of the valmap. The difference between the choices is apparent when you note that

the ordering of the entries “9” and “10” depends upon whether we are interpreting the sort as a numeric sort, or as a text sort. Selecting **Value - Numeric** tells EViews that, where possible, you wish to interpret strings as numbers when performing comparisons (so that “9” is less than “10”); selecting **Value - Text** says that all values should be treated as text for purposes of comparison (so that “10” is less than “9”).


Click on OK to accept the sort settings.

Examining Properties of a Valmap

You may examine a summary of your valmap by selecting **View/Statistics** in the valmap window. EViews will display a view showing the properties of the labels defined in the object.

The top portion of the view shows the number of mappings in the valmap, and the number of unique labels used in those definitions. Here we see that the valmap has four definitions, which map four values into four unique labels. Two of the four definitions are the special entries for blank strings and the numeric NA value.

The remaining portions of the view provide a detailed summary of the valmap describing the properties of the map when applied to numeric and to text values.



When applied to an ordinary numeric series, our FEMALEMAP example contains three relevant definitions that provide labels for the values 0, 1, and NA. Here, EViews reports that the numeric value mapping is one-to-one since there are no two values that produce the same value label.

The output also reports that the FEMALEMAP has three relevant definitions for mapping the three text values, “0”, “1”, and the blank string, into three unique labels. We see that the text interpreted maps are also one-to-one.


Note that in settings where we map an interval into a given label, or where a given text label is repeated for multiple values, EViews will report a many-to-one mapping. Knowing that a valmap is many-to-one is important since it implies that the values of the underlying source series are not uniquely identified by the label values. This lack of identification has important implications in editing mapped series and in interpreting the results from various statis-

tical output (see [“Editing a Mapped Series” on page 176](#) and [“Valmap Definition Cautions” on page 180](#)).

Tracking Valmap Usage

A single valmap may be applied to more than one series. You may track the usage of a given valmap by selecting View/Usage from the valmap main menu. EViews will examine every numeric and alpha series in the workfile page to determine which, if any, have applied the specified valmap.

The valmap view then changes to show the number and names of the series that employ the valmap, with separate lists for the numeric and the alpha series. Here we see that there is a single numeric series named FEMALE that uses FEMALEMAP.




Working with a Mapped Series

Once you assign a map to a series, EViews allows you to display and edit your series using the mapped values and will use the labels when displaying the output from selected procedures.


Displaying series values

By default, once you apply a value map to a series, the EViews spreadsheet view will change to display the newly mapped values.

For example, after applying the FEMALE-MAP to our FEMALE series, the series spreadsheet view changes to show the labels associated with each value instead of the underlying encoded values. Note that the display format combo box usually visible in series toolbar indicates that EViews is displaying the Default series values, so that it shows the labels “Male” and “Female” rather than the underlying 0 and 1 values.




Note that if any of the values in the series does not have a corresponding valmap entry, EViews will display a mix of labeled and unlabeled values, with the unlabeled value “showing through” the mapping. For example, if the last observation in the FEMALE series had the value 3, the series spreadsheet will show observations with “Male” and “Female” corresponding to the mapped values, as well as the unmapped value 3.



The screenshot shows the 'Series: FEMALE' window in EViews. The 'View' menu is open, and the 'Default' option is selected. The spreadsheet displays the following data:

FEMALE	
Last updated: 08/12/09 - 19:28	
Fred	Male
George	Male
Karen	Female
Mark	Male
Paula	Female
Rebecca	3

There may be times when you wish to view the underlying series values instead of the labels. There are two possible approaches. First, you may remove the valmap assignment from the series. Simply go to the Properties dialog and delete the name of the valmap object from the Value Map page. The display will revert to showing the underlying values. Less drastically, you may use the display method combo box to change the display format for the spreadsheet view. If you select **Raw Data**, the series spreadsheet view will change to show the underlying series data.



The screenshot shows the 'Series: FEMALE' window in EViews. The 'View' menu is open, and the 'Raw Data' option is selected. The spreadsheet displays the following data:

FEMALE	
Last updated: 08/12/09 - 19:29	
Fred	0
George	0
Karen	1
Mark	0
Paula	1
Rebecca	1

Editing a Mapped Series

To edit the values of your mapped series, first make certain you are in edit mode, then enter the desired values, either by typing in the edit field, or by pasting from the clipboard. How EViews interprets your input will differ depending upon the current display format for the series.

If your mapped series is displayed in its original form using the **Raw Data** setting, EViews will interpret any input as representing the underlying series values, and will place the input directly into the series. For example, if our FEMALE series is displayed using the **Raw Data** setting, any numeric input will be entered directly in the series, and any string input will be interpreted as an NA value.

In contrast, if the series is displayed using the **Default** setting, EViews will use the attached valmap both in displaying the labeled values and in interpreting any input. In this setting, EViews will first examine the attached valmap to determine whether the given input value is also a label in the valmap. If a matching entry is found, and the label matches a unique

underlying value, EViews will put the value in the series. If there is no matching valmap label entry, or if there is an entry but the corresponding value is ambiguous, EViews will put the input value directly into the series. One implication of this behavior is that so long as the underlying values are not themselves valmap labels, you may enter data in either mapped or unmapped form. Note, again, that text value and label matching is case-sensitive.

Let us consider a simple example.

Suppose that the FEMALE series is set to display mapped values, and that you enter the value “Female”. EViews will examine the assigned valmap, determine that “Female” corresponds to the underlying value “1”, and will assign this value to the series. Since “1” is a valid form of numeric input, the numeric value 1 will be placed in the series. Note that even though we have implicitly entered 1 into the series, the mapped spreadsheet view will continue to show the value “Female”.

Series: FEMALE	
Female	FEMALE
Last updated: 08/12/09 - 19:30	
Fred	Male
George	Male
Karen	Female
Mark	Male
Paula	Female
Rebecca	Female

Alternatively, we could have directly entered the “1” corresponding to the underlying numeric value. Since “1” is not a valmap label, EViews will put the value 1 in the series, which will be displayed using the label “Female”.

While quite useful, entering data in mapped display mode requires some care, as your results may be somewhat unexpected. For one you should bear in mind that the required reverse lookup of values associated with a given input requires an exact match of the input to a label value, and a one-to-one correspondence between the given label and a valmap value. If this condition is not met, the original input value will be placed in the series.

Consider, for example, the result of entering the string “female” instead of “Female”. In this case, there is no matching valmap label entry, so EViews will put the input value, “female”, into the series. Since FEMALE is a numeric series, the resulting value will be an NA, and the display will show the mapped value for numeric missing values.

Similarly, suppose you enter “3” into the last observation of the FEMALE series. Again, EViews does not find a corresponding valmap label entry, so the input is entered directly into the series. In this case, the input represents a valid number so that the resulting value will be a 3. Since there is no valmap entry for this value, the underlying value will be displayed.

Lastly, note that if the matching valmap label corresponds to multiple underlying values, EViews will be unable to perform the reverse lookup. If, for example, we modify our valmap so that the interval “[1, 10]” (instead of just the value 1) maps to the label “Female”, then

when you enter “Female” as your input, it is impossible to determine a unique value for the series. In this case, EViews will enter the original input, “Female”, directly into the series, resulting in an NA value.

See [“Valmap Definition Cautions” on page 180](#) for additional cautionary notes.

Using a Mapped Series

You may use a mapped series as though it were any series. We emphasize the fact that the mapped values of a series are not replacements of the underlying data; they are only labels to be used in output. Thus, when performing numeric calculations with a series, EViews will always use the underlying values of the series, not the label values. For example, if you map the numeric value -99 to the text “NA”, and take the absolute value of the mapped numeric series containing that value, you will get the value 99, and not a missing value.

In appropriate settings (where the series values are treated as categories), EViews routines will use the labels when displaying output. For example, a one-way frequency tabulation of the FEMALE series with the assigned FEMALEMAP yields:

Tabulation of FEMALE
Date: 09/30/03 Time: 11:36
Sample: 1 6
Included observations: 6
Number of categories: 2

Value	Count	Percent	Cumulative	
			Count	Percent
Female	3	50.00	3	50.00
Male	3	50.00	6	100.00
Total	6	100.00	6	100.00

Similarly, when computing descriptive statistics for the SALES data categorized by the values of the FEMALE series, we have:

Descriptive Statistics for SALES
Categorized by values of FEMALE
Date: 10/01/03 Time: 19:30
Sample: 1 6
Included observations: 6

FEMALE	Mean	Std. Dev.	Obs.
Female	323.3333	166.2328	3
Male	263.3333	169.2139	3
All	293.3333	153.5795	6

Valmap Functions

To facilitate working with valmaps, three new `genr` functions are provided which allow you to translate between unmapped and mapped values. These functions may be used as part of standard series or alpha expressions.

First, to obtain the mapped values corresponding to a set of numbers or strings, you may use the command:

```
@map(arg[, map_name])
```

where `arg` is a numeric or string series expression or literal, and the optional `map_name` is the name of a valmap object. If `map_name` is not provided, EViews will attempt to determine the map by inspecting `arg`. This attempt will succeed only if `arg` is a numeric series or alpha series that has previously been mapped.

Let us consider our original example where the `FEMALEMAP` maps 0 to "Male" and 1 to "Female". Suppose that we have two series that contain the values 0 and 1. The first series, `MAPPEDSER`, has previously applied the `FEMALEMAP`, while the latter series, `UNMAPPEDSER`, has not.

Then the commands:

```
alpha s1 = @map(mappedser)
alpha s2 = @map(mappedser, femalemap)
```

are equivalent. Both return the labels associated with the numeric values in the series. The first command uses the assigned valmap to determine the mapped values, while the second uses `FEMALEMAP` explicitly.

Alternately, the command:

```
alpha s3 = @map(unmappedser)
```

will generate an error since there is no valmap assigned to the series. To use `@map` in this context, you must provide the name of a valmap, as in:

```
alpha s4 = @map(unmappedser, femalemap)
```

which will return the mapped values of `UNMAPPEDSER`, using the valmap `FEMALEMAP`.

Conversely, you may obtain the numeric values associated with a set of string value labels using the `@unmap` function. The `@unmap` function takes the general form:

```
@unmap(arg, map_name)
```

to return the numeric values that have been mapped into the string given in the string expression or literal `arg`, where `map_name` is the name of a valmap object. Note that if a given label is associated with multiple numeric values, the missing value `NA` will be returned. Note that the `map_name` argument is required with the `@unmap` function.

Suppose, for example, that you have an alphaseries STATEAB that contains state abbreviations (“AK”, “AL”, etc.) and a valmap STATEMAP that maps numbers to the abbreviations. Then:

```
series statecode = @unmap(stateab, statemap)
```

will contain the numeric values associated with each value of STATEAB.

Similarly, you may obtain the string values associated with a set of string value labels using:

```
@unmaptxt (arg, map_name)
```

where `arg` is a string expression or literal, and `map_name` is the name of a valmap object. `@unmaptxt` will return the underlying string values that are mapped into the string labels provided in `arg`. If a given label is associated with multiple values, the missing blank string “” will be returned.

Valmap Definition Cautions

EViews allows you to define quite general value maps that may be used with both numeric and alpha series. While potentially useful, the generality comes with a cost, since if used carelessly, valmaps can cause confusion. Accordingly, we caution you that there are many features of valmaps that should be used with care. To illustrate the issues, we list a few of the more problematic cases.

Many-to-one Valmaps

A many-to-one valmap is a useful tool for creating labels that divide series values into broad categories. For example, you may assign the label “High” to a range of values, and the label “Low” to a different range of values so that you may, when displaying the series labels, easily view the classification of an observation.

The downside to many-to-one valmaps is that they make interpreting some types of output considerably more difficult. Suppose, for example, that we construct a valmap in which several values are mapped to the label “Female”. If we then display a one-way frequency table for a series that uses the valmap, the label “Female” may appear as multiple entries. Such a table is almost impossible to interpret since there is no way to distinguish between the various “Female” values.

A series with an attached many-to-one valmap is also more difficult to edit when viewing labels since EViews may be unable to identify a unique value corresponding to a given label. In these cases, EViews will assign a missing value to the series, which may lead to confusion (see [“Editing a Mapped Series” on page 176](#)).

Mapping Label Values

Defining a map in which one of the label values is itself a value that is mapped to a label can cause confusion. Suppose for example, that we have a valmap with two entries: the

first maps the value 6 to the label “six”, and the second maps the value “six” to the label “high”.

Now consider editing an alpha series that has this valmap attached. If we use theDefault display, EViews will show the labeled values. Thus, the underlying value “six” will display as the value “high”; while the value “6” will display as “six”. Since the string “six” is used both as a label and as a value, in this setting we have the odd result that it must be entered indirectly. Thus, to enter the string “six” in the alpha series, we have the counterintuitive result that you must type “high” instead of “six”, since entering the latter value will put “6” in the series.

Note, however, that if you display the series in Raw Data form, all data entry is direct; entering “six” will put the value “six” into the series and entering “high” will put the value “high” in the series.

Mapping Values to Numbers

Along the same lines, we strongly recommend that you not define value maps in which numeric values can be mapped to labels that appear to be numeric values. Electing, for example, to define a valmap where the value 5 is mapped to the label “6” and the value 6 is mapped to the label “5”, is bound to lead to confusion.

Chapter 8. Series Links

The series link object (or link, for short) provides you with powerful tools for combining information from different workfile pages. Links provide an easy-to-use interface to a wide range of sophisticated data operations such as:

- merging data from one workfile page into another
- saving “by-group” summary statistics into a workfile page
- matching observations between dated workfile pages
- performing frequency conversion between regular dated workfile pages

Links operate both dynamically and on demand, so that the desired operation is performed only when needed, and is updated automatically whenever your data change.

You may find that working with links is in many ways similar to working with data tables in a relational database management system. Indeed links have specifically been designed to provide much of the power of these sophisticated systems. But you need not have worked with such a system to take advantage of the power, ease-of-use, and flexibility associated with link objects.

We begin with a discussion of basic link concepts that outlines the basic operations supported by links. In later sections we document the use of links in EViews.

Basic Link Concepts

A link is a series-like object that exists in one workfile page, but “refers” to series data in another workfile page. At a basic level, a link is a description of how EViews should use data in a source workfile page to determine values of a series in the current, or destination, workfile page.

A link contains three fundamental components:

- First, there is the name of a source series. The source series identifies the series in the source workfile page that is used as a basis for obtaining values in the destination page.
- Second, the link contains the names of one or more link identifier (ID) series in both the source and destination pages. The source ID and destination ID series will be used to match observations from the two pages.
- Lastly, the link contains a description of how the source series should be used to construct link values for matching observations in the destination page.

The basic series link employs a method called match merging to determine the link values in the destination page. More advanced links combine match merging with automatic frequency conversion. We describe these two methods in detail below, in [“Linking by general match merging” on page 184](#) and [“Linking by date with frequency conversion” on page 193](#).

As the name suggests, the series link object shares most of the properties of a series. You may, in fact, generally use a series link as though it were a series. You may examine series views, perform series procedures, or use the series link to generate new data, or you may use the link as a regressor in an equation specification.

Another important property of links is that they are “live”, in the sense that the values in the link change as its underlying data change. Thus, if you have a link in a given workfile page, the link values will automatically be updated when the source series or ID series values change.

Lastly, links are memory efficient. Since links are computed and updated as needed, the values of the series link are not held in memory unless they are in use. Thus, it is possible to create a page populated entirely by links that takes up only the minimum amount of memory required to perform all necessary operations.

Linking by general match merging

We begin our discussion of linking with a brief, and admittedly terse, description of how a basic link with match merging works. More useful, perhaps, will be the extended examples that follow.

The basic link first compares values for one or more source ID series with the values in the destination ID series. Observations in the two pages are said to match if they have identical ID values. When matches are observed, values from the source series are used to construct values of the link for the corresponding observations in the destination page.

Each link contains a description of how the source series should be used to construct link values in the destination page. Constructing values for a basic match merge link involves two steps:

- First, we perform a contraction of the source series to ensure that there is a single value associated with each distinct source ID value. The contraction method employed describes how the (possibly) multiple source series observations sharing a given ID value should be translated into a single value.
- Next, we take the distinct source IDs and contracted source series values, and perform a match merge in which each contracted value is repeated for all matching observations in the destination page.

This basic method is designed to handle the most general cases involving many-to-many match merging by first computing a many-to-one contraction (by-group summary) of the source series, and then performing a one-to-many match merge of the contracted data.

All other match merges are handled as special cases of this general method. For a many-to-one match merge, we first compute the contraction, then perform one-to-one matching of the contracted data into the destination page. In the more common one-to-many or one-to-one match merge, the contraction step typically has no practical effect since the standard contractions simply return the original source series values. The original values are then linked into the destination page using a simple one-to-one or one-to-many match merge.

While all of this may seem a bit abstract, a few simple examples should help to fix ideas. Suppose first that we have a state workfile page containing four observations on the series STATE1 and TAXRATE:

State1	TaxRate
Arkansas	.030
California	.050
Texas	.035
Wyoming	.012

In the same workfile, we have a second workfile page containing individual level data, with a name, NAME, state of residence, STATE2 and SALES volume for six individuals:

Name	State2	Sales
George	Arkansas	300
Fred	California	500
Karen	Arkansas	220
Mark	Texas	170
Paula	Texas	120
Rebecca	California	450

We wish to link the data between the two pages. Note that in this example, we have given the state series different names in the two pages to distinguish between the two. In practice there is no reason for the names to differ, and in most cases, the names will be the same.

One-to-many match merge

Our first task will be to create, in the page containing individual information, a series containing values of the TAXRATE faced by every individual. We will determine the individual rates by examining each individual's state of residence and locating the corresponding tax

rate. George, for example, who lives in Arkansas, will face that state's tax rate of 0.030. Similarly, Mark, who lives in Texas, has a tax rate of 0.035.

We will use a series link to perform a one-to-many match merge in which we assign the TAXRATE values in our source page to multiple individuals in our destination page.

For the three basic components of this link, we define:

- the source series TAXRATE
- the source identifier STATE1 and destination identifier STATE2
- the merge rule that the values of TAXRATE will be repeated for every individual with a matching STATE2 value in the destination page

This latter merge rule is always used for basic links involving one-to-many match merges. Here, the rule leads to the natural result that each individual is assigned the TAXRATE value associated with his or her state.

After performing the link, the individual page will contain the merged values for the tax rate in TAXRATE2. We use the "2" in the TAXRATE2 name to denote the fact that these data are generated by merging data using STATE2 as the destination ID series:

Name	State2	Sales	TaxRate2
George	Arkansas	300	.030
Fred	California	500	.050
Karen	Arkansas	220	.030
Mark	Texas	170	.035
Paula	Texas	120	.035
Rebecca	California	450	.050

We mention one other issue in passing that will become relevant in later discussion. Recall that all basic links with match merging first contract the source series prior to performing the match merge. In this case, the specified merge rule implicitly defines a contraction of the source series TAXRATE that has no effect since it returns the original values of TAXRATE. It is possible, though generally not desirable, to define a contraction rule which will yield alternate source values in a one-to-many match merge. See ["Link calculation settings" on page 199](#)

Many-to-one match merge

Alternatively, we may wish to link data in the opposite direction. We may, for example, choose to link the SALES data from the individual page to the destination state page, again matching observations using the two state IDs. This operation is a many-to-one match

merge, since there are many observations with STATE2 ID values in the individual page for each of the unique values of STATE1 in the state page.

The components of this new link are easily defined:

- the source series SALES
- the source identifier STATE2 and destination identifier STATE1
- a merge rule stating that the values of SALES will first be contracted, and that the contracted values will be placed in matching observations in the destination page

Specifying the last component, the merge rule, is a bit more involved here since there are an unlimited number of ways that we may contract the individual data. EViews provides an extensive menu of contraction methods. Obvious choices include computing the mean, variance, sum, minimum, maximum, or number of observations for each source ID value. It is worth noting here that only a subset of the contraction methods are available if the source is an alpha series.

To continue with our example, suppose that we choose to take the sum of observations as our contraction method. Then contraction involves computing the sum of the individual observations in each state; the summary value for SALES in Arkansas is 520, the value in California is 950, and the value in Texas is 290. Wyoming is not represented in the individual data, so the corresponding contracted value is NA.

Given this link definition, the many-to-one match merge will result in a state page containing the match merged summed values for SALES1:

State1	TaxRate	Sales1	Sales1ct
Arkansas	.030	520	2
California	.050	950	2
Texas	.035	290	2
Wyoming	.012	NA	0

Similarly, we may define a second link to the SALES data containing an alternative contraction method, say the count of non-missing observations in each state. The resulting link, SALES1CT, shows that there are two individual observations for each of the first three states, and none for Wyoming.

Many-to-many match merge

Lastly, suppose that we have a third workfile page containing a panel structure with state data observed over a two year period:

Year	State3	TaxRate

1990	Arkansas	.030
1991	Arkansas	.032
1990	California	.050
1991	California	.055
1990	Texas	.035
1991	Texas	.040
1990	Wyoming	.012
1991	Wyoming	.035

Linking the SALES data from the individual page to the panel page using the STATE2 and STATE3 identifiers involves a many-to-many match merge since there are multiple observations for each state in both pages.

The components of this new link are easily defined:

- the source series SALES
- the source identifier STATE2 and destination identifier STATE3
- a merge rule stating that the values of SALES will first be contracted, and that the contracted values will be repeated for every observation with a matching STATE3 value in the destination page

This merge rule states that we perform a many-to-many merge by first contracting the source series, and then performing a one-to-many match merge of the contracted results into the destination. For example, linking the SALES data from the individual page into the panel state-year page using the sum and cointcontraction methods yields the link series SALES3 and SALES3A:

Year	State3	TaxRate	Sales3	Sales3a
1990	Arkansas	.030	520	2
1991	Arkansas	.032	520	2
1990	California	.050	950	2
1991	California	.055	950	2
1990	Texas	.035	290	2
1991	Texas	.040	290	2
1990	Wyoming	.012	NA	0
1991	Wyoming	.035	NA	0

It is worth noting that this many-to-many match merge is equivalent to first performing a many-to-one link from the individual page into the state page, and then constructing a one-to-many link of those linked values into the panel page. This two-step method may be

achieved by first performing the many-to-one link into the state page, and then performing a one-to-many link of the SALES1 and SALES1CT links into the panel page.

Linking by date match merging

To this point, we have primarily considered simple examples involving a single categorical link identifier series (states). You may, of course, construct more elaborate IDs using more than one series. For example, if you have data on multinational firms observed over time, both the firm and date identifiers may be used as the link ID series.

The latter example is of note since it points to the fact that dates may be used as valid link identifiers. The use of dates as identifiers requires special discussion as the notion of a match may be extended to take account of the calendar.

We begin our discussion of merging using dates by noting that a date may be employed as an identifier in two distinct ways:

- First, an ID series containing date values or alphanumeric representations of dates may be treated like any other ID series. In this case, the value in one workfile page must be identical to the value in the other page for a match to exist.
- Alternatively, when we are working with regular frequency data, we may take advantage of our knowledge of the frequency and the calendar to define a broader notion of date matching. This broader form of matching, which we term date matching, involves comparing dates by first rounding the date ID values down to the lowest common regular frequency and then comparing the rounded values. Note that date matching requires the presence of at least one regular frequency for the rounding procedure to be well-defined.

In practical terms, date matching produces the outcomes that one would naturally expect. With date matching, for example, the quarterly observation “2002Q1” matches “2002” in a regular annual workfile, since we round the quarterly observation down to the annual frequency, and then match the rounded values. Likewise, we would match the date “March 3, 2001” to the year 2001 in an annual workfile, and to “2001Q1” in a quarterly workfile. Similarly, the date “July 10, 2001” also matches 2001 in the annual workfile, but matches “2001Q3” in the quarterly workfile.

Basic links with date matching

Consider the following simple example of linking using date matching. Suppose that we have a workfile containing two pages. The first page is a regular frequency quarterly page containing profit data (PROFIT) for 2002 and 2003:

Quarter	Profit
2002Q1	120

2002Q2	130
2002Q3	150
2002Q4	105
2003Q1	100
2003Q2	125
2003Q3	200
2003Q4	170

while the second page contains irregular data on special advertising events (ADVERT):

Date	Advert
Jan 7, 2002	10
Mar 10, 2002	50
Apr 9, 2002	40
May 12, 2002	90
Mar 1, 2003	70
Dec 7, 2003	30
Dec 23, 2003	20

We would like to link the quarterly profit data to the irregular data in the advertising page. The quarterly values in the source page are unique so that we have a one-to-one or one-to-many match merge; accordingly, we may select any contraction method that leaves the original PROFIT data unchanged (mean, unique, etc.).

We first employ date matching by using the “@DATE” and “@DATE” keywords as our ID series. This specification instructs EViews to use the knowledge about the date structures in the page to perform a sophisticated matching across pages. Using this approach, we construct a PROFIT1 link containing the values:

Date	Advert	Profit1
Jan 7, 2002	10	120
Mar 10, 2002	50	120
Apr 9, 2002	40	130
May 12, 2002	90	130
Mar 1, 2003	70	100
Dec 7, 2003	30	170
Dec 23, 2003	20	170

In evaluating the values in PROFIT1, we simply repeat the value of PROFIT for a given quarter for every matching observation in the advertising page. Since we are using date matching, we employ matching across pages that uses calendar knowledge to determine matches. For example, the observation for quarter “2002Q1” matches both “Jan 7, 2002” and “Mar 10, 2002” in the advertising page so that the latter observations are assigned the value of 120.

Conversely, using date matching to link the ADVERT series to the quarterly page, we have a many-to-one match merge since, after rounding down to the lower frequency, multiple observations in the advertising page have “@DATE” values that match the unique “@DATE” values in the quarterly page. If we choose to employ the mean contraction method in the link ADVERT1, we have:

Quarter	Profit	Advert1
2002Q1	120	30
2002Q2	130	65
2002Q3	150	NA
2002Q4	105	NA
2003Q1	100	70
2003Q2	125	NA
2003Q3	200	NA
2003Q4	170	25

Here, the values of ADVERT1 contain the mean values over the observed days in the quarter. For example, the value for ADVERT1 in 2002Q1 is taken by averaging the values of ADVERT for “Jan 7, 2002” and “Mar 10, 2002”. Note that the value for quarter 2002Q3 is NA since there are no observations with matching DATE values, i.e., there are no observations in the advertising page that fall within the quarter.

It is worth noting that in both of these examples, had we employed exact matching using by specifying our ID series as QUARTER and DATE, we would have observed no matches since the date numbers for the quarterly data do not match any of the irregular date numbers. As a result, all of the values in the resulting link would be assigned the value NA.

Panel links with date matching

When using date matching to link dated panel data to a page with a different frequency, you should pay particular attention to the behavior of the merge operation since the results may differ from expectations.

An example will illustrate the issue. Consider the following simple panel featuring quarterly revenue data from 2002Q1 to 2003Q4:

Firm	Quarter	Revenue
1	2002Q1	120
1	2002Q2	130
1	2002Q3	150
1	2002Q4	105
1	2003Q1	100
1	2003Q2	125
1	2003Q3	200
1	2003Q4	170
2	2002Q1	40
2	2002Q2	40
2	2002Q3	50
2	2002Q4	35
2	2003Q1	20
2	2003Q2	25
2	2003Q3	50
2	2003Q4	40

We will consider the results from linking the REVENUE data into an annual page using date matching of the QUARTER and the YEAR identifiers. Using date match merging (with the “@DATE” and “@DATE” keywords), and employing both the sum and number of observations contractions, we observe the results in REVENUE1 (sum) and REVENUE1A (obs):

Year	Revenue1	Revenue1a
2002	670	8
2003	730	8

The important thing to note here is that the sums for each year have been computed over all eight matching observations in the panel page.

The key to understanding the result is to bear in mind that date matching only changes the way that a match between observations in the two pages is defined; the remaining match merge operation remains unchanged. The outcome is simply the result of applying standard link behavior in which we first identify matches, compute a contraction over all matching observations, and perform the one-to-one match merge.

An alternative approach to obtaining annual revenue values from the panel data would be to first contract the panel data to a quarterly frequency by averaging across firms, and then to convert the quarterly data to an annual frequency by summing over quarters. This

approach, which produces very different results from the first method, may be undertaken in two steps: by first linking the quarterly panel data into a quarterly page (using the mean contraction), and then frequency converting by linking the quarterly data to the annual frequency (summing over quarters).

In cases where you are linking between two panel pages at different frequencies there are yet more complication. See [“Panel frequency conversion” on page 195](#) for a description of the issues involved in constructing these types of links.

Linking by date with frequency conversion

In the special case where we wish to link data between two regular frequency pages using dates as the sole identifier, EViews allows you to define your links in two ways. First, you may use the date match merging described in [“Linking by date match merging” on page 189](#) or you can define special links that employ frequency conversion.

Basic frequency conversion

Links specified by date will primarily be used to perform automatic frequency conversion of simple regular frequency data. For example, you may choose to hold your quarterly frequency data in one page, your monthly frequency data in a second page, and to create links between pages which automatically perform the up or down frequency conversion as necessary.

You can instruct EViews to use the source series default methods for converting between frequencies, or you may use the link definition to specify the up and down conversion methods. Furthermore, the live nature of links means that changes in the source data will generate automatic updates of the frequency converted link values.

We divide our discussion of frequency conversion links into those that link data from high to low frequency pages and those that link from low to high frequency pages.

High to low frequency conversion

Frequency conversion linking from a simple regular high frequency page to a regular low frequency page is fundamentally the same as using a link with date matching to perform basic many-to-one match merging. In both cases, we match dates, compute a contraction of the source series, and then perform a one-to-one match merge.

Given the specialized nature of frequency conversion, links specified by date with frequency conversion offer a subset of the ordinary link contraction methods. All of the standard high to low frequency conversion methods (average, sum, first, last, maximum and minimum) are supported, but the match merge methods which do not preserve levels, (such as the sum-of-squares or the variance) are not included.

Frequency conversion links also allow you to disable conversions for partially observed periods, so that a missing value for the sourceseries in a given month generates a missing value for the corresponding quarterly observation. This option is not available for basic match merge links.

Low to high- frequency conversion

In contrast, linking from low to high frequency pages using frequency conversion differs substantively from linking using basic date match merging.

When linking using general date match merging, the frequency conversion implied by the one-to-many match merge may only be performed by repeating the low frequency observation for every matching high frequency observation. Thus, in a one-to-many date match merge, an annual observation is always repeated for each matching quarter, month, or day.

In contrast, EViews provides additional up-conversion methods for frequency conversion links. In addition to the simple repeated-observation (constant-match average) method, frequency conversion links support all of the standard frequency conversion methods including constant-match sum, quadratic-match sum, quadratic-match average, linear-match sum, linear-match last, and cubic-match last.

Suppose that, in addition to our regular frequency quarterly PROFIT workfile page ([p. 189](#)), we have a regular frequency monthly page containing observations spanning the period from August 2002 to March 2003. Linking the PROFIT data from the quarterly page into the monthly page by date, with frequency conversion, requires that we specify an up-conversion method. Here, we show results of a frequency conversion link using both the simple constant-match average (PROFIT2) and quadratic-match average (PROFIT3) methods:

Month	Profit2	Profit3
Aug 2002	150	152.407
Sep 2002	150	144.630
Oct 2002	105	114.074
Nov 2002	105	103.519
Dec 2002	105	97.407
Jan 2003	100	97.222
Feb 2003	100	98.889
Mar 2003	100	103.889

Note that the PROFIT2 values are the same as those obtained by linking using simple date match merging, since the constant-match average method simply repeats the PROFIT observations for each matching month. Conversely, the PROFIT3 values are obtained using an interpolation method that is only available for linking by date with frequency conversion.

Panel frequency conversion

There are additional issues to consider when performing frequency conversion links in panel workfile settings:

- When working with two regular frequency panel pages, each defined by a single ID, frequency conversion links construct values by performing the frequency conversion separately for each value of the panel ID.
- If the source page is a regular frequency panel and the destination is an ordinary regular frequency page, we contract the source series by computing means across the panel identifiers to form a single time series (note that “mean” is the only contraction allowed). The resulting time series, which is in the source frequency, is then frequency converted to the destination frequency. Finally, the resulting series is date match merged to the destination page.

Note that this behavior is the same as performing a general match merge using “@DATE” as the identifiers, with a mean contraction.

- If the source page is an ordinary regular frequency page, and the destination is a regular frequency panel, we frequency convert to the destination frequency, then date match merge to the corresponding dates in each ID in the destination. Thus given source value is repeated for all matching dates in the destination page (i.e., all IDs will have the same time-series).

In all three of these cases, all of the high-to-low conversion methods are supported, but low-to-high frequency conversion only offers Constant-match average (repeating of the low frequency observations).

Lastly, frequency conversion involving a panel page with more than one dimension or an undated page will be performed using raw data copy unless you elect to employ general match merging, as described in [“Panel links with date matching” on page 191](#).

An example will illustrate the general approach. Suppose again that we are working with the regular frequency, quarterly panel REVENUE data. For convenience, we repeat the data here:

Firm	Quarter	Revenue
1	2002Q1	120
1	2002Q2	130
1	2002Q3	150
1	2002Q4	105
1	2003Q1	100
1	2003Q2	125

1	2003Q3	200
1	2003Q4	170
2	2002Q1	40
2	2002Q2	40
2	2002Q3	50
2	2002Q4	35
2	2003Q1	20
2	2003Q2	25
2	2003Q3	50
2	2003Q4	40

We now wish to use frequency conversion to link these data into an annual panel, using the average frequency conversion method to go from high-to-low frequency. Then the panel-to-panel frequency conversion will simply perform a frequency conversion for each firm.

Firm	Year	Revenue2
1	2002	505
1	2003	595
2	2002	165
2	2003	135

Here we have performed an ID specific sum as our high-to-low conversion method. The observation for FIRM 1 in YEAR 2002 in the annual page is simply the sum of the quarterly data for that firm in 2002. Similarly, the value for FIRM 2 in 2003 is the sum of the four quarterly values for FIRM 2 in 2003.

It is important to note that these results differ significantly from the results obtained by general match merging using date processing of matches (with “@DATE” and “@DATE” as the two identifiers). Using the latter approach, we would have obtained:

Firm	Year	Revenue3
1	2002	670
1	2003	730
2	2002	670
2	2003	730

While these results may at first seem a bit odd, they simply follow the logic of the discussion in [“Panel links with date matching” on page 191](#). Note that our link which matches dates between the two panel workbook pages is an example of a many-to-many match merge,

since there are multiple IDs with the same dates in each page. Thus, we will first contract across IDs to obtain a unique time series in the original frequency, then frequency convert, then one-to-many match in the destination page. In this case, the initial contraction involves summing over firms to obtain a quarterly time series, then frequency converting (summing) to the destination frequency to obtain annual values for 2002 (670) and 2003 (730). The final step match merges these converted values into the annual panel using a one-to-many match merge rule.

Creating a Link

Links may be created interactively either by copying-and-pasting or drag-and-dropping a series from the source to the destination page, or by issuing a link declaration in the destination page.

Creating a link using copy-and-paste or drag-and-drop

To define a link using copy-and-paste, first select one or more source series in the source workfile page, and either click on the right mouse button and select Copy, or select Edit/Copy from the main EViews menu. Next, switch to the destination page by clicking on the appropriate tab, and either click on the right mouse button and select Paste Special..., or select Edit/Paste Special... from the main menu.

Alternately, you may right-click to select the source series, then drag-and-drop to the destination page. EViews will display the Paste Special dialog.

General match merge links

Here we have used Paste Special... to copy-and-paste the series TAXRATE from the source page into a destination page. If neither the source nor the destination series are dated pages, EViews will display a dialog prompting you to merge by date or by match merge. Select General match merge criteria in the bottom left to specify match merge options.

Destination name

The field in the upper left-hand portion of the dialog should be used for specifying the name of the destination object. Here, we have the default wildcard value of "*" indicating that the series named TAXRATE in the source page will be used in the destination page. We may modify the name by typing an explicit name such as "NEWTAX", or by entering an

expression containing the wildcard character. For example, if we wish to use the name “NEWTAXRATE” in the destination page, we may enter “NEW*” in the edit field.

The wildcard processing is particularly useful if you are copying multiple series into a new page since it facilitates batch renaming of series.

Destination type

Next, you will choose between pasting the series by value, or pasting the series as a link. If you paste by value, EViews will create an ordinary series in the destination page, and will fill it with the values from the link evaluation. If you paste your series as a link, EViews will create an actual link object containing the desired specification. As you might expect, there are significant differences between the two methods of copying your series.

In the first method, the link computations are performed immediately and the destination series values are assigned at the time the series is created. This behavior follows the traditional model of match merging and frequency conversion in which the operation is performed once to compute static values.

When you paste your series as a link, EViews defines a link object containing a specification of the match merge or frequency conversion. At creation, the link object is not evaluated and uses no memory. Then, whenever you access the values in the link series, EViews will determine whether the object needs evaluation and if so, will allocate memory and perform the link calculations.

With links, you gain the benefits of efficient memory use and dynamic updating of the values in the destination, at the cost of some speed since the link calculations may be performed more than once. Along these lines, it is worth pointing out that links may be converted into ordinary series at any time. Once a series is created, however, it may not be converted back into a link.

Match merge options

Whether you elect to create a new series with fixed values or to create a new link series, you must specify link options.

Match ID information

First, you must specify the information that EViews will use to identify matches between observations in the two pages.

In the Source ID and Destination ID edit fields, you will enter the names of one or more source ID series and one or more destination ID series. The number and order of the names in the two fields should match. Thus, if you wish to match both CXID1 and PERIOD1 in the source page to CXID2 and PERIOD2 in the second page, you should enter the sets of names in parallel. Here, we choose to match observations using the values of the STATE1 series in the source page and the values of the STATE2 series in the destination page.

Next, there is a checkbox labeled `Treat NA as ID category` for whether to use observations which have NA values in the source and destination ID values. By default, observations are ignored if there are NAs in the ID series; by selecting this option, you instruct EViews to match observations with NA ID values from the source page to observations with NA ID values in the destination page.

Link calculation settings

The remaining options are used when computing the link values.

First, you should specify a source series contraction method. As described in [“Linking by general match merging” on page 184](#) the first step in every match merge is to perform a contraction to ensure uniqueness of the source values. Since contraction is always performed, you should pay attention to your contraction method even when the source IDs are unique, since some settings will not yield the original source data.

There is an extensive list of contractions from which you may choose. For links involving numeric series you may choose to employ obvious methods such as the `Mean` (default) or the `Median` of the observations, or less obvious summary statistics such as the `Variance (population)` , `Std. Deviation (sample)` , `Kurtosis` , `Quantile` , `Number of obs` , or `Number of NAs`.

For links involving alpha series, you must select from a subset of the numeric contractions: `Unique values` (default), `No contractions allowed` , `First` , `Last` , `Maximum` , `Minimum` , `Number of obs` , `Number of NAs`.

Most of these options are self-explanatory, though a few comments about the choice of method may prove useful.

First, there are two options at the bottom of the list which deserve additional explanation. The last choice, `No contractions allowed` , may be used to ensure that contractions are never performed prior in the first step of a link match merge. The option is designed for cases where you believe that your source ID values are unique, and wish the link to generate an error if they are not.

The `Unique values` option provides a less strict version of the `No contractions allowed` setting, allowing for non-unique source ID values so long as any observations with matching IDs share the same source series value. In this case, the contraction will simply identify the unique source value associated with each unique source ID value. If there are observations with a single ID that have more than one source series value, the link will generate an error.

To see the difference between the two settings, note that contracting the following `SOURCE` and `ID` series

ID	Source
1	80
1	80
1	80
2	100
2	100

generates an error with the Unique values setting, but not with the No contractions allowed setting. Alternatively, the SOURCE and ID series

ID	Source
1	80
1	80
1	50
2	100
2	100

generate errors with both contractions.

Second, you should note that if you select First or Last, EViews will contract the source series by selecting the first or last observation in each set of observations with repeated source IDs. First or Last is defined here as depending on the order in which the observations appear in the original source workfile. Thus, selecting First means that the contracted value for each source ID value will be taken from the first observation in the workfile with that ID value.

Lastly, you should bear in mind that unless you select No contractions allowed or Unique values, EViews will perform a first stage contraction of the data using the specified settings. In cases where the source ID values are not unique, this contraction is a necessary step; in cases where the source ID values are unique, the contraction is not necessary for the resulting one-to-one or one-to-many match merge, but is performed so that EViews can support more complicated many-to-many merge operations.

For most of the choices, performing a contraction on the unique source data has no practical effect on the outcome of a one-to-one or one-to-many match merge. For example, a choice of any of the data preserving options: Mean, Median, Maximum, Minimum, Sum, First, Last, Unique values, or No contractions allowed will create a link that performs the standard one-to-one or one-to-many match merge of the values of the original source series into the destination page.

On the other hand, selecting a contraction method that alters the source values will create a link that performs a match merge of the summary values into the destination page. Thus, selecting Sum of Squares, Variance (population) , Std. Deviation (sample) , Skewness, Kurtosis , Quantile , Number of obs , or Number of NAs , will generate link values that differ from those obtained in a traditional one-to-one or one-to-many match merge.

It is worth emphasizing that the default contraction setting, Mean, preserves values for data with unique source IDs. Thus, unless you specifically set the contraction method to a non-preserving method, a one-to-one or one-to-many match merge will link the original values into the destination page. You may also ensure that EViews performs the traditional one-to-one or one-to-many match merge by selecting any of the other value preserving transformation methods, or even better by selecting No contractions allowed or Unique values to validate the IDs.


Finally, in the Source sample edit field, you should enter a description of the source sample to be used when constructing link values. By default, the full sample keyword “@ALL” is entered in the field so that EViews will use all of the observations in the source page.

One important application involving sample settings is to restrict the observations over which the contraction is performed prior to performing the match merge. Suppose, for example, that we have a workfile with observations on individuals with state of residence. Then we could construct two links from the individual page to a state page, one of which computes the mean INCOME for males in each state, and another which computes the mean INCOME for females.

Date match merge links

Dates may be used in matching in two ways: exact matching or date matching (see [“Linking by date match merging” on page 189](#) for details).


Suppose we have a workfile containing the quarterly data on PROFITS described earlier. The quarterly PROFITS data is contained in a regular frequency quarterly workfile page. Also contained in the page is a date series DT generated by taking the first instance in each quarter (“series dt=@date”). We show here DT formatted to show the day-month-year, alongside the PROFIT series.



The screenshot shows an EViews workfile window titled "Group: UNTITLED Workfile: LINK_SALES::Quarterly". The main table displays two series: DT and PROFIT. The DT series is formatted as day-month-year, and the PROFIT series shows numerical values for each quarter from 2002Q1 to 2003Q4.

View	Proc	Object	Print	Name	Freeze	Default	Sort	Transp
obs		DT		PROFIT				
2002Q1		1/1/2002		120				
2002Q2		4/1/2002		130				
2002Q3		7/1/2002		150				
2002Q4		10/1/2002		105				
2003Q1		1/1/2003		100				
2003Q2		4/1/2003		125				
2003Q3		7/1/2003		200				
2003Q4		10/1/2003		170				

Contained in a separate, unstructured page are advertising data ADVERT, and another series DT showing the corresponding irregular dates.



The screenshot shows an EViews workfile window titled "Group: UNTITLED Workfile: LINK_SALES::Advertising". The main table displays two series: DT and ADVERT. The DT series shows irregular dates, and the ADVERT series shows numerical values for each date from 1/7/2002 to 12/23/2003.

View	Proc	Object	Print	Name	Freeze	Default	Sort	Transp
obs		DT		ADVERT				
obs		DT		ADVERT				
1		1/7/2002		10				
2		3/10/2002		50				
3		4/9/2002		40				
4		5/12/2002		90				
5		3/1/2003		70				
6		12/7/2003		30				
7		12/23/2003		20				

If we attempt to match merge these data using the DT date series as identifiers, EViews will use the first method, exact matching, to identify common observations. Thus, if we try to link the PROFIT data into the advertising page using the DT series as the identifiers, we will find that there are no observations in the quarterly source page that match observations in the irregular daily destination page. The resulting link values will all be NAs.

When one or both of the pages follow a regular frequency, we may instruct EViews to employ date matching. We may do so by using the special ID keyword “@DATE” as an ID in the regular frequency page ID to indicate that we wish to use date matching with the built-in date identifiers given by the structure of the page. In this case, we will use “@DATE” as the ID for the regular frequency quarterly page, and match it against the values in the DT series in the destination page.

In this example, we use the Paste Special dialog to instruct EViews to copy the quarterly PROFIT series to a link named PROFIT1 in the destination page. We select General match merge criteria and employ date matching to match the quarters in the source page to the values in the DT series in the destination page, rounding to the lowest common frequency.

We first compute a Mean contraction of the source data for all observations, then match merge the contracted results into the destination. Note that since the match merge in this example is one-to-many, the Mean contraction method is irrelevant since it leaves the source data unchanged. If we wish to guarantee that the source IDs are unique, we may change the Contraction method to No contractions allowed.

In the special case where you have two dated structured pages, you may construct the link using the “@DATE” keyword for both page identifiers. Here, where the advertising page is structured as an (irregular) daily dated page, we could replace DT in the destination index field with the keyword “@DATE”.

If “@DATE” is used as an ID in both pages, EViews will use the observation date identifiers associated with the structure of each page, round them to the lowest common frequency, and then find matching observations.


Index	Value	Other
1	120	
2	120	
3	130	
4	130	
5	100	
6	170	
7	170	

Frequency conversion links

In the special case where we link numeric series between two regular frequency pages, we may copy-and-paste to define a link (or a by value copy of the source series) that employs frequency conversion (“[Linking by date with frequency conversion](#)” on page 193). In this setting, the Paste Special dialog offers you an additional choice between linking by general match merge, or linking by date using frequency conversion.

If you select General match merge criteria in the Merge by section of the dialog, the right side of the dialog will change to show the standard match merge version described in “General match merge links” on page 197.

Alternately, to define a frequency conversion link, click on the Date with frequency conversion selection. The dialog will change to display the frequency conversion options for converting data both from high to low, and low to high frequency.



By default, EViews will use the high to low and the low to high conversion methods specified in the original source series.

If you wish to change the high to low conversion methods, simply select the desired setting from the drop-down menu. In addition, if you select one of the non-default methods, choose whether to select the No conversion of partial periods checkbox. If this setting is selected, EViews will propagate NAs when performing the frequency conversion so that the average of observations with an NA value will not drop the observation, and will instead generate an NA.

Note that the last conversion method, No down conversions, may be used to disallow down frequency conversion of the data. This setting allows you to ensure that when evaluated, the link involves same frequency (one-to-one) or low to high (one-to-many) frequency conversion, otherwise the link evaluation will generate an error.

To set the low to high conversion method, select the desired method from the drop-down menu. Once again, the last frequency conversion method, No up conversions, allows you to inform EViews that you expect the link to work only for same frequency, or high-to-low frequency linking, and that the link evaluation should generate an error if it encounters data requiring up conversion.

Creating a link by command

While the copy-and-paste interface is the easiest approach to specifying a link, we note that you may also create links using the link declaration statement and the linkto procedure.

You may, at the command line, enter the keyword `link` followed by the name of a new link object. EViews will create a new, incompletely specified, link object in the current (destination) workfile page. The destination page should be active when you enter the command.

You may modify a link specification, defining link IDs, as well as contraction and in some cases, expansion methods using `thdinkto` proc.

Consider our earlier example where we link the TAXRATE data from the state page to the individual page. The following command creates a link object in the current workfile page:

```
link taxrate2
```

You may modify the TAXRATE2 link by providing a link definition using the `linkto` procedure. The `linkto` keyword should be followed by the name of the source series and the source and destination IDs, with the latter separated by `@src` and `@dest` keywords. For example, if the link object TAXRATE2 exists in our individual page, the link proc:

```
taxrate2.linkto state::taxrate @src state1 @dest state2
```

instructs EViews to define the link TAXRATE2 so that it uses the TAXRATE series in the source page named "STATE" as the source series, and matches the source page STATE1 values to the current page STATE2 values.

In the special case where there is only one ID series in each page, we may, without introducing ambiguity, omit the `@src` and `@dest` keywords. Here, we may shorten our link definition statement to:

```
taxrate2.linkto state::taxrate state1 state2
```

Lastly, we may combine these declaration and definition statements in to one. The command

```
link taxrate2.linkto state::taxrate state1 state2
```

both creates a link object in the active workfile page and defines the source and link ID series.

In this one-to-many example where we link state data to individuals, we need not consider contraction methods as the default (mean) contraction method preserves the original data. If you wish to disallow contractions, or to limit them to cases where the values of the source data are unique, you may use contraction options as in:

```
link taxrate2.linkto(c=none) state::taxrate state1 state2
```

or

```
link taxrate2.linkto(c=unique) state::taxrate state1 state2
```

Conversely, linking the SALES data from the individual page to the state page yields a many-to-one conversion in which the contraction method is important. In this setting, we may optionally specify a contraction method so that when the state page is active, the statement

```
link sales2.linkto(c=sum) indiv::sales state2 state1
```

links the SALES data from the “INDIV” source page, matching the source page STATE2 values to the current page STATE1 values, and contracting observations using the sum transformation. If the contraction option is not provided, EViews will use the mean contraction default.

In the special case where you wish to link your data using date matching, you must use the special keyword `@date` as an ID series for the regular frequency page. For example, when linking from our quarterly to our advertising page, we may specify:

```
link profit1.linkto quarterly::profit @date dt
```

to tell EViews to link the quarterly page PROFIT data, matching the built-in identifier for the quarter with the date series DT in the destination advertising page.

As in the copy-and-paste interface, the presence of the special `@date` keyword tells EViews that you wish to perform date matching using the date structure of the corresponding regular frequency page. If `@date` is not specified as an ID, EViews will employ a general match merge using the specified identifiers.

When linking data between dated regular frequency workfile pages, the `linkto` proc will perform a frequency conversion link between the two pages unless ID series are explicitly provided, or a general match merge specific conversion method (such as variance or kurtosis) is specified. Thus, issuing the command

```
link profit2.linkto quarterly::profit
```

in an annual page, creates a frequency conversion link PROFIT2 using the PROFIT data from the quarterly page. Since no conversion options are provided, EViews will use the default frequency conversion method specified in the quarterly PROFIT series.

If ID series are provided, EViews will perform the link using general match merging. Thus, the closely related command

```
link profit2a.linkto quarterly::profit @date @date
```

will produce a link named PROFIT2A that employs date match merging using the dates in the workfile page structures. Since no conversion options are provided, EViews will use the default match merge contraction method, taking means, to perform the conversion.

If no ID series are specified, but a match merge specific option is provided, “`@DATE @DATE`” is appended to the ID list, and general match merging is assumed. Thus, the command

```
link profit2b.linkto(c=med) quarterly::profit
```

is equivalent to

```
link profit2b.linkto(c=med) quarterly::profit @date @date
```


since “c=med” is a match merge specific conversion option. This link is evaluated using general match merging, with date matching.

For additional details see [Link](#) (p. 275) and [linkto](#) (p. 278) in the Command and Programming Reference

Working with Links

Once a link is defined, you may, for all intents and purposes, use it as though it were an ordinary series or an alpha series.

Links may be identified in the workfile directory by the presence of a pink series or alpha series icon, or by an icon containing a “?”. If a link definition uses an ordinary source series, it will appear in the workfile directory with a pink version of the series icon. If a link uses an alpha source series, it will appear with a pink alpha series icon. In both cases, the link may be used as though it were a series of the specified type.

If the link source series is not specified or if its type cannot be identified, the link icon will feature a “?” indicating that the link is unavailable. Undefined links will be classified as numeric series that generate NA values for every observation.


Using links

Links use virtually no memory until used. A link goes into use either when you are examining the contents of the link, when it is placed in a group which evaluates the link, or when the link is used in a series expression. Once a link goes out of use, the memory for the link is cleared and made available for other uses. In this way, links take up only the minimum amount of memory required to perform a given operation.

When links are in use, any modification to the data underlying the link will lead to a reevaluation of the link values. If you modify either the source series, or the source or destination ID series, EViews will automatically recompute the link values. In this way, you may use the link to define an automatically updating match merge or frequency conversion.

For example, suppose that we open a workfile containing the state and individual pages. Here we see the individual page containing the state TAXRATE data linked into the link series TAXRATE2. From the (colored) series icon, we see that TAXRATE2 is a link of a numeric series.

If the TAXRATE2 link is not in use, the link series contains no values and takes



up no memory. Links are placed in use either by opening the link window, by placing the link in a group object, or by using the link in a series expression. Whenever the link comes into use, or one of the link components is changed, the link is evaluated, and its values updated as necessary.

For example, if we double click on the TAXRATE2 icon, we open a standard series spreadsheet view. At this point, EViews evaluates the link, performing the match merge operation, and assigning the values to the TAXRATE2 link. Note that the “Last updated” line will show the time that the link values were evaluated.

All of the menus and toolbars are those found in ordinary series—you may work with this link as though it were any ordinary series. Indeed, the only hint you will have that TAXRATE2 is not an ordinary series or alpha series is in the titlebar, which will indicate that we are working with a link object. For example, if you select View/One-way tabulation... uncheck the grouping settings, and click on OK to continue, EViews will display a frequency tabulation of the contents of the link, just as it would for an ordinary series.

Tabulation of TAXRATE2
Date: 07/25/06 Time: 17:51
Sample: 1 6
Included observations: 6
Number of categories: 3

Value	Count	Percent	Cumulative	
			Count	Percent
0.0300	2	33.33	2	33.33
0.0350	2	33.33	4	66.67
0.0500	2	33.33	6	100.00
Total	6	100.00	6	100.00


If you then close the link window, EViews will examine any open windows or existing group objects to see whether the link is still in use. If the link is no longer used, its contents will be cleared and memory will be released. The next time you use the link, it will come into use and will be reevaluated.

Similarly, you may use TAXRATE2 in any place that a series may be used. For example, we may generate a new series, TAXPCT that contains the values of TAXRATE2 expressed in percentage terms:

series taxpct = taxrate2 * 100

Assuming that TAXRATE2 is not currently in use, EViews will evaluate the link and assign values to each observation, then will multiply each of these values by 100 and assign them to TAXPCT. When the series assignment operation is completed, the values of TAXRATE2 will no longer be used, so that EViews will clear the link contents.

If you attempt to open a link that is improperly defined, either because the source or ID series are not found, or because the observed data require a contraction or frequency conversion method that has been disallowed, EViews will display a link view showing the definition of the link and the error encountered. If you attempt to use this link, you will find that all of the link values are set to NA.



Modifying links


You may, at any time, modify the definition of a link by dialog or command.

To modify a link interactively, we must open the Link Spec dialog page. First open the desired link by double clicking on the icon in the workfile directory. Then click on the Properties toolbar button, or select View/Properties... from the main menu to bring up the link properties dialog. Lastly, select the Link Spec tab.

The Link Spec property page is a slightly modified version of the original Paste Special dialog used to create links. While the majority of the dialog is unchanged, in place of the destination name, we now have edit fields in which you specify the names of the source series and the source workfile page.

Here we see that the current link uses the PROFIT series in the QUARTERLY page as the source.

The link is performed by general match merge, using date matching to link the quarterly dates to the destination series DT. The match merge first performs a mean contraction of the PROFIT series over the entire sample, and then performs the match merge.



To modify the link using the dialog, simply alter any of the dialog settings. For example, we may change the link contraction method from Mean to Minimum by changing the selection in the Contraction method combo box, or we may change the source sample by entering a new sample in the edit box. More fundamental changes in the link will result from changing the source series or workfile page, or any of the match merge identifiers.

To modify a link by command, you may use the `linkto` proc. See [“Creating a link by command” on page 204](#) for details. Issuing a `linkto` proc command for an existing link will replace the existing values with the new specification.

Breaking links

The auto-updating feature is one of the most important characteristics of links. Given the live nature of links, changes to either the source series, or the source or destination IDs will lead EViews to recalculate the values of the link. Links may be used to create auto-updating match merges or frequency conversion of series between workfile pages.

Suppose, for example, that while displaying the TAXRATE2 spreadsheet view, you elect to edit the values in the individual STATE2 ID series. Changing Mark's value for STATE2 from “Texas” to “Arkansas” changes the values of an ID series used to compute the values in TAXRATE2. EViews automatically recomputes TAXRATE2, changing the value for Mark from 0.35 to 0.30, and updates the open spreadsheet view accordingly. Furthermore, any future use of the TAXRATE2 link will use the updated values.


In some circumstances, you may wish to fix the values of the link so that future changes to the source or ID series do not alter the existing values. There are two ways in which you may achieve this result. First, you may simply generate a new series that contains the current values of the link, as in:

```
series fixrate = taxrate2
```

The new ordinary series FIXRATE contains the current values of TAXRATE2. Furthermore, FIXRATE remains unchanged in the face of changes in TAXRATE2. With this method, both the original link series and a new series will be kept in the workfile.

The second method of fixing values is to convert the link into a series. We term this process unlinking or breaking the link. In this case, the existing link is replaced by a series with the same name, containing the values in the link at the time the link is broken.

To break a link, simply select **Object/Manage Links & Formulae...** from the workfile window. EViews will display a dialog allowing you to prompt you specify the links you wish to break. Fill out the dialog as desired and click on OK to proceed, bearing in mind that the process of unlinking is irreversible.



Chapter 9. Advanced Workfiles

In [Chapter 3. "Workfile Basics,"](#) we described the basics of workfiles; how to create and work with a workfile, as well as the basics of using multi-page workfiles. In this chapter, we describe advanced workfile types and tools for working with workfiles.

First, we describe the fundamentals of structured workfiles. You will need to understand the concepts underlying structured workfiles to work with irregular dated data, data involving cross-section identifiers, or panel structures.

Next, we outline various workfile level tools for managing your data. Among other things, we discuss the basics of resizing a workfile, saving a workfile to foreign formats, subsetting a workfile, and rearranging the format of the data in your workfile.

Structuring a Workfile

You may, at any time, change the underlying structure of an existing workfile or workfile page by applying structuring information. We call this process structuring a workfile. There are four primary types of structuring information that you may provide:

- regular date descriptions.
- variables containing observation identifiers for dated data.
- variables containing observation identifiers for cross-section data.
- variables containing observation identifiers defining a panel data structure.

The ability to structure your data is an important feature, and we will explore structured workfiles at some length.

Types of Structured Data

Before describing the process of structuring a workfile or workfile page, we define some concepts related to the various data structures.

Regular and Irregular Frequency Data

As the name suggests, regular frequency data arrive at regular intervals (daily, monthly, annually, etc.). Standard macroeconomic data such as quarterly GDP or monthly housing starts are examples of regular frequency data. This type of data is introduced in ["Creating a Workfile by Describing its Structure" on page 35.](#)

Unlike regular frequency data, irregular frequency data do not arrive in a precisely regular pattern. An important example of irregular data is found in stock and bond prices,

where the presence of missing days due to holidays and other market closures means that the data do not follow a regular daily (7- or 5-day) frequency.

The most important characteristic of regular data is that there are no structural gaps in the data—all observations in the specified frequency exist, even if there are missing values that are not observed. Alternatively, irregular data allow for gaps between successive observations in the given regular frequency. This is a subtle distinction, but has important consequences for lag processing.

The distinction is best illustrated by an example. Suppose that we are working with a daily calendar and that we have two kinds of data: data on bond prices (BOND), and data on temperature in Los Angeles in Fahrenheit (TEMP):

Day	Day of Week	Bond	Temp
12/21	Sun	<mkt.closed>	68
12/22	Mon	102.78	70
12/23	Tues	102.79	NA
12/24	Wed	102.78	69
12/25	Thurs	<mkt.closed>	68
12/26	Fri	102.77	70

Notice that in this example, the bond price is not available on 12/21 and 12/25 (since the market was closed), and that the temperature reading was not available on 12/23 (due to equipment malfunction).

Typically, we would view the TEMP series as following a 7-day regular daily frequency with a missing value for 12/23. The key feature of this interpretation is that the day 12/23 exists even though a temperature reading was not taken on that day. Most importantly, this interpretation implies that the lagged value of TEMP on 12/24 (the previous day's TEMP value) is NA.

In contrast, most analysts would view BOND prices as following an irregular daily frequency in which days involving market closures do not exist. Under this interpretation, we would remove weekends and holidays from the calendar so that the bond data would be given by:

Day	Day of Week	Bond
12/22	Mon	102.78
12/23	Tue	102.79
12/24	Wed	102.78
12/26	Fri	102.77

The central point here is that lags are defined differently for regular and irregular data. Given a regular daily frequency, the lagged value of BOND on 12/26 would be taken from the previous day, 12/25, and would be NA. Given the irregular daily frequency, the lagged value on 12/26 is taken from the previous observation, 12/24, and would be 102.78. In defining an irregular calendar, we explicitly skip over the structural gaps created by market closure.

You may always convert irregular frequency data into regular frequency data by adding any observations required to fill out the relevant calendar. If, for example, you have 7-day irregular data, you may convert it to a regular frequency by adding observations with IDs that correspond to any missing days.

Undated Data with Identifiers

Perhaps the simplest data structure involves undated data. We typically refer to these data as cross-section data. Among the most common examples of cross-section data are state data taken at a single point in time:

Obs	Year	State	TaxRate
1	2002	Alabama	.000
2	2002	Arkansas	.035
3	2002	Arizona	.035
...	2002	...	...
50	2002	Wyoming	.010

Here we have an alphabetically ordered dataset with 50 observations on state tax rates. We emphasize the point that these data are undated since the common YEAR of observation does not aid in identifying the individual observations.

These cross-section data may be treated as an unstructured dataset using the default integer identifiers 1 to 50. Alternatively, we may structure the data using the unique values in STATE as identifiers. These state name IDs will then be used when referring to or labeling observations. The advantages of using the state names as identifiers should be obvious—comparing data for observation labeled “Arizona” and “Wyoming” is much easier than comparing data for observations “3” and “50”.

One last comment about the ordering of observations in cross-section data. While we can (and will) define the lag observation to be that “preceding” a given observation, such a definition is sensitive to the arbitrary ordering of our data, and may not be meaningful. If, as in our example, we order our states alphabetically, the first lag of “Arkansas” is taken from the “Arizona” observation, while if we order our observations by population, the lag of “Arkansas” will be the data for “Utah”.

Panel Data

Some data involve observations that possess both cross-section (group) and within-cross-section (cell) identifiers. We will term these to be panel data. Many of the previously encountered data structures may be viewed as a trivial case of panel data involving a single cross-section.

To extend our earlier example, suppose that instead of observing the cross-section state tax data for a single year, we observe these rates for several years. We may then treat an observation on any single tax rate as having two identifiers: a single identifier for STATE (the group ID), and an identifier for the YEAR (the cell ID). The data for two of our states, “Kansas” and “Kentucky” might look like the following:

Obs	State	Year	TaxRate
...	...	...	...
80	Kansas	2001	.035
81	Kansas	2002	.037
82	Kansas	2003	.036
83	Kentucky	2001	.014
84	Kentucky	2003	.016
...	...	...	...

We emphasize again that identifiers must uniquely determine the observation. A corollary of this requirement is that the cell IDs uniquely identify observations within a group. Note that requiring cell IDs to be unique within a group does not imply that the cell IDs are unique. In fact, cell ID values are usually repeated across groups; for example, a given YEAR value appears in many states since the tax rates are generally observed in the same years.

If we observe repeated values in the cell identifiers within any one group, we must either use a different cell identifier, or we must redefine our notion of a group. Suppose, for example, that Kansas changed its tax rate several times during 2002:

Obs	State	Year	Cell_ID1	Cell_ID2	TaxRate
...	...	...	...	...	...
80	Kansas	2001	1	1	.035
81	Kansas	2002	2	1	.037
82	Kansas	2002	3	2	.038
83	Kansas	2002	4	3	.035
84	Kansas	2003	5	1	.036

85	Kentucky	2001	1	1	.014
86	Kentucky	2003	2	2	.016
...	...	...	...	...	...

In this setting, YEAR would not be a valid cell ID for groups defined by STATE, since 2002 would be repeated for STATE="Kansas".

There are a couple of things we may do. First, we may simply choose a different cell identifier. We could, for example, create a variable containing a default integer identifier running within each cross-section. For example, the newly created variable CELL_ID1 is a valid cell ID since it provides each "Kansas" and "Kentucky" observation with a unique (integer) value.

Alternately, we may elect to subdivide our groups. We may, for example, choose to use both STATE and YEAR as the group identifier. This specification defines a group for each unique STATE and YEAR combination (e.g., observations for which STATE="Kansas" and YEAR="2002" would comprise a single group). Given this new group definition, we may use either CELL_ID1 or CELL_ID2 as cell identifiers since they are both unique for each STATE and YEAR group. Notice that CELL_ID2 ~~could~~ not have been used as a valid cell ID for STATE groups since it does not uniquely identify observations within Kansas.

While it may at first appear to be innocuous, the choice between creating a new variable or redefining your groups has important implications (especially for lag processing). Roughly speaking, if you believe that observations within the original groups are closely "related", you should create a new cell ID; if you believe that the subdivision creates groups that are more alike, then you should redefine your group IDs.

In our example, if you believe that the observations for "Kansas" in "2001" and "2002" are both fundamentally "Kansas" observations, then you should specify a new cell ID. On the other hand, if you believe that observations for "Kansas" in "2002" are very different from "Kansas" in "2001", you should subdivide the original "Kansas" group by using both STATE and YEAR as the group ID.

Lags, Leads, and Panel Structured Data

Following convention, the observations in our panel dataset are always stacked by cross-section. We first collect the observations by cross-section and sort the cell IDs within each cross-section. We then stack the cross sections on top of one another, with the data for the first cross-section followed by the data for the second cross-section, the second followed by the third, and so on.

The primary impact of this data arrangement is its effect on lag processing. There are two fundamental principles of lag processing in panel data structures:

- First, lags and leads do not cross group boundaries, so that they never use data from a different group.
- Second, lags and leads taken within a cross-section are defined over the sorted values of the cell ID. This implies that lags of an observation are always associated with lower value of the cell ID, and leads always involve a higher value (the first lag observation has the next lowest value and the first lead has the next highest value).

Let us return to our original example with STATE as the group ID and YEAR as the cell ID, and consider the values of TAXRATE, TAXRATE(-1), and TAXRATE(1). Applying the two rules for panel lag processing, we have:

Obs	State	Year	TaxRate	TaxRate(-1)	TaxRate(1)
...	...	...	...	...	...
80	Kansas	2001	.035	NA	.037
81	Kansas	2002	.037	.035	.036
82	Kansas	2003	.036	.037	NA
83	Kentucky	2001	.014	NA	.016
84	Kentucky	2003	.016	.014	NA
...	...	...	...		

Note in particular, that the lags and leads of TAXRATE do not cross the group boundaries; the value of TAXRATE(-1) for Kentucky in 2001 is an NA since the previous value is from Kansas, and the value TAXRATE(1) for Kansas in 2003 is NA since the next value is from Kentucky.

Next, consider an example where we have invalid IDs since there are duplicate YEAR values for Kansas. Recall that there are two possible solutions to this problem: (1) creating a new cell ID, or (2) redefining our groups. Here, we see why the choice between using a new cell ID or subdividing groups has important implications for lag processing. First, we may simply create a new cell ID that enumerates the observations in each state (CELL_ID1). If we use CELL_ID1 as the cell identifier, we have:

Obs	State	Year	Cell_ID1	TaxRate	TaxRate(-1)
...	...	...	...	...	
80	Kansas	2001	1	.035	NA
81	Kansas	2002	2	.037	.035
82	Kansas	2002	3	.038	.037
83	Kansas	2002	4	.035	.038
84	Kansas	2003	5	.036	.035

85	Kentucky	2001	1	.014	NA
86	Kentucky	2003	2	.016	.014
...	...	...	...	...	

Note that the only observations for TAXRATE(-1) that are missing are those at the “seams” joining the cross-sections.

Suppose instead that we elect to subdivide our STATE groupings by using both STATE and YEAR to identify a cross-section, and we create CELL_ID2 which enumerates the observations in each cross-section. Thus, each group is representative of a unique STATE-YEAR pair, and the cell ID indexes observations in a given STATE for a specific YEAR. The TAXRATE(-1) values are given in:

Obs	State	Year	Cell_ID2	TaxRate	TaxRate(-1)
...	...	...	...	...	...
80	Kansas	2001	1	.035	NA
81	Kansas	2002	1	.037	NA
82	Kansas	2002	2	.038	.037
83	Kansas	2002	3	.035	.038
84	Kansas	2003	1	.036	NA
85	Kentucky	2001	1	.014	NA
86	Kentucky	2003	2	.016	.014
...	...	...	...	...	...

Once again, the missing observations for TAXRATE(-1) are those that span cross-section boundaries. Note however, that since the group boundaries are now defined by STATE and YEAR, there are more seams and TAXRATE(-1) has additional missing values.

In this simple example, we see the difference between the alternate approaches for handling duplicate IDs. Subdividing our groups creates additional groups, and additional seams between those groups over which lags and leads are not processed. Accordingly, if you wish your lags and leads to span all of the observations in the original groupings, you should create a new cell ID to be used with the original group identifier.

Types of Panel Data

Panel data may be characterized in a variety of ways. For purposes of creating panel workfiles in EViews, there are several concepts that are of particular interest.

Dated vs. Undated Panels

We characterize panel data as dated or undated on the basis of the cell ID. When the cell ID follows a frequency, we have a dated panel of the given frequency. If, for example, our cell

IDs are defined by a variable like YEAR, we say we have an annual panel. Similarly, if the cell IDs are quarterly or daily identifiers, we say we have a quarterly or daily panel.

Alternatively, an undated panel uses group specific default integers as cell IDs; by default the cell IDs in each group are usually given by the default integers (1, 2, ...).

Regular vs. Irregular Dated Panels

Dated panels follow a regular or an irregular frequency. A panel is said to be a regular frequency panel if the cell IDs for every group follow a regular frequency. If one or more groups have cell ID values which do not follow a regular frequency, the panel is said to be an irregular frequency panel.

One can convert an irregular frequency panel into a regular frequency panel by adding observations to remove gaps in the calendar for all cross-sections. Note that this procedure is a form of internal balancing (see [“Balanced vs. Unbalanced Panels”](#) below) which uses the calendar to determine which observations to add instead of using the set of cell IDs found in the data.

See [“Regular and Irregular Frequency Data” on page 213](#) for a general discussion of these topics.

Balanced vs. Unbalanced Panels

If every group in a panel has an identical set of cell ID values, we say that the panel is fully balanced. All other panel datasets are said to be unbalanced.

In the simplest form of balanced panel data, every cross-section follows the same regular frequency, with the same start and end dates—for example, data with 10 cross-sections, each with annual data from 1960 to 2002. Slightly more complex is the case where every cross-section has an identical set of irregular cell IDs. In this case, we say that the panel is balanced, but irregular.

We may balance a panel by adding observations to the unbalanced data. The procedure is quite simple—for each cross-section or group, we add observations corresponding to cell IDs that are not in the current group, but appear elsewhere in the data. By adding observations with these “missing” cell IDs, we ensure that all of the cross-sections have the same set of cell IDs.

To complicate matters, we may partially balance a panel. There are three possible methods—we may choose to balance between the starts and ends, to balance the starts, or to balance the ends. In each of these methods, we perform the procedure for balancing data described above, but with the set of relevant cell IDs obtained from a subset of the data. Performing all three forms of partial balancing is the same as fully balancing the panel.

Balancing data between the starts and ends involves adding observations with cell IDs that are not in the given group, but are both observed elsewhere in the data and lie between the

start and end cell ID of the given group. If, for example, the earliest cell ID for a given group is “1985m01” and the latest ID is “1990m01”, the set of cell IDs to consider adding is taken from the list of observed cell IDs that lie between these two dates. The effect of balancing data between starts and ends is to create a panel that is internally balanced, that is, balanced for observations with cell IDs ranging from the latest start cell ID to the earliest end cell ID.

A simple example will better illustrate this concept. Suppose we begin with a two-group panel dataset with the following data for the group ID (INDIV), and the cell ID (YEAR):

Indiv	Year	Indiv	Year
1	1985	2	1987
1	1987	2	1989
1	1993	2	1992
1	1994	2	1994
1	1995	2	1997
1	1996	2	2001

For convenience, we show the two groups side-by-side, instead of stacked. As depicted, these data represent an unbalanced, irregular, annual frequency panel. The data are unbalanced since the set of observed YEAR identifiers are not common for the two individuals; i.e. — “1985” appears for individual 1 (INDIV=“1”), but does not appear for individual 2 (INDIV=“2”). The data are also irregular since there are gaps in the yearly data for both individuals.

To balance the data between starts and ends, we first consider the observations for individual 1. The earliest cell ID for this cross-section is “1985” and the latest is “1996”. Next, we examine the remainder of the dataset to obtain the cell IDs that lie between these two values. This set of IDs is given by {“1987,” “1989,” “1992,” “1994”}. Since “1989” and “1992” do not appear for individual 1, we add observations with these two IDs to that cross-section. Likewise, for group 2, we obtain the cell IDs from the remaining data that lie between “1987” and “2001”. This set is given by {“1993,” “1994,” “1995,” “1996”}. Since “1993,” “1995,” and “1996” do not appear for individual 2, observations with these three cell IDs will be added for individual 2.

The result of this internal balancing is an expanded, internally balanced panel dataset containing:

Indiv	Year	Indiv	Year
1	1985	2	—
1	1987	2	1987

1	*1989	2	1989
1	*1992	2	1992
1	1993	2	*1993
1	1994	2	1994
1	1995	2	*1995
1	1996	2	*1996
1	—	2	1997
1	—	2	2001

We have marked the five added observations with an asterisk, and arranged the data so that the cell IDs line up where possible. Observations that are not present in the dataset are marked as “—”. Notice that the effect of the internal balancing is to fill in the missing cell IDs in the central portion of the data.

It is worth a digression to note here that an alternative form of internal balancing is to add observations to remove all gaps in the calendar between the starts and ends. This method of balancing, which converts the data from an irregular to a regular panel, uses the calendar to determine which observations to add instead of using the set of observed cell IDs found. If we are balancing the expanded dataset, we would add observations with the cell IDs for missing years: {“1986,” “1988,” “1990,” “1991” } for individual 1, and {“1988,” “1990,” “1991,” “1998,” “1999,” “2000” } for individual 2.

Lastly, we consider the effects of choosing to balance the starts or balance the ends of our data. In the former case, we ensure that every cross-section adds observations corresponding to observed cell IDs that come before the current starting cell ID. In this case, balancing the starts means adding an observation with ID “1985” to group 2. Similarly, balancing the ends ensures that we add, to every cross-section, observations corresponding to observed cell IDs that follow the cross-section end cell ID. In this case, balancing the ends involves adding observations with cell IDs “1997” and “2001” to group 1.

Nested Panels

While cell IDs must uniquely identify observations within a group, they typically contain values that are repeated across groups. A nested panel data structure is one in which the cell IDs are nested, so that they are unique both within and across groups. When cell IDs are nested, they uniquely identify the individual observations in the dataset.

Consider, for example, the following nested panel data containing identifiers for both make and model of automobile:

Make	Model
Chevy	Blazer

Chevy	Corvette
Chevy	Astro
Ford	Explorer
Ford	Focus
Ford	Taurus
Ford	Mustang
Chrysler	Crossfire
Chrysler	PT Cruiser
Chrysler	Voyager

We may select MAKE as our group ID, and MODEL as our cell ID. MODEL is a valid cell ID since it clearly satisfies the requirement that it uniquely identify the observations within each group. MODEL is also nested within MAKE since each cell ID value appears in exactly one group. Since there are no duplicate values of MODEL, it may be used to identify every observation in the dataset.


There are a number of complications associated with working with nested panel data. At present, EViews does not allow you to define a nested panel data structure.

Applying a Structure to a Workfile


To structure an existing workfile, select Proc/“Structure/Resize Current Page...” in the main workfile window, or double-click on the portion of the window displaying the current range (“Range:”).

Selecting a Workfile Type

EViews opens the Workfile structure dialog. The basic structure of the dialog is quite similar to the Workfile create dialog ([“Creating a Workfile” on page 34](#)). On the left-hand side is a combo box where you will select a structure type.



Clicking on the structure type combo box brings up several choices. As before, you may choose between the Unstructured/Undated , and Dated - regular frequency types. There are, however, several new options. In the place of Balanced Panel, you have the option to select from Dated - specified by date series, Dated Panel, Undated with ID series , or Undated Panel.




Workfile Structure Settings

As you select different workfile structure types, the right-hand side of the dialog changes to show relevant settings and options for the selected type. For example, if you select the Dated - regular frequency type , you will be prompted to enter information about the frequency of your data and date information; if you select an Undated Panel, you will be prompted for information about identifiers and the handling of balancing operations.

Dated - Regular Frequency


Given an existing workfile, the simplest method for defining a regular frequency structured workfile is to select Dated - regular frequency in the structure type combo box. The right side of the dialog changes to reflect your choice, prompting you to describe your data structure.

You are given the choice of a Frequency, as well as a Start date and End date. The only difference between this dialog and the workfile create version is that the End date field is pre-filled with “@LAST”. This default reflects the fact that given a start date and the number of observations in the existing workfile, EViews can calculate the end date implied by



“@LAST”. Alternatively, if we provide an ending date, and enter “@FIRST” in the Start date field, EViews will automatically calculate the date associated with “@FIRST”.


If we fill out the desired fields and click on OK, EViews will restructure the workfile. In this example, we have specified a monthly frequency starting in 1960:01 and continuing until “@LAST”. There are exactly 500 observations in the workfile since the end date was calculated to match the existing workfile size.



Alternatively, we might elect to enter explicit values for both the starting and ending dates. In this case, EViews will calculate the number of observations implied by these dates and the specified frequency. If the number does not match the number of observations in the existing workfile, you will be informed of this fact, and prompted to continue. If you choose to proceed, EViews will both restructure and resize the workfile to match your specification.

One consequence of this behavior is that resizing a workfile is a particular form of restructuring. To resize a workfile, simply call up the Workfile structure dialog, and change the beginning or ending date.

Here we have changed the End date from “2011:08” to “2011:12”, thereby instructing EViews to add 4 observations to the end of the workfile. If you select OK, EViews will inform you that it will add 4 observations and prompt you to continue. If you proceed, EViews will resize the workfile to your specification.



Specifying Start and End Times

The method used to specify the start and end dates or times should be discussed a bit further. Time periods are generally specified by intervals, such that an hour is represented by the specification 00:00 to 59:59. Thus, a full 24 hour day is defined with a start time of 00:00:00 and an end time of 23:59:59. You will notice that for intraday data, the defaults provided by EViews when you create a workfile reflect this. Similarly, a seven day week can

be defined from Monday at 00:00:00 through Sunday at 23:59:59. One second after this ending time, 24:00:00, refers to the following Monday at midnight and is the first second of the next period.

Not only does specifying an end time of 24:00:00 extend into the next day by one second, it will extend by an amount relative to the frequency being defined for the workfile. For instance, given an hourly workfile, an end time of 24:00:00 would add an extra hour to each day, since extending even a second into the next period adds a full interval.

In general, when specifying a range of time for observations, time can be looked at in terms of intervals or in terms of single measurements. For example, the time period 9 a.m. to 12 p.m. can be considered to be three hourly intervals: 9 a.m. to 10 a.m., 10 a.m. to 11 a.m., and 11 a.m. to 12 p.m. Alternately, it could be considered as four on-the-hour measurements: the first at 9 a.m., the second at 10 a.m., the third at 11 a.m., and the fourth at 12 p.m. While the interval model may be more frequently used for continuous measurements over time, it is really up to you to decide which model fits your data better.

In the first case, which defines three intervals from 9 a.m. to 12 p.m., you would specify your workfile with a start time of 9 a.m. and an end time of 11 a.m. This may not seem intuitive, but remember that specifying an end time of 12 p.m. would add an additional hour, defining the interval from 12 p.m. to 1 p.m. In fact, you could specify any end time from 11:00:00 to 11:59:59 for the third interval.

If we wish to look at our data in terms of four discrete hourly measurements, as in the second case, we would specify our workfile with a start time of 9 a.m. and an end time of 12 p.m. Our data points could then be measured at 9 a.m., 10 a.m., 11 a.m., and 12 p.m.

The distinction between thinking of time in terms of intervals or as discrete measurements is subtle. Generally, simply remember that the starting time will be defined as the first observation, and the following observations are defined by the length of time between the starting time and each subsequent time period. Specifying a start time of 9 a.m. and an end time of 9 a.m. will generate a workfile with one observation per day. To determine the number of observations, subtract the start time from the end time and add one for the first observation.

Dated - specified by date series

The second approach to structuring your workfile is to provide the name of a series containing the dates (or series than maybe interpreted as dates) to be used as observation identifiers. Select Dated - specified by date series in the combo box, and fill out the remainder of the dialog.

The first thing you must do is enter the name of one or more Date series that describe the unique date identifiers.

The series may contain EViews date values (a true date series), or the single or multiple series may contain numeric or string representations of unique dates. In the latter case, EViews will create a single date series containing the date values associated with the numeric or string representations. This new series, which will be given a name of the form DATE ID##, will be used as the identifier series.

The screenshot shows the 'Workfile Structure' dialog box. It has two main sections. The left section, 'Workfile structure type', has a dropdown menu set to 'Dated - specified by date series' and a text box for 'Date series' containing 'dater'. The right section, 'Observation inclusion/creation', has a 'Frequency' dropdown set to 'Auto detect', 'Start date' set to '@first', and 'End date' set to '@last'. At the bottom right, there is a checkbox labeled 'Insert empty obs to remove gaps' which is currently unchecked, with a note below it: 'No gaps implies a regular frequency'. At the bottom of the dialog are 'OK' and 'Cancel' buttons.

On the right side of the dialog, you will specify additional information about your workfile structure. In the first combo box, you will choose one of the standard EViews workfile frequencies (annual, quarterly, monthly, etc.). As shown in the image, there is an additional (default) option, Auto detect, where EViews attempts to detect the frequency of your data from the values in the specified series. In most cases you should use the default; if, however, you choose to override the auto-detection EViews will associate the date values in the series with observations in the specified frequency.

You may elect to use the EViews defaults, "@FIRST" and "@LAST", for the Start date and the End date. In this case, the earliest and latest dates found in the identifier series will be used to define the observations in the workfile. Alternatively, you may specify the start and end dates explicitly. If these dates involve resizing the workfile, you will be informed of this fact, and prompted to continue.


The last option is the Insert empty obs checkbox. This option should be used if you wish to ensure that you have a regular frequency workfile. If this option is selected, EViews will add any observations necessary to remove gaps in the calendar at the given frequency. If the option is not selected, EViews will use only the observed IDs in the workfile and the workfile may be structured as an irregular workfile.

Suppose, for example, that you have observation with IDs for the quarters 1990Q1, 1990Q2, 1990Q4, but not 1990Q3. If `Insert empty obs` is checked, EViews will remove the gap in the calendar by adding an observation corresponding to 1990:3. The resulting workfile will be structured as a regular quarterly frequency workfile. If you do not insert observations, the workfile will be treated as an irregular quarterly workfile.

Once you click on OK, EViews will first look for duplicate observation IDs. If duplicates are not found, EViews will sort the data in your workfile by the values in the date series and define the specified workfile structure. In addition, the date series is locked so that it may not be altered, renamed, or deleted so long as it is being used to structure the workfile.

To illustrate the process of structuring a workfile by an ID series, we consider a simple example involving a 10 observation unstructured workfile.

Suppose that the workfile contains the alpha series B consisting of string representations of dates, as depicted. The first thing you should notice about B is that the years are neither complete, nor ordered—there is, for example, no “1962,” and “1965” precedes “1961”. You should also note that since we have an unstructured workfile, the observation identifiers used to identify the rows of the table are given by the default integer values.




1	1960
2	1961
3	1965
4	1966
5	1967
6	1968
7	1970
8	1971
9	1972
10	1976

From the workfile window we call up the `Workfile structure` dialog, select `Dated - specified by date series` as our workfile type, and enter the name “B” in the `Date series edit` box. We will start by leaving all of the other settings at their defaults: the frequency is set at `Auto detect`, and the start and end dates are given by “@FIRST” and “@LAST”.

The resulting (structured) workfile window shown here indicates that we have a 10 observation irregular annual frequency workfile that ranges from an earliest date of 1960 to the latest date of 1976

Since the series B contained only text representations of dates, EViews has created a new series `DATEID` containing date values corresponding to those



Range:	1960 1976 (irregular)	-- 10 obs	Filter: *
Sample:	1960 1976	-- 10 obs	
Series:	a		
	b		
	c		
	dateid		
	resid		

Here, we show a group containing the

Second, since we have sorted the contents of the workfile by the ID series, the values in B

lar defined by DATEID—for example, the lag of the 1965 value is given by 1961.

To see the effect of this option, we

Workfile: RESTRUCT - (c:\views\data\restruct.wf1)

View Proc Object Print Save Details+/- Show Fetch Store Delete Go

Range: 1960 1976 -- 17 obs Filter: *

Sample: 1960 1976 -- 17 obs

☒ a

☐ abc

☐ c

☒ dateid

☒ resid

Undated New Page

We again show the group containing B, DATEID, and B(-1). Notice that while the observation identifiers and DATEID now include values for the previously missing dates, B and B(-1), do not. When EViews adds observations in the restructure operation, it sets all ordinary series values to NA or missing for those new observations. You are responsible for filling in values as desired.

Dated Panels

To create a dated panel workfile, you should call up the Workfile structure dialog then select Dated Panel as our structure type.

There are three parts to the specification of a dated panel. First, you must specify one or more Date series that describe date identifiers that are unique within each group. Next, you must specify the Cross-section ID series that identify members of a given group. Lastly, you should set options which govern the choice of frequency of your dated data, starting and ending dates, and the adding of observations for balancing the panel or ensuring a regular frequency.

The screenshot shows the EViews Workfile window titled "Group: UNTITLED Workfile: RESTRUCT::Undated". The main table displays the following data:

obs	B	DATEID	B(-1)
1960	1960	1960-01-01	
1961	1961	1961-01-01	1960
1962		1962-01-01	1961
1963		1963-01-01	
1964		1964-01-01	
1965	1965	1965-01-01	
1966	1966	1966-01-01	1965
1967	1967	1967-01-01	1966
1968	1968	1968-01-01	1967
1969		1969-01-01	1968
1970	1970	1970-01-01	
1971	1971	1971-01-01	1970
1972	1972	1972-01-01	1971
1973		1973-01-01	1972
1974		1974-01-01	
1975		1975-01-01	
1976	1976	1976-01-01	

The screenshot shows the "Workfile Structure" dialog box with the following settings:

- Workfile structure type:** Dated Panel
- Panel identifier series:**
 - Cross section ID series: fn
 - Date series: yr
- Observation inclusion/creation:**
 - Frequency: Auto detect
 - Start date: @first
 - End date: @last
 - ☒ Balance between starts & ends
 - ☐ Balance starts
 - ☐ Balance ends
 - ☐ Insert obs to remove date gaps so date follows regular frequency


Dated Panel Basics

We begin by considering the Grunfeld data that have been described in a number of places (see, for example, Baltagi (2005), *Econometric Analysis of Panel Data*, Third Edition, from which this version of the data has been taken). The data measure R&D expenditure and other economic measures for 10 firms for the years 1935 to 1954. These 200 observations form a balanced panel dataset. We begin by reading the data into an unstructured, 200 observation workfile.



To structure the panel for these data, we call up the Workfile structure dialog, select Dated Panel as our structure type, and enter the name of the Cross-section ID series representing firm number, FN, along with the Date series (cell ID) representing the year, YR. If we leave the remaining settings at their default values, EViews will auto detect the frequency of the panel, setting the start and end dates on the basis of the values in the YR series, and will add any observations necessary so that the data between the starts and ends is balanced.

When you click on OK to accept these settings, EViews creates a DATEID series, sorts the data by ID and DATEID, locks the two series, and applies the structure. The auto detecting of the date frequency and endpoints yields an annual (balanced) panel beginning in 1935 and ending in 1954.



The basic information about this structure is displayed at the top of the workfile window. There are a total of 200 observations representing a balanced panel of 10 cross-sections with data from 1935 to 1954.

Notice that the observation labels for the structured panel workfile show both the group identifier and the cell identifier.

Dated Panel Balancing

In the basic Grunfeld example, the data originally formed a balanced panel so the various balance operations have no effect on the resulting workfile. Similarly, the option to insert observations to remove gaps has no effect since the data already follow a regular (annual) frequency with no gaps.

View	Proc	Object	Print	Name	Freeze	Default	Sort	Transpose	E
obs		FN		DATEID		YR			
1 - 35		1		1935-01-01		1935			
1 - 36		1		1936-01-01		1936			
1 - 37		1		1937-01-01		1937			
1 - 38		1		1938-01-01		1938			
1 - 39		1		1939-01-01		1939			
1 - 40		1		1940-01-01		1940			
1 - 41		1		1941-01-01		1941			
1 - 42		1		1942-01-01		1942			
1 - 43		1		1943-01-01		1943			
1 - 44		1		1944-01-01		1944			
1 - 45		1		1945-01-01		1945			
1 - 46		1		1946-01-01		1946			
1 - 47									

Let us now consider a slightly more complicated example involving panel data that are both unbalanced and irregular. For simplicity, we have created an unbalanced dataset by taking a 150 observation subset of the 200 observations in the Grunfeld dataset.

First, we call up the Workfile structure dialog and again select Dated Panel. We begin by using FN and YR as our group and cell

View	Proc	Object	Print	Save	Details+/-	Show	Fetch	Store	Delete	Genr	S
Range: 1935 1954 x 10 -- 150 obs											
Sample: 1935 1954 -- 150 obs											
Filter: *											

IDs, respectively. Use Auto detect to determine the frequency, do not perform any balancing, and click on OK. With these settings, our workfile will be structured as an unbalanced, irregular, annual workfile ranging from 1935 to 1954.

Alternatively, we can elect to perform one or more forms of balancing either at the time the panel structure is put into place, or in a restructure step. Simply call up the Workfile structure dialog and select the desired forms of balancing. If you have previously structured your workfile, the dialog will be pre-filled with the existing identifiers and frequency. In this example, we will have our existing annual panel structure with identifiers DATEID and FN.

In addition to choosing whether to Balance starts and Balance ends, you may choose, at most, one of the two options Balance between starts and ends, and Insert obs to remove date gaps so date follows regular frequency.

If balancing between starts and ends, the balancing procedure will use the observed cell IDs (in this case, the years encoded in DATEID for all cross-sections) between a given start and end date. All cross-sections will share the same possibly irregular calendar for observations between their starts and ends. If you also elect to insert observations to remove date gaps, EViews balances each cross-section between starts and ends using every date in the calendar for the given frequency. In the latter case, all cross-sections share the same regular calendar for observations between their starts and ends.

Selecting all three options, Balance starts, Balance ends and Balance between starts and ends, ensures a balanced panel workfile. If we substitute the option Insert obs to remove date gaps so date follows regular frequency for Balance between starts and ends, we further guarantee that the data follow a regular frequency.


obs	FN	DATEID	YR
1 - 35	1	1935-01-01	1935
1 - 36	1	1936-01-01	NA
1 - 37	1	1937-01-01	1937
1 - 38	1	1938-01-01	1938
1 - 39	1	1939-01-01	NA
1 - 40	1	1940-01-01	NA
1 - 41	1	1941-01-01	1941
1 - 42	1	1942-01-01	1942
1 - 43	1	1943-01-01	1943
1 - 44	1	1944-01-01	NA
1 - 45	1	1945-01-01	1945
1 - 46	1	1946-01-01	1946
1 - 47			

In partly or fully balancing the panel workfile, EViews will add observations as necessary, and update the corresponding data in the identifier series. All other variables will have their values for these observations set to NA. Here, we see that EViews has added data for the two identifier series FN and DATEID while the ordinary series YR values associated with the added observations are missing.

Undated with ID series


If you wish to provide cross-section identifiers for your undated data, select `Undated with identifier series` in the combo box.

EViews will prompt you to enter the names of one or more ID series. When you click on OK, EViews will first sort the workfile by the values of the ID series, and then lock the series so that it may not be altered so long as the structure is in place. The values of the ID series will now be used in place of the default integer identifiers.



Let us consider a simple example. Suppose that we have a 52 observation unstructured workfile, with observations representing the 50 states in the U.S., D.C., and Puerto Rico.

We wish to use the values in the alpha series `STATE` (which contains the standard U.S. Postal Service abbreviations) to identify the observations. The data for `STATE` and a second series, `X`, are displayed here.




obs	STATE	X
38	OR	-1.5136
26	MS	-1.4002
3	AR	-1.2747
4	AZ	-1.2673
9	DE	-1.2605
37	OK	-1.2353
21	MD	-1.1242
11	GA	-1.0324
25	MO	-0.9656
49	WA	-0.8762
23	MI	-0.7244
6	CO	-0.6963
51	WV	-0.5894
28		

Notice that the data are ordered from low to high values for `X`.

Simply select `Undated with identifier series`, enter “state” as the identifier series, and click OK to accept the settings. EViews will sort the observations in the workfile by the values in the ID series, and then apply the requested structure, using and locking down the contents of `STATE`.

Visually, the work file window will change slightly with the addition of the description “(indexed)” to the upper portion of the window, show-



ing that the workfile has been structured. Note, however, that since the dataset is still undated, the workfile range and sample are still expressed in integers ("1 52").

To see the two primary effects of structuring cross-section workfiles, we again examine the values of STATE and the variable X. Notice that the data have been sorted (in ascending order) by the value of STATE and that the observation identifiers in the left-hand border now use the values of STATE.

obs	STATE	X
AK	AK	0.7761
AL	AL	2.3266
AR	AR	-1.2747
AZ	AZ	-1.2673
CA	CA	-0.1221
CO	CO	-0.6963
CT	CT	-0.0918
DC	DC	0.4461
DE	DE	-1.2605
FL	FL	0.7749
GA	GA	-1.0324
HI	HI	-0.1689
IA	IA	0.4890
ID	ID	0.1275

Note that as with irregular structured workfiles, the observation labels will adopt the characteristics of the classifier series display format. If you wish to change the appearance of the observation labels, you should set the spreadsheet display format for STATE (see ["Changing the Spreadsheet Display" on page 82](#)).

Undated Panels

To apply an undated panel structure to your workfile, you must specify one or more Cross-section ID series that identify members of a given group. First, select Undated Panel from the combo box, and then enter the names of your identifier series. You may optionally instruct EViews to balance between the starts and ends, the starts, or the ends of your data.

As an example, we consider the Harrison and Rubinfeld data on house prices for 506 observations located in 92 towns and cities in the harbor area near New Bedford, MA (Harrison and Rubinfeld 1978; Gilley and Pace 1996).

Workfile Structure

Workfile structure type: Undated Panel

Identifier series: townid

Observation inclusion/creation:


- ☒ Balance between starts & ends
- ☐ Balance starts
- ☐ Balance ends

OK Cancel

The group identifiers for these data are given by the series TOWNID, in which the town for a given observation is coded from 1 to 92. Observa-


tions within a town are not further identified, so there is no cell ID within the data. Here we specify only the group identifier TOWNID.

When we click on OK, EViews analyzes the data in TOWNID and determines that there are duplicate observations—there are, for example, 22 observations with a TOWNID of 5. Since TOWNID does not uniquely identify the individual observations, EViews prompts you to create a new cell ID series.



If you click on No, EViews will return you to the specification page where you may define a different set of group identifiers. If you choose to continue, EViews will create a new series with a name of the form CELLID## (e.g., CELLID, CELLID01, CELLID02etc.) containing the default integer cell identifiers. This series will automatically be used in defining the workfile structure.


There are important differences between the two approaches (i.e., creating a new ID series, or providing a second ID series in the dialog) that are discussed in [“Lags, Leads, and Panel Structured Data” on page 217](#). In most circumstances, however, you will click on Yes to continue. At this point, EViews will inform you that you have chosen to define a two-dimensional, undated panel, and will prompt you to continue. In this example, the data are unbalanced, which is also noted in the prompt.



When you click on Yes to continue, EViews will restructure the workfile using the identifiers TOWNID and CELLID##. The data will be sorted by the two identifiers, and the two-dimensional panel structure applied. The workfile window will change to show this restructuring. As depicted in the upper portion, we have a 506 observation, undated panel with dimension (92, 30)—92 groups with a maximum of 30 observations in any group.

Note that in this example, balancing the starts or interiors has no effect on the workfile since CELLID## has cell IDs that begin at 1 and run consecutively for every group. If, however, we choose to balance the ends, which vary between 1

and 30, the corresponding resample operation would add 2254 observations. The final result would be a workfile with 2760 observations, comprised of 92 groups, each with 30 observations.



Common Structuring Errors

In most settings, you should find that the process of structuring your workfile is relatively straightforward. It is possible, however, to provide EViews with identifier information that contains errors so that it is inconsistent with the desired workfile structure. In these cases,

EViews will either error, or issue a warning and offer a possible solution. Some common errors warrant additional discussion.

Non-unique identifiers

The most important characteristic of observation identifiers is that they uniquely identify every observation. If you attempt to structure a workfile with identifiers that are not unique, EViews will warn you of this fact, will offer to create a new cell ID, and will prompt you to proceed. If you choose to proceed EViews will then prompt you to create a panel workfile structure using both the originally specified ID(s) and the new cell ID to identify the observations. We have seen an example of this behavior in our discussion of the undated panel workfile type ([“Undated Panels” on page 235](#)).

In some cases, however, this behavior is not desired. If EViews reports that your date IDs are not unique, you might choose to go back and either modify or correct the original ID values, or specify an alternate frequency in which the identifiers are unique. For example, the date string identifier values “1/1/2002” and “2/1/2002” are not unique in a quarterly workfile, but are unique in a monthly workfile.

Invalid date identifiers

When defining dated workfile structures, EViews requires that you enter the name or names of series containing date information. This date information may be in the form of valid EViews date values, or it may be provided in numbers or strings which EViews will attempt to interpret as valid date values. In the latter case, EViews will attempt to create a new series containing the interpreted date values.

If EViews is unable to translate your date information into date values, it will issue an error indicating that the date series has invalid values or that it is unable to interpret your date specification. You must either edit your date series, or structure your workfile as an undated workfile with an ID series.

In cases where your date information is valid, but contains values that correspond to unlikely dates, EViews will inform you of this fact and prompt you to continue. Suppose, for example, that you have a series that contains 4-digit year identifiers (“1981,” “1982,” etc.), but also has one value that is coded as a 2-digit year (“80”). If you attempt to use this series as your date series, EViews will warn you that it appears to be an integer series and will ask you if you wish to recode the data as integer dates. If you proceed, EViews will alter the values in your series and create an integer dated (i.e., not time dated) workfile, which may not be what you anticipated.

Alternately, you may cancel the restructure procedure, edit your date info series so that it contains valid values, and reattempt to apply a structure.

Missing value identifiers

Your identifier series may be numeric or alpha series containing missing values. How EViews handles these missing values depends on whether the series is used as a date ID series, or as an observation or group ID series.

Missing values are not allowed in situations where EViews expects date information. If EViews encounters missing values in a date ID series, it will issue a warning and will prompt you to delete the corresponding observations. If you proceed, EViews will remove the observations from the workfile. If removed, the observations may not be recovered, even if you subsequently change or remove the workfile structure.

If the missing values are observed in an observation or group ID series, EViews will offer you a choice of whether to keep or remove the corresponding observations, or whether to cancel the restructure. If you choose to keep the observations, the missing value, NA, for numeric series, and a blank string for alpha series, will be used as an observation or cross-section ID in the restructured workfile. If you choose to drop the observations, EViews will simply remove them from the workfile. These observations may not be recovered.

Removing a Workfile Structure

You may remove a workfile structure at any time by restructuring to an unstructured or regular frequency dated workfile. Call up the Workfile structure dialog and select Unstructured/Undated or Dated - regular frequency from the combo box. Fill out the appropriate entries and click OK.

EViews will remove the workfile structure and will unlock any series used as date, group, or observation identifiers.

Resizing a Workfile

Resizing a workfile page is a special case of restructuring. Simply call up the Workfile structure dialog for any workfile page by selecting Proc/“Structure/Resize Current Page...” from a workfile window, or by clicking on the “Range:” description header near the top of the main workfile window. EViews will open the workfile structure dialog with your current settings displayed in the appropriate fields.


Dated - regular frequency / Unstructured

For workfile types where the structure of the data is described explicitly (dated with regular frequency, or unstructured), the Start date and End date, or Observations values will be filled out with actual values.

To change the sizes of regular frequency workfiles, enter the appropriate Start date and End date information using explicit dates or offsets from “@FIRST” and “@LAST”.

To change the size of an unstructured workfile, change the number of Observations. Note that for unstructured data, you may only add or delete observations from the end of the workfile, you may not change the starting observation; if you wish to modify the starting observation you will need to work with an integer dated workfile.

EViews will inform you of the number of observations to be added and/or deleted, and will prompt you to continue.



For example, changing the End date for your annual workfile from “2001” to “ 2009”, or the number of Observations in your unstructured workfile from “100” to “107” will both add 7 observations to the end of the respective workfiles. Likewise, changing the Start date of your monthly workfile from “1990:01” to “@FIRST-24” will add 24 months to the beginning of the workfile while changing the End date to “@LAST-3” removes (deletes) the last three observations.

Dated - specified by date series

For a dated workfile that is structured using a date series, the dialog will open with pre-filled Start date and End date values containing “@FIRST” and “@LAST” as stand-ins for the earliest and latest observed dates. To change the size of a dated workfile structured by a date series, simply enter the appropriate information using explicit dates or offsets from “@FIRST” and “@LAST”.

Given your start and end date values, EViews will analyze your date identifiers to determine whether you need to add or remove observations. If required, EViews will inform you of the number of observations to be added or deleted, and you will be prompted to continue. If observations are added, the date series will be modified to hold the corresponding date values. As with other forms of restructuring, deleted observations may not be recovered.

An observation will be deleted if the corresponding date ID falls outside the range implied by the start and end dates. If we enter “1970” as the Start date and “2010” as the End date in our annual workfile, any observations whose date series value is earlier than 1970 or later than 2010 will be removed from the workfile. If we enter “@ FIRST+2” and “@LAST-3” as our Start date and End date, EViews will delete the first two and last three observations from the workfile.

EViews will add observations to the workfile if the Start date is earlier than “@FIRST” or the End date is later than “@LAST”. The observations to be added are determined by examining the regular frequency calendar to find all possible dates which fall in the desired range. If, in our annual workfile that ranges from 1980 to 2000, we specify a Start date of “1975”, EViews will add observations for all of the years from 1975 to 1979, and will modify the date series so that it contains the associated date values. Alternatively, entering

“@FIRST–2” and “@LAST+2” adds two observations corresponding to 1978 and 1979, and two observations corresponding to 2001 and 2002.

Note that there is a bit of asymmetry here in the use of offsets to “@FIRST” and “@LAST”. Offsets that remove observations from the workfile simply count from the first or last observation, while offsets that add observations to the workfile use the regular frequency calendar to determine the dates to be added.

Dated Panel

For dated panel workfiles, the prefilled Start date and End date values will contain “@FIRST” and “@LAST” as stand-ins for the cross-section specific earliest and latest observed dates. To resize a dated panel workfile, you may enter an explicit date value in one or both of those fields. If you elect to use offsets, you must take care to understand the inherent complexities involved.

When you enter “@FIRST+2” and “@LAST–2”, EViews trims off 2 observations from the beginning and end of each cross-section. Used in this fashion, “@FIRST” refers to the earliest date for each cross-section, and the offsets are in observation space.

If we combine this trimming with balancing starts or ends, balancing occurs prior to the trimming of observations. Interestingly, this means that the starts or ends will not necessarily be balanced following trimming.

In order to use “@FIRST–2” or “@LAST+2”, EViews must balance starts or ends. The interpretation of the offsets that extend beyond the range of observations differs since they are evaluated in regular date space. If you enter “@FIRST–2” and choose to balance starts, the behavior is: first balance starts, then add two observations to the beginning in date space. Note that this operation is the same as adding two observations in regular date space to the cross-section with the earliest observed date and then balancing starts.

This behavior means that you cannot easily add two observations (in date space) to the start or end of each cross-section, without possibly adding more via start or end balancing. The panel data will have balanced starts or ends following the operation.

Undated with ID series / Undated Panel

Resizing an undated workfile that is structured using an ID series requires several distinct operations, since there is no simple way to describe the restructure operation. At a deep level, resizing these types of workfiles involves modifying your identifiers, and then adding or deleting observations with specific identifier values.

To alter the identifier series you must first remove the workfile structure. Call up the Workfile structure dialog and select Unstructured/Undated from the combo box. Click on OK. EViews will remove the existing workfile structure and will unlock the ID series.

If you wish to remove observations, you should edit one of the ID series so that the desired observations have missing IDs. If you reapply the original Undated with ID series or Undated Panel structure, EViews will prompt you to remove observations with the missing ID values. We remind you that this step will remove all observations with missing values for the identifiers; if you originally used the missing value as a valid identifier, the corresponding observation will also be removed.

To add observations, you must first append observations to the workfile by expanding the unstructured workfile and then editing the ID series to add unique identifiers for the new values, or by using the built-in tools to append to the workfile page described below. Once you have added the new observations, you may reapply the workfile structure. EViews will sort your data using the identifier values, lock down the ID series, and then apply the structure to the expanded workfile.

Appending to a Workfile


One method of combining two workfile pages is to append observations from a source workfile page to the end of a target workfile page. When appending data, EViews first removes any structure from the target page, then expands its range to encompass the combined range of the original page and the appended data. The data from the source page are then copied to the expanded part of the target workfile range, either in existing series or alpha objects, or in newly created objects.

When appending, you should first make certain that the workfiles containing both the source and target page are open in EViews. In some cases (for example, concatenating a workfile page with itself), you only need to have a single open workfile since the source and target workfiles are the same.

To open the Workfile Append dialog, click on the Proc button on the target workfile toolbar and select Append to Current Page... , or select Proc/Append to Current Page... from the main menu.

Selecting Data to Append

You should begin by selecting a workfile page containing data to be appended to the target page. The first combo box contains a list of all workfiles currently in memory from which you should select the source workfile; in the second combo box, you should choose a page from those in the workfile you have selected. Here, we have instructed EViews to append data from the ANNUAL page in the workfile LINK_SALES.



Next, you should specify a sample of observations in the source page to be appended; any valid EViews sample may be provided. Here, we have specified the default sample “@ALL”, which ensures that we use all of the observations in the source page.

If you wish, you may use the Objects to append settings to specify the objects to be appended or copied. By default (All series & alpha), EViews will append all series and alphas (and links) from the source page into the destination page. If you select All objects, EViews will append all series and alphas, and will copy all other objects into the destination. Alternatively, choosing Listed objects allows you to specify the individual objects to be copied by name, using wildcards if convenient. To append only those data objects that exist in both pages, you should select Series & alpha that exist in both workfiles . If this setting is selected, a series or numeric link Y in the source page will only be appended if a series Y exists in the active page, and an alpha or alpha link X in the source will only be appended if an alpha series X exists in the destination.

Handling Name Collision

The settings in Name collision control the method EViews uses to append data when a source object name is present in the target page. To understand the effects of the various settings, consider the three possible scenarios that may occur when appending from an object into a workfile page:

- there is no object with the same name in the target page.

- an object with the same name exists in the target, but the object type is not compatible.
- an object with the same name exists in the target, and the object type is compatible with the source object.

In saying that the source and destination objects are compatible, we indicate that the source data may be added to the end of the existing object. Series and numeric link data may only be added to the end of series objects, while alpha and alpha link data may only be added to the end of alpha objects. All other combinations of objects are said to be incompatible.

Suppose that we wish to append the source series *X* or numeric link to the target page. If there is no object with the same name in the target page, EViews will create a new series, *X*, containing NA values for the original target page observations, and the values of the source series *X* for observations in the expanded part of the range.

If there is an incompatible matching object, a new object will be created with a name formed from the original name and the text specified in the Suffix to apply to renamed objects edit field. If, for example, the target page contains an incompatible *X* (e.g., it contains the equation *X*), EViews will create a new series using the original name, and the specified suffix, for example, "*X_A*" (using the default suffix, "*_A*").

If there is a compatible matching object, EViews will examine your dialog settings to determine the appropriate behavior. By default, EViews will append the data from a compatible source object to the end of the existing object. Thus, data from the series or numeric link *X* will be copied to the expanded part of the range of the target series *X*, and data from the alpha or alpha link *Y* will be copied to the end of the alpha series *Y*. You may override this default so that EViews creates a new object even when the matching objects are compatible, by unselecting the Merge series or Merge alpha checkboxes.

Creating Identifier Series

The optional Created series settings in the dialog allow you to save series containing information about each observation in the combined workfile.

To save a series containing the date or observation ID associated with each observation in the combined workfile, you should enter a unique name in the edit field labeled Date/Obs ID. The specified series will be created in the target page, and will contain the observation or cell identifiers given by the structures associated with the source and the original target pages. Saving the IDs is particularly useful since appending to a workfile removes the existing page structure.

The optional Workfile ID series identifies the source of the observation in the combined workfile: observations in the original target page are assigned the value 0, while observations in the appended portion of the target will be given the value 1.


Contracting a Workfile

Samples are an important tool for restricting the set of observations used by EViews when performing calculations. You may, for example, set an estimation sample to restrict the observations used in a regression to only include females, or to only use the observations with dates between 1990 and 2003. An important advantage to working with samples is that the exclusion of observations is temporary, and may be reset simply by providing a new sample specification. Note also that even as they are excluded from calculations, out-of-sample observations still exist, and are used for lag processing.

There may be times, however, when you wish to drop or remove observations from a workfile page. For example, if you have daily data on stock trades and want lags to skip holidays, you must permanently remove holidays from the workfile. Similarly, if the focus of your analysis is on female labor force participation, you may wish to subset your workfile by excluding all males. Contracting the workfile in this fashion both reduces the size of the workfile and makes it easier to work with, since you no longer have to remember to set all samples to exclude males.

To contract a workfile page in place, you should click on the Proc button on the workfile toolbar and select Contract Current Page..., or select Proc/Contract Current Page... from the main menu.

EViews will open the Workfile Contract dialog prompting you to input a valid sample specification. Simply enter a sample specification and EViews will drop all observations in the current page that do not meet the specified criteria. Here, we drop all observations where the ID series is greater than 7 or where K lies between 100 and 200 (inclusive).



We emphasize that the workfile contraction occurs in place so that the existing workfile page will no longer exist. If you wish to keep the original page, you should make a copy of the page, or save it to disk.

Copying from a Workfile

EViews provides you with convenient tools for copying or extracting subsamples of observations and series objects from existing workfiles and creating new pages containing the extracted data or links to the data. You may, for example, wish to create separate workfile pages for the males and females in your cross-section workfiles, or to keep only non-holiday dates from your regular frequency daily-7 data. Similarly, you may wish to create a page containing a small subset of the series found in your original workfile.

Copying or extracting the series object data may be performed in two distinct ways: by creating links in a new page in the same workfile, or by copying the series objects into a new page in the existing or an alternate workfile.

The first method uses link objects to create memory efficiently, dynamically updating copies of the data in your series, link, and alpha objects, but requires that the new destination page be in the same workfile.

The second method copies the actual values in the objects. Since links are not involved, you may use this approach to copy data into new pages in different workfiles. In addition, when copying by value, you may copy other types of EViews objects and you will have access to built-in tools for creating random samples of the observations in the source workfile.

Copying by Link


To copy all or part of the data in a work file by creating links, you should select Proc/“Copy Extract from Current Page ”/By Link to New Page... . EViews will open the Workfile Copy By Link dialog in which you will specify the data to be copied.

There are two principal ways that you can specify a subset of the data to be copied: you may specify a subsample of observations in the workfile or you may specify a subset of the series objects.


EViews will copy all of the observations in the sample specified in the edit box labeled Sample - observations to copy . To specify a subsample of observations, you should replace the default “@ALL” with a valid EViews sample.

You may elect to copy all series, alphas, and valmaps, or you may select the Listed Series - Alphas - Valmaps radio button and enter a list of the series to be copied, with wildcards, if desired.

If the Include Links checkbox is selected, EViews will copy series and alpha links along with ordinary series and alphas. If you uncheck Include Links , EViews will drop all link objects from the copy list.



The copy by link procedure will create the links in a new page in the existing workfile. By default, the page will be given a name based on the page structure (e.g., “Annual”, or “Daily5”). You may provide a name for this destination page by clicking on the Page Destination tab and enter the desired name. If a page with that name already exists in the workfile, EViews will create a new page using the next available name. Note that since we are copying by link, you may not create a page in a different workfile.



When you click on OK to accept the dialog settings, EViews first examines your source workfile and the specified sample, and then creates a new page with the appropriate number of observations.

Next, EViews will copy, by value, the ID series used to structure the source workfile page for the specified sample of observations. Using the new series, EViews will structure the new workfile in a manner similar to the source workfile page. If, for example, you have an undated workfile that is structured using an ID series COUNTRIES, EViews will create a series in the destination page, copy the relevant values, and structure the page as an undated workfile using the new ID series COUNTRIES. Similarly, if the original page has an annual panel structure that is defined using multiple ID series, all of the ID series will be copied to the new page, and the page will be structured as an annual panel using these new series.

Lastly, EViews will create links in the new page for all of the specified series objects. The links will be defined as general match merge links using the source and destination ID series. Since the new page is a subset of the original page, the contraction methods will be set to No contractions allowed (see [“Link calculation settings” on page 199](#)).


Copying by Value

To copy all or part of the work file by value, you should select Proc/“Copy/Extract from Current Page”/By Value to New Page or Workfile... . EViews will open the Workfile Copy By Value dialog.

You should first specify an EViews sample describing the observations to be copied. By default, EViews will use the sample “@ALL”.

Next, you should use the combo box to select a Random subsample method. By default, all of the observations in the sample will be used (No random subsampling), but you may choose to extract a random sample in one of three ways:

- You may extract a subsample with a fixed number of observations (Fixed subsample size - number of observations). If the specified subsample size is larger than the number of observations, the entire sample is used.
- You may select a subsample with a fixed size, where the number of observations is specified as a percent of the total number of observations (Fixed subsample size - % of observations).
- You may take a simple random sample in which every observation has a fixed probability of being selected (Random subsample size - % applied to each obs). As the label suggests, the number of observations in the resulting subsample is itself random.



In the remainder of the dialog page you should specify the objects to be copied. There are two parts to the object specification: a list of object names, and a set of modifiers for object types.

By default, the All objects radio button is selected so that the list of object names provided to EViews will include every object in the source workfile. You may instead provide an explicit list by clicking on the Listed objects radio button and entering the names of objects (using wildcards if appropriate).

The type matching checkboxes (Series - Alphas - Valmaps, Links, Estimation & Model Objects, All others) may be used to restrict the object list on the basis of broad classifications for type; an object will be copied only if it is in the list of object names provided in the edit box, and if its type matches a classification that you elect to copy. If, for example, you wish to remove all objects that are not series objects or valmaps from your list, you should uncheck the Estimation & Model objects and the All others checkboxes.

Lastly, you may optionally provide a destination workfile page. By default, EViews will copy the data to a new workfile in a page named after the workfile page structure (e.g., “Quarterly,” “Monthly”). You may provide an alternative destination by clicking on the **Page Destination** tab in the dialog, and entering the desired destination workfile and/or page.

When you click on **OK**, EViews examines your source workfile and the specified sample, and creates a new page with the appropriate number of observations. EViews then copies the ID series used to structure the source workfile, and structures the new workfile in identical fashion. Lastly, the specified objects are copied to the new workfile page.

Reshaping a Workfile

In a typical study, each subject (individual, firm, period, etc.) is observed only once. In these cases, each observation corresponds to different subject, and each series, alpha, or link in the workfile represents a distinct variable.

In contrast, repeated measures data may arise when the same subject is observed at different times or under different settings. The term repeated measures comes from the fact that for a given subject we may have repeated values, or measures, for some variables. For example, in longitudinal surveys, subjects may be asked about their economic status on an annual basis over a period of several years. Similarly, in clinical drug trials, individual patient health may be observed after several treatment events.

It is worth noting that standard time series data may be viewed as a special case of repeated measures data, in which there are repeated higher frequency observations for each lower frequency observation. Quarterly data may, for example, be viewed as data in which there are four repeated values for each annual observation. While time series data are not typically viewed in this context, the interpretation suggests that the reshaping tools described in this section are generally applicable to time series data.

There are two basic ways that repeated measures data may be organized in an EViews workfile. To illustrate the different formats, we consider a couple of simple examples.

Suppose that we have the following dataset:

ID1	ID2	Sales
1	Jason	17
1	Adam	8
2	Jason	30
2	Adam	12
3	Jason	20

We may view these data as representing repeated measures on subjects with identifiers given in ID1, or as repeated measures for subjects with names provided in ID2. There are, for example, two repeated values for subjects with “ID1=1”, and three repeated values for SALES for Jason. Note that in either case, the repeated values for the single series SALES are represented in multiple observations.

We can rearrange the layout of the data into an equivalent form where the values of ID2 are used to break SALES into multiple series (one for each distinct value of ID2):

ID1	SalesJason	SalesAdam
1	17	8
2	30	12
3	20	NA

The series ID2 no longer exists as a distinct series in the new format, but instead appears implicitly in the names associated with the new series (SALESJASON and SALESADAM). The repeated values for SALES are no longer represented by multiple observations, but are instead represented in the multiple series values associated with each value of ID1.

Note also that this representation of the data requires that we add an additional observation corresponding to the case ID1=3, ID2=“Adam” . Since the observation did not exist in the original representation, the corresponding value of SALESADAM is set to NA.

Alternatively, we may rearrange the data using the values in ID1 to break SALES into multiple series:

ID2	Sales1	Sales2	Sales3
Jason	17	30	20
Adam	8	12	NA

In this format, the series ID1 no longer exists as a distinct series, but appears implicitly in the series names for SALES1, SALES2, and SALES3. Once again, the repeated responses for SALES are not represented by multiple observations, but are instead held in multiple series.

The original data format is often referred to as repeated observations format, since multiple observations are used to represent the SALES data for an individual ID1 or ID2 value. The latter two representations are said to be in repeated variable or multivariate form since they employ multiple series to represent the SALES data.

When data are rearranged so that a single series in the original workfile is broken into multiple series in a new workfile, we term the operation *unstacking the workfile*. Unstacking a workfile converts data from repeated observations to multivariate format.

When data are rearranged so that sets of two or more series in the original workfile are combined to form a single series in a new workfile, we call the operation **stacking the workfile**. Stacking a workfile converts data from multivariate to repeated observations format.

In a time series context, we may have the data in the standard stacked format:

Date	Year	Quarter	Z
2000Q1	2000	1	2.1
2000Q2	2000	2	3.2
2000Q3	2000	3	5.7
2000Q4	2000	4	6.3
2001Q1	2001	1	7.4
2001Q2	2001	2	8.1
2001Q3	2001	3	8.8
2001Q4	2001	4	9.2

where we have added the columns labeled YEAR and QUARTER so that you may more readily see the repeated measures interpretation of the data.

We may rearrange the time series data so that it is unstacked by QUARTER,

Year	Z1	Z2	Z3	Z4
2000	2.1	3.2	5.7	6.3
2001	7.4	8.1	8.8	9.2

or in the alternative form where it is unstacked by YEAR:

Quarter	Z2000	Z2001
1	2.1	7.4
2	3.2	8.1
3	5.7	8.8
4	6.3	9.2

EViews provides you with convenient tools for reshaping workfiles between these different formats. These tools make it easy to prepare a workfile page that is set up for use with built-in pool or panel data features, or to convert data held in one time series representation into an alternative format.

Unstacking a Workfile

Unstacking a workfile involves taking series objects in a workfile page, and in a new workfile, breaking the original series into multiple series.

We employ an unstacking ID series in the original workfile to determine the destination series, and an observation ID series to determine the destination observation, for every observation in the original workfile. Accordingly, we say that a workfile is “unstacked by” the values of the unstacking ID series.

To ensure that each series observation in the new workfile contains no more than one observation from the existing workfile, we require that the unstacking ID and the observation ID are chosen such that no two observations in the original workfile have the same set of values for the identifier series. In other words, the identifier series must together uniquely identify observations in the original workfile.

While you may use any series in the workfile as your unstacking and observation identifier series, an obvious choice for the identifiers will come from the set of series used to structure the workfile (if available). In a dated panel, for example, the cross-section ID and date ID series uniquely identify the rows of the workfile. We may then choose either of these series as the unstacking ID, and the other as the observation ID.

If we unstack the data by the cross-section ID, we end up with a simple dated workfile with each existing series split into separate series, each corresponding to a distinct cross-section ID value. This is the workfile structure used by the EViews pool object, and is commonly used when the number of cross-sectional units is small. Accordingly, one important application of unstacking a workfile involves taking a page with a panel structure and creating a new page suitable for use with EViews pool objects.

On the other hand, if we unstack the panel workfile by date (using the date ID series or @DATE), we end up with a workfile where each row represents a cross-sectional unit, and each original series is split into separate series, one for each observed time period. This format is frequently used in the traditional repeated measures setting where a small number of variables in a cross-sectional dataset have been observed at different times.

To this point, we have described the unstacking of panel data. Even if your workfile is structured using a single identifier series, however, it may be possible to unstack the workfile by first splitting the single identifier into two parts, and using the two parts as the identifier series. For example, consider the simple quarterly data given by:

Date	X	Y
2000Q1	NA	-2.3
2000Q2	5.6	-2.3

2000Q3	8.7	-2.3
2000Q4	9.6	-2.3
2001Q1	12.1	1.6
2001Q2	8.6	1.6
2001Q3	14.1	1.6
2001Q4	15.2	1.6

Suppose we wish to unstack the X series. We may split the date identifier into a year component and a quarter component (using, say, the EViews @YEAR and @QUARTER functions). If we extract the QUARTER and YEAR from the date and use the QUARTER as the unstacking identifier, and the YEAR as the observation identifier, we obtain the unstacked data:

Year	X1	X2	X3	X4
2000	NA	5.6	8.7	9.6
2001	12.1	8.6	14.1	15.2

Note that we have chosen to form the series names by concatenating the name of the X series, and the values of the QUARTER series.

Alternatively, if we use YEAR as the unstacking ID, and QUARTER as the observation ID, we have:

Quarter	X2000	X2001
1	NA	12.1
2	5.6	8.6
3	8.7	14.1
4	9.6	15.2

In some cases, a series in the original workfile will not vary by the unstacking ID. In our example, we have a series Y that is only updated once a year. Stacking by QUARTER yields:

Year	Y1	Y2	Y3	Y4
2000	-2.3	-2.3	-2.3	-2.3
2001	1.6	1.6	1.6	1.6

Since there is no change in the observations across quarters, these data may be written as:

Year	Y
2000	-2.3
2001	1.6

without loss of information. When unstacking, EViews will automatically avoid splitting any series which does not vary across different values of the unstacking ID. Thus, if you ask EViews to unstack the original Y by QUARTER, only the compacted (single series) form will be saved. Note that unstacking by YEAR will not produce a compacted format since Y is not constant across values of YEAR for a given value of QUARTER.

Unstacking a Workfile in EViews

To unstack the active workfile page, you should select Proc/Reshape Current Page/Unstack in New Page... from the main workfile menu. EViews will respond by opening the tabbed Workfile Unstack dialog.

When unstacking data, there are four key pieces of information that should be provided: a series object that contains the unstacking IDs, a series object that contains the observation IDs, the series in the source workfile that you wish to unstack, and a rule for defining names for the unstacked series.

Unstacking Identifiers

To unstack data contained in a workfile page, your source page must contain a series object containing the unstacking identifiers associated with each observation. For example, you may have an alpha series containing country abbreviations ("US," "JPN," "UK"), or individual names ("Joe Smith," "Jane Doe"), or a numeric series with integer identifiers ("1," "2," "3," "50," "100," ...). Typically, there will be repeated observations for each of the unique unstacking ID values.

You should provide the name of your unstacking ID series object in the top edit field of the dialog. When unstacking, EViews will create a separate series for each distinct value of the ID series, with each of these series containing the multiple observations associated with that value. The series used as the unstacking ID is always dropped from the destination workfile since its values are redundant since they are built into the multiple series names.

If you wish to unstack using values in more than one series, you must create a new series that combines the two identifiers by identifying the subgroups, or you may simply repeat the unstacking operation.

Observation Identifiers

Next, you must specify a series object containing an observation ID series in the second edit field. The values of this series are used to identify both the individual observations in the unstacked series and the structure of the destination page.

Once again, if your workfile is structured, an obvious choice for the unstacking identifier series comes from the series used to structure the workfile, either directly (the date or cross-section ID in a panel page), or indirectly (the YEAR or QUARTER extracted from a quarterly date).

EViews will, if necessary, create a new observation ID series in the unstacked page with the same name as, and containing the unique values of, the original observation ID series. This series will be used to structure the workfile.

If the original observation ID is an ordinary series or alpha, the new page will be structured as a cross-section page using the new identifier series. Alternatively, if the observation ID is a date series or the “@DATE” keyword, EViews will analyze the observed date values and will create a dated page with the appropriate frequency.

Series to be Unstacked

You may enter the names of the series, alphas, and links that you wish to unstack in the edit field Series to be unstacked into new workfile page . You may enter the names directly, or use expressions containing wildcards. For example, the expression “SALES A*” instructs EViews to unstack both the SALES series as well as all series objects beginning with the letter “A”.

Note that the RESID series and the unstacking ID series may not be unstacked.

Naming Unstacked Series

EViews will use the pattern in the Name pattern for unstacked series field to construct the names for the new unstacked series or alphas associated with each stacked series object.

By default, the wildcard pattern “*?” will be used, meaning that unstacked series names will be constructed by concatenating the name of the series object to be unstacked and a string containing one of the unique values found in the unstacking ID series.

In our example above, when unstacking the SALES series using NAME as the unstacking ID series and the wildcard name pattern “*?”, EViews will create the series JASONSales and ADAMSales. If instead, we enter the pattern “*_*”, EViews will put the unstacked values in the series Sales_Jason and Sales_Adam.


Unstacking Destination

By default, EViews will unstack the data in a new UNTITLED page in the existing workfile. You may provide an alternative destination by clicking on the Page Destination tab in the dialog, and entering the desired destination.

An Example

Consider a workfile that contains the series GDP and CONS, which contain the values of Gross Domestic Product and consumption for three countries stacked on top of each other.

Suppose further that there is an alpha object called COUNTRY containing the values "US," "UK," and "JPN", which identify the country associated with each observation on GDP and CONS. Finally, suppose there is a date series DATEID which identifies the date associated with each observation in the page. COUNTRY and DATEID uniquely determine the observation identifiers.



In our example, we assume that the source page contains annual data from 1991 to 2000 for the three countries in our panel. We can better see this structure by opening a group window showing the values of COUNTRY, DATEID (displayed in year-date format), and GDP.

obs	COUNTRY	DATEID	GDP
jpn - 91	jpn	1991	1021.885
jpn - 92	jpn	1992	1067.209
jpn - 93	jpn	1993	1071.909
jpn - 94	jpn	1994	1075.097
jpn - 95	jpn	1995	1046.525
jpn - 96	jpn	1996	1122.045
jpn - 97	jpn	1997	1041.075
jpn - 98	jpn	1998	1123.299
jpn - 99	jpn	1999	1098.159
jpn - 00	jpn	2000	1122.300
uk - 91	uk	1991	1071.246
uk - 92	uk	1992	1040.945
uk - 93	uk	1993	1060.413
uk - 94			

We wish to unstack the data in GDP and CONS using the unstacking ID values in COUNTRY, and the observation IDs in DATEID. Click on Proc/Reshape Current Page/Unstack in New Page... in the workfile window to bring up the unstacking dialog.



Enter “COUNTRY” as the unstacking ID series, and “DATEID” for the observation identifier. We leave the remainder of the dialog settings at the default values, so that EViews will use “*?” as the name pattern, will copy all series objects in the page (with the exception of RESID and COUNTRY), and will place the results in a new page in the same workfile.

If you click on OK to accept the settings, EViews will first examine the DATEID series to determine the number of unique observation identifiers. Note that the number of unique observation identifier values determines the number of observations in the unstacked workfile. Next, EViews will determine the number of unique values in COUNTRY, which is equal to the number of unstacked series created for each stacked series.


In this example, we start with a balanced panel with 10 distinct values for DATEID, and three distinct values in COUNTRY. The resulting UNTITLED workfile page will follow an annual frequency from the 10 observations from 1991 to 2000, and will have three unstacked series corresponding to each of the source series. The names of these series will be formed by taking the original series name and appending the distinct values in COUNTRY (“US,” “UK,” and “JPN”).

Note that in addition to the six unstacked series CONSJPN, CONSUKE, CONSUS, GDPJPN, GDPUK, GDPUS, EViews has created four additional objects. First, the unstacked page contains two group objects taking the name of, and corresponding to, the original series CONS and GDP.

Each group contains all of the unstacked series, providing you with easy access to all of the series associated with the original stacked series. For example, the group GDP contains the three series, GDPJPN, GDPUK, and GDPUS, while CONS contains CONSJPN, CONSUKE, and CONSUS.



Opening the GDP group spreadsheet, we see the result of unstacking the original GDP series into three series: GDPJPN, GDPUK, and GDPUS. In particular, the values of the GDPJPN and GDPUK series should be compared with the values of GDP depicted in the group spreadsheet view of the stacked data.



View	Proc	Object	Print	Name	Freeze	Default	Sort	Transpose
obs		GDPJPN		GDPUK		GDPUS		
1991		1021.885		1071.246		1009.893		
1992		1067.209		1040.945		1060.955		
1993		1071.909		1060.413		1032.949		
1994		1075.097		1048.092		1099.095		
1995		1046.525		1100.471		1010.690		
1996		1122.045		1062.437		1100.267		
1997		1041.075		1080.443		1024.706		
1998		1123.299		1039.915		1021.927		
1999		1098.159		1048.163		1054.704		
2000		1122.300		1054.837		1067.139		

Second, EViews has created a (date) series DATEID containing the distinct values of the observation ID series. If necessary, this series will be used to structure the unstacked workfile.

Lastly, EViews has created a pool object named COUNTRY, corresponding to the specified unstack ID series, containing all of the unstacking identifiers. Since the unstacked series have names that were created using the specified name pattern, this pool object is perfectly set up for working with the unstacked data.

Stacking a Workfile

Stacking a workfile involves combining sets of series with related names into single series, or repeatedly stacking individual series into single series, and placing the results in a new workfile. The series in a given set to be stacked may be thought of as containing repeated measures data on a given variable. The individual series may be viewed as ordinary, non-repeated measures data.

The stacking operation depends crucially on the set of stacking identifiers. These identifiers are used to determine the sets of series, and the number of times to repeat the values of individual series.

In order for all of the series in a given set to be stacked, they must have names that contain a common component, or base name, and the names must differ systematically in containing an identifier. The identifiers can appear as a suffix, prefix, or even in the middle of the base name, but they must be used consistently across all series in each set.

Suppose, for example, we have a workfile containing the individual series Z, and the two groups of series: XUS, XUK and XJPN, and US_Y, UK_Y, and JPN_Y. Note that within each set of series, the identifiers "US," "UK," and "JPN" are used, and that they are used consistently within each set of series.

If we employ the set of three identifier values "US," "UK," and "JPN" to stack our workfile, EViews will stack the three series XUS, XUK, and XJPN on top of each other, and the series

US_Y, UK_Y, and JPN_Y on top of each other. Furthermore, the individual series Z will be stacked on top of itself three times so that there are three copies of the original data in the new series.

Stacking a Workfile in EViews

To stack the data in an existing workfile page, you should select Proc/Reshape Current Page/Stack in New Page... from the main work file menu. EViews will respond by opening the tabbed Workfile Stack dialog.

There are two key pieces of information that you must provide in order to create a stacked workfile: the set of stack ID values, and the series that you wish to stack. This information should be provided in the two large edit fields. The remaining dialog settings involve options that allow you to modify the method used to stack the series and the destination of the stacked series.


Stacking Identifiers

There are three distinct methods that you may use to specify your stack ID values:

First, you may enter a space separated list containing the individual ID values (e.g., “1 2 3”, or “US UK JPN”). This is the most straightforward method, but can be cumbersome if you have a large list of values.

Second, you may enter the name of an existing pool object that contains the identifier values.

Lastly, you may instruct EViews to extract the ID values from a set of series representing repeated measures on some variable. To use this method, you should enter a series name pattern containing the base name and the “?” character in place of the IDs. EViews will use this expression to identify a set of series, and will extract the ID values from the series names. For example, if you enter “SALES?”, EViews will identify all series in the workfile with names beginning with the string “SALES”, and will form a list of identifiers from the remainder of the observed series names. In our example, we have the series SALES1, SALES2, and SALES3 in the workfile, so that the list of IDs will be “1”, “2”, and “3”.



Series to be Stacked

Next, you should enter the list of series, alphas, and links that you wish to stack. Sets of series objects that are to be treated as repeated measures (stacked on top of each other) should be entered using “?” series name patterns, while individual series (those that should be repeatedly stacked on top of themselves), should be entered using simple names or wildcards.

You may specify the repeated measures series by listing individual stacked series with “?” patterns (“CONS? EARN?”), or you may use expressions containing the wildcard character “*” (“*?” and “?C*”) to specify multiple sets of series. For example, entering the expression “?C* ?E*” will tell EViews to find all repeated measures series that begin with the letters “C” or “E” (e.g., “CONS? CAP? EARN? EXPER?”), and then to stack (or interleave) the series using the list of stack ID values. If one of the series associated with a particular stack ID does not exist, the corresponding stacked values will be assigned the value NA.

Individual series may also be stacked. You may list the names of individual simple series (e.g., “POP INC”), or you can specify your series using expressions containing the wildcard character “*” (“*”, “*C”, “F*”). The individual series will repeatedly be stacked (or interleaved), once for each ID value. If the target workfile page is in the same workfile, EViews will create a link in the new page; otherwise, the stacked series will contain repeated copies of the original values.

It should be noted that the wildcard values for individual series are processed after the repeated measures series are evaluated, so that a given series will only be used once. If a series is used as part of a repeated measures series, it will not be used when matching wildcards in the list of individual series to be stacked.

The default value “*? *” is suitable for settings where the repeated series have names formed by taking the base name and appending the stack ID values. The default will stack all repeated measures series, and all remaining individual series (except for RESID). Entering “*” alone will copy or link all series, but does not identify any repeated measures series.

Naming Stacked Series

Stacked individual series will be named in the destination page using the name of the series in the original workfile; stacked repeated measures series will, by default, be named using the base name. For example, if you stack the repeated measures series “SALES?” and the individual series GENDER, the corresponding stacked series will, by default, be named “SALES” and “GENDER”, respectively.

This default rule will create naming problems when the base name of a repeated measures series is also the name of an individual series. Accordingly, EViews allows you to specify an alternative rule for naming your stacked repeated measures series in the Name for stacked series section of the dialog.

The default naming rule may be viewed as one in which we form names by replacing the “?” in the original specification with a blank space. To replace the “?” with a different string, you should enter the desired string in the edit field. For example, if you enter the string “_STK”, then EViews will name the stacked series “CONS?” and “EARN?” as “CONS_STK” and “EARN_STK” in the destination workfile.

Stacking Order

EViews will, by default, create series in the new page by stacking series on top of one another. If we have identifiers “1”, “2”, and “3”, and the series SALES1, SALES2, and SALES3, EViews will stack the entire series SALES1 followed by the entire series SALES2, followed by SALES3.

You may instruct EViews to interleave the data, by selecting the Interleaved radio button in the Order of Obs section of the dialog. If selected, EViews will stack the first observations for SALES1, SALES2, and SALES3, on top of the second observations, and so forth.

It is worth pointing out that stacking by series means that the observations contained in a given series will be kept together in the stacked form, while interleaving the data implies that the multiple values for a given original observation will be kept together. In some contexts, one form may be more natural than another.

In the case where we have time series data with different series representing different countries, stacking the data by series means that we have the complete time series for the “US” (USGDP), followed by the time series for the “UK” (UKGDP), and then “JPN” (JPNGDP). This representation is more natural for time series analysis than interleaving so that the observations for the first year are followed by the observations for the second year, and so forth.

Alternatively, where the series represent repeated measures for a given subject, stacking the data by series arranges the data so that all of the first measures are followed by all of the second measures, and so on. In this case, it may be more natural to interleave the data, so that all of the observations for the first individual are followed by all of the observations for the second individual, and so forth.

One interesting case where interleaving may be desirable is when we have data which has been split by period, within the year. For example, we may have four quarters of data for each year:

Year	XQ1	XQ2	XQ3	XQ4
2000	NA	5.6	8.7	9.6
2001	12.1	8.6	14.1	15.2

If we stack the series using the identifier list “Q1 Q2 Q3 Q4”, we get the data:

Year	ID01	X
2000	Q1	NA
2001	Q1	12.1
2000	Q2	5.6
2001	Q2	8.6
2000	Q3	8.7
2001	Q3	14.1
2000	Q4	9.6
2001	Q4	15.2

which is not ordered in the traditional time series format from earliest to latest. If instead, we stack by “Q1 Q2 Q3 Q4” but interleave, we obtain the standard format:

Year	ID01	X
2000	Q1	NA
2000	Q2	5.6
2000	Q3	8.7
2000	Q4	9.6
2001	Q1	12.1
2001	Q2	8.6
2001	Q3	14.1
2001	Q4	15.2

Note that since interleaving changes only the order of the observations in the workfile and not the structure, we can always sort or restructure the workfile at a later date to achieve the same effect.

Stacking Destination

By default, EViews will stack the data in a new page in the existing workfile named “UNTITLED” (or the next available name, “UNTITLED1,” “UNTITLED2,” etc., if there are existing pages in the workfile with the same name).

You may provide an alternative destination for the stacked data by clicking on the Page Destination tab in the dialog, and entering the desired destination.

Here, we instruct EViews to put the stacked series in the workfile named STACKWF in the named page ANNUAL-PANEL. If a page with that name already exists in the workfile, EViews will create a new page using the next available name.

We note that if you are stacking individual series, there is an important consequence of specifying a different workfile as the destination for your stacked series.

If the target page is in the same workfile as the original page, EViews will stack individual series by creating link objects in the new page. These link objects have the standard advantages of being memory efficient and dynamically updating. If, however, the target page is in a different workfile, it is not possible to use links, so the stacked series will contain repeated copies of the original individual series values.



An Example

Consider an annual (1971 to 2000) workfile, “Wfstack.WF1”, that contains the six series: CONSUS, CONSUM, CONSJPN, and GDPUS, GDPUK, GDPJPN, along with the ordinary series CONSTVAL and WORLDGDP.

We wish to stack series in a new page using the stack IDs: “US,” “UK,” and “JPN”.

Click on the Proc button and select Reshape Current Page/Stack in new Page...

We may specify the stacked series list explicitly by entering “US UK JPN” in the first edit box, or we can instruct EViews to extract the identifiers from series names by entering “GDP?”. Note that we cannot use “CONS?” in place of “GDP?” since the presence of the ordinary series CONSTVAL means that “CONS?” is associated with the wrong number of identifiers.




Assuming that we have entered “US UK JPN” or “GDP?” in the Stacking Identifiers edit box, we may then enter the expression

gdp? cons?

as our Series to stack. We leave the remainder of the dialog settings at their defaults, and click on OK.

EViews will first create a new page in the existing workfile and then will stack the GDPUS, GDPUK, and GDPJPN series and the CONSUS, CONSUM, and CONSJPN series. Since the dialog settings were retained at the default values, EViews will stack the data by series, with all of the values of GDPUS followed by the values of GDPUK and then the values GDPJPN, and will name the stacked series GDP and CONS.



Here we see the resulting workfile page ANNUAL_STK, containing the stacked series GDP and CONS, as well as two EViews created series objects, ID01 and ID02, that contain identifiers that may be used to structure the workfile.

ID01 is an alpha series that contains the stack ID values “US,” “UK,” and “JPN” which are used as group identifiers, and ID02 is a data series containing the year observation identifiers (more generally, ID02 will contain the values of the observation identifiers from the original page).

You may notice that EViews has already applied a panel structure to the page, so that there are three cross-sections of annual data from 1971 to 2000, for a total of 90 observations.

obs	ID01	ID02
US - 79	US	1/1/1979
US - 80	US	1/1/1980
US - 81	US	1/1/1981
US - 82	US	1/1/1982
US - 83	US	1/1/1983
US - 84	US	1/1/1984
US - 85	US	1/1/1985
US - 86	US	1/1/1986
US - 87	US	1/1/1987
US - 88	US	1/1/1988
US - 89	US	1/1/1989
US - 90	US	1/1/1990
US - 91	US	1/1/1991
US - 92	US	1/1/1992
US - 93	US	1/1/1993

Note that EViews will only apply a panel structure to the new page if we stack the data by series, but not if we interleave observations. Here, had we chosen to interleave, we would obtain a new 90 observation unstructured page containing the series GDP and CONS and the alpha ID01 and series ID02, with the observations for 1971 followed by observations for 1972, and so forth.

We may add our individual series to the stacked series list, either directly by entering their names, or using wildcard expressions. We may use either of the stack series expressions:

```
gdp? cons? worldgdp constval
```

or

```
gdp? cons? *
```


to stack the various “GDP?” and “CONS?” series on top of each other, and the individual series WORLDGDP and CONSTVAL will be linked to the new page so that the original series values are repeatedly stacked on top of themselves.

It is worth reminding you that the wildcard values for individual series are processed after the repeated measures series “GDP?” and “CONS?” are evaluated, so that a given series will only be used once. Thus, in the example above, the series CONSUS is used in forming the stacked CONS series, so that it is ignored when matching the individual series wildcard.

If we had instead entered the stacking list

```
gdp? *
```

EViews would stack the various “GDP?” series on top of each other, and would treat the remaining series as individual series so that the values of CONSUS, CONSUM, CONSJPN, CONSTVAL, and WORLDGDP are repeated in the stacked page. In this latter case, the wildcard implies that since the series CONSUS, CONSUM, and CONSJPN are not used in forming a stacked repeated measures series, they are used to create stacked individual series.



Lastly, we note that since EViews will, by default, create a new page in the existing workfile, all individual series will be stacked or interleaved by creating link objects. If, for example, you enter the stack series list

```
gdp? cons? worldgdp constval
```

the series WORLDGDP and CONSTVAL will be linked to the destination page using the ID02 values. Alternately, if we were to save the stacked data to a new workfile, by clicking on the Page Destination tab and entering appropriate values, EViews will copy the original WORLDGDP and CONSTVAL series to the new page, repeating the values of the original series in the stacked series.



Sorting a Workfile

Basic data in workfiles are held in objects called series. If you click on Proc/Sort Current Page ... in the workfile toolbar, you can sort all of the series in an unstructured workfile on the basis of the values of one or more of the series. A dialog box will open where you can provide the details about the sort.

If you list two or more series, EViews uses the values of the second series to resolve ties in the first series, and values of the third series to resolve ties in the first and second, and so forth. If you wish to sort in descending order, select the appropriate option in the dialog.

EViews will only sort unstructured workfiles since sorting a dated or structured workfile will break the link between an observation and the corresponding date identifier.

If you attempt to sort a dated or structured workfile, EViews will display a warning informing you that it will first unstructure your data, and then sort the data. Click on OK to continue with the operation.



Exporting from a Workfile

MicroTSP Files

You can read or write your workfile in a format that is compatible with MicroTSP. The Files of type and Save as type combo boxes in the Open and Save As dialogs allow you to handle DOS and Macintosh MicroTSP files. Simply click on the combo box and select either Old Dos Workfile or Old Mac Workfile, as appropriate. You should be aware, however, that if you choose to save a workfile in MicroTSP format, only basic series data will be saved—the remainder of the workfile contents will be discarded.

Foreign Formats

To save your series (and possibly value map data) into a foreign data source, first select File/Save As..., from the workfile menu to bring up the standard file Save dialog. Clicking on the Files of type combo box brings up a list of the output file types that EViews currently supports.

The data export interface is available for Microsoft Access, Aremos TSD, Gauss Dataset, GiveWin/Pc-Give, Rats 4.x, Rats Portable, SAS program files, SAS Transport, native SPSS (using the SPSS Input/output .DLL installed on your system), SPSS Portable, Stata, TSP Por-

table, Excel, raw ASCII or binary files, or ODBC Databases (using the ODBC driver already present on your system).

References

- Baltagi, Badi H. (2005). *Econometric Analysis of Panel Data*, Third Edition West Sussex, England: John Wiley & Sons.
- Gilley, O.W., and R. Kelley Pace (1996) "On the Harrison and Rubinfeld Data," *Journal of Environmental Economics and Management* 31, 403–405.
- Harrison, D. and D. L. Rubinfeld (1978). "Hedonic Housing Prices and the Demand for Clean Air," *Journal of Environmental Economics and Management* 5, 81-102.

Chapter 10. EViews Databases

An EViews database resembles a workfile in that it is used to contain a collection of EViews objects. It differs from a workfile in two major ways. First, unlike a workfile, the entire database need not be loaded into memory in order to access an object inside it; an object can be fetched or stored directly to or from the database on disk. Second, unlike a workfile page, the objects in a database are not restricted to being of a single frequency or range. A database could contain a collection of annual, monthly, and daily series, all with different numbers of observations.

EViews databases also differ from workfiles in that they support powerful query features which can be used to search through the database to find a particular series or a set of series with a common property. This makes databases ideal for managing large quantities of data.

While EViews has its own native storage format for databases, EViews also allows direct access to data stored in a variety of other formats through the same database interface. You can perform queries, copy objects to and from workfiles and other databases, and rename and delete objects within a database, all without worrying about in what format the data are actually stored.

Database Overview

An EViews database is a set of files containing a collection of EViews objects. In this chapter we describe how to:

- Create a new database or open an existing database.
- Work with objects in the database, including how to store and fetch objects into workfiles, and how to copy, rename and delete objects in the database.
- Use auto-series to work with data directly from the database without creating a copy of the data in the workfile.
- Use the database registry to create shortcuts for long database names and to set up a search path for series names not found in the workfile.
- Perform a query on the database to get a list of objects with particular properties.
- Use object aliases to work with objects whose names are illegal or awkward.
- Maintain a database with operations such as packing, copying, and repairing.
- Work with remote database links to access data from remote sites.

Database Basics

What is an EViews Database?

An EViews native format database consists of a set of files on disk. There is a main file with the extension .EDB which contains the actual object data, and a number of index files with extensions such as .E0, .E1A and .E1B which are used to speed up searching operations on the database. In normal use, EViews manages these files for the user, so there is no need to be aware of this structure. However, if you are copying, moving, renaming, or deleting an EViews database from outside of EViews (using Windows Explorer for example), you should perform the operation on both the main database file and all the index files associated with the database. If you accidentally delete or damage an index file, EViews can regenerate it for you from the main data file using the repair command (see [“Maintaining the Database” on page 293](#)).

The fact that EViews databases are kept on disk rather than in memory has some important consequences. Any changes made to a database cause immediate changes to be made to the disk files associated with the database. Therefore, unlike workfiles, once a change is made to a database, there is no possibility of discarding the change and going back to the previously saved version. Because of this, you should take care when modifying a database, and should consider keeping regular backup copies of databases which you modify frequently.


EViews also allows you to deal with a variety of foreign format databases through the same interface provided to EViews' native format databases. Foreign databases can have many different forms, including files on disk, or data made available through some sort of network server. See [“Foreign Format Databases” on page 295](#) for a discussion of the different types of foreign databases that EViews can access.

Creating a Database

To create a database, simply select **File/New/Database...** from the main menu.

For a native EViews database, simply enter a name for the database in the field labeled **DB File name/path**, then click on the button marked **OK**. This will create a new EViews database in the current path.

To create a database in a different directory, you can enter the full path and database name in the **DB File name/path** edit field. Alternatively, you can browse to the desired directory. Simply click on the **Browse Files** button to call up the common file dialog, and then navigate to the target directory. Enter the name of the new database in the **File name** edit field, then click on the **OK** button to accept the information



and close the file dialog. EViews will put the new path and filename in the DB File name/path edit field.

The Database/File Type field allows you to create different types of databases. See [Foreign Format Databases](#) on page 295 for a discussion of working with different database types.

The Open As field allows you to specify the shorthand that will be associated with this database. A shorthand is a short text label which is used to refer to the database in commands and programs. If you leave this field blank, a default shorthand will be assigned automatically (see [Database Shorthands](#) on page 27).

The Browse Registry and Add to Registry buttons provide a convenient way to recall information associated with a previously registered database or to include the new database in the database registry (see [The Database Registry](#) on page 28).

A database can also be created from the command line or in a program using the command:


```
dbcreate db_name
```

where db_name is the name of the database using the same rules given above.

The Database Window

When you create a new database, a database window will open on the screen.

The database window provides a graphical interface which allows you to query the database, copy-and-paste objects to and from your workfile, and perform basic maintenance on the database. Note that some database operations can also be carried out directly without first opening the database window.



To open a database window for an existing database, select File/Open/Database... from the main menu. The same dialog will appear as was used during database creation. To open an EViews database, use the Browse Files button to select a file using the common file dialog, then click on OK to open the file. A new window should appear representing the open database.


From the command line or in a program, you can open a database window by typing:

```
dbopen db_name
```

Unlike a workfile window, a database window does not display the contents of the database when it is first opened, although it does tell you how many objects are in the database. The second line of the window text shows the number of objects currently displayed (zero when the window is first opened) followed by the total number of objects stored in the database.

You can bring up an alphabetical listing of every object in the database by clicking on the All button:

As for a workfile, each object is preceded by a small icon that identifies the type of the object. When performing an All query, no other information about the object is visible. However, by double clicking on an object you can bring up a full description of the object including its name, type, modification date, frequency, start and end date (for series), and label.



For large databases, the All button generally displays too many objects and not enough information about each object. The database query features ([Querying the Database" on page 283](#)) allow you to control precisely which objects should be displayed, and what information about each object should be visible. The text form of the query currently being displayed is always visible in the top line of the database window.

When working with foreign data bases, the object names may appear in color to indicate that they are illegal names or that an alias has been attached to an object name (see [Object Aliases and Illegal Names" on page 293](#)).

The "Packable space" field in the database window displays the percentage of unused space in the database that can be recovered by a database pack operation (see [Packing the Database" on page 293](#)).

A brief technical note: having a database window open in EViews generally does not keep a file open at the operating system level. EViews will normally open files only when it is performing operations on those files. Consequently, multiple users may have a database open at the same time and can perform operations simultaneously. There are some limits imposed by the fact that one user cannot read from a database that another user is writing to at the same time. However, EViews will detect this situation and continue to retry the operation until the database becomes available. If the database does not become available within a specified time, EViews will generate an error stating that a "sharing violation" on the database has occurred.

For some foreign formats, even minor operations on a database may require full rewriting of the underlying file. In these cases, EViews will hold the file open as long as the database window is open in order to improve efficiency. The formats that currently behave this way

are Aremos TSD files, RATS Portable/TROLL files and TSP portable files. When using these formats, only one user at a time may have an open database window for the file.

Database Shorthands

In many situations, EViews allows you to prefix an object name with a database identifier to indicate where the series is located. These database identifiers are referred to as “short-hands”. For example, the command:

```
fetch db1::x db2::y
```

indicates to EViews that the object named X is located in the database with the shorthand db1 and the object named y is located in the database with the shorthand db2.

Whenever a database is opened or created, it's assigned a shorthand. The shorthand can be specified by the user in the Open as field when opening a database, or using the “As” clause in the dbopen command (see [dbopen](#) (p. 233) in the Command and Programming Reference). If a shorthand is explicitly specified when opening a database, an error will occur if the shorthand is already in use.

If no shorthand is provided by the user, a shorthand is assigned automatically. The default value will be the name of the database after any path or extension information has been removed. If this shorthand is already in use, either because a database is already open with the same name, or because an entry in the database registry already uses the name, then a numerical suffix is appended to the shorthand, counting upwards until an unused shorthand is found.

For example, if we open two databases with the same name in a program:

```
dbopen test.edb
dbopen test.dat
```

then the first database will receive the shorthand “TEST” and the second database will receive the shorthand “TEST1”. If we then issue the command:

```
fetch test::x
```

the object X will be fetched from the EViews database TEST.EDB. To fetch X from the Haver database TEST.DAT we would use:

```
fetch test1::x
```

To minimize confusion, you should assign explicit shorthands to databases whenever ambiguity could arise. For example, we could explicitly assign the shorthand TEST_HAVER to the second database by replacing the second dbopen command with:

```
dbopen test.dat as test_haver
```

The shorthand attached to a database remains in effect until the database is closed. The shorthand assigned to an open database is displayed in the title bar of the database window.

The Default Database

In order to simplify common operations, EViews uses the concept of a default database. The default database is used in several places, the most important of which is as the default source or destination for store or fetch operations when an alternative database is not explicitly specified.

The default database is set by opening a new database window, or by clicking on an already open database window if there are multiple databases open on the screen. The name of the default database is listed in the status line at the bottom of the main EViews window (see [Chapter 4. “Object Basics,” on page 67](#) for details). The concept is similar to that of the current workfile with one exception: when there are no currently open databases there is still a default database; when there are no currently open workfiles, the current workfile is listed as “none.”

EViews .DB? files

Early versions of EViews and MicroTSP supported a much more limited set of database operations. Objects could be stored on disk in individual files, with one object per file. Essentially, the disk directory system was used as a database and each database entry had its own file. These files had the extension “.DB” for series, and .DB followed by an additional character for other types of objects. EViews refers to these collectively as .DB? files.

While the new database features added to EViews provide a superior method of archiving and managing your data, .DB? files provide backward compatibility and a convenient method of distributing data to other programs. Series .DB files are now supported by a large number of programs including TSP, RATS, and SHAZAM. Additionally, some organizations such as the National Bureau of Economic Research (NBER), distribute data in .DB format.

Working with Objects in Databases

Since databases are simply containers of other EViews objects, most of your work with databases will involve moving objects into and out of them. The sections on storing, fetching and exporting objects discuss different ways of doing this.


You will also need to manage the objects inside a database. You can create duplicate copies of objects, change their names, or remove them from the database entirely. The sections on copying, renaming and deleting discuss how these operations can be carried out.

Storing Objects in the Database

An object may be stored in a database in a number of ways. If you have a workfile open on the screen and would like to store objects contained inside it into a database, just select the objects from the workfile window with the mouse, then click on the Store button in the workfile toolbar. A sequence of dialogs will come up, one for each object selected, which

provide a number of options for renaming the object and determining where the object should be stored.

By default, the object will be stored in the default database with the name used as the workfile. Click **Yes** to store the specified object. If you are storing more than one object, EViews will allow you to select **Yes-to-All** to store all of the objects using the current settings.



If you would like to store the object with a different name, simply type the new name over the old name in the Store object_name as edit box. If you would like to store the object in a different database, either enter the name of the new database in the text box marked Database Alias or Path (see [“The Database Registry” on page 281](#) for an explanation of database aliases), or click on the button marked **Browse** to select the database name interactively. To store the object to disk as an EViews .DB? file, click on the arrow to the right of the field labeled **Store in** and select **Individual .DB? files**. You may then specify a path in which to place the file using the field labeled **Path for DB files**.


If there is already an existing object in the database with the same name, EViews will display a dialog. The first and last of the three options should be self explanatory. The second option may only be used if the object you are storing from the workfile and the object already in the database are both series of the same frequency. In this case, EViews will merge the data from the two series so that the

new series in the database has all the observations from the series being stored, as well as any observations from the existing series which have not been overwritten. For example, if the existing series in the database is an annual series from 1950 to 1990, and the series being stored is an annual series from 1980 to 1995, the new series will run from 1950 to 1995, with data from the existing series for 1950 to 1979, and data from the new series for 1980 to 1995.

Fetching Objects from the Database


There are a number of ways to fetch objects from a database, most of which are similar to the methods for storing.

The first method is to click on the button marked **Fetch** on the toolbar of the workfile into which you would like to fetch the object. A dialog will come up which is similar to the dialog for store:



The dialog allows you to specify the names of the objects to fetch, and the database or directory from which to retrieve them.

Enter the names of the objects you would like to fetch in the field Objects to Fetch. Alternatively, you can use the mouse to select objects from the workfile window before clicking on the Fetch button, in which case the names of these objects will appear automatically.



The fields labeled Database Alias or Path and Fetch from are the same as for the store dialog with one exception. In addition to EViews Database and Individual .DB? files, Fetch from has an option titled Search Databases. This option tells EViews to search multiple databases for objects which match the specified names. To use this option, you must first define a search order in the database registry (see [“The Database Registry” on page 281](#)).

The checkbox labeled Link objects to database on the bottom of the dialog instructs EViews to bring any listed series or alpha objects into the workfile as links to the data in the database. When you open an existing workfile containing database links, EViews will prompt you for whether you wish to refresh the data series. If you click on No, EViews will retain the existing data in the link, otherwise the data will be reimported from the database when you load the workfile. You may also update existing links manually by selecting Object/Manage Links & Formulae... in the workfile window, specifying the links to update, and clicking on the Refresh Links - update data from source button.

When you click on OK, EViews will fetch all the objects. If an object which is being fetched is already contained in the workfile, a dialog will appear asking whether to replace the object or not. Click on Yes to replace the object in the workfile or No to leave the object in the workfile unchanged.

Because a workfile has a fixed frequency and range, fetching a series into a workfile may cause the data in the series to be modified to match the frequency and range of the workfile (see [“Frequency Conversion” on page 110](#)). Be aware that loading a series into a workfile then saving it back into the database can cause truncation and frequency conversion of the series stored in the database.


Object/Update selected from DB... from the workfile toolbar is the same as Fetch except that there is no overwrite warning message. If the object in the database is the same type as the one in the workfile, it is automatically overwritten. If it is of a different type, the fetch

does not proceed. Update is also available from the Object button in individual object windows.

Database Export

You can also move data into a workfile from the database window. From an open database window, select the objects you would like to copy using the mouse, then click on the button marked Export in the toolbar at the top of the database window. The Database Export dialog will appear on the screen:

When you click on the down arrow on the right of the field labeled Workfile, a list of all workfiles that are currently open will appear from which you may choose the workfile into which you would like to copy the objects. In addition, you may use the Page drop down menu to select an existing page in the selected workfile, or to create a new page. Clicking on the button marked OK will copy the selected objects to specified page of the selected workfile.



There is an extra option in the list of open workfiles for specifying a new workfile as your copy destination. If you select New Workfile, EViews will create a new workfile containing the objects you have selected. After you click on OK, a second dialog will appear in which you can set the frequency and range of the workfile to be created. The default frequency is set to the lowest frequency of any of the objects selected, and the default range is set to cover all the data points contained in the objects. Clicking on OK will open a new workfile window and copy the selected objects into it, performing frequency conversion where necessary.

Lastly, you may export your series or alpha objects to the workfile as database links. When you reopen your workfile containing database links, EViews will prompt you for whether you wish to refresh the data series from the database.

Copying Objects

In addition to the above methods for moving objects, EViews provides general support for the copying of objects between any two EViews container objects (workfiles or databases). You may use these features to move objects between two databases or between two workfiles, to create duplicate copies of objects within a workfile or database, or as an alternative method for store and fetch.

Copy-and-Paste

For copying objects between containers, the procedure is very similar no matter what types of container objects are involved. Before you start, make sure that the windows for both

containers are open on the screen. In the container from which you would like to copy the objects, select the objects then click on **Edit/Copy** in the EViews program menu. Click on the container object into which you would like to paste the objects, then select **Edit/Paste** or **Edit/Paste Special...** from the EViews program menu.

Depending on the types of the two containers, you may be presented with one or more dialogs. If, for example, you are performing a copy to or from a database, and click on **Edit/Paste**, the standard **Store** or **Fetch** dialogs will appear as if you had carried out the operations using the toolbar buttons on the workfile window. If you click on **Edit/Paste Special...**, an alternate dialog will be displayed, allowing you to override the default frequency conversion methods.


If, instead, you are copying between two workfiles, selecting **Edit/Paste** will simply copy the series using the default frequency conversion if necessary. You will only be prompted with a dialog if there is a name collision. Selecting **Edit/Paste Special...** will display a dialog allowing you to override the default conversion methods.

Drag-and-Drop

An alternative to copy-and-paste is to use drag-and-drop to copy files between containers. If you use the right-mouse button to select the series, dropping them on the new tab is equivalent to copying and then selecting **Edit/Paste Special...**

Copy Procedure

You may perform similar operations using the object copy procedure. From the main menu select **Object/Copy** (this may appear as **Object/Copy selected...**). The **Object Copy** dialog will be displayed.



The **Source** field specifies the object or objects you would like to copy, the **Destination** field specifies where you would like to copy them and what names they should be given.

The **Source** field should be filled in with an expression of the form:

`source_db::source_pattern`

where `source_db::` is optional, and indicates which database the objects should be copied from (if no database name is supplied, the source is taken to be the default workfile), and `source_pattern` is either a simple object name or a name pattern. A name pattern may include the wildcard characters “?” which matches any single character, and “*” which matches zero or more characters.

The **Destination** field should be filled in with an expression of the form:

```
dest_db::dest_name
```

where `dest_db::` is again optional, and indicates which database the objects should be copied to (if no database name is supplied, the destination is taken to be the default workfile), and `dest_name`, which is also optional, is the name to be given to the new copy of the object. If no name is given, the object will be copied with its existing name. If a pattern was used when specifying the source, a pattern must also be used when specifying the destination (see [“Source and Destination Patterns” on page 560](#) of the Command and Programming Reference).

For example, to copy an object from the database DB1 to the database DB2, keeping the existing name, you would fill in the dialog:

```
source:      db1::object_name
destination: db2::
```

where `OBJECT_NAME` is the original name as displayed by EViews.

To copy all the objects in the database DB1 beginning with the letter X into the current workfile, changing the names so that they begin with Y, you would fill in the dialog

```
source:      db1::x*
destination: y*
```

To make a duplicate copy of the object named ABC in the database DB1, giving it the new name XYZ, you would fill in the dialog:

```
source:      db1::abc
destination: db1::xyz
```

Renaming Objects in the Database

You may rename an object in the database by selecting the object in an open database window, then clicking on the button marked **Rename** in the database window toolbar. A dialog will come up in which you can modify the existing name or type in a new name. You can rename several objects at the same time using wildcard patterns and the **rename** command. See [\(p. 236\)](#) in the Command and Programming Reference for details.

Deleting Objects From the Database

To delete objects from the database, select the objects in an open database window, then click on the button marked **Delete** on the database window toolbar. You may delete several objects at the same time using wildcard patterns. There is also a **delete** command. See [delete](#) (p. 236) in the Command and Programming Reference for details.

Store, Fetch, and Copy of Group Objects


A group object in EViews is essentially a list of series names that form the group. The data of each series are contained in the series object, not in the group object. When you do a

store, fetch, or copy operation on a group object, an issue arises as to whether you want to do the operation on each of the series or to the group definition list.

Storing a Group Object

When you store a group object to a database, there are four available options:

- Store the group definition and the series as separate objects: stores the group object (only its definition information) and each of its series as separate objects in the database. If any of the series already exist in the database, EViews will ask whether or not to overwrite the existing series if in interactive mode, and will error if in batch mode.
- Store the group definition and the series as one object: stores each series within the group object. A group object that contains series data will have an icon G+ in the database directory window. A group object with only its definition information will have the usual icon G. If you use this option, you can store two different series with the same name (with one of the series as member of a group).
- Store only the series (as separate objects): only stores each series as separate objects in the database. If you want to store a long list of series into a database, you can create a temporary group object that contains those series and issue the store command only once.
- Store only the group definition: stores only the group definition information; none of the series data are stored in the database. This option is useful if you want to update the member data from the database but want to keep the group information (e.g. the dated data table settings) in the group.



By default, EViews will display a dialog asking you to select a group store option every time you store a group object. You can, however, instruct EViews to suppress the dialog and use the global option setting. Simply click on Options/Database Storage Defaults... in the main EViews menu to bring up a dialog that allows you both to set the global storage options, and to suppress the group store option dialog.

Fetching a Group Object

When you fetch a group object to a database, there are three options available:

- Fetch both group definition and the actual series: fetches both group definition and its series as separate objects. If any of the series defined in the group is not found in the database, the corresponding series will be created in the workfile filled with NAs. If any of the series already exist in the workfile, EViews will ask whether or not to overwrite the existing series if in interactive mode, and will error if in batch mode.



- Fetch only the series in the group: only fetches each series defined in the group. If the series exists both within the group object (with a G+ icon) and as a separate series object in the database, the series within the group object will be fetched.
- Fetch only the group definition: fetches only the group definition (but not the series data). If any of the series defined in the group does not exist in the workfile, EViews will create the corresponding series filled with NAs.

You can click on Options/Database Default Storage Options... in the main menu to bring up a dialog that allows you both to set the global fetch options, and to suppress the fetch option dialog.

Copying Group Objects between Workfiles and Databases

You can also copy groups between different containers. The options that are available will differ depending on the type of source and destination container:

- Copy from workfile to database: same options as the store operation.
- Copy from database to workfile: same options as the fetch operation.
- Copy from workfile to workfile: both the group definition and series will be copied.
- Copy from database to database. If the group object contains only the group definition (with a G icon), only the group definition will be copied. If the group object also contains its series data (with a G+ icon), then the group will be copied containing the series data and the copied group will also appear with a G+ icon.

Database Auto-Series

We have described how to fetch series into a workfile. There is an alternative way of working with databases which allows you to make direct use of the series contained in a database without first copying the series. The advantage of this approach is that you need not go through the process of importing the data every time the database is revised. This approach follows the model of auto-series in EViews as described in [“Auto-series,” beginning on page 145](#)

There are many places in EViews where you can use a series expression, such as `log(X)`, instead of a simple series name, and EViews will automatically create a temporary auto-series for use in the procedure. This functionality has been extended so that you can now directly refer to a series in a database using the syntax:

```
db_name::object_name
```

where `db_name` is the shorthand associated with the database. If you omit the database name and simply prefix the object name with a double colon like this:

```
::object_name
```

EViews will look for the object in the default database.

A simple example is to generate a new series:

```
series lgdp = log(macro_db::gdp)
```

EViews will fetch the series named GDP from the database with the shorthand `MACRO_DB`, and put the log of GDP in a new series named LGDP in the workfile. It then deletes the series GDP from memory, unless it is in use by another object. Note that the generated series LGDP only contains data for observations within the current workfile sample.

You can also use auto-series in a regression. For example:

```
equation eq1.ls log(db1::y) c log(db2::x)
```

This will fetch the series named Y and X from the databases named DB1 and DB2, perform any necessary frequency conversions and end point truncation so that they are suitable for use in the current workfile, take the log of each of the series, then run the requested regression. Y and X are then deleted from memory unless they are otherwise in use.

The auto-series feature can be further extended to include automatic searching of databases according to rules set in the database registry (see [“The Database Registry” on page 281](#)). Using the database registry you can specify a list of databases to search whenever a series you request cannot be found in the workfile. With this feature enabled, the series command:

```
series lgdp = log(gdp)
```

looks in the workfile for a series named GDP. If it is not found, EViews will search through the list of databases one by one until a series called GDP is found. When found, the series will be fetched into EViews so that the expression can be evaluated. Similarly, the regression:

```
equation logyeq.ls log(y) c log(x)
```

will fetch Y and X from the list of databases in the registry if they are not found in the workfile. Note that the regression output will label all variables with the database name from which they were imported.

In general, using auto-series directly from the database has the advantage that the data will be completely up to date. If the series in the database are revised, you do not need to repeat the step of importing the data into the workfile. You can simply reestimate the equation or model, and EViews will automatically retrieve new copies of any data which are required.

There is one complication to this discussion which results from the rules which regulate the updating and deletion of auto-series in general. If there is an existing copy of an auto-series already in use in EViews, a second use of the same expression will not cause the expression to be reevaluated (in this case reloaded from the database); it will simply make use of the existing copy. If the data in the database have changed since the last time the auto-series was loaded, the new expression will use the old data.

One implication of this behavior is that a copy of a series from a database can persist for any length of time if it is stored as a member in a group. For example, if you type:

```
show db1::y db2::x
```

this will create an untitled group in the workfile containing the expressions `db1::y` and `db2::x`. If the group window is left open and the data in the database are modified (for example by a `store` or a `copy` command), the group and its window will not update automatically. Furthermore, if the regression:

```
equation logyeq.ls log(db1::y) c log(db2::x)
```

is run again, this will use the copies of the series contained in the untitled group; it will not refetch the series from the database.


The Database Registry

The database registry is a file on disk that manages a variety of options which control database operations. It gives you the ability to assign short alias names that can be used in place of complete database paths, and also allows you to configure the automatic searching features of EViews.

Selecting Options/Data-base Registry... from the main menu brings up the Database Registry dialog allowing you to view and edit the database registry:

The box labeled Registry Entries lists the databases that have been registered with EViews. The first time you bring up the dialog, the box will usually be empty.

If you click on the Add new entry button, a Database Registry Entry dialog appears.



There are three things you must specify in the dialog: the full name (including path) of the database, the alias which you would like to associate with the database, and the option for whether you wish to include the database in automatic searches.


The full name and path of the database should be entered in the top edit field. Alternatively, click the Browse button to select your database interactively.

The next piece of information you must provide is a database alias, a short name that you can use in place of the full database path in EViews commands. The database alias will also be used by EViews to label database auto-series. For example, suppose you have a database named DRIBASIC located in the subdirectory C:\EViews\DATA. The following regression command is legal but awkward:

```
equation eq1.ls c:\views\data\dribasic::gdp c
c:\views\data\dribasic::gdp(-1)
```

Long database names such as these also cause output labels to truncate, making it difficult to see which series were used in a procedure.

By assigning full database path and name the alias DRI, we may employ the more readable command:



equation eq1.ls dri::gdp c dri::gdp(-1)

and the regression output will be labeled with the shorter names. To minimize the possibility of truncation, we recommend the use of short alias names if you intend to make use of database auto-series.

Finally, you should tell EViews if you want to include the database in automatic database searches by checking the `Include in auto search` checkbox. Click on OK to add your entry to the list

Any registry entry may be edited, deleted, switched on or off for searching, or moved to the top of the search order by highlighting the entry in the list and clicking the appropriate button to the right of the list box.

The remainder of the Database Registry dialog allows you to set options for automatic database searching. The `Auto-search` checkbox is used to control EViews behavior when you enter a command involving a series name which cannot be found in the current workfile. If this checkbox is selected, EViews will automatically search all databases that are registered for searching, before returning an error. If a series with the unrecognized name is found in any of the databases, EViews will create a database auto-series and continue with the procedure.

The last section of the dialog, `Default Database in Search Order`, lets you specify how the default database is treated in automatic database searches. Normally, when performing an automatic search, EViews will search through the databases contained in the `Registry Entries` window in the order that they are listed (provided that the `Include in auto search` box for that entry has been checked). These options allow you to assign a special role to the default database when performing a search.

- `Include at start of search order`— means that the current default database will be searched first, before searching the listed databases.
- `Include at end of search order`— means that the current default database will be searched last, after searching the listed databases.
- `Do not include in search`— means that the current default database will not be searched unless it is already one of the listed databases.

Querying the Database

A great deal of the power of the database comes from its extensive query capabilities. These capabilities make it easy to locate a particular object, and to perform operations on a set of objects which share similar properties.


The query capabilities of the database can only be used interactively from the database window. There are two ways of performing a query on the database: the easy mode and the

advanced mode. Both methods are really just different ways of building up a text query to the database. The easy mode provides a simpler interface for performing the most common types of queries. The advanced mode offers more flexibility at the cost of increased complexity.

Easy Queries

To perform an easy query, first open the database, then click on the EasyQuery button in the toolbar at the top of the database window. The Easy Query dialog will appear containing two text fields and a number of check boxes:

There are two main sections to this dialog: Select and Where. The Select section determines which fields to display for each object that meets the query condition. The Where section allows you to specify conditions that must be met for an object to be returned from the query. An Easy Query allows you to set conditions on the object name, object description, and/or object type.



The two edit fields (name and description) and the set of check boxes (objecttype) in the Where section provide three filters of objects that are returned from the query to the database. The filters are applied in sequence (using a logical 'and' operation) so that objects in the database must meet all of the criteria selected in order to appear in the results window of the query.

The name and description fields are each used to specify a pattern expression that the object must meet in order to satisfy the query. The simplest possible pattern expression consists of a single pattern. A pattern can either be a simple word consisting of alphanumeric characters, or a pattern made up of a combination of alphanumeric characters and the wildcard symbols "?" and "*", where "?" means to match any one character and "*" means to match zero or more characters. For example:

pr?d*ction

would successfully match the words production, prediction, and predilection. Frequently used patterns include "s*" for words beginning in "S," "*s" for words ending in "S," and "*s*" for words containing "S." Upper or lower case is not significant when searching for matches.

Matching is done on a word-by-word basis, where at least one word in the text must match the pattern for it to match overall. Since object names in a database consist of only a single word, pattern matching for names consists of simply matching this word.

For descriptions, words are constructed as follows: each word consists of a set of consecutive alphanumeric characters, underlines, dollar signs, or apostrophes. However, the following list words are explicitly ignored: "a," "an," "and," "any," "are," "as," "be," "between," "by," "for," "from," "if," "in," "is," "it," "not," "must," "of," "on," "or," "should," "that," "the," "then," "this," "to," "with," "when," "where," "while." (This is done for reasons of efficiency, and to minimize false matches to patterns from uninteresting words.) The three words "and," "or," and "not" are used for logical expressions.

For example:

bal. of p'ment: seas.adj. by X11

is broken into the following words: "bal," "p'ment," "seas," "adj," and "x11." The words "of" and "by" are ignored.

A pattern expression can also consist of one or more patterns joined together with the logical operators "and," "or," and "not" in a manner similar to that used in evaluating logical expressions in EViews. That is, the keyword `and` requires that both the surrounding conditions be met, the keyword `or` requires that either of the surrounding conditions be met, and the keyword `not` requires that the condition to the right of the operator is not met. For example:

`s* and not *s`

matches all objects which contain words which begin with, but do not end with, the letter "S".

More than one operator can be used in an expression, in which case parentheses can be added to determine precedence (the order in which the operators are evaluated). Operators inside parentheses are always evaluated logically prior to operators outside parentheses. Nesting of parentheses is allowed. If there are no parentheses, the precedence of the operators is determined by the following rules: `not` is always applied first; `and` is applied second; and `or` is applied last. For example:

`p* or s* and not *s`

matches all objects which contain words beginning with P, or all objects which contain words which begin with, but do not end with, the letter S.

The third filter provided in the Easy Query dialog is the ability to filter by object type. Simply select the object types which you would like displayed, using the set of check boxes near the bottom of the dialog.

Advanced Queries

Advanced queries allow considerably more control over both the filtering and the results which are displayed from a query. Because of this flexibility, advanced queries require some understanding of the structure of an EViews database to be used effectively.

Each object in an EViews database is described by a set of fields. Each field is identified by a name. The current list of fields includes:

name	The name of the object.
type	The type of the object.
last_write	The time this object was last written to the database.
last_update	The time this object was last modified by EViews.
freq	The frequency of the data contained in the object.
start	The date of the first observation contained in the object.
end	The date of the last observation contained in the object.
obs	The number of data points stored in the series (including missing values).
description	A brief description of the object.
source	The source of the object.
units	The units of the object.
remarks	Additional remarks associated with the object.
history	Recent modifications of the object by EViews.
display_name	The EViews display name.

An advanced query allows you to examine the contents of any of these fields, and to select objects from the database by placing conditions on these fields. An advanced query can be performed by opening the database window, then clicking on the button marked Query in the toolbar at the top of the window. The Advanced Query dialog is displayed.

The first edit field labeled Select: is used to specify a list of all the fields that you would like displayed in the query results. Input into this text box consists of a series of field names separated by commas. Note that the name and type fields are always fetched automatically.

The ordering of display of the results of a query is determined by the Order By edit field. Any field name can be entered into this box, though some fields are likely to be more useful than others. The description field, for example, does not provide a useful ordering of the objects.

The Order By field can be useful for grouping together objects with the same value of a particular field. For example, ordering by type is an effective way to group together the results so that objects of the same type are placed



together in the database window. The Ascending and Descending buttons can be used to reverse the ordering of the objects. For example, to see objects listed from those most recently written in the database to those least recently written, one could simply sort by the field `last_write` in Descending order.

The Where edit field is the most complicated part of the query. Input consists of a logical expression built up from conditions on the fields of the database. The simplest expression is an operator applied to a single field of the database. For example, to search for all series which are of monthly or higher frequencies (where higher frequency means containing more observations per time interval), the appropriate expression is:

```
freq >= monthly
```

Field expressions can also be combined with the logical operators `and`, `or` and `not` with precedence following the same rules as those described above in the section on easy queries. For example, to query for all series of monthly or higher frequencies which begin before 1950, we could enter the expression:

```
freq >= monthly and start < 1950
```

Each field has its own rules as to the operators and constants which can be used with the field.

Name

The name field supports the operators `"<"`, `"<="`, `">"`, `">="`, `"="`, and `"<>"` to perform typical comparisons on the name string using alphabetical ordering. For example,

```
name >= c and name < m
```

will match all objects with names beginning with letters from C to L. The name field also supports the operator `"matches"`. This is the operator which is used for filtering the name field in the easy query and is documented extensively in the previous section. Note that if `matches` is used with an expression involving more than one word, the expression must be contained in quotation marks. For example,

```
name matches "x* or y*" and freq = quarterly
```

is a valid query, while

```
name matches x* or y* and freq = quarterly
```

is a syntax error because the part of the expression that is related to the `matches` operator is ambiguous.

Type

The type field can be compared to the standard EViews object types using the `"="` operator and the keywords: `alpha`, `coef`, `equation`, `factor`, `graph`, `group`, `logl`, `matrix`, `model`, `pool`, `sample`, `scalar`, `series`, `spool`, `sspace`, `string`, `svector`, `sym`, `system`,

table , text , var , vector . Relational operators are defined for the type field, although there is no particular logic to the ordering. The ordering can be used, however, to group together objects of similar types in the Order By field.

Freq

The frequency field has one of the following values:

u	Undated
2y, 3y, 4y, 5y, 6y, 7y, 8y, 9y, 10y, 20y	Multi-year in intervals of: 2, 3, 4, 5, 6, 7, 8, 9, 10, or 20 years, respectively.
a	Annual
s	Semiannual
q	Quarterly
m	Monthly
bm	Bimonthly
f	Fortnight
t	Ten-day (daily in intervals of ten)
w	Weekly
5	5 day daily, Monday through Friday
7	7 day daily
h	Hourly
min	Minute
sec	Second

Any word beginning with the letter above is taken to denote that particular frequency, so that monthly can either be written as “m” or “monthly”. Ordering over frequencies is defined so that a frequency with more observations per time interval is considered “greater” than a series with fewer observations per time interval. The operators “<”, “>”, “<=”, “>=”, “=”, “<>” are all defined according to these rules. For example,

freq <= quarterly

will match objects whose frequencies are quarterly, semiannual, annual or undated.

Start and End

Start and end dates use the following representation. A date from an annual series is written as an unadorned year number such as “1980”. A date from a semiannual series is written as a year number followed by an “S” followed by the six month period, for example “1980S2”. The same pattern is followed for quarterly and monthly data using the letters “Q” and “M”

between the year and period number. Weekly, 5-day daily, and 7-day daily data are denoted by a date in the format:

`mm/dd/yyyy`

where `m` denotes a month digit, `d` denotes a day digit, and `y` denotes a year digit.

Operators on dates are defined in accordance with calendar ordering where an earlier date is less than a later date. Where a number of days are contained in a period, such as for monthly or quarterly data, an observation is ordered according to the first day of the period.

For example:

`start <= 1950`

will include dates whose attributed day is the first of January 1950, but will not include dates which are associated with other days in 1950, such as the second, third, or fourth quarter of 1950. However, the expression:

`start < 1951`

would include all intermediate quarters of 1950.

Last_write and Last_update

As stated above, `last_write` refers to the time the object was written to disk, while `last_update` refers to the time the object was last modified inside EViews. For example, if a new series was generated in a workfile, then stored in a database at some later time, `last_write` would contain the time that the store command was executed, while `last_update` would contain the time the new series was generated. Both of these fields contain date and time information which is displayed in the format:

`mm/dd/yyyy hh:mm`

where `m` represents a month digit, `d` represents a day digit, `y` represents a year digit, `h` represents an hour digit and `m` represents a minute digit.

The comparison operators are defined on the time fields so that earlier dates and times are considered less than later dates and times. A typical comparison has the form:

`last_write >= mm/dd/yyyy`

A day constant always refers to twelve o'clock midnight at the beginning of that day. There is no way to specify a particular time during the day.

Description, Source, Units, Remarks, History, Display_name


These fields contain the label information associated with each object (which can be edited using the Label view of the object in the workfile). Only one operator is available on these fields, the `matches` operator, which behaves exactly the same as the description field in the section on easy queries.

Query Examples


Suppose you are looking for data related to gasoline consumption and gasoline prices in the database named DRIBASIC. First open the database: click **File/Open**, select **Files of type: Database.edb** and locate the database. From the database window, click **Query** and fill in the **Advanced Query** dialog as follows:

- Select: name, type, freq, description
- Where: description matches gasoline

If there are any matches, the results are displayed in the database window similar to the following:



To view the contents of all fields of an item, double click on its name. EViews will open an **Object Description** window that looks as follows:



To further restrict your search to series with at least quarterly frequency and to display the start and end dates of the results, click **Query** and again and modify the fields as follows:

- Select name, type, start, end, description
- Where: description matches gasoline and freq>=q

If you are interested in seasonally adjusted series, which happen to contain sa or saar in their description in this database, further modify the fields to

Select name, type, start, end, description

Where: description matches "gasoline and (sa or saar)" and freq>=q

The display of the query results now looks as follows:

EViews Database: DRI - (c:\reviews\data\dribasic.edb)

View Proc Object All EasyQuery Query Rename Delete Export

Select name, type, start, end, description Where description matches "gasoline and (sa or saar)" a

Displayed: 6 of 6029 Packable space: 0%

☒	gmcng	1959M1	2000M11	PERS CONSUM EXPEND: GASOLINE & OIL, (BI
☒	gmcngq	1959M1	2000M11	PERSONAL CONS EXPEND (CHAINED) - GASO
☒	pr471	1967M1	2000M11	CPI-W: GASOLINE (82-84=100, SA)
☒	pu471	1967M1	2000M11	CPI-U: GASOLINE (82-84=100, SA)
☒	pwgasa	1973M1	2000M11	PRODUCER PRICE INDEX: GASOLINE (82=100
☒	rt554r	1967M1	2000M11	RETAIL SALES: GASOLINE SERVICE STATIONS


Object Aliases and Illegal Names

When working with a database, EViews allows you to create a list of aliases for each object in the database so that you may refer to each object by a different name. The most important use of this is when working with a data base in a foreign format where some of the names used in the database are not legal EViews object names. However, the aliasing features of EViews can also be used in other contexts, such as to assign a shorter name to a series with an inconveniently long name.

The basic idea is as follows: each database can have one or more object aliases associated with it where each alias entry consists of the name of the object in the database and the name by which you would like it to be known in EViews.

The easiest way to create an object alias for an illegal name is to attempt to fetch the object with the illegal name into EViews. If you are working with query results, you can tell which object names are illegal because they will be displayed in the database window in red. When you try to fetch an object with an illegal name, a dialog will appear.


The field labeled EViews Name initially contains the illegal name of the database object. You should edit this to form a legal EViews object name. In this example, we could change the name C to CONSUMP. The checkbox labeled Add this name to the database alias list (which is not checked by default), determines whether you want to create a permanent association between the name you have just typed and the illegal name. If you check the box, then whenever you use the edited object name in the future, EViews will take it to refer to the underlying illegal name. The edited name acts as an alias for the underlying name. It is as though you had renamed the object in the database to the new legal name, except that you have not actually modified the database itself, and your changes will not affect other users of the database.



When EViews displays an object in the database window for which an alias has been set, EViews will show the alias, rather than the underlying name of the object. In order to indicate that this substitution has been done, EViews displays the name of the aliased object in blue.

Creating an alias can cause shadowing of object names. Shadowing occurs when you create an alias for an object in the database, but the name you use as an alias is the name of another object in the database. Because the existence of the alias will stop you from accessing the other object, that object is said to be shadowed. To indicate that an object name being displayed has been shadowed, EViews displays the name of shadowed objects in green. You will not be able to fetch an object which has been shadowed without modifying either its name or the alias which is causing it to be shadowed. Even if the shadowed series is explicitly selected with the mouse, operations performed on the series will use the series with the conflicting alias, not the shadowed series.

You can view a list of the aliases currently defined for any database by clicking on the View button at the top of the database window, then selecting Object Aliases. A list of all the aliases will be displayed in the window.



Each line represents one alias attached to the database and follows the format:

alias = database_object_name

You can edit the list of aliases to delete unwanted entries, or you can type in, or cut-and-paste, new entries into the file. You must follow the rule that both the set of aliases and the set of database names do not contain any repeated entries. (If you do not follow this rule, EViews will refuse to save your changes). To save any modifications you have made, simply switch back to the Object Display view of the database. EViews will prompt you for whether you want to save or discard your edits.

The list of currently defined database aliases for all databases is kept in the file OBALIAS.INI in the EViews installation directory. If you would like to replicate a particular set of aliases onto a different machine, you should copy this file to the other machine, or use a text editor to combine a portion of this file with the file already in use on the other machine. You must exit and restart EViews to be sure that EViews will reread the aliases from the file.

Maintaining the Database

In many cases an EViews database should function adequately without any explicit maintenance. Where maintenance is necessary, EViews provides a number of procedures to help you perform common tasks.

Database File Operations

Because EViews databases are spread across multiple files, all of which have the same name but different extensions, simple file operations like copy, rename and delete require multiple actions if performed outside of EViews. The Proc button in the database window toolbar contains the procedures Copy the database, Rename the database, and Delete the database that carry out the chosen operation on all of the files that make up the database.

Note that file operations do not automatically update the database registry. If you delete or rename a database that is registered, you should either create a new database with the same name and location, or edit the registry.

Packing the Database

If many objects are deleted from an EViews database without new objects being inserted, a large amount of unused space will be left in the database. In addition, if objects are frequently overwritten in the database, there will be a tendency for the database to grow gradually in size. The extent of growth will depend on the circumstances, but a typical database is likely to stabilize at a size around 60% larger than what it would be if it were written in a single pass.

A database can be compacted down to its minimum size by using the pack procedure. Simply click on the button marked Proc in the toolbar at the top of the database window, then select the menu item Pack the Database. Depending on the size of the database and the

speed of the computer which you are using, performing this operation may take a significant amount of time.

You can get some idea of the amount of space that will be reclaimed during a pack by looking at the Packable Space percentage displayed in the top right corner of the database window. A figure of 30%, for example, indicates that roughly a third of the database file consists of unused space. A more precise figure can be obtained from the Database Statistics view of a database. The number following the label “unused space” gives the number of unused bytes contained in the main database file.

Dealing with Errors

EViews databases are quite robust, so you should not experience problems working with them on a regular basis. However, as with all computer files, hardware or operating system problems may produce conditions under which your database is damaged.

The best way to protect against damage to a database is to make regular backup copies of the database. This can be performed easily using the Copy the Database procedure documented above. EViews provides a number of other features to help you deal with damaged databases.

Damaged databases can be divided into two basic categories depending on how severely the database has been damaged. A database which can still be opened in a database window but generates an error when performing some operations may not be severely damaged and may be repairable. A database which can no longer be opened in a database window is severely damaged and will need to be rebuilt as a new database.

EViews has two procedures designed for working with databases which can be opened: Test Database Integrity and Repair Database. Both procedures are accessed by clicking on the button marked Proc in the database window toolbar, then selecting the appropriate menu item.

Test Database Integrity conducts a series of validity checks on the main database and index files. If an error is detected, a message box will be displayed, providing some information as to the type of error found and a suggestion as to how it might be dealt with. Because testing performs a large number of consistency checks on the database files, it may take considerable time to complete. You can monitor its progress by watching the messages displayed in the status line at the bottom of the EViews window. Testing a database does not modify the database in any way, and will never create additional damage to a database.

Repair Database will attempt to automatically detect and correct simple problems in the database. Although care has been taken to make this command as safe as possible, it will attempt to modify a damaged database, so it is probably best to make a backup copy of a damaged database before running this procedure.

Rebuilding the Database

If the database is badly corrupted, it may not be possible for it to be repaired. In this case, EViews gives you the option of building a new database from the old one using the `dbrebuild` command. This operation can only be performed from the command line (since it may be impossible to open the database). The command is:

```
dbrebuild old_dbname new_dbname
```

The `dbrebuild` command does a low level scan through the main data file of the database `old_dbname` looking for any objects which can be recovered. Any such objects are copied into the new database `new_dbname`. This is a very time consuming process, but it will recover as much data as possible from even heavily damaged files.

Foreign Format Databases

While most of your work with databases will probably involve using EViews native format databases, EViews also gives you the ability to access data stored in a variety of other formats using the same database interface. You can perform queries, copy objects to and from workfiles and other databases, rename and delete objects within the database, add databases to your search path, and use EViews' name aliasing features, all without worrying about how the data are stored.

When copying objects, EViews preserves not only the data itself, but as much as possible of any date information and documentation associated with the object. Missing values are translated automatically.

To Convert Or Not To Convert?

Although EViews allows you to work with foreign files in their native format, in some cases you may be better off translating the entire foreign file into EViews format. If necessary, you can then translate the entire file back again when your work is complete. EViews native databases have been designed to support a certain set of operations efficiently, and while access to foreign formats has been kept as fast as possible, in some cases there will be substantial differences in performance depending on the format in use.

One significant difference is the time taken to search for objects using keywords in the description field. If the data are in EViews format, EViews can typically query databases containing tens of thousands of series in a couple of seconds. When working with other formats, you may find that this same operation takes much longer, with the time increasing substantially as the database grows.

On the other hand, keeping the data in the foreign format may allow you to move between a number of applications without having to retranslate the file. This minimizes the number of copies of the data you have available, which may make the data easier to update and maintain.

Using EViews, you can either translate your data or work with your data directly in the foreign format. You should choose between the two based on your particular needs.

Opening a Foreign Database


Working with foreign formats requires very little additional knowledge. To open a foreign database, simply select **File/Open/Database...** from the main menu to open the dialog. In the field **Database/File Type:** select the type of the foreign database or file you wish to open. If the database is a local file, you can then use the **Browse Files** button to locate the database in exactly the same way as for a native EViews database. You can create a new foreign format database by a similar procedure way using **File/New/Database...** from the main EViews menu.

If the database is accessed through a client-server model, selecting the dialog will change to show extra fields necessary for making the connection to the server. For example, when accessing a database located on a FAME server, the dialog will include fields for the FAME server, username and password.

Since access to a server requires many fields to be entered, you may wish to save this information as an entry in the database registry (see [“The Database Registry” on page 281](#) for details).

There are special issues relating to working with DRIPro links. See [“DRIPro Link” on page 297](#) for details.

You can also create and open foreign format files using the `dbopen` or `dbcreate` commands. You may either use an option to specify the foreign type explicitly, or let EViews determine the type using the file extension. See [`dbopen` \(p. 233\)](#) and [`dbcreate` \(p. 231\)](#) in the [Command and Programming Reference](#) for details.



Copying a Foreign Database

Once you have opened a window to a foreign database, you can copy the entire database into a new format using **Proc/Copy the Database** from the database menus. A dialog will appear which allows you to specify the type and other attributes of the new database you would like to create.

When performing a database copy to a new format, objects which cannot be copied due to incompatibility between formats will result in error messages in the EViews command win-

dow but will not halt the copying process. Upon completion, a message in the status line reports how many objects could not be copied.

Notes on Particular Formats

Datastream

The Datastream database allows you to fetch data remotely over the internet from Datastream's extensive collection of financial and economic data. Data are retrieved from the Thomson Financial Datastream historical XML API. The location of the XML API must be entered in the server specification of the open database dialog window.

Datastream database access requires the Enterprise Edition of EViews.

In addition, you must be able to access the Thomson Datafeeds service using Datastream Advance through an internet connection, and you must have a valid XML API account from Thomson Financial. (Note that the XML API user name is not the Datastream user name as used with thick client products such as Datastream Advance.)

Please contact Thomson Reuters for further information (<http://www.thomsonreuters.com>).

DRIPro Link

A DRIPro link is a special type of database which allows you to fetch data remotely over the internet from DRI's extensive collection of economic data. To access these data, you must have a valid DRIPro account with DRI, and you must have already installed and configured the DRIPro server software.

There are special issues involved with using DRIPro links, which are discussed in detail in "Working with DRIPro Links" on page 306.

DRIBase Database

The DRIBase system is a client server system used by DRI to provide databases at the client site which can be kept current by remote updates. Customers can also use DRIBase as a means of storing their own databases in an Sybase or Microsoft SQL Server system.

DRIBase access is only available in the Enterprise Edition of EViews.

To access DRIBase databases, the TSRT library from DRI must already be installed on the client machine (this will normally be done by DRI as part of the DRIBase installation procedure).

When working with DRIBase databases, the Server specification field should be set to contain the DRIBase database prefix, while the Database name field should contain the DRIBase bank name, including the leading "@" where appropriate. Note that these fields, as well

as the Username and Password fields may be case sensitive, so make sure to preserve the case of any information given to you.

A DRIBase database has slightly different handling of frequencies than most other databases supported by EViews. See [“Issues with DRI Frequencies” on page 310](#) for details. You should also read [“Dealing with Illegal Names” on page 309](#) for a discussion of how DRI names are automatically remapped by EViews.

For further information on DRIBase, please contact IHS Global Insight (<http://www.globalinsight.com>).

EcoWin

EcoWin database support provides online access to economic and financial market data from EcoWin. The EcoWin Economic and Financial databases contain global international macroeconomic and financial data from more than 100 countries and multinational aggregates. Additional databases provide access to equities information and detailed country-specific information on earnings estimates, equities, funds, fixed income, and macroeconomics. For further information on EcoWin data and software, please contact EcoWin directly (http://www.thomsonreuters.com/products_services/financial/financial_products/investment_management/research_analysis/ecowin_pro).

EcoWin database access is only available in the Enterprise Edition of EViews.



With EViews Enterprise Edition, you can open an EViews window into an online EcoWin database. This window allows browsing and text search of the series in the database, selecting series, and copying/exporting series into an EViews workfile or another EViews database. In addition, EViews provides a set of commands that may be used to perform tasks such as fetching a particular series from a EcoWin database.

Access to EcoWin databases within EViews Enterprise Edition requires that the EcoWin Pro software has already been installed on the local machine, and that configuration of EcoWin database access using the EcoWin Database Configuration software has already been completed outside of EViews.

Interactive Graphical Interface

To open a graphical window to an EcoWin database, you should first open Database Specification dialog by selecting File/Open/Database... from the main EViews menu. Next, choose EcoWin Database in the Database/File Type combo, and enter the name of the online database as specified in the EcoWin Database Configuration software, typically "DEFAULT".

Clicking on OK will open an empty EViews database window. To access the EcoWin data, click on the Query–Select button in the database window toolbar. EViews will open a window containing a EcoWin Pro control for browsing and searching the online data. Note that it may take a bit of time to initialize the EcoWin control. Once initialized, EViews will open the EcoWin Query window.




The EcoWin Query window provides you with two methods for selecting series to be brought into your EViews database.


First, you may use Tree Search to browse a directory structure of the online database. You should use the tree on the left to navigate to the directory of interest, then select series in the window on the right by clicking or control-clicking on the entry, or by clicking on the

right-mouse button and choosing Select All . Once the desired series have been highlighted, click on OK to bring the selected data into your EViews database.

This procedure, first browsing to find a directory containing data of interest, selecting series, and then clicking on OK to bring in data, can be performed multiple times, until a list of all the series that you wish to use has been accumulated within the EViews database window. At this point the EcoWin browse control can be closed using the Cancel button.



In place of browsing the tree structure of the database, you may elect to use text search to display a list of series in the database. Click on the Text Search selection at the top of the dialog to change the dialog to the search display, and enter the information in the appropriate fields. For example, to search for all series in the database using the text "PETROLEUM" and "US", we have:



Highlight the series of interest and click on OK to bring them into the database. Repeat the tree browsing or search method of adding series until the list in the database is complete, then click on Cancel to close the query window.

Once series of interest have been included in the database window, all of the standard EViews database tools, such as copy and paste to an existing workfile or database using the right mouse menus, creating a new EViews workfile containing the data using the Export button, or importing data into an existing EViews workfile using the Fetch menu item from the workfile window, are available.

Note that after you have completed your initial query, you may reopen the EcoWin query window at any time. To add series to those already available in the database window, press the Query Append Select button in the database window, then browse or search for your series. To first clear the contents of the database window, you should press the Query Select button instead of the Query Append Select button.

Tips for Working with EcoWin Databases

If an EcoWin database is going to be used frequently or for direct access to individual series, you should find it useful to add an EcoWin entry in the database registry ([“The Database Registry” on page 281](#)).

The EViews database registry may be accessed by choosing Options/Database Registry... from the main EViews menu. Press Add New Entry to add a new database registry entry to the list. The procedure for adding an EcoWin database to the registry is identical to that for opening an EcoWin database. The Database/File Type field should be set to EcoWin Database and the Database Name/Path field should be filled with the name assigned to the database in the EcoWin Database Configuration software (generally “DEFAULT”).

Once the EcoWin database has been put in the registry, it may be referred to by its alias (short hand) name. For example, if you have assigned the EcoWin database the alias “EW”, you can open the database with the simple command:

```
dbopen ew
```

or by using the Browse Registry button in the Database Specification dialog. The database name “EW” will be added to the most recently used file list, where it may be selected at a later time to reopen the database.

Assigning the EcoWin database a shorthand name also allows you to reference data without explicitly opening the database. For example, the command

```
equation eq1.ls ew::usa09016 c ew::usa09016(-1) @trend
```

runs a regression of U.S. unemployment on an intercept, its own lagged value, and a time trend. The series USA09016 will be accessed directly from the EcoWin servers, and does not need to appear within a currently open database window for this command to be used.

Other commands such as `scopy` allow the name associated with the series to be changed during the procedure, as well as supporting the copying of series directly from an EcoWin database to another EViews database.

```
show ew::usa09016
```

displays a table of U. S. unemployment.

Note that series in the EcoWin “Economic” or EcoWin “Financial” databases may be referenced merely by using the database shorthand and the series name. In the example above, EViews looks for USA09016 in the two base EcoWin databases.

Series located in add-on EcoWin databases such as “Bank of England,” “Bundesbank,” “Bureau of Economic Analysis,” must also provide the name of the add-on database in which the series is located. You should provide the name of the EcoWin shortcut followed by a double colon, an EcoWin add-on database prefix, a slash, and then the series name. For example, you can fetch the mortgage rate (LUM5WTL) in the Bank of England database with

```
fetch ew::boe\lum5wtl
```

where we follow the database name with the add-on name BOE. The series will be named “BOE\LUM5WTL” in EViews. Note that the add-on name BOE is taken from the EcoWin name prefix (for example, LUM5WTL appears as “BOE:LUM5WTL” within EcoWin).

FactSet

The FactSet database is a remote database provided by FactSet Research Systems. It is composed of more than 800 commercial data sets of financial data. Data include international macroeconomic, commodity, and financial time series from more than 150 countries.

Use of FactSet databases requires the Enterprise Edition of EViews and installation of FactSet client software. For further information on using Factset please contact Factset directly (<http://www.factset.com>).

FAME

The FAME format is a binary file format written by FAME database products. FAME provides a variety of products and services for working with time series data.

FAME access is only available in the Enterprise Edition of EViews.

In order to access FAME databases, a valid installation of FAME must already be available. EViews makes use of the FAME C Host Language Interface (C HLI) library, and will error unless the FAME .DLLs are correctly installed on the machine. EViews currently supports only version 8 of the FAME libraries.

A local FAME database can have any file extension, and EViews supports access to a FAME database with any name. However, because many commands in EViews use the file extension to automatically detect the file type, you will generally find it easier to work with FAME databases which have the default “.DB” extension.

EViews also allows access to FAME databases located on a FAME Database Server. When working with a FAME server, the Server specification should be given in the form:

#port_number@ip_address

For example, the server specification for access to a FAME/Channel database might appear as:

#2552@channel.fame.com

Access to a server will require a valid username and password for that server.

Please contact Sungard directly (<http://www.sungard.com/fame>) for further information about the FAME database system and other FAME products.

FRED

FRED(Federal Reserve Economic Data) is a publicly accessible database of more than 20,000 U.S. and international time series of multiple frequencies, provided by the Economic Research Division of the Federal Reserve Bank of St. Louis. The FRED database offers a wide variety of freely downloadable data, including interest rates, exchange rates, national income accounts, and many others. Data found in FRED are drawn from several national and international sources and is updated frequently.

Prior to EViews 7, importing data from FRED required that the data first be downloaded into either a Microsoft Excel or text file, and then be imported into an EViews workfile. EViews users can now use EViews to directly connect to, open, query, and import data from the FRED database using the familiar EViews database interface.

Both the Standard and Enterprise versions of EViews offer FRED access. Please note that an internet connection will be required to obtain FRED data.

For more information on the FRED database, please see <http://research.stlouisfed.org/fred2>.

Haver

The Haver database format is a binary file format used by Haver Analytics when distributing data.

Direct access to Haver database files is only available in the Enterprise Edition of EViews.

The main difference between Haver databases and other file formats supported by EViews is that Haver databases are read-only. You cannot create your own database in Haver format, nor can you modify an existing database. EViews will error if you try to do so.

Please contact Haver Analytics (<http://www.haver.com>) directly for further information about Haver Analytics data products.

Moody's Economy.com

The Moody's Economy.com format is a binary file format written by Moody's Economy.com tools. Moody's Economy.com features a database containing more than 190 million economic, financial, and demographic time series covering more than 180 countries and their sub-regions.

The Enterprise Edition of EViews is required to read Moody's Economy.com formatted data.

Additional information on Moody's Economy.com databases can be found at <http://www.economy.com>.

AREMOS TSD

The TSD format is a portable ASCII file format written by the AREMOS package. The EViews database tools provide an intuitive graphical interface to the data, and allows you to move data directly in and out of an EViews database without having to move the data through a workfile (which may force the data to be converted to a single frequency).

GiveWin/PcGive

The GiveWin/PcGive format is a binary file format used by GiveWin, PcGive versions 7 through 10, and PcFiml.

There are two issues when working with GiveWin/PcGive files. The first is that EViews is case insensitive when working with object names, while GiveWin and PcGive are case sensitive. Because of this, if you intend to work with a file in both packages, you should avoid having two objects with names distinguished only by case. If your files do not follow this rule, EViews will only be able to read the last of the objects with the same name. Any early objects will be invisible.

The second issue concerns files with mixed frequency. The GiveWin/PcGive file format does support series of mixed frequency, and EViews will write to these files accordingly. However, GiveWin itself appears to only allow you to read series from one frequency at a time, and will ignore (with error messages) any series which do not conform to the chosen frequency. Consequently, depending on your application, you may prefer to store series of only one frequency per GiveWin/PcGive file.

RATS 4.x

The RATS 4.x format is a binary file format used by RATS Version 4 through 7 on all platforms.

The main issue to be aware of when working with RATS 4.x format files is that the “.RAT” extension is also used by RATS version 3 files. EViews will neither read from nor write to RATS files in this earlier format. If you try to use EViews to open one of these files, EViews will error, giving you a message that the file has a version number which is not supported.

To work with a RATS Version 3 file in EViews, you will first have to use RATS to translate the file to the Version 4 format. To convert a Version 3 file to a Version 4 file, simply load the file into RATS and modify it in some way. When you save the file, RATS will ask you whether you would like to translate the file in to the new format. One simple way to modify the file without actually changing the data is to rename a series in the file to the name which it already has. For example, if we have a Version 3 file called “OLDFILE.RAT”, we can convert to a Version 4 by first opening the file for editing in RATS:

```
dedit oldfile.rat
```

then listing the series contained in the file:

```
catalog
```

then renaming one of the series (say “X”) to its existing name

```
rename x x
```

and finally saving the file

```
save
```

At this point, you will be prompted whether you would like to translate the file into the Version 4 format.

See the RATS documentation for details.

RATS Portable/TROLL

The RATS portable format is an ASCII file format which can be read and written by RATS. It is generally slower to work with than RATS native format, but the files are human readable and can be modified using a text editor.

You can read the contents of a RATS portable file into memory in RATS with the following commands:

```
open data filename.trl
data(format=portable) start end list_of_series
close data
```

To write what is currently in memory in RATS to a RATS portable file, use:

```
open copy filename.trl
copy(format=portable) start end list_of_series
close copy
```

See the RATS documentation for details.

TSP Portable

The TSP portable format is an ASCII file format which can be read and written by copies of TSP on all platforms. The file consists of a translation of a TSP native databank (which typically have the extension “.TLB”) into a TSP program which, when executed, will regenerate the databank on the new machine.

To create a TSP portable file from a TSP databank file, use the DBCOPY command from within TSP:

```
dbcop databank_name
```

To translate a TSP portable file back into a TSP databank file, simply execute the TSP file as a TSP program.

Once the data are in TSP databank format, you can use the TSP command,

```
in databank_name
```

to set the automatic search to use this databank and the TSP command,

```
out databank_name
```

to save any series which are created or modified back to the databank.

See the TSP documentation for details.

Working with DRIPro Links

EViews has the ability to remotely access databases hosted by DRI. Subscribers to DRI DRIPro data services can use these features to access data directly from within EViews.

Although the interface to remote databases is very similar to that of local databases, there are some differences due to the nature of the connection. There are also some issues specifically related to accessing DRI data. The following sections document these differences.

Enabling DRI Access

In order to access DRI data services, you will need to have an active DRIPro account. If you are not an existing DRIPro customer but may be interested in becoming one, you should contact Global Insight for details (<http://www.globalinsight.com>).

Access to DRI data will not be possible unless you have already installed and configured the DRIPRO server software. If you have difficulties with getting the software to work, you should contact Global Insight directly for technical support.

Creating a Database Link

A remote DRI database is represented in EViews by a database link. A database link resembles a local database, consisting of a set of files on disk, but instead of containing the data itself, a database link contains information as to how to access the remote data. A database link also contains a cache in which copies of recently retrieved objects are kept, which can substantially reduce the time taken to perform some database operations.

You can create a database link by following a similar procedure to that used to create a local database. Select **File/New/Database...** from the main menu, then select **DRIPRO Link** in the field **Database/File Type**. The dialog should change appearance so that a number of extra fields are displayed. Enter the name you would like to give the new database link in **Cache name/path**. You may wish to name the database link after the DRI databank to which it links.

In the **Connection name** field you should enter the name of the DRIPRO connection you would like to use, as it appears in the **Connection Settings** box in the DRIPRO configuration program. If you have only configured a single connection, and have not modified the connection name, the connection name will be **DEFAULT**, and this will be filled in automatically by EViews if you leave the field blank.

In the **DRI Databank** field you should input the full name of the DRIPRO bank to which you would like to connect, not including any leading "@" sign. For example, to connect to the DRI U.S. Central database, you should enter the name **uscen**. Each EViews database link may be associated with only one DRI databank, although you can create as many database links as you require.

The **Local Password** field may be used to set a password that must be entered whenever you wish to use the database link. This should not be confused with your DRIPRO username and password, which you must already have provided in the DRIPRO configuration program. Accessing a database link which contains a local password will cause a dialog to appear which prompts the user to input the password. Access to the remote database is only provided if the remote password is valid. Leave this field blank if you do not want a password to be attached to the database link.

When you have finished filling in the dialog fields, click on the OK button. A new database will be created and a database window should appear on the screen.

The database link window is very similar to a normal EViews database window. You should be able to perform basic query operations and simple fetching of series without any special instructions. Note, however, that it is not possible to modify a remote DRI database from within EViews, so operations which involve writing to the database have been removed. There are a number of other complications related to dealing with DRI Pro databases that are described [“Issues with DRI Frequencies” on page 310](#)

Understanding the Cache


A database link includes a cache of recently fetched objects which is used to speed up certain operations on the database. In some circumstances, fetching an object from the database will simply retrieve a copy from the local cache, rather than fetching a fresh copy of the data from the remote site. Even if a fresh copy is retrieved, having a previous copy of the series in the cache can substantially speed up retrieval.

You can regulate the caching behavior of the database link in a number of different ways. The basic option which determines under what circumstances a new copy of the data should be fetched is the days before refresh. If you attempt to fetch an object from the database link, and the copy of the object currently in the cache was fetched more recently than the days before refresh value, then the object currently in the cache will be returned instead of a fresh copy being fetched. For example, if days before refresh is set to one, any object which has already been fetched today will be retrieved from the cache, while any object which has not yet been fetched today will be retrieved from the remote site. Similarly, if days before refresh is set to seven, then an object in the cache must be more than a week old before a new copy of the object will be fetched. If days before refresh is set to zero, then a new copy of the data is fetched every time it is used.

You can change the days before refresh setting by clicking on the Proc button at the top of the database link window, then choosing Link Options... from the pop-up menu. A dialog will appear:

The dialog contains a number of fields, one of which is labeled Days before refreshing objects. Type a new number in the field to change the value.

The same dialog also contains a button marked Reset cache now. This button can be used to modify the behavior documented above. Clicking on the button causes the cache to mark all objects in the cache as out of date, so that the next



time each object is fetched, it is guaranteed that a fresh copy will be retrieved. This provides a simple way for you to be certain that the database link will not return any data fetched before a particular time.

The dialog also contains some options for managing the size of the cache. The field marked `Maximum cache size in kilobytes` can be used to set the maximum size that the cache will be allowed to grow to on disk. If the cache grows above this size, a prompt will appear warning you that the cache has exceeded the limit and asking if you would like to compact the cache. Compacting is performed by deleting objects from oldest to newest until the cache size is reduced to less than three quarters of its maximum size. The cache is then packed to reclaim the empty space.

You can also completely clear the contents of the cache at any time by clicking on the button marked `Reset & Clear Cache Now`.

You can always examine the current contents of the database cache by clicking on the `Cache` button at the top of the database link window. This will display the names of all objects currently in the cache.

Configuring Link Options

The `Database Link Options` dialog also allows you to specify a number of timeout values. In most cases, the default values will behave acceptably. If you believe you are having problems with EViews aborting the connection too early, or you would like to shorten the times so as to receive a timeout message sooner, then enter new values in the appropriate fields.

- `Connection timeout`— is the length of time, in seconds, that EViews will wait for a response when first connecting to DRI. Depending on the type of connection you are making to DRI, this can take a significant amount of time.
- `Conversation timeout`— is the length of time, in seconds, that EViews will wait for a response from DRIPro when carrying out a transaction after a connection has already been made.

The values are attached to a particular database link, and can be reset at any time.

Dealing with Illegal Names

DRI databanks contain a number of series with names which are not legal names for EViews objects. In particular, DRI names frequently contain the symbols “@”, “&” and “%”, none of which are legal characters in EViews object names. We have provided a number of features to allow you to work with these series within EViews.

Because the “@” symbol is so common in DRI names, while the underline symbol (which is a legal character in EViews) is unused, we have hard-coded the rule that all underlines in EViews are mapped into “@” symbols in DRI names when performing operations on an DRI database link. For example, if there is a series with the name `JQIMET@UK`, you should refer

to this series inside EViews as JQIMET_UK. Note that when performing queries, EViews will automatically replace the “@” symbol by an underline in the object name before displaying the query results on the screen. Consequently, if you are fetching data by copying-and-pasting objects from a query window, you do not need to be aware of this translation.

For other illegal names, you should use the object aliasing features (see [“Object Aliases and Illegal Names” on page 291](#)) to map the names into legal EViews object names.

Issues with DRI Frequencies

DRI databases have a different structure than EViews databases. An EViews database can contain series with mixed frequencies. A DRI database can contain data of only a single frequency. In order that similar data may be grouped together, each DRI databank is actually composed of a series of separate databases, one for each frequency. When working with DRI data from within DRIPro software, you will often have to specify at exactly which frequency a particular series can be found. In some cases, a DRI databank may contain a series with the same name stored at several different frequencies.

Because this approach is inconsistent with the way that EViews works, we have tried to create a simpler interface to DRI data where you do not need to keep track of the frequency of each series that you would like to fetch. Instead, you can simply fetch a series by name or by selecting it from the query window, and EViews will do whatever is necessary to find out the frequency for you.

An ambiguity can arise in doing this, where a series with the same name appears at a variety of different frequencies in the DRI databank. By default, EViews resolves this ambiguity by always fetching the highest frequency data available. EViews will then perform necessary frequency conversions using the standard rules for frequency conversion in EViews (see [“Frequency Conversion” on page 110](#)).

In many cases, this procedure will exactly replicate the results that would be obtained if the lower frequency data was fetched directly from DRIPro. In some cases (typically when the series in question is some sort of ratio or other expression of one or more series), the figures may not match up exactly. In this case, if you know that the DRI data exists at multiple frequencies and you are familiar with DRI frequency naming conventions, you can explicitly fetch a series from a DRI database at a particular frequency by using a modified form of the command line form of fetch. Simply add the DRI frequency in parentheses after the name of the series. For example, the command:

```
fetch x(Q) y(A)
```

will fetch the series X and Y from the current default database, reading the quarterly frequency copy of X and the annual frequency copy of Y. If you request a frequency at which the data are not available, you will receive an error message. You should consult DRI documentation for details on DRI frequencies.

Limitations of DRI Queries

Queries to DRI database links are more limited than those available for EViews databases. The following section documents the restrictions.

First, queries on DRI databases allow only a subset of the fields available in EViews databases to be selected. The fields supported are name, type, freq, start, end, last_update and description.

Second, the only fields which can be used in “where” conditions in a query on a DRIPRO database link are name and description. (EViews does not support queries by frequency because of the ambiguities arising from DRI frequencies noted above).

Each of these fields has only one operator, the “matches” operator, and operations on the two fields can only be joined together using the “and” operator.

The “matches” operator is also limited for queries on DRI databases, matching only a subset of the expressions available for EViews databases. In particular, the pattern expression in a query on an DRI database must either have the form

a or b or ... c

or the form

a and b and ... c

Mixing of “and” and “or” is not allowed, and the “not” operator is not supported.

Patterns, however, are allowed and follow the normal EViews rules where “?” denotes any single character and “*” denotes zero or more characters.

Sorting of results by field is not supported.

Dealing with Common Problems

As stated in the introduction, you must install and configure the DRIPRO software before EViews will be able to connect to DRI. If you cannot connect to DRI using the DRIPRO software, you should contact DRI directly for assistance.

Assuming that you have correctly configured your DRIPRO connection, in most cases EViews will be able to recover adequately from unexpected problems which arise during a DRIPRO session without user intervention. Sometimes this will require EViews to automatically disconnect then reconnect to DRI.

There are some circumstances in which EViews may have problems making a connection. In order to connect to DRI, EViews uses a program written by DRI called DRIPROSV. You can tell when this program is running by looking for the icon labeled “DRIPRO server” in the Windows taskbar. Because of problems that can arise with multiple connections, EViews will not attempt to use the program if it is already running. Instead, EViews will report an

error message “DRI server software already running”. If there is another application which is using the connection to DRI, you can simply close down that program and the DRIPro server software should shut down automatically. If this is not the case, you may have to close down the DRIPro server software manually. Simply click on the icon in the Windows taskbar with the right mouse button, then select Close from the pop-up menu.

You may also use this as a procedure for forcing the DRIPro connection to terminate. Closing down the server software may cause EViews to report an error if it is currently carrying out a database transaction, but should otherwise be safe. EViews will restart the server software whenever it is needed.

Note that running other DRIPro software while EViews is using the DRIPro server software may cause EViews to behave unreliably.

Part II. Basic Data Analysis

The following chapters describe the EViews objects and tools that you will use to perform basic data analysis.

- [Chapter 11. “Series,” beginning on page 315](#) describes the series object. Series are the basic unit of numeric data in EViews and are the basis for most univariate analysis. This chapter documents the basic data analysis and display features associated with series.
- [Chapter 12. “Groups,” on page 379](#) documents the views and procedures for the group object. Groups are collections of series (and series equivalent objects) which form the basis for a variety of multivariate graphical display and data analyses.
- [Chapter 13. “Graphing Data,” beginning on page 435](#) describes the display of graph views of data in series and group objects.
- [Chapter 14. “Categorical Graphs,” on page 523](#) describes the construction of categorical graphs formed using subsets of the data in series or groups

Chapter 11. Series

EViews provides various statistical graphs, descriptive statistics, and procedures as views and procedures of a numeric series. Once you have read or generated data into series objects using any of the methods described in [Chapter 5. “Basic Data Handling,”](#) [Chapter 6. “Working with Data,”](#) and [Chapter 10. “EViews Databases,”](#) you are ready to perform statistical and graphical analysis using the data contained in the series.

Series views compute various statistics for a single series and display these statistics in various forms such as spreadsheets, tables, and graphs. The views range from a simple line graph, to kernel density estimators. Series procedures create new series from the data in existing series. These procedures include various seasonal adjustment methods, exponential smoothing methods, and the Hodrick-Prescott filter.

The group object is used when working with more than one series at the same time. Methods which involve groups are described in [Chapter 12. “Groups,”](#) on page 379

To access the views and procedures for series, open the series window by double clicking on the series name in the workfile, or by typing `show` followed by the name of the series in the command window.

Series Views Overview


The series view drop-down menu is divided into four blocks. The first block lists views that display the underlying data in the series. The second and third blocks provide access to general statistics (the views in the third block are mainly for time series analysis). The fourth block allows you to modify and display the series labels.

Spreadsheet

The spreadsheet view is the basic tabular view for the series data. Displays the raw, mapped, or transformed data series data in spreadsheet format.

You may customize your spreadsheet view extensively (see [“Changing the Spreadsheet Display”](#) in [“Data Objects”](#) on [page 82](#)).

In addition, the right-mouse button menu allows you to write the contents of the spreadsheet view to a CSV, tab-delimited ASCII text, RTF, or HTML file. Simply right-mouse button click, select the [Save table to disk...](#) menu item, and fill out the resulting dialog.



Graph

The [Graph...](#) menu item brings up the [Graph Options](#) dialog, which allows you to select various types of graphical display of the series. You can create graph objects by freezing these views. See [Chapter 13. “Graphing Data,” beginning on page 435](#) for a discussion of techniques for creating and customizing the graphical display.

Descriptive Statistics & Tests


This set of views displays various summary statistics for the series. The submenu contains entries for histograms, basic statistics, and statistics by classification.

Histogram and Stats

This view displays the frequency distribution of your series in a histogram. The histogram divides the series range (the distance between the maximum and minimum values) into a number of equal length intervals or bins and displays a count of the number of observations that fall into each bin.

(If you would like to produce a histogram where you have greater control over the bin width and placement, or if you would like to construct related graphs such as a kernel density plot or histogram polynomial, you should use the graph view of the series.)

A complement of standard descriptive statistics are displayed along with the histogram. All of the statistics are calculated using the observations in the current sample.



- Mean is the average value of the series, obtained by adding up the series and dividing by the number of observations.
- Median is the middle value (or average of the two middle values) of the series when the values are ordered from the smallest to the largest. The median is a robust measure of the center of the distribution that is less sensitive to outliers than the mean.
- Max and Min are the maximum and minimum values of the series in the current sample.
- Std. Dev. (standard deviation) is a measure of dispersion or spread in the series. The standard deviation is given by:

$$s = \sqrt{\frac{1}{N} \sum_{i=1}^N (y_i - \bar{y})^2} \quad (11.1)$$

where N is the number of observations in the current sample and $\bar{y}$ is the mean of the series.

- Skewness is a measure of asymmetry of the distribution of the series around its mean. Skewness is computed as:

$$S = \frac{1}{N} \sum_{i=1}^N \frac{y_i - \bar{y}}{\hat{\sigma}}^3 \quad (11.2)$$

where $\hat{\sigma}$ is an estimator for the standard deviation that is based on the biased estimator for the variance $\hat{\sigma}^2 = \frac{1}{N} \sum_{i=1}^N (y_i - \bar{y})^2$. The skewness of a symmetric distribution, such as the normal distribution, is zero. Positive skewness means that the distribution

- Kurtosis measures the peakedness or flatness of the distribution of the series. Kurtosis is computed as

where $\hat{\sigma}^2$ is again based on the biased estimator for the variance. The kurtosis of the normal distribution is 3. If the kurtosis exceeds 3, the distribution is peaked (leptokurtic) relative to the normal; if the kurtosis is less than 3, the distribution is flat (platykurtic) relative to the normal.

- where S is the skewness, and K is the kurtosis.

Under the null hypothesis of a normal distribution, the Jarque-Bera statistic is distributed as χ^2 with 2 degrees of freedom. The reported Probability is the probability that a Jarque-Bera statistic exceeds (in absolute value) the observed value under the null hypothesis—a small probability value leads to the rejection of the null hypothesis of a normal distribution. For the LWAGE series displayed above, we reject the hypothesis of normal distribution at the 5% level but not at the 1% significance level.

The Stats Table view displays descriptive statistics for the series in tabular form.

Stats by Classification

View	Proc	Object	Properties	Print	Name	Freeze	Sample	Genr	Sheet	Graph
			LWAGE							
Mean			2.275496							
Median			2.302585							
Maximum			4.174387							
Minimum			0.955511							
Std. Dev.			0.563464							
Skewness			0.077570							
Kurtosis			2.640649							
Jarque-Bera			6.383398							
Probability			0.041102							
Sum			2275.496							
Sum Sq. Dev.			317.1742							
Observations			1000							

Statistics & Tests/Stats by Classification... a Statistics by Classification dialog box appears:

The Statistics option at the left allows you to choose the statistic(s) you wish to compute.

In the Series/Group for Classify field enter series or group names that define your subgroups. You must type at least one name. Descriptive statistics will be calculated for each unique value of the classification series (also referred to as a factor) unless binning is selected. You may type more than one series or group name;

separate each name by a space. The quantile statistic requires an additional argument (a number between 0 and 1) corresponding to the desired quantile value. Click on the Options button to choose between various methods of computing the quantiles. See [“Empirical CDF” on page 504](#) for details.

By default, EViews excludes observations which have missing values for any of the classification series. To treat NA values as a valid subgroup, select the NA handling option.

The Layout option allows you to control the display of the statistics. Table layout arrays the statistics in cells of two-way tables. The list form displays the statistics in a single line for each classification group.

The Table and List options are only relevant if you use more than one series as a classifier.

The Sparse Labels option suppresses repeating labels in list mode to make the display less cluttered.

The Row Margins, Column Margins, and Table Margins instruct EViews to compute statistics for aggregates of your subgroups. For example, if you classify your sample on the basis of gender and age, EViews will compute the statistics for each gender/age combination. If you elect to compute the marginal statistics, EViews will also compute statistics corresponding to each gender, and each age subgroup.

A classification may result in a large number of distinct values with very small cell sizes. By default, EViews automatically groups observations into categories to maintain moderate cell sizes and numbers of categories. Group into Bins provides you with control over this process.

Setting the # of values option tells EViews to group data if the classifier series takes more than the specified number of distinct values.

The Avg. count option is used to bin the series if the average count for each distinct value of the classifier series is less than the specified number.

The Max # of bins specifies the maximum number of subgroups to bin the series. Note that this number only provides you with approximate control over the number of bins.

The default setting is to bin the series into 5 subgroups if either the series takes more than 100 distinct values or if the average count is less than 2. If you do not want to bin the series, unmark both options.

For example, consider the following stats by classification table view of the series LWAGE, categorized by values of MARRIED and UNION (from the workfile “Cps88.WF1”):

Descriptive Statistics for LWAGE
Categorized by values of MARRIED and UNION
Date: 08/18/09 Time: 16:26
Sample: 1 1000
Included observations: 1000

		UNION		
		0	1	All
Mean				
Median				
Std. Dev.				
Obs.				
0		1.993829	2.387019	2.052972
		1.906575	2.409132	2.014903
		0.574636	0.395838	0.568689
		305	54	359
MARRIED 1		2.368924	2.492371	2.400123
		2.327278	2.525729	2.397895
		0.557405	0.380441	0.520910
		479	162	641
All		2.223001	2.466033	2.275496
		2.197225	2.500525	2.302585
		0.592757	0.386134	0.563464
		784	216	1000

The header indicates that the table cells are categorized by two series MARRIED and UNION. These two series are dummy variables that take only two values. No binning is performed; if the series were binned, intervals rather than a number would be displayed in the margins.

The upper left cell of the table indicates the reported statistics in each cell; in this case, the median and the number of observations are reported in each cell. The row and column labeled All correspond to the Row Margin and Column Margin options described above.

Here is the same view in list form with sparse labels:

Descriptive Statistics for LWAGE
Categorized by values of MARRIED and UNION
Date: 08/18/09 Time: 16:27
Sample: 1 1000
Included observations: 1000

UNION	MARRIED	Mean	Median	Std. Dev.	Obs.
0	0	1.993829	1.906575	0.574636	305
	1	2.368924	2.327278	0.557405	479
	All	2.223001	2.197225	0.592757	784
1	0	2.387019	2.409132	0.395838	54
	1	2.492371	2.525729	0.380441	162
	All	2.466033	2.500525	0.386134	216
All	0	2.052972	2.014903	0.568689	359
	1	2.400123	2.397895	0.520910	641
	All	2.275496	2.302585	0.563464	1000

For series functions that compute by-group statistics and produce new series, see ["By-Group Statistics" on page 406](#) in the Command and Programming Reference

Simple Hypothesis Tests

This view carries out simple hypothesis tests regarding the mean, median, and the variance of the series. These are all single sample tests; see ["Equality Tests by Classification" on page 324](#) for a description of two sample tests. If you select View/Descriptive Statistics & Tests/Simple Hypothesis Tests, the Series Distribution Tests dialog box will be displayed. Depending on which edit field on the left you enter a value, EVIEWS will perform a different test.

Mean Test

Carries out the test of the null hypothesis that the mean m of the series X is equal to a specified value m_0 against the two-sided alternative that it is not equal to m_0 :

$$\begin{aligned} H_0: m &= m_0 \\ H_1: m &\neq m_0 \end{aligned} \quad (11.5)$$

If you do not specify the standard deviation of X , EVIEWS reports a t-statistic computed as:

$$t = \frac{\bar{X} - m_0}{s / \sqrt{N}} \quad (11.6)$$

where $\bar{X}$ is the sample mean of X , s is the unbiased sample standard deviation, and N is the number of observations of X . If X is normally distributed, under the null hypothesis the t-statistic follows a t-distribution with $N - 1$ degrees of freedom.

If you specify a value for the standard deviation of X , EViews also reports a z -statistic:

$$z = \frac{\bar{X} - m}{j / \sqrt{N}} \quad (11.7)$$

where j is the specified standard deviation of X . If X is normally distributed with standard deviation j , under the null hypothesis, the z -statistic has a standard normal distribution.

To carry out the mean test, type in the value of the mean under the null hypothesis in the edit field next to Mean. If you want to compute the z -statistic conditional on a known standard deviation, also type in a value for the standard deviation in the right edit field. You can type in any number or standard EViews expression in the edit fields.

Hypothesis Testing for LWAGE

Date: 07/31/06 Time: 11:03

Sample: 1 1000

Included observations: 1000

Test of Hypothesis: Mean = 2.000000

Sample Mean = 2.275496

Sample Std. Dev. = 0.563464

<u>Method</u>	<u>Value</u>	<u>Probability</u>
t-statistic	15.46139	0.0000

The reported probability value is the p -value, or marginal significance level, against a two-sided alternative. If this probability value is less than the size of the test, say 0.05, we reject the null hypothesis. Here, we strongly reject the null hypothesis for the two-sided test of equality. The probability value for a one-sided alternative is one half the p -value of the two-sided test.

Variance Test

Carries out the test of the null hypothesis that the variance of a series X is equal to a specified value j^2 against the two-sided alternative that it is not equal to j^2 :

$$\begin{aligned} H_0: \text{var } x &= j^2 \\ H_1: \text{var } x &> j^2. \end{aligned} \quad (11.8)$$

EViews reports a χ^2 statistic computed as:

$$\chi^2 = \frac{(N-1)s^2}{j^2} \quad (11.9)$$

where N is the number of observations, s is the sample standard deviation, and $\bar{X}$ is the sample mean of X . Under the null hypothesis and the assumption that X is normally distributed, the statistic follows a χ^2 distribution with $N-1$ degrees of freedom. The probability

value is computed as $\min(p, 1 - p)$, where p is the probability of observing a χ^2 -statistic as large as the one actually observed under the null hypothesis.

To carry out the variance test, type in the value of the variance under the null hypothesis in the field box next to Variance. You can type in any positive number or expression in the field.

Hypothesis Testing for LWAGE		
Date: 071/31/06 Time: 01:22		
Sample: 1 1000		
Included observations: 1000		
Test of Hypothesis: Variance = 0.300000		
Sample Variance = 0.317492		
<u>Method</u>	<u>Value</u>	<u>Probability</u>
Variance Ratio	1057.247	0.0979

Median Test

Carries out the test of the null hypothesis that the median of a series X is equal to a specified value m against the two-sided alternative that it is not equal to m :

$$\begin{aligned} H_0: \text{med } x &= m \\ H_1: \text{med } x &> m. \end{aligned} \quad (11.10)$$

EViews reports three rank-based, nonparametric test statistics. The principal references for this material are Conover (1980) and Sheskin (1997).

- Binomial sign test. This test is based on the idea that if the sample is drawn randomly from a binomial distribution, the sample proportion above and below the true median should be one-half. Note that EViews reports two-sided p -values for both the sign test and the large sample normal approximation (with continuity correction).
- Wilcoxon signed ranks test. Suppose that we compute the absolute value of the difference between each observation and the mean, and then rank these observations from high to low. The Wilcoxon test is based on the idea that the sum of the ranks for the samples above and below the median should be similar. EViews reports a p -value for the asymptotic normal approximation to the Wilcoxon T -statistic (correcting for both continuity and ties). See Sheskin (1997, p. 82–94) and Conover (1980, p. 284).
- Van der Waerden (normal scores) test. This test is based on the same general idea as the Wilcoxon test, but is based on smoothed ranks. The signed ranks are smoothed by converting them to quantiles of the normal distribution (normal scores). EViews reports the two-sided p -value for the asymptotic normal test described by Conover (1980).

To carry out the median test, type in the value of the median under the null hypothesis in the edit box next to Median . You can type any numeric expression in the edit field.

Hypothesis Testing for LWAGE
Date: 07/31/06 Time: 11:06
Sample: 1 1000
Included observations: 1000
Test of Hypothesis: Median = 2.250000

Sample Median = 2.302585

Method	Value	Probability
Sign (exact binomial)	532	0.0463
Sign (normal approximation)	1.992235	0.0463
Wilcoxon signed rank	1.134568	0.2566
van der Waerden (normal scores)	1.345613	0.1784

Median Test Summary

Category	Count	Mean Rank
Obs > 2.250000	532	489.877820
Obs < 2.250000	468	512.574786
Obs = 2.250000	0	
Total	1000	


Equality Tests by Classification

This view allows you to test equality of the means, medians, and variances across subsamples (or subgroups) of a single series. For example, you can test whether mean income is the same for males and females, or whether the variance of education is related to race. The tests assume that the subsamples are independent.

For single sample tests, see the discussion of “Simple Hypothesis Tests” on page 321. For tests of equality across different series, see “Tests of Equality” on page 408.

Select View/Descriptive Statistics & Tests/Equality Tests by Classification... and the Tests by Classification dialog box appears.

First, select whether you wish to test the mean, the median or the variance. Specify the subgroups, the NA handling, and the grouping options as described in “Stats by Classification,” beginning on page 318.



Mean Equality Test

This test is a single-factor, between-subjects, analysis of variance (ANOVA). The basic idea is that if the subgroups have the same mean then the variability between the sample means (between groups) should be the same as the variability within any subgroup (within group).

Denote the i -th observation in subgroup g as $x_{g,i}$, where $i = 1, \dots, n_g$ for groups $g = 1, 2, \dots, G$. The between and within sums of squares are defined as:

$$SS_B = \sum_{g=1}^G n_g (\bar{x}_g - \bar{x})^2 \quad (11.11)$$

$$SS_W = \sum_{g=1}^G \sum_{i=1}^{n_g} x_{g,i}^2 - \sum_{g=1}^G n_g \bar{x}_g^2 \quad (11.12)$$

where $\bar{x}_g$ is the sample mean within group g and $\bar{x}$ is the overall sample mean. The F-statistic for the equality of group means is computed as:

$$F = \frac{SS_B / (G - 1)}{SS_W / (N - G)} \quad (11.13)$$

where N is the total number of observations. The F-statistic has an F-distribution with $G - 1$ numerator degrees of freedom and $N - G$ denominator degrees of freedom under the null hypothesis of independent and identical normal distributed data, with equal means and variances in each subgroup.

When the subgroup variances are heterogeneous, we may use the Welch (1951) version of the test statistic. The basic idea is to form a modified F-statistic that accounts for the unequal variances. Using the Cochran (1937) weight function,

$$w_g = n_g s_g^2 \quad (11.14)$$

where s_g^2 is the sample variance in subgroup g , we form the modified F-statistic

$$F = \frac{\sum_{g=1}^G w_g (\bar{x}_g - \bar{x})^2 / (G - 1)}{1 + \frac{2(G - 2)}{G^2 - 1} \sum_{g=1}^G \frac{1 - h_g}{n_g - 1}} \quad (11.15)$$

where h_g is a normalized weight and $\bar{x}$ is the weighted grand mean,

$$h_g = \frac{w_g}{\sum_{g=1}^G w_g} \quad (11.16)$$

$$\bar{x} = \sum_{g=1}^G h_g \bar{x}_g$$

The numerator of the adjusted statistic is the weighted between-group mean squares and the denominator is the weighted within-group mean squares. Under the null hypothesis of equal means but possibly unequal variances, F has an approximate F -distribution with $G - 1$, DF degrees-of-freedom, where

$$DF = \frac{G^2 - 1}{3 \sum_{g=1}^G \frac{1 - h_g^2}{n_g - 1}} \quad (11.17)$$

For tests with only two subgroups $G = 2$, EViews also reports the t -statistic, which is simply the square root of the F -statistic with one numerator degree of freedom. Note that for two groups, the Welch test reduces to the Satterthwaite (1946) test.

The top portion of the output contains the ANOVA results for a test of equality of means for LWAGE categorized by the four groups defined by the series MARRIED and UNION:

Test for Equality of Means of LWAGE
Categorized by values of MARRIED and UNION
Date: 08/18/09 Time: 16:31
Sample: 1 1000
Included observations: 1000

Method	df	Value	Probability
Anova F-test	(3, 996)	43.40185	0.0000
Welch F-test*	(3, 231.728)	45.31787	0.0000

*Test allows for unequal cell variances

Analysis of Variance

Source of Variation	df	Sum of Sq.	Mean Sq.
Between	3	36.66990	12.22330
Within	996	280.5043	0.281631
Total	999	317.1742	0.317492

The results show that there is strong evidence that LWAGE differs across groups defined by MARRIED and UNION; both the standard ANOVA and the Welch adjusted ANOVA statistics are in excess of 40, with probability values near zero.

The analysis of variance table shows the decomposition of the total sum of squares into the between and within sum of squares, where:

$$\text{Mean Sq.} = \text{Sum of Sq.} / \text{df}$$

The F -statistic is the ratio:

$$F = \text{Between Mean Sq.} / \text{Within Mean Sq.}$$

The bottom portion of the output provides the category statistics:

Category Statistics

UNION	MARRIED	Count	Mean	Std. Dev.	Std. Err. of Mean
0	0	305	1.993829	0.574636	0.032904
0	1	479	2.368924	0.557405	0.025468
1	0	54	2.387019	0.395838	0.053867
1	1	162	2.492371	0.380441	0.029890
	All	1000	2.275496	0.563464	0.017818

Median (Distribution) Equality Tests

EViews computes various rank-based nonparametric tests of the hypothesis that the subgroups have the same general distribution, against the alternative that at least one subgroup has a different distribution.

We note that the “median” category in which we place these tests is somewhat misleading since the tests focus more generally on the equality of various statistics computed across subgroups. For example, the Wilcoxon test examines the comparability of mean ranks across subgroups. The categorization reflects common usage for these tests and various textbook definitions. The tests should, of course, have power against median differences.

In the two group setting, the null hypothesis is that the two subgroups are independent samples from the same general distribution. The alternative hypothesis may loosely be defined as “the values [of the first group] tend to differ from the values [of the second group]” (see Conover 1980, p. 281 for discussion). See also Bergmann, Ludbrook and Spooren (2000) for a more precise analysis of the issues involved.

- Wilcoxon rank sum test . This test is computed when there are two subgroups. The test is identical to the Wilcoxon signed rank median test (“Median Test” on page 323) but the division of the series into two groups is based upon the values of the classification variable instead of the value of the observation relative to the median.
- Chi-square test for the median. This is a rank-based ANOVA test based on the comparison of the number of observations above and below the overall median in each subgroup. This test is sometimes referred to as the median test (Conover, 1980).

Under the null hypothesis, the median chi-square statistic is asymptotically distributed as a χ^2 with $G - 1$ degrees of freedom. EViews also reports Yates' continuity corrected statistic. You should note that the use of this correction is controversial (Sheskin, 1997, p. 218).

- Kruskal-Wallis one-way ANOVA by ranks . This is a generalization of the Mann-Whitney test to more than two subgroups. The idea behind the Mann-Whitney test is to rank the series from smallest value (rank 1) to largest, and to compare the sum of

the ranks from subgroup 1 to the sum of the ranks from subgroup 2. If the groups have the same median, the values should be similar.

EViews reports the asymptotic normal approximation to the U-statistic (with continuity and tie correction) and the p-values for a two-sided test. For details, see Sheskin (1997). The test is based on a one-way analysis of variance using only ranks of the data. EViews reports the χ^2 chi-square approximation to the Kruskal-Wallis test statistic (with tie correction). Under the null hypothesis, this statistic is approximately distributed as a χ^2 with $G - 1$ degrees of freedom (see Sheskin, 1997).

- van der Waerden (normal scores) test. This test is analogous to the Kruskal-Wallis test, except that we smooth the ranks by converting them in to normal quantiles (Conover, 1980). EViews reports a statistic which is approximately distributed as a χ^2 with $G - 1$ degrees of freedom under the null hypothesis.

The top portion of the output displays the test statistics:

Test for Equality of Medians of LWAGE			
Categorized by values of MARRIED and UNION			
Date: 07/31/07 Time: 01:29			
Sample: 1 1000			
Included observations: 1000			
Method	df	Value	Probability
Med. Chi-square	1	95.40100	0.0000
Adj. Med. Chi-square	1	92.99015	0.0000
Kruskal-Wallis	3	116.1189	0.0000
Kruskal-Wallis (tie-adj.)	3	116.1557	0.0000
van der Waerden	3	112.5606	0.0000

In addition to the test statistics and p-values, EViews reports values for the components of the test statistics for each subgroup of the sample. For example, the column labeled Mean Score contains the mean values of the van der Waerden scores (the smoothed ranks) for each subgroup.

Category Statistics

UNION	MARRIED	> Overall				
		Count	Median	Median	Mean Rank	Mean Score
0	0	305	1.906575	89	358.9082	-0.489333
0	1	479	2.327278	245	540.5073	0.161730
1	0	54	2.409132	35	568.6852	0.194415
1	1	162	2.525729	109	626.0556	0.380258
	All	1000	2.302585	478	500.5000	0.000322

Variance Equality Tests

Variance equality tests evaluate the null hypothesis that the variances in all G subgroups are equal against the alternative that at least one subgroup has a different variance. See Conover, et al. (1981) for a general discussion of variance equality testing.

- **F-test.** This test statistic is reported only for tests with two subgroups $G = 2$. First, compute the variance for each subgroup and denote the subgroup with the larger variance as L and the subgroup with the smaller variance as S . Then the F -statistic is given by:

$$F = \frac{s_L^2}{s_S^2} \quad (11.18)$$

where s_g^2 is the variance in subgroup g . This F -statistic has an F -distribution with $n_L - 1$ numerator degrees of freedom and $n_S - 1$ denominator degrees of freedom under the null hypothesis of equal variance and independent normal samples.

- **Siegel-Tukey test.** This test statistic is reported only for tests with two subgroups $G = 2$. The test assumes the two subgroups are independent and have equal medians. The test statistic is computed using the same steps as the Kruskal-Wallis test described above for the median equality tests ([“Median \(Distribution\) Equality Tests” on page 327](#)), with a different assignment of ranks. The ranking for the Siegel-Tukey test alternates from the lowest to the highest value for every other rank. The Siegel-Tukey test first orders all observations from lowest to highest. Next, assign rank 1 to the lowest value, rank 2 to the highest value, rank 3 to the second highest value, rank 4 to the second lowest value, rank 5 to the third lowest value, and so on. EViews reports the normal approximation to the Siegel-Tukey statistic with a continuity correction (Sheskin, 1997, p. 196–207).
- **Bartlett test.** This test compares the logarithm of the weighted average variance with the weighted sum of the logarithms of the variances. Under the joint null hypothesis that the subgroup variances are equal and that the sample is normally distributed, the test statistic is approximately distributed as a χ^2 with $G - 1$ degrees of freedom. Note, however, that the joint hypothesis implies that this test is sensitive to departures from normality. EViews reports the adjusted Bartlett statistic. For details, see Sokal and Rohlf (1995) and Judge, et al. (1985).
- **Levene test.** This test is based on an analysis of variance (ANOVA) of the absolute difference from the mean. The F -statistic for the Levene test has an approximate F -distribution with $G - 1$ numerator degrees of freedom and $N - G$ denominator degrees of freedom under the null hypothesis of equal variances in each subgroup (Levene, 1960).
- **Brown-Forsythe (modified Levene) test.** This is a modification of the Levene test in which we replace the absolute mean difference with the absolute median difference. The Brown-Forsythe test appears to be a superior in terms of robustness and power to

Levene (Conover, et al. (1981), Brown and Forsythe (1974a, 1974b), Neter, et al. (1996)).

As with the other equality tests, the top portion of the output displays the test results:

Test for Equality of Variances of LWAGE			
Categorized by values of UNION and MARRIED			
Date: 07/31/07 Time: 01:44			
Sample: 1 1000			
Included observations: 1000			
Method	df	Value	Probability
Bartlett	3	42.78468	0.0000
Levene	(3, 996)	16.08021	0.0000
Brown-Forsythe	(3, 996)	14.88998	0.0000

The bottom portion of the output shows the intermediate calculations used in forming the test statistic:

Category Statistics					
MARRIED	UNION	Count	Std. Dev.	Mean Abs. Mean Diff.	Mean Abs. Median Diff.
0	0	305	0.574636	0.479773	0.474788
0	1	54	0.395838	0.312659	0.311047
1	0	479	0.557405	0.445270	0.444236
1	1	162	0.380441	0.291903	0.290293
	All	1000	0.563464	0.423787	0.421424

Bartlett weighted standard deviation: 0.530689

Empirical Distribution Tests


EViews provides built-in Kolmogorov-Smirnov, Lilliefors, Cramer-von Mises, Anderson-Darling, and Watson empirical distribution tests. These tests are based on the comparison between the empirical distribution and the specified theoretical distribution function. For a general description of empirical distribution function testing, see D'Agostino and Stephens (1986).

You can test whether your series is normally distributed, or whether it comes from, among others, an exponential, extreme value, logistic, chi-square, Weibull, or gamma distribution. You may provide parameters for the distribution, or EViews will estimate the parameters for you.

To carry out the test, simply double click on the series and select View/Descriptive Statistics & Tests/Empirical Distribution Tests... from the series window.

There are two tabs in the dialog. The Test Specification tab allows you to specify the parametric distribution against which you want to test the empirical distribution of the series. Simply select the distribution of interest from the drop-down menu. The small display window will change to show you the parameterization of the specified distribution.

You can specify the values of any known parameters in the edit field or fields. If you leave any field blank, EViews will estimate the corresponding parameter using the data contained in the series.



The Estimation Options tab provides control over any iterative estimation that is required. You should not need to use this tab unless the output indicates failure in the estimation process. Most of the options in this tab should be self-explanatory. If you select User-specified starting values, EViews will take the starting values from the C coefficient vector.

It is worth noting that some distributions have positive probability on a restricted domain. If the series data take values outside this domain EViews will report an out-of-range error. Similarly, some of the distributions have restrictions on domain of the parameter values. If you specify a parameter value that does not satisfy this restriction, EViews will report an error message.

The output from this view consists of two parts. The first part displays the test statistics and associated probability values.

Empirical Distribution Test for LWAGE
Hypothesis: Normal
Date: 08/18/09 Time: 16:51
Sample: 1 1000
Included observations: 1000

Method	Value	Adj. Value	Probability
Lilliefors (D)	0.033172	NA	0.0115
Cramer-von Mises (W2)	0.132835	0.132902	0.0402
Watson (U2)	0.132577	0.132644	0.0288
Anderson-Darling (A2)	1.149731	1.150596	0.0052

Here, we show the output from a test for normality where both the mean and the variance are estimated from the series data. The first column, "Value", reports the asymptotic test statistics while the second column, "Adj. Value", reports test statistics that have a finite

sample correction or adjusted for parameter uncertainty (in case the parameters are estimated). The third column reports p-value for the adjusted statistics.

All of the reported EViews p-values will account for the fact that parameters in the distribution have been estimated. In cases where estimation of parameters is involved, the distributions of the goodness-of-fit statistics are nonstandard and distribution dependent, so that EViews may report a subset of tests and/or only a range of p-value. In this case, for example, EViews reports the Lilliefors test statistic instead of the Kolmogorov statistic since the parameters of the normal have been estimated. Details on the computation of the test statistics and the associated p-values may be found in Anderson and Darling (1952, 1954), Lewis (1961), Durbin (1970), Dallal and Wilkinson (1986), Davis and Stephens (1989), Csörgö and Faraway (1996) and Stephens (1986).

Method: Maximum Likelihood - d.f. corrected (Exact Solution)

Parameter	Value	Std. Error	z-Statistic	Prob.
MU	2.275496	0.017818	127.7056	0.0000
SIGMA	0.563464	0.012606	44.69899	0.0000
Log likelihood	-844.7868	Mean dependent var.		2.275496
No. of Coefficients	2	S.D. dependent var.		0.563464

The second part of the output table displays the parameter values used to compute the theoretical distribution function. Any parameters that are specified to estimate are estimated by maximum likelihood (for the normal distribution, the ML estimate of the standard deviation is subsequently degree of freedom corrected if the mean is not specified a priori). For parameters that do not have a closed form analytic solution, the likelihood function is maximized using analytic first and second derivatives. These estimated parameters are reported with a standard error and p-value based on the asymptotic normal distribution.

One-Way Tabulation

This view tabulates the series in ascending order, optionally displaying the counts, percentage counts, and cumulative counts. When you select View/One-Way Tabulation... the Tabulate Series dialog box will be displayed.

The Output options control which statistics to display in the table. You should specify the NA handling and the grouping options as described above in the discussion of [“Stats by Classification”](#) on page 318

Tabulate Series

Output

- ☒ Show Count
- ☒ Show Percentages
- ☒ Show Cumulatives

Group into bins if

- ☒ # of values > 100
- ☒ Avg. count < 2
- Max # of bins: 5

NA handling

- ☐ Treat NAs as category

OK Cancel

Series: GRADE Workfile: CPS88::Cps881

View Proc Object Properties Print Name Freeze Sample Genr Sheet Gr

Tabulation of GRADE
Date: 08/13/09 Time: 19:41
Sample: 1 1000
Included observations: 1000
Number of categories: 18

Value	Count	Percent	Cumulative Count	Cumulative Percent
0	1	0.10	1	0.10
2	1	0.10	2	0.20
3	1	0.10	3	0.30
4	2	0.20	5	0.50
5	3	0.30	8	0.80
6	6	0.60	14	1.40
7	8	0.80	22	2.20
8	17	1.70	39	3.90
9	30	3.00	69	6.90
10	45	4.50	114	11.40
11	40	4.00	154	15.40
12	412	41.20	566	56.60
13	76	7.60	642	64.20

Cross-tabulation (n -way tabulation) is also available as a group view. See ["N-Way Tabulation" on page 404](#) for details.

Correlogram

This view displays the autocorrelation and partial autocorrelation functions up to the specified order of lags. These functions characterize the pattern of temporal dependence in the series and typically make sense only for time series data. When you select View/Correlogram... the Correlogram Specification dialog box appears.

You may choose to plot the correlogram of the raw series (level) x , the first difference $d(x)=x-x(-1)$, or the second difference

$$d(x)-d(x(-1)) = x-2x(-1)+x(-2)$$

of the series.

You should also specify the highest order of lag to display the correlogram; type in a positive integer in the field box. The series view displays the correlogram and associated statistics:

Correlogram Specification

Correlogram of

☒ Level

☐ 1st difference


☐ 2nd difference

OK

Lags to include

36

Cancel



Autocorrelations (AC)

The autocorrelation of a series Y at lag k is estimated by:

$$t_k \quad \frac{\sum_{t=k+1}^T (Y_t - \bar{Y})(Y_{t-k} - \bar{Y})}{\sum_{t=1}^T (Y_t - \bar{Y})^2} \quad (11.19)$$

where $\bar{Y}$ is the sample mean of Y . This is the correlation coefficient for values of the series k periods apart. If t_1 is nonzero, it means that the series is first order serially correlated. If t_k dies off more or less geometrically with increasing lag k , it is a sign that the series obeys a low-order autoregressive (AR) process. If t_k drops to zero after a small number of lags, it is a sign that the series obeys a low-order moving-average (MA) process. See [“Serial Correlation Theory” on page 85](#) of User’s Guide II for a more complete description of AR and MA processes.

Note that the autocorrelations estimated by EViews, which follow those in the literature, differ slightly from the theoretical definition of the autocorrelation:

$$t_k \quad \frac{\sum_{t=k+1}^T (Y_t - \bar{Y})(Y_{t-k} - \bar{Y}_{t-k})}{\sum_{t=1}^T (Y_t - \bar{Y})^2} \quad (11.20)$$

where $\bar{Y}_{t-k} = \frac{1}{T-k} \sum_{t=k+1}^T Y_{t-k}$. The difference arises since, for computational simplicity, EViews employs the same overall sample mean $\bar{Y}$ as the mean of both Y_t and Y_{t-k} . While both formulations are consistent estimators, the EViews formulation biases the result toward zero in finite samples.

The dotted lines in the plots of the autocorrelations are the approximate two standard error bounds computed as $\pm 2/\sqrt{T}$. If the autocorrelation is within these bounds, it is not significantly different from zero at (approximately) the 5% significance level.

Partial Autocorrelations (PAC)

The partial autocorrelation at lag k is the regression coefficient on Y_{t-k} when Y_t is regressed on a constant, $Y_{t-1}, \dots, Y_{t-k}$. This is a partial correlation since it measures the correlation of Y values that are k periods apart after removing the correlation from the intervening lags. If the pattern of autocorrelation is one that can be captured by an autoregression of order less than k , then the partial autocorrelation at lag k will be close to zero.

The PAC of a pure autoregressive process of order p , $AR(p)$, cuts off at lag p , while the PAC of a pure moving average (MA) process asymptotes gradually to zero.

EViews estimates the partial autocorrelation at lag k recursively by

$$f_k = \begin{cases} t_1 & \text{for } k = 1 \\ \frac{t_k - \sum_{j=1}^{k-1} f_{k-1,j} t_{k-j}}{1 - \sum_{j=1}^{k-1} f_{k-1,j} t_{k-j}} & \text{for } k \geq 2 \end{cases} \quad (11.21)$$

where t_k is the estimated autocorrelation at lag k and where,

$$f_{k,j} = f_{k-1,j} - f_k f_{k-1,k-j}. \quad (11.22)$$

This is a consistent approximation of the partial autocorrelation. The algorithm is described in Box and Jenkins (1976, Part V, Description of computer programs). To obtain a more precise estimate of f_k , simply run the regression:

$$Y_t = b_0 + b_1 Y_{t-1} + \dots + b_{k-1} Y_{t-k+1} + f_k Y_{t-k} + e_t \quad (11.23)$$

where e_t is a residual. The dotted lines in the plots of the partial autocorrelations are the approximate two standard error bounds computed as $\pm 2/\sqrt{T}$. If the partial autocorrelation is within these bounds, it is not significantly different from zero at (approximately) the 5% significance level.

Q-Statistics

The last two columns reported in the correlogram are the Ljung-Box Q-statistics and their p-values. The Q-statistic at lag k is a test statistic for the null hypothesis that there is no autocorrelation up to order k and is computed as:

$$Q_{LB} = \frac{T}{T-1} \sum_{j=1}^k \frac{t_j^2}{T-j} \quad (11.24)$$

where t_j is the j -th autocorrelation and T is the number of observations. If the series is not based upon the results of ARIMA estimation, then under the null hypothesis, Q is asymptotically distributed as a χ^2 with degrees of freedom equal to the number of autocorrelations. If the series represents the residuals from ARIMA estimation, the appropriate degrees of freedom should be adjusted to represent the number of autocorrelations less the number of AR and MA terms previously estimated. Note also that some care should be taken in interpreting the results of a Ljung-Box test applied to the residuals from an ARMAX specification (see Dezhbaksh, 1990, for simulation evidence on the finite sample performance of the test in this setting).

The Q -statistic is often used as a test of whether the series is white noise. There remains the practical problem of choosing the order of lag to use for the test. If you choose too small a lag, the test may not detect serial correlation at high-order lags. However, if you choose too large a lag, the test may have low power since the significant correlation at one lag may be diluted by insignificant correlations at other lags. For further discussion, see Ljung and Box (1979) or Harvey (1990, 1993).

Long-run Variance

You may compute estimates of the long-run variance of a series using this view. See [Appendix E. “Long-run Covariance Estimation,” beginning on page 775](#) of User’s Guide II for a discussion of the long-run variance and role of this statistic in modern econometric analysis.

The group object version of this view, which is almost identical to the series object version, is described in detail in [“Long-run Covariance” on page 422](#).

Unit Root Test

This view carries out the Augmented Dickey-Fuller (ADF), GLS transformed Dickey-Fuller (DFGLS), Phillips-Perron (PP), Kwiatkowski, et. al. (KPSS), Elliot, Richardson and Stock (ERS) Point Optimal, and Ng and Perron (NP) unit root tests for whether the series (or it’s first or second difference) is stationary.

In the panel context, this view carries out Levin, Lin and Chu, Breitung, Im, Pesaran and Shin, Fisher-type tests using ADF and PP test (Maddala and Wu, and Choi), and Hadri panel unit root tests.

See [“Unit Root Testing” on page 379](#) of User’s Guide II for a discussion of stationary and nonstationary time series and additional details on how to carry out the unit roots tests in EViews.

Variance Ratio Test

The variance ratio test view EViews allows you to perform the Lo and MacKinlay variance ratio test to determine whether differences in a series are uncorrelated, or follow a random walk or martingale property.

See [“Variance Ratio Test” on page 402](#) of User’s Guide II for a discussion of the Lo and MacKinlay test and other variance ratio tests that you may perform using the series view.

BDS Independence Test

This view carries out the BDS test for independence, as described in Brock, Dechert, Scheinkman and LeBaron (1996).


The BDS test is a portmanteau test for time based dependence in a series. It can be used for testing against a variety of possible deviations from independence, including linear dependence, non-linear dependence, or chaos. The test can be applied to a series of estimated residuals to check whether the residuals are independent and identically distributed (iid). For example, the residuals from an ARMA model can be tested to see if there is any non-linear dependence in the series after the linear ARMA model has been fitted.

See [“BDS Independence Test” on page 411](#) of User’s Guide II for a description of the BDS test.

Label

This view displays a description of the series object.

You can edit any of the field cells in the series label, except the Last Update cell which displays the date/time the series was last modified. Each field contains a single line, except for the Remarks and History fields which can contain up to 20 comment lines. Note that if you insert a line, the last (of the 20) line of these fields will be deleted.



The Name is the series name as it appears in the workfile; you can rename your series by editing this cell. If you fill in the Display Name field, this name may be used in tables and graphs in place of the standard objectname. Unlike ordinary object names, Display Names may contain spaces and preserve capitalization (upper and lower case letters).


See [Chapter 10. “EViews Databases,” on page 267](#) for further discussion of label fields and their use in Database searches.

Properties

Clicking on the Properties button on the series toolbar provides access to the dialog controlling various series properties.

There are several tabs in the dialog. The first tab, labeled Display, allows you to set the default display characteristics for the series (see [“Changing the Spreadsheet Display” on page 82](#)). The Values tab may be used to define or modify a formula, turning the series into an auto-updating series, or to freeze the series values at their current levels (see [“Defining an Auto-Updating Series” on page 150](#)). The last Value Map tab should be used to assign value maps to the series (see [“Value Maps” on page 169](#)).

In dated workfiles, the Freq Conversion tab will also be displayed. You may use this tab to set the default frequency conversion settings for the series. Recall that when you fetch a series from an EViews database or when you copy a series to a workfile or workfile page with a different frequency, the series will automatically be converted to the frequency of the destination workfile. The conversion options view allows you to set the method that will be used to perform these conversions (see [“Reading EViews Data using Other Applications” on page 112](#)).



Each series has a default up and down frequency conversion method. By default, the series will take its settings from the EViews global options (see [“Frequency Conversion” on page 624](#)). This default series setting is labeled EViews default. You may, of course, override these settings for a given series. Here, instead of using the global defaults, the high to low conversion method is set to Sum observations without propagating NAs.

Series Procs Overview

Series procedures may be used to generate new series that are based upon the data in the original series. You may generate new series using expressions, or you may generate series by classifying the original series.

When working with numeric series, you may also use series procs to resample from the original series, to perform seasonal adjustment or exponential smoothing, to filter the series using the Hodrick-Prescott or band-pass filters, or to output data used in constructing various distribution graphs such as histograms and kernel density plots.

For alpha series you may use a series proc to make a value-mapped numeric series. EViews will create a new numeric series and value-map so that each value in the numeric series is mapped to the original alpha series value.

Generate by Equation

This is a general procedure that allows you to create new series by using expressions to transform the values in the existing series. The rules governing the generation of series are explained in detail in [“Series Expressions” on page 133](#)

It is equivalent to using the `genr` command.

Generate by Classification

The series classification procedure generates a categorical series using ranges, or bins, of values in the numeric source series. You may assign individuals into one of k classes based on any of the following: equally sized ranges, ranges defined by quantile values, arbitrarily defined ranges. A variety of options allow you to control the exact definition of the bins, the method of encoding, and the assignment of value maps to the new categorical series.

We illustrate these features using data on the 2005 Academic Performance Index (API) for California public schools and local educational agencies (“Api05btx.WF1”). The API is a numeric index ranging from 200 to 1000 formed by taking the weighted average of the student results from annual statewide testing at grades two through eleven.

The series API5B contains the base API index. Open the series and select Proc/Generate by Classification... to display the dialog. For the moment, we will focus on the Output and the Specification sections.

Output

In the Output section you will list the name of the target series to hold the classifications, and optionally, the name of a valmap object to hold information about the mapping. Here, we will save the step size classification into the series API5B_CT and save the mapping description in API5B_MP. If the classification series already exists, it will be overwritten; if an object with the map name already exists, the map will be saved in the next available name ("API5B_MP01", etc.).

Specification

The Specification section is where you will define the basic method of classification. The Method combo allows you to choose from the four methods of defining ranges: Step Size, Number of Bins, Quantile Values, Limit Values. The first two methods specify equal sized bins, the latter two define variable sized bins.

Step Size

We will begin by selecting the default Step Size method and entering "100" and "200" for the Step size and Grid start edit fields. The step size method defines a grid of bins of fixed size (the step size) beginning at the specified grid start, and continuing through the grid end. In this example, we have specified a step size of 100, and a Grid start value of 200. The Grid end is left blank so EViews uses the data maximum extended by 5%, ensuring that the rightmost bin extends beyond the data values. These settings define a set of ranges of the form: [100, 200), [200, 300), ..., [1000, 1100). Note that by default the ranges are closed on the left so that we say x lies in the first bin if $100 \leq x < 200$.

Click on OK to accept these settings, then display the spreadsheet view of API5B_CT. We see that observations 1 and 3 fall in the [500, 600) bin, while observations 4 and 5 fall in the [400, 600) bin. Observations 2 and 6 were NAs in the original data and those values have been carried over to the classification.

API5B_CT			
1	[500, 600)		
2	NA		
3	[500, 600)		
4	[400, 500)		
5	[400, 500)		
6	NA		
7			

Keep in mind that since we have created both the classification series and a value map, the values displayed in the spreadsheet are mapped values, not the underlying data. To see the underlying classification data, you may go to the series toolbar and change the Default setting to Raw Data.

Opening the valmap API5B_MP, we see that the actual data in API5B_CT are integer values from 1 to 9, and that observations 1 and 3 are coded as 4s, while observations 4 and 5 are coded as 3s.

Value	Label
<blank>	<blank>
< NA >	NA
1	[200, 300)
2	[300, 400)
3	[400, 500)
4	[500, 600)
5	[600, 700)
6	[700, 800)
7	[800, 900)
8	[900, 1000)
9	[1000, 1100)

Number of Bins

The second method of creating equal sized bins is to select Number of Bins in the Method combo. The label for the second edit field will change from "Bin size" to "# of bins", prompting you for an integer value. EViews will define a set of bins by dividing the grid range into k equal sized bins. For example, specifying 9 bins beginning at 200 and ending at 1100 generates a classification that is the same as the one specified using the step size of 100.

Quantile Values

One commonly employed method of classifying observations is to divide the data into quantiles. In the previous example, each school was assigned a value 1 to 9 depending on which of 9 equally sized bins contained its API. We may instead wish to assign each school an index for its decile. In this way we can determine whether a given school falls in the lowest 10% of schools, second lowest 10%, etc.

To create a decile classification, display the dialog, select Quantile Values from the Method combo, and enter the number of quantile values, in this case “10”.

We see that the first 4 (non-NA) values are all in the first decile (<583.8), while observations 7 and 8 lie in the eighth decile [780, 815). As before, these values are the mapped values; the underlying values are encoded with integer values from 1 to 10.

API5B_CT	
Last updated: 08/13/09 - 20:02	
Created by api5b.classify 100	
Created by api5b.classify(method=quants, q=r) 10	
1	< 583.8
2	NA
3	< 583.8
4	< 583.8
5	< 583.8
6	NA
7	[780, 815)
8	[780, 815)
9	
10	

It is worth emphasizing that the mapped values are text representations of the quantile values, akin to labels, and will generally not be displayed in full precision.

Limit Values

You may also define your bins by providing an arbitrary set of two or more limit points. Simply select Limit Values from the Method combo and provide a list of numeric values, scalars, or vectors.

Value	Label
<blank>	<blank>
< NA >	NA
1	< 583.8
2	[583.8, 639)
3	[639, 671)
4	[671, 698)
5	[698, 724)
6	[724, 751)
7	[751, 780)
8	[780, 815)
9	[815, 863)
10	>= 863

EViews will sort the numbers and define a set of bins using those limits.

Options

EViews provides various options that allow you to fine tune the classification method or to alter the encoding of classification values.

Encoding

The combo box labeled Encoding allows you to select different methods of assigning values to the classified observations. By default, EViews classifies observations using the integers 1, 2, etc. so that the observations falling in the first bin are assigned the value 1, observations in the second bin are assigned 2, and so forth.

In addition to the default Index (0, 1, 2,...) method, you may elect to use the Left edges of bins, the Right edges of bins, or the Midpoints of bins. Each of these encoding methods

should be self-explanatory. Note that index encoding is the only method available for classification by quantile values.

Value maps are not created for classifications employing non-index encoding.

NA classification

By default, observations in the original series which are NA are given the value NA in the classification series. If you treat the NA as a category by checking Include NAs in classification, EViews will assign NAs the index value of 0 in the classification, and will map this value to the label "NA".

For example, re-running our first example (step size of 100, a grid start value of 200) but keeping NAs, we have the following raw data. Note that the mapped values will be identical to those from the earlier example, so we have switched the series to Raw Data to see the values for NA:

API5B_CT	
Last updated: 08/14/09 - 14:24	
Created by api5b.classify(keepna) 100	
1	4.000000
2	0.000000
3	4.000000
4	3.000000
5	3.000000
6	0.000000
7	6.000000
8	

We see that the observations 2 and 6, which were missing values in the original data, are encoded with the index value 0.

Out-of-Range Values

You may instruct EViews to generate an error if it encounters an observation that does not fall into one of the specified bins; by default, observations that lie outside the bin range are simply assigned an NA.

This option is irrelevant for quantile value classification.

Right-closed Bins

Bins are left-closed by default, so that x lies in the bin defined by a and b if $a \leq x < b$. To change the non-strict inequality from the left to the right $a < x \leq b$ you must instruct EViews to use right-closed bins by checking the box Right-closed bin intervals (a, b]. This setting should have little effect, if any, if your data are reasonably continuous.

A Couple of Warnings

In determining whether an observation is in a particular interval, EViews performs comparisons of real numbers to assess, for example, whether $a \leq x$ and whether $x \leq b$. We urge you to exercise caution in cases where a and b are finite precision representations of real numbers.

To take a specific example, suppose that we wish to divide the interval from 0 to 1 into bins of size 0.1 (so that our limit points are 0.1, 0.2, 0.3, etc.). Since 0.1 cannot be represented in floating point by a computer, comparisons will be made with numbers that are close to, but not exactly equal to 0.1. As a result, when there are data values approximately equal to the limit points, classifications may behave unexpectedly since they are based on a comparison of two floating point numbers.

A related issue occurs when you classify by number of bins, and set the start or end values equal to the data minimum or maximum. In this situation, depending upon whether you have selected left or right-closed intervals, observations with values equal to the start or end may fall out-of-range.

To illustrate this issue, we extend our example by assuming that we wish to divide the 0–1 range into right-closed bins. Each bin will be of the form $[0.1(i-1), 0.1i]$, with the first interval given by $(0, 1]$. Now consider classifying those data values that are exactly equal to 0, and note that these values are out-of-range since they lie outside the first interval. The same is true for observations equal to 1 if we have defined left-closed bins. The comparison is more complex if the relevant endpoint is real valued since the out-of-range status would depend upon a floating point comparison.

The obvious recommendation in this latter case are that: (1) you specify at most only one of range start and range end at the data extremes and (2) if you set either the start or end to the corresponding data extreme, you define the intervals so that they are closed on that end (i.e., starts that equal the minimum have left-closed intervals, and ends that equal the maximum have right-closed intervals) and you set the range so that it extends past the other extreme. Our first example above adopts this strategy, setting the low value to the data minimum (200), setting the step size, and leaving the upper limit unspecified.

More generally, we urge you to exercise caution when defining intervals with real-valued limits.

Resample

The series resampling procedure selects from the observations in a series to create a new series (the resampled series). You may draw your new sample with replacement (allow a given observation to be drawn multiple times) or without replacement. When you select Proc/Resample... from the series window, you will be prompted to specify various options.

Input Sample

Describes the sample from which observations are to be drawn. The default is the current workfile sample.

If you select the Draw without replacement option, each row will be drawn at most once. This option requires the input sample to be at least as large as the output sample. If you do not select this option, each row will be drawn with replacement.

Output Sample

Specifies the sample into which the resampled series will be saved. Any value outside the output sample will not be changed. The default output sample is the current workfile sample. If you select the Draw without replacement option, the output sample cannot be larger than the input sample.

NA Handling

The default Include NAs in draws instructs EViews to draw from every observation in the input sample, including those that contain missing values. Alternatively, you may select the Exclude NAs from draws option so that you draw only from observations in the input sample that do not contain any missing values. Finally, the Exclude NAs from draws but copy NA rows to output option first copies matching observations in the input sample that contain missing values to the output sample. The remaining rows of the output sample are then filled by drawing from observations in the input sample that do not contain any missing values. This option keeps observations with missing values fixed and resamples those that do not contain any missing values.

Series Name

The new series will be named using the specified series name. You may provide a series name or a wildcard expression. If you use a wildcard expression, EViews will substitute the existing series name in place of the wildcard. For example, if you are sampling from the series X and specify “*_SMP” as the output series, EViews will save the results in the series X_SMP. You may not specify a destination series that is the same as the original series.

If another series with the specified name exists in the workfile, the existing values in the output sample will be overwritten with the resampled values. Any values outside the output sample will remain unchanged. If there is a non-series object with the specified name, EViews will return an error message.

Because of these naming conventions, your original series cannot be an auto-series. For example, if the original series is $X(-1)$ or $\text{LOG}(X)$, EViews will issue an error. You will have to generate a new series, say by setting $\text{XLAG} = X(-1)$ or $\text{LOGX} = \text{LOG}(X)$, and then resample from the newly generated series.

Weighting

By default, the procedure draws from each row in the input sample with equal probabilities. If you want to attach different probabilities to the rows (importance sampling), you can specify a name of an existing series that contains weights that are proportional to the desired probabilities in each row. The weight series must have non-missing non-negative values in the input sample, but the weights need not add up to 1 since EViews will normalize the weights.

Block Length

By default, sets the block length to 1, meaning that we draw one observation at a time from the input sample. If you specify a block length larger than 1, EViews will draw blocks of consecutive rows of the specified length. The blocks drawn in the procedure form a set of overlapping moving blocks in the input sample. The drawn blocks will be appended one after the other in the output series until it fills the output sample (the final block will be truncated if the block size is not an integer multiple of the output sample size). Block resampling with a block length larger than 1 makes the most sense when resampling time series data.

Block resampling requires a continuous output sample. Therefore a block length larger than 1 cannot be used when the output sample contains “gaps” or when you have selected the Exclude NAs from draws but copy NA rows to output option. If you choose the Exclude NAs from draws option and the block length is larger than 1, the input sample will shrink in the presence of NAs in order to ensure that there are no missing values in any of the drawn blocks.

Interpolate

The interpolation procedure for a series fills in missing values, or NAs, within a series by interpolating from values that are non-missing. EViews offers a number of different algorithms for performing the interpolation: Linear, Log-Linear, the Catmull-Rom Spline, and the Cardinal Spline.

The Linear interpolation method simply computes a linear approximation based on the previous non-missing value and the next non-missing value. The interpolated value is then calculated as:

$$IV_{\text{Lin}} = (1 - I) P_{i-1} + I P_{i+1} \quad (11.25)$$

where P_{i-1} is the previous missing value, P_{i+1} is the next non-missing value, and I is the relative position of the missing value divided by the total number of missing values in a row.

Thus if you have a single NA, then the interpolated value will be half way between the previous value and the next value. If you have two NAs in a row, the first will be interpolated as 1/3 of the distance between the previous value and the next. The second value will be interpolated as 2/3 of the distance.

Log-linear interpolation is calculated in the same way as the Linear method, but the series values are logged before the calculation is made, then the interpolated value is exponentiated. If the source series contains negative values before and after the missing values, then the absolute value is used for interpolation, with the result being negated. If the values to either side of the missing values contain both a negative and a positive number, the interpolation routine will return an NA. Thus the interpolated value is calculated as:

$$IV_{pos} = \text{EXP} \left(1 - I \log P_{i-1} + I \log P_{i+1} \right) \quad (11.26)$$

$$IV_{neg} = -\text{EXP} \left(1 - I \log -P_{i-1} + I \log -P_{i+1} \right) \quad (11.27)$$

Note that both the linear and log-linear routines will return an NA if there are no previous or next non-missing values available – i.e. if the first observation in the sample is an NA, it will not be interpolated since there is no previous value available.

The Cardinal Spline is based on the previous two non-missing values, and the next two non-missing values, and tries to fit the missing data to a non-linear, or curved, pattern. Denoting P_{i-2} and P_{i-1} as the previous two non-missing values, and P_{i+1} and P_{i+2} as the next two non-missing values, the interpolated value is calculated as:

$$IV_{CS} = \frac{2I^3 - 3I^2}{2I^3 - 3I^2 P_{i-1} + 1 - t} P_{i-1} + \frac{1 - t}{I^3 - 2I^2 + I} P_{i+1} - \frac{1 - t}{I^3 - I^2} P_{i+2} - \frac{1 - t}{I^3 - I^2} P_{i-2} \quad (11.28)$$

where t is called a tension parameter and affects the curvature of the spline.

The Catmull-Rom Spline is a special case of the Cardinal Spline, with the tension parameter, t , set at 0.

Note that as with the linear and log-linear routines, both spline routines will return an NA if either P_{i-1} or P_{i+1} are missing. However if P_{i-2} is missing, it is simply set equal to P_{i-1} , and if P_{i+2} is missing, it is set equal to P_{i+1} .

For example, the following series is interpolated using Linear and Log-Linear interpolation:

Obs	Data	I	Linear	Log-Linear	Catmull-Rom
1	-1	--	-1	-1	-1

2	-0.8	--	-0.8	-0.8	-0.8
3	NA	1/2	-0.6	-0.56569	-0.4750
4	-0.4	--	-0.4	-0.4	-0.4
5	NA	1/3	-0.66667	-0.56769	-0.60741
6	NA	2/3	-0.93333	-0.83203	-0.90370
7	-1.2	--	-1.2	-1.2	-1.2

For this series, the first missing value is at observation 3. The linear interpolation of this value is simply 1/2 of the value of observation two (the previous non-missing observation) plus 1/2 of the value of observation four (the next non-missing observation), i.e. $1/2 \cdot -0.8 + 1/2 \cdot (-0.4)$. The second missing value is at observation five, and is equal to 2/3 of the value of observation four, plus $(1-1/3)$ of the value of observation 7, i.e., $2/3 \cdot (-0.4) + 1/3 \cdot (-1.2)$. The final interpolated value, at observation six, is calculated as $1/3 \cdot (-0.4) + 2/3 \cdot (-1.2)$

For log-linear interpolation, the calculated value for observation three is equal to the negative of the exponent of 1/2 of the logged value at observation two (negated since it is negative) plus 1/2 of the value of observation five (negated):

$$-\exp \frac{1}{2} \log 0.8 \quad \frac{1}{2} \log 0.4 \quad \frac{S}{C} \quad (11.29)$$

The calculations for observations five and six, respectively, are:

$$-\exp \frac{2}{3} \log 0.4 \quad \frac{1}{3} \log 1.2 \quad \frac{S}{C} \quad (11.30)$$

$$-\exp \frac{1}{3} \log 0.4 \quad \frac{2}{2} \log 1.2 \quad \frac{S}{C} \quad (11.31)$$


For the Catmull-Rom spline, the calculated value for observation three is equal to:

$$\begin{aligned} & 2 \frac{1}{2} \frac{S^3}{C^3} - 3 \frac{1}{2} \frac{S^2}{C^2} \frac{S}{C} - 0.8 \quad \frac{1}{2} \frac{S^3}{C^3} - 2 \frac{1}{2} \frac{S^2}{C^2} \frac{S}{C} - 0.4 \quad \frac{1}{2} \frac{S}{C} - 1 \quad (11.32) \\ & 2 \frac{1}{2} \frac{S^3}{C^3} - 3 \frac{1}{2} \frac{S^2}{C^2} \frac{S}{C} - 0.4 \quad \frac{1}{2} \frac{S^3}{C^3} - \frac{1}{2} \frac{S^2}{C^2} \frac{S}{C} - 1.2 \quad \frac{1}{2} \frac{S}{C} - 0.8 \quad -0.4750 \end{aligned}$$

The values at observations five and six are calculated similarly, although note that both for both observations, P_{i-1} and P_{i-2} are equal to -1.2.

To perform interpolation from within EViews, open up the series, then click on Proc/Interpolate... which will open up the Interpolation dialog. The Interpolation method box lets you select which interpolation method you would like to use.

The Output series name box lets you enter a name for the output series in which the interpolated values will be stored. If left blank an untitled series will be created.



The Sample box lets you select a sample over which the interpolation will run. If left blank, the default workfile sample will be used. Note that observations outside of the selected sample will not be interpolated, nor will they be used as part of the interpolation calculations. The checkbox labeled Insert source series for out of sample observations controls whether the output series will be filled with the source series values for out of sample observations, or will be filled with NAs.

Seasonal Adjustment

Time series observed at quarterly and monthly frequencies often exhibit cyclical movements that recur every month or quarter. For example, ice cream sales may surge during summer every year and toy sales may reach a peak every December during Christmas sales. Seasonal adjustment refers to the process of removing these cyclical seasonal movements from a series and extracting the underlying trend component of the series.

The EViews seasonal adjustment procedures are available only for quarterly and monthly series. To seasonally adjust a series, click on Proc/Seasonal Adjustment in the series window toolbar and select the adjustment method from the submenu entries (Census X12, X11 (Historical), Tramo/Seats or Moving Average Methods).

Census X12

EViews provides a convenient front-end for accessing the U.S. Census Bureau's X12 seasonal adjustment program from within EViews. The X12 seasonal adjustment program X12A.EXE is publicly provided by the Census and is installed in your EViews directory.

When you request X12 seasonal adjustment from EViews, EViews will perform all of the following steps:

- write out a specification file and data file for the series.

- execute the X12 program in the background, using the contents of the specification file.
- read back the output file and saved data into your EViews workfile.

The following is a brief description of the EViews menu interface to X12. While some parts of X12 are not available via the menus, EViews also provides a more general command interface to the program (see [x12](#) (p. 471) in the Command and Programming Reference

Users who desire a more detailed discussion of the X12 procedures and capabilities should consult the Census Bureau documentation. The full documentation for the Census program, X12-ARIMA Reference Manual can be found in the “docs” subdirectory of your EViews installation directory in the PDF files “Finalpt1.PDF” and “Finalpt2.PDF”.

To call the X12 seasonal adjustment procedure, select Proc/Seasonal Adjustment/Census X12... from the series window menu. A dialog will open with several tabs for setting the X12 options for seasonal adjustment, ARIMA estimation, trading day/holiday adjustment, outlier handling, and diagnostic output.


It is worth noting that when you open the X12 dialog, the options will be set to those from the previously executed X12 dialog. One exception to this rule is the outlier list in the Outliers tab, which will be cleared unless the previous seasonal adjustment was performed on the same series.

Seasonal Adjustment Options

X11 Method specifies the form of the seasonal adjustment decomposition. A description of the four choices can be found in pages 75-77 of the X12-ARIMA Reference Manual. Be aware that the Pseudo-additive method must be accompanied by an ARIMA specification (see [“ARIMA Options” on page 352](#) for details on specifying the form of your ARIMA).

Note that the multiplicative, pseudo-additive, and log-additive methods do not allow for zero or negative data.

The Seasonal Filter drop-down box allows you to select a seasonal moving average filter to be used when estimating the seasonal factors. The default Auto (X12 default) setting is an automatic procedure based on the moving seasonality ratio. For details on the remaining seasonal filters, consult the X12-ARIMA Reference Manual. To



approximate the results from the previous X11 program's default filter, choose the X11-default option. You should note the following:

- The seasonal filter specified in the dialog is used for all frequencies. If you wish to apply different filters to different frequencies, you will have to use the more general X12 command language described in detail in [x12 \(p. 471\)](#) in the Command and Programming Reference
- X12 will not allow you to specify a 3 – 15 seasonal filter for series shorter than 20 years.
- The Census Bureau has confirmed that the X11-default filter option does not produce results which match those obtained from the previous version of X11. The difference arises due to changes in extreme value identification, replacement for the latest values, and the way the end weights of the Henderson filter is calculated. For comparability, we have retained the previous (historical) X11 routines as a separate procedure (see [“Census X11 \(Historical\)” on page 358](#)). Please note that the old X11 program is year 2000 compliant only through 2100 and supports only DOS 8.3 format filenames.

The Trend Filter (Henderson) settings allow you to specify the number of terms in the Henderson moving average used when estimating the trend-cycle component. You may use any odd number greater than 1 and less than or equal to 101. The default is the automatic procedure used by X12.

You must provide a base name for the series stored from the X12 procedure in the Name for Adjusted Series/Component Series to Save edit box. To save a series returned from X12 in the workfile, click on the appropriate check box. The saved series will have the indicated suffix appended to the base name. For example, if you enter a base name of “X” and ask to save the seasonal factors (“_SF”), EViews will save the seasonal factors as X_SF.

You should take care when using long base names, since EViews must be able to create a valid series using the base name and any appended Census designations. In interactive mode, EViews will warn you that the resulting name exceeds the maximum series name length; in batch mode, EViews will create a name using a truncated base name and appended Census designations.

The dialog only allows you to store the four most commonly used series. You may, however, store any additional series as listed on Table 6-8 (p. 74) of the X12-ARIMA Reference Manual by running X12 from the command line (see [x12 \(p. 471\)](#) in the Command and Programming Reference).

ARIMA Options

The X12 program also allows you to fit ARMA models to the series prior to seasonal adjustment. You can use X12 to remove deterministic effects (such as holiday and trading day effects) prior to seasonal adjustment and to obtain forecasts/backcasts that can be used for seasonal adjustment at the boundary of the sample. To fit an ARMA, select the ARIMA Options tab in the X12 Options dialog and fill in the desired options.

The Data Transformation setting allows you to transform the series before fitting an ARMA model. The Auto option selects between no transformation and a log transformation based on the Akaike information criterion. The Logistic option transforms the series y to

$\log y + 1 - y$ and is defined only for series with values that are strictly between 0 and 1. For the Box-Cox option, you must provide the parameter value λ for the transformation


$$\begin{aligned} & \log y_t & \text{if } \lambda = 0 \\ & \frac{1}{\lambda^2} (y_t^\lambda - 1) & \text{if } \lambda > 0 \end{aligned} \tag{11.33}$$

See the “transform spec” (p. 60–67) of the X12-ARIMA Reference Manual for further details.

ARIMA Specification allows you to choose between two different methods for specifying your ARIMA model. The Specify in-line option asks you to provide a single ARIMA specification to fit. The X12 syntax for the ARIMA specification is different from the one used by EViews and follows the Box-Jenkins notation “(p d q)(P D Q)” where:

p	nonseasonal AR order
d	order of nonseasonal differences
q	nonseasonal MA order
P	(multiplicative) seasonal AR order
D	order of seasonal differences
Q	(multiplicative) seasonal MA order

The default specification “(0 1 1)(0 1 1)” is the seasonal IMA model:



$$(1 - L - L^s) y_t = (1 - v_1 L - v_s L^s) e_t \quad (11.34)$$

Here are some other examples (L is the lag operator):

(1 0 0)	$1 - f_1 L y_t = e_t$
(0 1 1)	$1 - L y_t = 1 - v_1 L e_t$
(1 0 1)(1 0 0)	$1 - f_1 L - f_s L^s y_t = 1 - v_1 L e_t$ where $s = 4$ for quarterly data and $s = 12$ for monthly data.

You can skip lags using square brackets and explicitly specify the seasonal order after the parentheses:

([2 3] 0 0)	$1 - f_2 L^2 - f_3 L^3 y_t = e_t$
(0 1 1)12	$1 - L^{12} y_t = 1 - v_1 L^{12} e_t$

See the X12-ARIMA Reference Manual (p. 110–114) for further details and examples of ARIMA specification in X12. Note that there is a limit of 25 total AR, MA, and differencing coefficients in a model and that the maximum lag of any AR or MA parameter is 24 and the maximum number of differences in any ARIMA factor is 3.

Alternatively, if you choose **Select from file**, X12 will select an ARIMA model from a set of possible specifications provided in an external file. The selection process is based on a procedure developed by Statistics Canada for X11-ARIMA/88 and is described in the X12-ARIMA Reference Manual (p. 133). If you use this option, you will be asked to provide the name of a file that contains a set of possible ARIMA specifications. By default, EViews will use a file named X12A.MDL that contains a set of default specifications provided by Census (the list of specifications contained in this file is given below).

To provide your own list in a file, the ARIMA specification must follow the X12 syntax as explained in the ARIMA Specification section above. You must specify each model on a separate line, with an “X” at the end of each line except the last. You may also designate one of the models as a “default” model by marking the end of a line with an asterisk “*” instead of “X”; see p. 133 of the X12-ARIMA Reference Manual for an explanation of the use of a default model. To ensure that the last line is read, it should be terminated by hitting the return key.

For example, the default file (X12A.MDL) provided by X12 contains the following specifications:

(0 1 1)(0 1 1) *

(0 1 2)(0 1 1) x
 (2 1 0)(0 1 1) x
 (0 2 2)(0 1 1) x
 (2 1 2)(0 1 1)

There are two additional options for **Select from file**. **Select best** checks all models in the list and looks for the model with minimum forecast error; the default is to select the first model that satisfies the model selection criteria. **Select by out-of-sample-fit** uses out-of-sample forecast errors (by leaving out some of the observations in the sample) for model evaluation; the default is to use within-sample forecast errors.

The **Regressors** option allows you to include prespecified sets of exogenous regressors in your ARIMA model. Simply use the checkboxes to specify a constant term and/or (centered) seasonal dummy variables. Additional predefined regressors to capture trading day and/or holiday effects may be specified using the **Trading Day/Holiday** tab. You can also use the **Outlier** tab to capture outlier effects.

Trading Day and Holiday Effects

X12 provides options for handling trading day and/or holiday effects. To access these options, select the **Trading Day/Holiday** tab in the **X12 Options** dialog.

As a first step you should indicate whether you wish to make these adjustments in the ARIMA step or in the X11 seasonal adjustment step. To understand the distinction, note that there are two main procedures in the X12 program: the X11 seasonal adjustment step, and the ARIMA estimation step. The X11 step itself consists of several steps that decompose the series into the trend/cycle/irregular components. The X12 procedure may therefore be described as follows:

- optional preliminary X11 step (remove trading day/holiday effects from series, if requested).
- ARIMA step: fit an ARIMA model (with trading/holiday effects, if specified) to the series from step 1 or to the raw series.

X12 Options

Seasonal Adjustment | ARIMA Options | Diagnostics

Trading Day/Holiday

Adjustment Options

☐ None
☒ Adjust in ARIMA step
☐ Adjust in X11 step ☒ Apply only if significant (AIC)

Trading Day Effects

☐ No trading day effects
☒ Flow day-of-week/leap year effects
☐ Flow weekday-weekend/leap year effects
☐ Stock day-of-week: 1 day of month observed

Holidays (Flow)

☐ Easter 8 days before
☐ Labor day 8 days before
☐ Thanksgiving/Christmas 8 days before
☐ Statistics Canada Easter 8 days before

OK Cancel

- X11 step: seasonally adjust the series from step 2 using backcasts/forecasts from the ARIMA model.

While it is possible to perform trading day/holiday adjustments in both the X11 step and the ARIMA step, Census recommends against doing so (with a preference to performing the adjustment in the ARIMA step). EViews follows this advice by allowing you to perform the adjustment in only one of the two steps.

If you choose to perform the adjustment in the X11 step, there is an additional setting to consider. The checkbox *Apply only if significant (AIC)* instructs EViews to adjust only if warranted by examination of the Akaike information criterion.

It is worth noting that in X11, the significance tests for use of trading day/holiday adjustment are based on an F-test. For this, and a variety of other reasons, the X12 procedure with “X11 settings” will not produce results that match those obtained from historical X11. To obtain comparable results, you must use the historical X11 procedure (see [“Census X11 \(Historical\)” on page 358](#)).

Once you select your adjustment method, the dialog will present additional adjustment options:

- **Trading Day Effects** — There are two options for trading day effects, depending on whether the series is a flow series or a stock series (such as inventories). For a flow series, you may adjust for day-of-week effects or only for weekday-weekend contrasts. Trading day effects for stock series are available only for monthly series and the day of the month in which the series is observed must be provided.
- **Holiday Effects** — Holiday effect adjustments apply only to flow series. For each holiday effect, you must provide a number that specifies the duration of that effect prior to the holiday. For example, if you select 8, the level of daily activity changes on the seventh day before the holiday and remains at the new level until the holiday (or a day before the holiday, depending on the holiday).

Note that the holidays are as defined for the United States and may not apply to other countries. For further details, see the X12-ARIMA Reference Manual Tables 6–15 (p. 94) and 6–18 (p. 133).

Outlier Effects



As with trading day/ holiday adjustments, outlier effects can be adjusted either in the X11 step or in the ARIMA step (see the discussion in [“Trading Day and Holiday Effects” on page 354](#)). However, outlier adjustments in the X11 step are done only to robustify the trading day/holiday adjustments in the X11 step. Therefore, in order to perform outlier adjustment in the X11 step, you must perform trading day/holiday adjustment in the X11 step. Only additive outliers are allowed in the X11 step; other types of outliers are available in the ARIMA step. For further information on the various types of outliers, see the X12-ARIMA Reference Manual Tables 6–15 (p. 94) and 6–18 (p. 133).

If you do not know the exact date of an outlier, you may ask the program to test for an outlier using the built-in X12 diagnostics.

Diagnostics

This tab provides options for various diagnostics. The Sliding spans and Historical revisions options test for stability of the adjusted series. While Sliding spans checks the change in adjusted series over a moving sample of fixed size (overlapping subspans), Historical revisions checks the change in adjusted series over an increasing sample as new observations are added to the sample. See the X12-ARIMA Reference Manual for further details and references of the testing procedure. You may also choose to display various diagnostic output:

- Residual diagnostics will report standard residual diagnostics (such as the autocorrelation functions and Q-statistics). These diagnos-



tics may be used to assess the adequacy of the fitted ARIMA model. Note that this option requires estimation of an ARIMA model; if you do not provide an ARIMA model nor any exogenous regressors (including those from the Trading day/Holiday or Outlier tab), the diagnostics will be applied to the original series.


- **Outlier detection** automatically detects and reports outliers using the specified ARIMA model. This option requires an ARIMA specification or at least one exogenous regressor (including those from the Trading day/Holiday or Outlier tab); if no regression model is specified, the option is ignored.
- **Spectral plots** displays the spectra of the differenced seasonally adjusted series (SP1) and/or of the outlier modified irregular series (SP2). The red vertical dotted lines are the seasonal frequencies and the black vertical dashed lines are the trading day frequencies. If you observe peaks at these vertical lines it is an indication of inadequate adjustment. For further details, see Findley et al. (1998, section 2.1). If you request this option, data for the spectra will be stored in a matrix named `seriesname_SA_SP1` and `seriesname_SA_SP2` in your workfile. The first column of these matrices are the frequencies and the second column are 10 times the log spectra at the corresponding frequency.

X11/X12 Troubleshooting

The currently shipping versions of X11 and X12 as distributed by the Census have the following limitation regarding directory length. First, you will not be able to run X11/X12 if you are running EViews from a shared directory on a server which has spaces in its name. The solution is to map that directory to a letter drive on your local machine. Second, the temporary directory path used by EViews to read and write data cannot have more than four subdirectories. This temporary directory used by EViews can be changed by selecting **Options/File Locations.../Temp File Path** in the main menu. If your temporary directory has more than four subdirectories, change the Temp File Path to a writeable path that has fewer subdirectories. Note that if the path contains spaces or has more than 8 characters, it may appear in shortened form compatible with the old DOS convention.

Census X11 (Historical)

The Census X11.2 methods (multiplicative and additive) are the standard methods used by the U.S. Bureau of Census to seasonally adjust publicly released data. The X11 routines are separate programs provided by the Census and are installed in the EViews directory in the files X11Q2.EXE and X11SS.EXE. The documentation for these programs can also be found in your EViews directory as text files X11DOC1.TXT through X11DOC3.TXT.



The X11 programs may be executed directly from DOS or from within EViews. If you run the X11 programs from within EViews, the adjusted series and the factor series will be automatically imported into your EViews workfile. X11 summary output and error messages will also be displayed in the series window at the end of the procedure.

The X11 method has many options, the most important of which are available in the Seasonal Adjustment dialog. However, there are other options not available in the EViews dialog; to use these other options, you should run the X11 programs from the DOS command line. All options available in the X11 methods are described in the X11DOC text files in your EViews directory.

You should note that there is a limit on the number of observations that you can seasonally adjust. X11 only works for quarterly and monthly frequencies, requires at least four full years of data, and can adjust only up to 20 years of monthly data and up to 30 years of quarterly data.

Tramo/Seats

Tramo ("Time Series Regression with ARIMA Noise, Missing Observations, and Outliers") performs estimation, forecasting, and interpolation of regression models with missing observations and ARIMA errors, in the presence of possibly several types of outliers. Seats ("Signal Extraction in ARIMA Time Series") performs an ARIMA-based decomposition of an observed time series into unobserved components. The two programs were developed by Victor Gomez and Agustin Maravall.

Used together, Tramo and Seats provide a commonly used alternative to the Census X12 program for seasonally adjusting a series. Typically, individuals will first "linearize" a series using Tramo and will then decompose the linearized series using Seats.

EViews provides a convenient front-end to the Tramo/Seats programs as a series proc. Simply select Proc/Seasonal Adjustment/Tramo Seats... and fill out the dialog. EViews writes an input file which is passed to Tramo/Seats via a call to a .DLL, and reads the output files from Tramo/Seats back into EViews (note: since EViews uses a new .DLL version of Tramo/Seats, results may differ from the older DOS version of the program).


Since EViews only provides an interface to an external program, we cannot provide any technical details or support for Tramo/Seats itself. Users who are interested in the technical details should consult the original documentation Instructions for the User which is provided as a .PDF file in the DOCS/TRAMOSEATS subdirectory of your EViews directory.

Dialog Options

The Tramo/Seats interface from the dialog provides access to the most frequently used options. Users who desire more control over the execution of Tramo/Seats may use the command line form of the procedure as documented in [tramoseats](#) (p. 459) in the Command and Programming Reference

The dialog contains three tabs. The main tab controls the basic specification of your Tramo/Seats run.

- **Run mode:** You can choose either to run only Tramo or you can select the Run Seats after Tramo checkbox to run both. In the latter case, EViews uses the input file produced by Tramo to run Seats. If you wish to run only Seats, you must use the command line interface.
- **Forecast horizon :** You may set the number of periods to forecast outside the current sample. If you choose a number smaller than the number of forecasts required to run Seats, Tramo will automatically lengthen the forecast horizon as required.
- **Transformation :** Tramo/Seats is based on an ARMA model of the series. You may choose to fit the ARIMA model to the level of the series or to the (natural) log of the series, or you select Auto select level or log . This option automatically chooses between the level model and the log transformed model using results from a trimmed



range-mean regression; see the original Tramo/Seats documentation for further details.

- **ARIMA order search** : You may either specify the orders of the ARIMA model to fit or ask Tramo to search for the “best” ARIMA model. If you select **Fix order** in the combo box and specify the order of all of the ARIMA components, Tramo will use the specified values for all components where the implied ARIMA model is of the form:

$$y_t = \alpha + \beta x_t + u_t$$

$$f(L)d(L)u_t = v(L)e_t$$

$$d(L) = 1 - L^D \quad 1 - L^S$$

$$f(L) = 1 - f_1L - \dots - f_{AR}L^{AR} \quad 1 - F_1L^S - \dots - F_{SAR}L^{S \cdot SAR}$$

$$v(L) = 1 - v_1L - \dots - v_{MA}L^{MA} \quad 1 - V_1L^S - \dots - V_{SMA}L^{S \cdot SMA}$$

with seasonal frequency S . When you fix the order of your ARIMA you should specify non-negative integers in the edit fields for D , SD , AR , SAR , MA , and SMA .

Alternatively, if you select **Fix only difference orders**, Tramo will search for the best ARMA model for differenced data of the orders specified in the edit fields.

You can also instruct Tramo to choose all orders. Simply choose **Search all** or **Search all and unit complex roots** to have Tramo find the best ARIMA model subject to limitations imposed by Tramo. The two options differ in the handling of complex roots. Details are provided in the original Tramo/Seats documentation.

Warning: if you choose to run Seats after Tramo, note that Seats has the following limit on the ARIMA orders: $D \leq 3$, $AR \leq 3$, $MA \leq 3$, $SD \leq 2$, $SAR \leq 1$, $SMA \leq 1$.

- **Series to Save** To save series output by Tramo/Seats in your workfile, provide a valid base name and check the series you wish to save. The saved series will have a postfix appended to the basename as indicated in the dialog. If the saved series contains only missing values, it indicates that Tramo/Seats did not return the requested series see [“Trouble Shooting” on page 362](#).

If Tramo/Seats returns forecasts for the selected series, EViews will append them at the end of the stored series. The workfile range must have enough observations after the current workfile sample to store these forecasts.

If you need access to series that are not listed in the dialog options, see [“Trouble Shooting” on page 362](#)

- **User specified exogenous series:** You may provide your own exogenous series to be used by Tramo. These must be a named series or a group in the current workfile and should not contain any missing values in the current sample and the forecast period.

If you selected a trading day adjustment option, you have the option of specifying exogenous series to be treated as a holiday series. The specification of the holiday series will depend on whether you chose a weekday/weekend adjustment or a 5-day adjustment. See the original Tramo/Seats documentation for further details.

If you are running Seats after Tramo, you must specify which component to allocate the regression effects. The Tramo default is to treat the regression effect as a separate additional component which is not included in the seasonally adjusted series.

EViews will write a separate data file for each entry in the exogenous series list which is passed to Tramo. If you have many exogenous series with the same specification, it is best to put them into one group.

- **Easter/Trading day adjustment** : These options are intended for monthly data; see the original Tramo/Seats documentation for details.
- **Outlier detection** : You may either ask Tramo to automatically detect possible outliers or you can specify your own outlier but not both. If you wish to do both, create a series corresponding to the known outlier and pass it as an exogenous series.

Similarly, the built-in intervention option in Tramo is not supported from the dialog. You may obtain the same result by creating the intervention series in EViews and passing it as an exogenous series. See the example below.

The original Tramo/Seats documentation provides definitions of the various outlier types and the method to detect them.

After you click OK, the series window will display the text output returned by Tramo/Seats. If you ran both Tramo and Seats, the output from Seats is appended at the end of Tramo output. Note that this text view will be lost if you change the series view. You should freeze the view into a text object if you wish to refer to the output file without having to run Tramo/Seats again.

It is worth noting that when you run Tramo/Seats, the dialog will generally contain the settings from the previous run of Tramo/Seats. A possible exception is the user specified outlier list which is cleared unless Tramo/Seats is called on the previously used series.

Comparing X12 and Tramo/Seats

Both X12 and Tramo/Seats are seasonal adjustment procedures based on extracting components from a given series. Methodologically, X12 uses a non-parametric moving average based method to extract its components, while Tramo/Seats bases its decomposition on an estimated parametric ARIMA model (the recent addition of ARIMA modelling in X12 appears to be used mainly to identify outliers and to obtain backcasts and forecasts for end-of-sample problems encountered when applying moving average methods.)

For the practitioner, the main difference between the two methods is that X12 does not allow missing values while Tramo/Seats will interpolate the missing values (based on the

estimated ARIMA model). While both handle quarterly and monthly data, Tramo/Seats also handles annual and semi-annual data. See the sample programs in the Example Files directory for a few results that compare X12 and Tramo/Seats.

Trouble Shooting

Error handling

As mentioned elsewhere, EViews writes an input file which is passed to Tramo/Seats via a call to a .DLL. Currently the Tramo/Seats .DLL does not return error codes. Therefore, the only way to tell that something went wrong is to examine the output file. If you get an error message indicating that the output file was not found, the first thing you should do is to check for errors in the input file.

When you call Tramo/Seats, EViews creates two subdirectories called Tramo and Seats in a temporary directory. This temporary directory is taken from the global option Options/File Locations.../Temp File Path (note that long directory names with spaces may appear in shortened DOS form). The Temp File Path can be retrieved in a program by a call to [@temp-path](#) (see [@temp-path](#) (p. 547) in the Command and Programming Reference).

The Tramo input file written by EViews will be placed in the subdirectory TRAMO and is named SERIE. A Seats input file written by Tramo is also placed in subdirectory TRAMO and is named SEATS.ITR.

The input file used by Seats is located in the SEATS subdirectory and is named SERIE2. If Seats is run alone, then EViews will create the SERIE2 file. When Tramo and Seats are called together, the Tramo file SEATSITR is copied into SERIE2.

If you encounter the error message containing the expression “output file not found”, it probably means that Tramo/Seats encountered an error in one of the input files. You should look for the input files SERIE and SERIE2 in your temp directories and check for any errors in these files.

Retrieving additional output

The output file displayed in the series window is placed in the OUTPUT subdirectory of the TRAMO and/or SEATS directories. The saved series are read from the files returned by Tramo/Seats that are placed in the GRAPH subdirectories. If you need to access other data files returned by Tramo/Seats that are not supported by EViews, you will have to read them back into the workfile using the `read` command from these GRAPH subdirectories. See the PDF documentation file for a description of these data file formats.

Warning: if you wish to examine these files, make sure to read these data files before you run the next Tramo/Seats procedure. EViews will clear these subdirectories before running the next Tramo/Seats command (this clearing is performed as a precautionary measure so that Tramo/Seats does not read results from a previous run).

Moving Average Methods

Ratio to moving average—multiplicative

The algorithm works as follows. Denote the series to be filtered by y_t .

1. First compute the centered moving average of y_t as:

$$x_t = \begin{cases} \frac{1}{12} (0.5y_{t-6} + y_{t-5} + y_{t-4} + y_{t-3} + y_{t-2} + y_{t-1} + y_t + y_{t+1} + y_{t+2} + y_{t+3} + y_{t+4} + 0.5y_{t+6}) & \text{if monthly} \\ \frac{1}{4} (0.5y_{t-2} + y_{t-1} + y_t + y_{t+1} + 0.5y_{t+2}) & \text{if quarterly} \end{cases} \quad (11.35)$$

2. Take the ratio $t_t = y_t / x_t$.
3. Compute the seasonal indices. For monthly series, the seasonal index i_m for month m is the average of t_t using observations only for month m . For quarterly series, the seasonal index i_q for quarter q is the average of t_t using observations only for quarter q .
4. We then adjust the seasonal indices so that they multiply to one. This is done by computing the seasonal factors as the ratio of the seasonal index to the geometric mean of the indices:

$$s = \begin{cases} i_m / \sqrt[12]{i_1 i_2 \cdots i_{12}} & \text{if monthly} \\ i_q / \sqrt[4]{i_1 i_2 i_3 i_4} & \text{if quarterly} \end{cases} \quad (11.36)$$

5. These s are the reported scaling factors in the series window and are saved as series if you provide a name in the field box. The interpretation is that the series y is s_j percent higher in period j relative to the adjusted series.
6. The seasonally adjusted series is obtained by dividing y_t by the seasonal factors s_j .

Difference from moving average—additive

Suppose that we wish to filter y_t .

1. First compute the centered moving average of y_t as in [Equation \(11.35\) on page 363](#)
2. Take the difference $d_t = y_t - x_t$.
3. Compute the seasonal indices. For monthly series, the seasonal index i_m for month m is the average of d_t using observations only for month m . For quarterly series, the seasonal index i_q for quarter q is the average of d_t using observations only for quarter q .
4. We then adjust the seasonal indices so that they add up to zero. This is done by setting $s_j = i_j - \bar{i}$ where $\bar{i}$ is the average of all seasonal indices. These s are the reported scaling factors. The interpretation is that the series y is s_j higher in period j relative to the adjusted series.

5. The seasonally adjusted series is obtained by subtracting the seasonal factors S_j from Y_t .

The main difference between X11 and the moving average methods is that the seasonal factors may change from year to year in X11. The seasonal factors are assumed to be constant for the moving average method.

Exponential Smoothing

Exponential smoothing is a simple method of adaptive forecasting. It is an effective way of forecasting when you have only a few observations on which to base your forecast. Unlike forecasts from regression models which use fixed coefficients, forecasts from exponential smoothing methods adjust based upon past forecast errors. For additional discussion, see Bowerman and O'Connell (1979).

To obtain forecasts based on exponential smoothing methods, choose Proc/Exponential Smoothing... . The Exponential Smoothing dialog box appears:

You need to provide the following information:

- Smoothing Method . You have the option to choose one of the five methods listed.
- Smoothing Parameters . You can either specify the values of the smoothing parameters or let EViews estimate them.

To estimate the parameter, type the letter e (for estimate) in the edit field. EViews estimates the parameters by minimizing the sum of squared errors. Don't be surprised if the estimated damping parameters are close to one—it is a sign that the series is close to a random walk, where the most recent value is the best estimate of future values.

To specify a number, type the number in the field corresponding to the parameter. All parameters are constrained to be between 0 and 1; if you specify a number outside the unit interval, EViews will estimate the parameter.

- Smoothed Series Name . You should provide a name for the smoothed series. By default, EViews will generate a name by appending SM to the original series name, but you can enter any valid EViews name.

Smoothing method	# of params
☐ Single	1
☐ Double	1
☒ Holt-Winters - No seasonal	2
☐ Holt-Winters - Additive	3
☐ Holt-Winters - Multiplicative	3

- **Estimation Sample**. You must specify the sample period upon which to base your forecasts (whether or not you choose to estimate the parameters). The default is the current workfile sample. EViews will calculate forecasts starting from the first observation after the end of the estimation sample.
- **Cycle for Seasonal**. You can change the number of seasons per year from the default of 12 for monthly or 4 for quarterly series. This option allows you to forecast from unusual data such as an undated workfile. Enter a number for the cycle in this field.

Single Smoothing (one parameter)

This single exponential smoothing method is appropriate for series that move randomly above and below a constant mean with no trend nor seasonal patterns. The smoothed series $\hat{y}_t$ of y_t is computed recursively, by evaluating:

$$\hat{y}_t = \alpha y_t + (1 - \alpha) \hat{y}_{t-1} \quad (11.37)$$

where $0 \leq \alpha \leq 1$ is the damping (or smoothing) factor. The smaller is the α , the smoother is the $\hat{y}_t$ series. By repeated substitution, we can rewrite the recursion as

$$\hat{y}_t = \alpha \sum_{s=0}^{t-1} (1 - \alpha)^s y_{t-s} \quad (11.38)$$

This shows why this method is called exponential smoothing—the forecast of y_t is a weighted average of the past values of y_t , where the weights decline exponentially with time.

The forecasts from single smoothing are constant for all future observations. This constant is given by:

$$\hat{y}_{T+k} = \hat{y}_T \quad \text{for all } k \geq 0 \quad (11.39)$$

where T is the end of the estimation sample.

To start the recursion, we need an initial value for $\hat{y}_t$ and a value for α . EViews uses the mean of the initial $T - 1 - 2$ observations of y_t to start the recursion (where T is the number of observations in the sample). Bowerman and O'Connell (1979) suggest that values of α around 0.01 to 0.30 work quite well. You can also let EViews estimate α to minimize the sum of squares of one-step forecast errors.

Double Smoothing (one parameter)

This method applies the single smoothing method twice (using the same parameter) and is appropriate for series with a linear trend. Double smoothing of a series y is defined by the recursions:

$$\begin{aligned} S_t &= \alpha y_t + (1-\alpha) S_{t-1} \\ D_t &= \alpha S_t + (1-\alpha) D_{t-1} \end{aligned} \quad (11.40)$$

where S is the single smoothed series and D is the double smoothed series. Note that double smoothing is a single parameter smoothing method with damping factor $0 < \alpha \leq 1$.

Forecasts from double smoothing are computed as:

$$\begin{aligned} \hat{y}_{T+k} &= 2 \frac{\alpha k s}{1-\alpha} S_T - 1 \frac{\alpha k s}{1-\alpha} D_T + \frac{1}{1-\alpha} (2S_T - D_T) \\ &\quad + \frac{\alpha}{1-\alpha} (S_T - D_T) k s \end{aligned} \quad (11.41)$$

The last expression shows that forecasts from double smoothing lie on a linear trend with intercept $2S_T - D_T$ and slope $\alpha (S_T - D_T) / (1-\alpha)$.

Holt-Winters—Multiplicative (three parameters)

This method is appropriate for series with a linear time trend and multiplicative seasonal variation. The smoothed series $\hat{y}_t$ is given by,

$$\hat{y}_{t-k} = a + bk + c_{t-k} \quad (11.42)$$

where

$$\begin{aligned} a &= \text{permanent component (intercept)} \\ b &= \text{trend} \\ c_t &= \text{multiplicative seasonal factor} \end{aligned} \quad (11.43)$$

These three coefficients are defined by the following recursions:

$$\begin{aligned} a_t &= \alpha \frac{y_t}{c_{t-s}} + (1-\alpha) a_{t-1} - b_{t-1} \\ b_t &= \beta a_t - \alpha a_{t-1} + (1-\beta) b_{t-1} \\ c_{t-t} &= \gamma \frac{y_t}{a_t} + (1-\gamma) c_{t-s} \end{aligned} \quad (11.44)$$

where $0 < \alpha, \beta, \gamma < 1$ are the damping factors and s is the seasonal frequency specified in the Cycle for Seasonal field box.

Forecasts are computed by:

$$\hat{y}_{t+k} = a_T + b_T k + c_{T+k-s} \quad (11.45)$$

where the seasonal factors are used from the last s estimates.

Holt-Winters—Additive(three parameter)

This method is appropriate for series with a linear time trend and additive seasonal variation. The smoothed series $\hat{y}_t$ is given by:

$$\hat{y}_{t-k} = a + bk + c_k \quad (11.46)$$

where a and b are the permanent component and trend as defined above in [Equation \(11.43\)](#) and c are the additive seasonal factors. The three coefficients are defined by the following recursions:

$$\begin{aligned} a_t &= \alpha y_t + (1-\alpha)a_{t-1} \\ b_t &= \beta a_t + (1-\beta)b_{t-1} \\ c_{t-s} &= \gamma y_t - a_t + (1-\gamma)c_{t-s} \end{aligned} \quad (11.47)$$

where $0 \leq \alpha, \beta, \gamma \leq 1$ are the damping factors and s is the seasonal frequency specified in the Cycle for Seasonal field box.

Forecasts are computed by:

$$\hat{y}_{T+k} = a_T + b_T k + c_{T+k-s} \quad (11.48)$$

where the seasonal factors are used from the last s estimates.

Holt-Winters—No Seasonal (two parameters)

This method is appropriate for series with a linear time trend and no seasonal variation. This method is similar to the double smoothing method in that both generate forecasts with a linear trend and no seasonal component. The double smoothing method is more parsimonious since it uses only one parameter, while this method is a two parameter method. The smoothed series $\hat{y}_t$ is given by:

$$\hat{y}_{t-k} = a + bk \quad (11.49)$$

where a and b are the permanent component and trend as defined above in [Equation \(11.43\)](#).

These two coefficients are defined by the following recursions:

$$\begin{aligned} a_t &= \alpha y_t + (1-\alpha)a_{t-1} \\ b_t &= \beta a_t + (1-\beta)b_{t-1} \end{aligned} \quad (11.50)$$

where $0 \leq \alpha, \beta \leq 1$ are the damping factors. This is an exponential smoothing method with two parameters.

Forecasts are computed by:

$$\hat{y}_{T+k} = a_T + b_T k \quad (11.51)$$

These forecasts lie on a linear trend with intercept a_T and slope b_T .

It is worth noting that Holt-Winters—No Seasonal, is not the same as additive or multiplicative with $\gamma = 0$. The condition $\gamma = 0$ only restricts the seasonal factors from changing over time so there are still (fixed) nonzero seasonal factors in the forecasts.

Illustration

As an illustration of forecasting using exponential smoothing we forecast data on monthly housing starts (HS) for the period 1985M01–1988M12 using the DRI Basics data for the period 1959M01–1984M12. These data are provided in the workfile “Hs.WF1”. Load the workfile, highlight the HS series, double click, select Proc/Exponential Smoothing... . We use the Holt-Winters - Multiplicative method to account for seasonality, name the smoothed forecasts as HS_SM, and estimate all parameters over the period 1959M1–1984M12. Leave the remaining settings at their default values.

When you click OK, EViews displays the results of the smoothing procedure. The first part displays the estimated (or specified) parameter values, the sum of squared residuals, the root mean squared error of the forecast. The zero values for Beta and Gamma in this example mean that the trend and seasonal components are estimated as fixed and not changing.


Date:	08/18/09	Time:	17:03
Sample:	1959M01 1984M12		
Included observations:	312		
Method:	Holt-Winters	Multiplicative	Seasonal
Original Series:	HS		
Forecast Series:	HSSM		
Parameters:	Alpha		0.7100
	Beta		0.0000
	Gamma		0.0000
Sum of Squared Residuals			40365.69
Root Mean Squared Error			11.37441

The second part of the table displays the mean a , and trend b at the end of the estimation sample that are used for post-sample smoothed forecasts.

End of Period Levels:	Mean	134.6584
	Trend	0.064556
Seasonals:	1984M01	0.680745
	1984M02	0.711559
	1984M03	0.992958
	1984M04	1.158501
	1984M05	1.210279
	1984M06	1.187010
	1984M07	1.127546
	1984M08	1.121792
	1984M09	1.050131
	1984M10	1.099288
	1984M11	0.918354
	1984M12	0.741837

For seasonal methods, the seasonal factors $\hat{g}$ used in the forecasts are also displayed. The smoothed series in the workfile contains data from the beginning of the estimation sample to the end of the workfile range; all values after the estimation period are forecasts.

When we plot the actual values (HS) and the smoothed forecasts(HS_SM) on a single graph, we get:



We have included the forecasted values HS_f from estimation of an AR model with an AR(1) and a SAR(12) term for comparison purposes. The forecasts from the multiplicative exponential smoothing method do a better job of tracking the seasonal movements in the actual series.

Hodrick-Prescott Filter

The Hodrick-Prescott Filter is a smoothing method that is widely used among macroeconomists to obtain a smooth estimate of the long-term trend component of a series. The method


was first used in a working paper (circulated in the early 1980's and published in 1997) by Hodrick and Prescott to analyze postwar U.S. business cycles.

Technically, the Hodrick-Prescott (HP) filter is a two-sided linear filter that computes the smoothed series $\hat{y}_t$ of y_t by minimizing the variance of y_t around $\hat{y}_t$, subject to a penalty that constrains the second difference of $\hat{y}_t$. That is, the HP filter chooses $\hat{y}_t$ to minimize:

$$\sum_{t=1}^T (y_t - \hat{y}_t)^2 + \lambda \sum_{t=2}^{T-1} (\hat{y}_{t-1} - \hat{y}_t - (\hat{y}_t - \hat{y}_{t-1}))^2. \quad (11.52)$$

The penalty parameter λ controls the smoothness of the series $\hat{y}_t$. The larger the λ , the smoother the $\hat{y}_t$. As $\lambda \rightarrow \infty$, $\hat{y}_t$ approaches a linear trend.

To smooth the series using the Hodrick-Prescott filter, choose Proc/Hodrick-Prescott Filter...:



First, provide a name for the smoothed series. EViews will suggest a name, but you can always enter a name of your choosing. Next, specify an integer value for the smoothing parameter, λ . You may specify the parameter using the frequency power rule of Ravn and Uhlig (2002) (the number of periods per year divided by 4, raised to a power, and multiplied by 1600), or you may specify λ directly. The default is to use a power rule of 2, yielding the original Hodrick and Prescott values for λ :

$$\lambda = \begin{cases} 100 & \text{for annual data} \\ 1,600 & \text{for quarterly data} \\ 14,400 & \text{for monthly data} \end{cases} \quad (11.53)$$

Ravan and Uhlig recommend using a power value of 4. EViews will round any non-integer values that you enter. When you click OK, EViews displays a graph of the filtered series

together with the original series. Note that only data in the current workfile sample are filtered. Data for the smoothed series outside the current sample are filled with NAs.

Frequency (Band-Pass) Filter

EViews computes several forms of band-pass (frequency) filters. These filters are used to isolate the cyclical component of a time series by specifying a range for its duration. Roughly speaking, the band-pass filter is a linear filter that takes a two-sided weighted moving average of the data where cycles in a “band”, given by a specified lower and upper bound, are “passed” through, or extracted, and the remaining cycles are “filtered” out.

To employ a band-pass filter, the user must first choose the range of durations (periodicities) to pass through. The range is described by a pair of numbers P_L , P_U , specified in units of the workfile frequency. Suppose, for example, that you believe that the business cycle lasts somewhere from 1.5 to 8 years so that you wish to extract the cycles in this range. If you are working with quarterly data, this range corresponds to a low duration of 6, and an upper duration of 32 quarters. Thus, you should set $P_L = 6$ and $P_U = 32$.

In some contexts, it will be useful to think in terms of frequencies which describe the number of cycles in a given period (obviously, periodicities and frequencies are inversely related). By convention, we will say that periodicities in the range P_L , P_U correspond to frequencies in the range $2\pi/P_U$, $2\pi/P_L$.

Note that since saying that we have a cycle with a period of 1 is meaningless, we require that $2 \leq P_L < P_U$. Setting P_L to the lower-bound value of 2 yields a high-pass filter in which all frequencies above $2\pi/P_U$ are passed through.

The various band-pass filters differ in the way that they compute the moving average:

- The fixed length symmetric filters employ a fixed lead/lag length. Here, the user must specify the fixed number of lead and lag terms to be used when computing the weighted moving average. The symmetric filters are time-invariant since the moving average weights depend only on the specified frequency band, and do not use the data. EViews computes two variants of this filter, the first due to Baxter-King (1999) (BK), and the second to Christiano-Fitzgerald (2003) (CF). The two forms differ in the choice of objective function used to select the moving average weights.
- Full sample asymmetric – this is the most general filter, where the weights on the leads and lags are allowed to differ. The asymmetric filter is time-varying with the weights both depending on the data and changing for each observation. EViews computes the Christiano-Fitzgerald (CF) form of this filter.

In choosing between the two methods, bear in mind that the fixed length filters require that we use same number of lead and lag terms for every weighted moving average. Thus, a filtered series computed using q leads and lags observations will lose q observations from

both the beginning and end of the original sample. In contrast, the asymmetric filtered series do not have this requirement and can be computed to the ends of the original sample.

Computing a Band-Pass Filter in EViews

The band-pass filter is available as a series Proc in EViews. To display the band-pass filter dialog, select Proc/Frequency Filter... from the main series menu.

The first thing you will do is to select a filter type. There are three types: Fixed length symmetric (Baxter-King), Fixed length symmetric (Christiano-Fitzgerald), or Full length asymmetric (Christiano-Fitzgerald). By default, the EViews will compute the Baxter-King fixed length symmetric filter.

For the Baxter-King filter, there are only a few options that require your attention. First, you must select a frequency length (lead/lags) for the moving average, and the low and high values for the cycle period P_L , P_U to be filtered. By default, these fields will be filled in with reasonable default values that are based on the type of your workfile.

The screenshot shows the 'Frequency Filter' dialog box with the following settings:

- Filter type:** Fixed length symmetric (Baxter-King)
- Lead/lags:** 28
- Generated output variables:**
 - Cycle series: bpfilter01
 - Non-cyclical series: (empty)
 - Matrix for weights: (empty)
- Stationarity assumption:** ☒ I(0) - stationary, ☐ I(1) - random walk
- Detrending method:** None
- Cycle periods:** Low: 18.0, High: 96.0
- Buttons:** OK, Cancel

Lastly, you may enter the names of objects to contain saved output for the cyclical and non-cyclical components. The Cycle series will be a series object containing the filtered series (cyclical component), while the Non-cyclical series is simply the difference between the actual and the filtered series. The user may also retrieve the moving average weights used in the filter. These weights, which will be placed in a matrix object, may be used to plot customized frequency response functions. Details are provided below in ["The Weight Matrix" on page 374](#).

Both of the CF filters (symmetric and asymmetric) provide you with additional options for handling trending data.

The first setting involves the Stationarity assumption. For both of the CF, you will need to specify whether the series is assumed to be an $I(0)$ covariance stationary process or an $I(1)$ unit root process.

The screenshot shows the 'Frequency Filter' dialog box with the following settings:


- Filter type:** Full sample asymmetric (Christiano-Fitzgerald)
- Lead/lags:** 28
- Generated output variables:**
 - Cycle series: bpfilter01
 - Non-cyclical series: (empty)
 - Matrix for weights: (empty)
- Stationarity assumption:** ☒ I(0) - stationary, ☐ I(1) - random walk
- Detrending method:** None
- Cycle periods:** Low: 18.0, High: 96.0
- Buttons:** OK, Cancel

Lastly, you will select a Detrending method using the combo. For a covariance stationary series, you may choose to demean or detrend the data prior to applying the filters. Alternatively, for a unit root process, you may choose to demean, detrend, or remove drift using the adjustment suggested by Christiano and Fitzgerald (2003).

Note that, as the name suggests, the full sample filter uses all of the observations in the sample, so that the Lead/Lags option is not relevant. Similarly, detrending the data is not an option when using the BK fixed length symmetric filter. The BK filter removes up to two unit roots (a quadratic deterministic trend) in the data so that detrending has no effect on the filtered series.

The Filter Output

Here, we depict the output from the Baxter-King filter using the series LOG(GDP) in the workfile “Bpf.WF1”. The results were produced by selecting Proc/Frequency Filter... from the main series menu and clicking on OK to accept the default settings. (We have added grid lines to the graph to make it easier to see the cyclical behavior). The left panel depicts the original series, filtered series, and the non-cyclical component (difference between the original and the filtered).



For the BK and CF fixed length symmetric filters, EViews plots the frequency response function $a(q)$ representing the extent to which the filtered series “responds” to the original series at frequency q . At a given frequency q , $|a(q)|^2$ indicates the extent to which a moving average raises or lowers the variance of the filtered series relative to that of the original series. The right panel of the graph depicts the function. Note that the horizontal axis of a frequency response function is always in the range 0 to 0.5, in units of cycles per duration. Thus, as depicted in the graph, the frequency response function of the ideal band-pass filter for periodicities P_L, P_U will be one in the range $1/P_U, 1/P_L$.

The frequency response function is not drawn for the CF time-varying filter since these filters vary with the data and observation number. If you wish to plot the frequency response

function for a particular observation, you will have to save the weight matrix and then evaluate the frequency response in a separate step. The example program BFP02.PRG and subroutine FREQRESP.PRG illustrate the steps in computing of gain functions for time-varying filters at particular observations.

The Weight Matrix

For time-invariant (fixed-length symmetric) filters, the weight matrix is of dimension $1 - q + 1$ where q is the user-specified lag length order. For these filters, the weights on the leads and the lags are the same, so the returned matrix contains only the one-sided weights. The filtered series can be computed as:

$$z_t = \sum_{c=1}^{q-1} w_{1,c} y_{t-1-c} + \sum_{c=2}^{q-1} w_{1,c} y_{t-c-1} \quad t = q-1, \dots, n-q$$

For time-varying filters, the weight matrix is of dimension $n - n$ where n is the number of non-missing observations in the current sample. Row r of the matrix contains the weighting vector used to generate the r -th observation of the filtered series where column c contains the weight on the c -th observation of the original series:

$$z_t = \sum_{c=1}^n w_{t,c} y_c \quad t = 1, \dots, n \quad (11.54)$$

where z_t is the filtered series, y_t is the original series and $w_{r,c}$ is the r, c element of the weighting matrix. By construction, the first and last rows of the weight matrix will be filled with missing values for the symmetric filter.

Whiten Data


EViews offers easy-to-use tools for whitening the data in a series. To access these tools, simply select Make Whiten... from the series toolbar or the main EViews menu. See [“Make Whiten,” on page 431](#) for a discussion of the use of these tools in a group object setting.

Distribution Plot Data

EViews offers the ability to display a variety of what we term analytical graphs—graphs created by first performing data reduction or statistical analysis on the series, then displaying the results visually ([“Analytical Graph Types” on page 493](#)). The central feature of these graphs is that they do not show data for each observation, but instead display a summary of the original data. One important class of analytical graphs are distribution graphs, which show various aspects of the distribution of the data in a series. Included among these graph types are histograms, kernel density plots, theoretical distribution plots, and theoretical quantile-quantile plots.

Typically, you will access the distribution graph tools by selecting Graph from the series window and then making the appropriate choice (see [“Graphing a Series” on page 439](#)). These graph tools allow you to display the constructed data graphically, but not to examine them directly.

In some cases, you may wish to save the data depicted in the graph, possibly for further analysis. To do so, simply select Proc/Make Distribution Plot Data... to bring up a dialog that is quite similar to the main graph dialog:



On the left-hand side of the dialog is a list box showing the types of distribution graph data that may be saved, along with the name of a matrix in which to save the results. As you select entries on the left, the right-hand side of the dialog will change to reflect the different options that are available for your selection. Specify your options as desired and click on OK to save your results.

References

- Anderson, T. W. and D. A. Darling (1952). "Asymptotic Theory of Certain Goodness of Fit Criteria Based on Stochastic Processes," *Annals of Mathematical Statistics*, 23, 193-212.
- Anderson, T. W. and D. A. Darling (1954), "A Test of Goodness of Fit," *Journal of the American Statistical Association*, 49, 765-769.
- Baxter, Marianne and Robert G. King (1999). "Measuring Business Cycles: Approximate Band-Pass Filters For Economic Time Series," *Review of Economics and Statistics*, 81, 575-593.
- Bergmann, Reinhard, John Ludbrook, and Will P. J. M. Spooren (2000). "Different Outcomes of the Wilcoxon-Mann-Whitney Test From Different Statistical Packages," *The American Statistician*, 45(1), 72-77.
- Bowerman, Bruce L. and Richard T. O'Connell (1979). *Time Series and Forecasting: An Applied Approach*, New York: Duxbury Press.

- Box, George E. P. and Gwilym M. Jenkins (1976). *Time Series Analysis: Forecasting and Control* Revised Edition, Oakland, CA: Holden-Day.
- Brown, M. B. and A. B. Forsythe (1974a). "Robust Tests for the Equality of Variances," *Journal of the American Statistical Association* 69, 364–367.
- Brown, M. B. and A. B. Forsythe (1974b). "The Small Sample Behavior of Some Test Statistics which Test the Equality of Several Means," *Technometrics* 16, 129–132.
- Christiano, Lawrence J. and Terry J. Fitzgerald (2003). "The Band Pass Filter," *International Economic Review* 44(2), 435–465.
- Cochran, W. G. (1937). "Problems Arising in the Analysis of a Series of Similar Experiments," *Supplement to the Journal of the Royal Statistical Society* 4(1), 102–118.
- Conover, W. J., M. E. Johnson and M. M. Johnson (1981). "A Comparative Study of Tests for Homogeneity of Variance with Applications to the Outer Continental Shelf Bidding Data," *Technometrics* 23, 351–361.
- Csörgö, Sandor and Julian Faraway (1996). "The Exact and Asymptotic Distributions of Cramer-von Mises Statistics," *Journal of the Royal Statistical Society, Series B* 58, 221–234.
- D'Agostino and Michael A. Stephens, (eds) (1986). *Goodness-of-Fit Techniques* New York: Marcel A. Dekker.
- Dallal, Gerard E. and Leland Wilkinson (1986). "An Analytic Approximation to the Distribution of Lilliefors's Test Statistic For Normality," *The American Statistician*, 40(4), 294–296.
- Davis, Charles S., and Michael A. Stephens (1989). "Empirical Distribution Function Goodness-of-Fit Tests," *Applied Statistics* 38(3), 535–582.
- Dezhbaksh, Hashem (1990). "The Inappropriate Use of Serial Correlation Tests in Dynamic Linear Models," *Review of Economics and Statistics* 72, 126–132.
- Durbin, J. (1970). *Distribution Theory for Tests Based on the Sample Distribution Function*. SIAM: Philadelphia.
- Findley, David F., Brian C. Monsell, William R. Bell, Mark C. Otto, Bor-Chung Chen (1998). "New Capabilities and Methods of the X-12-ARIMA Seasonal-Adjustment Program," *Journal of Business & Economic Statistics* 16(2), 127–152.
- Harvey, Andrew C. (1990). *The Econometric Analysis of Time Series* 2nd edition, Cambridge, MA: MIT Press.
- Harvey, Andrew C. (1993). *Time Series Models* 2nd edition, Cambridge, MA: MIT Press.
- Hodrick, R. J. and E. C. Prescott (1997). "Postwar U.S. Business Cycles: An Empirical Investigation," *Journal of Money, Credit, and Banking*, 29, 1–16.
- Judge, George G., W. E. Griffiths, R. Carter Hill, Helmut Lütkepohl, and Tsoung-Chao Lee (1985). *The Theory and Practice of Econometrics* 2nd edition, New York: John Wiley & Sons.
- Levene, H. (1960). "Robust Tests for the Equality of Variances," in I. Olkin, S. G. Ghurye, W. Hoeffding, W. G. Madow, and H. B. Mann (eds), *Contribution to Probability and Statistics*, Palo Alto, CA: Stanford University Press.
- Lewis, Peter A. W. (1961). "Distribution of the Anderson-Darling Statistic," *Annals of Mathematical Statistics*, 32, 1118–1124.
- Ljung, G. and G. Box (1979). "On a Measure of Lack of Fit in Time Series Models," *Biometrika*, 66, 265–270.
- Neter, John, Michael H. Kutner, Christopher J. Nachtsheim, and William Wasserman (1996). *Applied Linear Statistical Models* 4th Edition. Chicago: Times Mirror Higher Education Group, Inc. and Richard D. Irwin, Inc.

- Ravn, Morten O. and Harald Uhlig (2002). "On Adjusting the Hodrick-Prescott Filter for the Frequency of Observations," *Review of Economics and Statistics* 84, 371-375.
- Satterthwaite, F. E. (1946). "An Approximate Distribution of Estimates of Variance Components," *Biometrics Bulletin*, 2(6), 110-114.
- Sheskin, David J. (1997). *Parametric and Nonparametric Statistical Procedures* Boca Raton: CRC Press.
- Sokal, Robert R. and F. James Rohlf (1995) *Biometry*. New York: W. H. Freeman and Company.
- Stephens, Michael A. (1986). "Tests Based on EDF Statistics," in *Goodness-of-Fit Techniques* Ralph B. D'Agostino and Michael A. Stephens, (eds). New York: Marcel A. Dekker, 97-193.
- Welch, B. L. (1951). "On the Comparison of Several Mean Values: An Alternative Approach," *Biometrika*, 38, 330-336.

Chapter 12. Groups

This chapter describes the views and procedures of a group object. A group object is a collection of series which you wish to treat as a single unit. With a group, you can compute various statistics that describe the relationship between the series and display them in various forms such as spreadsheets, tables, and graphs.

To create a group object, you may select the desired series in the workfile, then right-mouse click and select **Open/as Group**. Alternately, you may enter the keyword `group` on the command line, followed by the name to be given the group object, then the list of series and series expressions to be placed in the group.

The remainder of this chapter assumes that you are already familiar with the basics of working with a group. See the documentation of EViews features beginning with [Chapter 4. "Object Basics,"](#) on page 67 for relevant details on the basic operations.

Group Views Overview

The group view menu is divided into four blocks:


- The views in the first block provide various ways of looking at the actual data in the group.
- The views in the second block display various basic statistics.
- The views in the third block are for specialized statistics typically computed using time series data.
- The fourth block contains the label view, which provides information regarding the group object.

Group Members

This view displays the member series in the group and allows you to alter the group. To change the group, simply edit the group window. You can add other series from the workfile, include expressions involving series, or you can delete series from the group.

The Group Members view displays a text window showing you the names of the series currently in the group.

You may edit the contents of this window to add, remove, or rearrange the series in a group. To add one series to the group, simply place the edit cursor in the desired position and enter the name of the series or the series expression. Removing or rearranging members may be accomplished by cutting and pasting as desired. You may also use the clipboard to cut-and-paste lists of series from group to group or even from other applications into EViews.



Change you make to the members view are not finalized until you click on the Update-Group button in the group toolbar. If you attempt to switch away from this group before updating the altered group members list, you will be prompted to save or discard your changes.

Alternately, you may use the right-button menu in the spreadsheet view as described below ([“Additional Customization” on page 381](#)) to change the group members, or you may drag-and-drop series into the Group Members or Spreadsheet views of the group as described in [“Adding to or Modifying a Group” on page 90](#)).


Spreadsheet

This view displays the data, in spreadsheet form, for each series in the group. If you wish, you can flip the rows and columns of the spreadsheet by pressing the Transpose button. In transpose format, each row contains a series, and each column an observation or date. Pressing the Transpose button toggles between the two spreadsheet views.

You may change the display mode of your spreadsheet view to show various common transformations of your data using the dropdown menu in the group toolbar. By default, EViews displays the original or mapped values in the series using the formatting specified in the series (Default). If you wish, you can change the spreadsheet display to show any transformations defined in the individual series (Series Spec), the underlying series data (Raw Data), or various differences of the series (in levels or percent changes), with or without log transformations.

You may edit the series data in either levels or transformed values. The Edit +/- on the group toolbar toggles the edit mode for the group. If you are in edit mode, an edit window appears in the top of the group window and a double-box is used to indicate the cell that is being edited.

Here, we are editing the data in the group in 1-period percent changes (note the label to the right of the edit field). If we change the 1952Q4 value of the percent change in GDP, from 3.626 to 5, the values of GDP from 1952Q4 to the end of the workfile will change to reflect the one-time increase in the value of GDP.



obs	GDP	M1	PR
1952Q1	87.87500	126.5370	0.197561
1952Q2	88.12500	127.5060	0.198167
1952Q3	89.62500	129.3850	0.200179
1952Q4	92.87500	128.5120	0.201246
1953Q1	94.62500	130.5870	0.201052
1953Q2	95.55000	130.3410	0.201444
1953Q3	95.42500	131.3890	0.202236
1953Q4	94.17500	129.8910	0.202723
1954Q1	94.07500	130.1730	0.203416
1954Q2	94.20000	131.3850	0.203841
1954Q3	95.45000	134.6270	0.204291
1954Q4			


Additional Customization

EViews provides you with additional tools for altering the display of your spreadsheet. To change the display properties, select one or more series by clicking on the series names in the headers, then right-click to bring up a menu.

Open selected will open a new group object containing the selected series in a new, untitled group.

You may use the Insert Series and Remove Series entries to change the contents of the current group.

Selecting Insert Series brings up a dialog which allows you to insert multiple series by simply entering their names or series expressions. The new series will be inserted after the currently selected series and all subsequent series will follow the newly inserted series. Remove Series works slightly differently, in that no dialog will be shown and all selected series will be removed from the group. (See also [“Group Members” on page 379](#) for an alternative method of changing the group contents.)



Insert Series

Series Name(s) or expression(s)


To insert more than 1 series separate names with a space.

OK Cancel

If the current ordering of the series is not desired, you may change the order by dragging a series to the desired position. Dragging is achieved by first selecting one or more series. Once the selection has been made, move the mouse to either the left edge of the first selected series or to the right edge of the last selected series. Once over the edge, the cursor


should change to the cursor shown in the following image. From here, press the left mouse button and drag the series to the desired location.

If you right-click and then select Display format... EViews will open a format dialog that will allow you to specify group display characteristics that override the individual series display characteristics. Once you specify the desired format and click on OK, EViews will update the group display to reflect your specification.



Note that, by default, changes to the group display format will apply only to the group spreadsheet and will not change the underlying series characteristics. If, for example, you elect to show series X in fixed decimal format in the group spreadsheet, but X uses significant digits in its individual series settings, the latter settings will not be modified. To update the display settings in the selected series, you must select the **Apply to underlying series** checkbox in the format dialog.

You may display the observations in the group in sorted order using the Sort/by dialog menu item in the right-mouse menu. EViews will open the Sort Order dialog, prompting you to select sort keys and orders for up to three series.



When you click on OK, EViews will rearrange the group spreadsheet display so that observations are displayed in the specified order.


A quicker alternative, assuming you only want to sort by only one series, is to use the right-mouse button menus. Selecting Sort/Ascending or Sort/Descending sorts the observations using the first selected column of data.

Note that the underlying data in the workfile is not sorted, only the display of observations and observation identifiers in the group spreadsheet. This method of changing the spreadsheet display may prove useful if you wish to determine the identities of observations with high or low values for some series in the group.

Selecting Clear Contents sets the selected observations and variables to NA.

Lastly, you should note that as with series, you may write the contents of the spreadsheet view to a CSV, tab-delimited ASCII text, RTF, or HTML file by selecting Save table to disk... and filling out the resulting dialog.

It is worth pointing out that if you select a set of specific cells in the group spreadsheet and then right-click, you will be presented with a slightly different menu that, among other things, allows you to copy the contents, insert, or delete observations.



Dated Data Table

The dated data table view is used to construct tables for reporting and presenting data, forecasts, and simulation results. This view displays the series contained in the group in a variety of formats. You can also use this view to perform common transformations and frequency conversions, and to display data at various frequencies in the same table.

For example, suppose you wish to show your quarterly data for the GDP and PR series, with data for each year, along with an annual average, on a separate line:

	<u>1994</u>				<u>1994</u>
GDP	1698.6	1727.9	1746.7	1774.0	1736.8
PR	1.04	1.05	1.05	1.06	1.05
	<u>1995</u>				<u>1995</u>
GDP	1792.3	1802.4	1825.3	1845.5	1816.4
PR	1.07	1.07	1.08	1.09	1.08
	<u>1996</u>				<u>1996</u>
GDP	1866.9	1902.0	1919.1	1948.2	1909.0
PR	1.09	1.10	1.11	1.11	1.10

The dated data table handles all of the work of setting up this table, and computing the summary values.

Alternatively, you may wish to display annual averages for each year up to the last, followed by the last four quarterly observations in your sample:

	1994	1995	1996	96:1	96:2	96:3	96:4
GDP	1736.8	1816.4	1909.0	1866.9	1902.0	1919.1	1948.2
PR	1.05	1.08	1.10	1.09	1.10	1.11	1.11

Again, the dated data table may be used to perform the required calculations and to set up the table automatically.

The dated data table is capable of creating more complex tables and performing a variety of other calculations. Note, however, that the dated data table view is currently available only for annual, semi-annual, quarterly, or monthly workfiles.

Creating and Specifying a Dated Data Table

To create a dated data table, create a group containing the series of interest and select View/Dated Data Table . The group window initially displays a default table view. The default is to show a single year of data on each line, along with a summary measure (the annual average).


You can, however, set options to control the display of your data through the Table and Row Options dialogs. Note the presence of two new buttons on the group window toolbar, labeled TabOptions (for Table Options) and RowOptions. TabOptions sets the global options for the dated data table. These options will apply to all series in the group object. The RowOptions button allows you to override the global options for a particular series. Once you specify table and row options for your group, EViews will remember these options the next time you open the dated data table view for the group.

Table Setup

When you click on the TabOptions button, the Table Options dialog appears. The top half of the dialog provides options to control the general style of the table.

The radio buttons on the left hand side of the dialog allow you to choose between the two display formats described above:

- The first style displays the data for n years per row, where n is the positive integer specified in the edit field.
- The second style is a bit more complex. It allows you to specify, for data displayed at a frequency other than annual, the number of observations taken from the end of the workfile sample that are to be displayed. For data displayed at an annual frequency, EViews will display observations over the entire workfile sample.



The two combo boxes on the top right of the dialog supplement your dated display choice by allowing you to display your data at multiple frequencies in each row. The First Columns selection describes the display frequency for the first group of columns, while the

Second Columns selection controls the display for the second group of columns. If you select the same frequency, only one set of results will be displayed.

In each combo box, you may choose among:

- Native frequency (the frequency of the workfile)
- Annual
- Quarterly
- Monthly

If necessary, EViews will perform any frequency conversion (to a lower frequency) required to construct the table.

The effects of these choices on the table display are best described by the following example. For purposes of illustration, note that the current workfile is quarterly, with a current sample of 1993Q1–1996Q4.

Now suppose that you choose to display the first style (two years per row), with the first columns set to the native frequency, and the second columns set to annual frequency. Each row will contain eight quarters of data (the native frequency data) followed by the corresponding two annual observations (the annual frequency data):

	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Year	
	1993				1994				1993	1994
GDP	1611.1	1627.3	1643.6	1676.0	1698.6	1727.9	1746.7	1774.0	1639.5	1736.8
PR	1.02	1.02	1.03	1.04	1.04	1.05	1.05	1.06	1.03	1.05
	1995				1996				1995	1996
GDP	1792.3	1802.4	1825.3	1845.5	1866.9	1902.0	1919.1	1948.2	1816.4	1909.0
PR	1.07	1.07	1.08	1.09	1.09	1.10	1.11	1.11	1.08	1.10

EViews automatically performs the frequency conversion to annual data using the specified method (see ["Transformation Methods" on page 386](#)).

If you reverse the ordering of data types in the first and second columns so that the first columns display the annual data, and the second columns display the native frequency, the dated data table will contain:

			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
	1993	1994	1993				1994			
GDP	1639.5	1736.8	1611.1	1627.3	1643.6	1676.0	1698.6	1727.9	1746.7	1774.0
PR	1.03	1.05	1.02	1.02	1.03	1.04	1.04	1.05	1.05	1.06
	1995	1996	1995				1996			
GDP	1816.4	1909.0	1792.3	1802.4	1825.3	1845.5	1866.9	1902.0	1919.1	1948.2
PR	1.08	1.10	1.07	1.07	1.08	1.09	1.09	1.10	1.11	1.11

Now, click on TabOptions, choose the second display style, and enter 4 in the edit box. Then specify Annual frequency for the first columns and Native frequency for the second columns. EViews will display the annual data for the current sample, followed by the last four quarterly observations:

	1993	1994	1995	1996	96:1	96:2	96:3	96:4
GDP	1639.5	1736.8	1816.4	1909.0	1866.9	1902.0	1919.1	1948.2
PR	1.03	1.05	1.08	1.10	1.09	1.10	1.11	1.11

Additional Table Options

The bottom of the Table Options dialog controls the default data transformations and numeric display for each series in the group. EViews allows you to use two rows, each with a different transformation and a different output format, to describe each series.

For each row, you specify the transformation method, frequency conversion method, and the number format.

Keep in mind that you may override the default transformation for a particular series using the RowOptions menu (see “Row Options” on page 389).

Transformation Methods

The following transformations are available:

None (raw data)	No transformation
1 Period Difference	$y - y_{-1}$
1 Year Difference	$y - y_{-f}$ where $f = \begin{cases} 1 & \text{for annual} \\ 2 & \text{for semi-annual} \\ 4 & \text{for quarterly} \\ 12 & \text{for monthly} \end{cases}$
1 Period % Change	$100 - y - y_{-1} \quad \frac{y}{y_{-1}} - 1$
1 Period % Change at Annual Rate	Computes R such that: $1 + r = 100^f$ where f is defined above and r is the 1 period% change.
1 Year % Change	$100 - y - y_{-f} \quad \frac{y}{y_{-f}} - f$, where f is defined above.
No second row	Do not display a second row

We emphasize that the above transformation methods represent only the most commonly employed transformations. If you wish to construct your table with other transformations, you should add an appropriate auto-series to the group.


Frequency Conversion

The following frequency conversion methods are provided:

Average then Transform	First convert by taking the average, then transform the average, as specified.
Transform then Average	First transform the series, then take the average of the transformed series.
Sum then Transform	First convert by taking the sum, then transform the sum, as specified.
First Period	Convert by taking the first quarter of each year or first month of each quarter/year.
Last Period	Convert by taking the last quarter of each year or last month of each quarter/year.

The choice betweenAverage then Transform and Transform then Average changes the ordering of the transformation and frequency conversion operations. The methods differ only for nonlinear transformations (such as the % change methods).

For example, if we specify the dated data table settings:



EViews will display a table with data formatted in the following fashion:

	Q1	Q2	Q3	Q4	Year
	<u>1993</u>				<u>1993</u>
GDP	1611.1	1627.3	1643.6	1676.0	6558.1
PR	1.02	1.02	1.03	1.04	4.11
	<u>1994</u>				<u>1994</u>
GDP	1698.6	1727.9	1746.7	1774.0	6947.1
PR	1.04	1.05	1.05	1.06	4.20
	<u>1995</u>				<u>1995</u>
GDP	1792.3	1802.4	1825.3	1845.5	7265.4
PR	1.07	1.07	1.08	1.09	4.31
	<u>1996</u>				<u>1996</u>
GDP	1866.9	1902.0	1919.1	1948.2	7636.1
PR	1.09	1.10	1.11	1.11	4.41

If, instead, you change the Frequency Conversion to First Period , EViews will display a table of the form:

	Q1	Q2	Q3	Q4	Year
	<u>1993</u>				<u>1993</u>
GDP	1611.1	1627.3	1643.6	1676.0	1611.1
PR	1.02	1.02	1.03	1.04	1.02
	<u>1994</u>				<u>1994</u>
GDP	1698.6	1727.9	1746.7	1774.0	1698.6
PR	1.04	1.05	1.05	1.06	1.04
	<u>1995</u>				<u>1995</u>
GDP	1792.3	1802.4	1825.3	1845.5	1792.3
PR	1.07	1.07	1.08	1.09	1.07
	<u>1996</u>				<u>1996</u>
GDP	1866.9	1902.0	1919.1	1948.2	1866.9
PR	1.09	1.10	1.11	1.11	1.09

In “[Illustration,](#)” [beginning on page 389](#) , we provide an example which illustrates the computation of the percentage change measures.

Formatting Options

EViews lets you choose between fixed decimal, fixed digit, and auto formatting of the numeric data. Generally, auto formatting will produce appropriate output formatting, but if not, simply select the desired method and enter an integer in the edit field. The options are:

Auto format	EViews chooses the format depending on the data.
Fixed decimal	Specify how many digits to display after the decimal point. This option aligns all numbers at the decimal point.
Fixed chars	Specify how many total characters to display for each number.

EViews will round your data prior to display in order to fit the specified format. This rounding is for display purposes only and does not alter the original data.

Row Options

These options allow you to override the row defaults specified by the Table Options dialog. You can specify a different transformation, frequency conversion method, and number format, for each series.

In the Series Table Row Description dialog that appears, select the series for which you wish to override the table default options. Then specify the transformation, frequency conversion, or number format you want to use for that series. The options are the same as those described above for the row defaults.

Series Table Row Description

Series Name: GDP

Row characteristics

First Row for Series: Transform: Table default, Frequency Conversion: Table default, ☒ Table default (2), ☐ Fixed decimal (7), ☐ Fixed chars (7), ☐ Auto format

Second Row for Series: Transform: Table default, Frequency Conversion: Table default, ☒ Table default (2), ☐ Fixed decimal (7), ☐ Fixed chars (7), ☐ Auto format

Header Row

☐ Place row above data for blank line or heading

OK Cancel

Other Options

Label for NA: allows you to define the symbol used to identify missing values in the table. Bear in mind

that if you choose to display your data in transformed form, the transformation may generate missing values even if none of the raw data are missing. Dated data table transformations are explained above.

If your series has display names, you can use the display name as the label for the series in the table by selecting the Use display names as default labels option. See Chapter 3 for a discussion of display names and the label view.

Illustration

As an example, consider the following dated data table which displays both quarterly and annual data for GDP and PR in 1995 and 1996:

	1995				1996
GDP	1792.3	1802.4	1825.3	1845.5	1816.4
(% ch.)	1.03	0.56	1.27	1.11	4.58
PR	1.07	1.07	1.08	1.09	1.08
(% ch.)	0.80	0.49	0.52	0.55	2.55

	1996				1996
GDP	1866.9	1902.0	1919.1	1948.2	1909.0
(% ch.)	1.16	1.88	0.90	1.52	5.10
PR	1.09	1.10	1.11	1.11	1.10
(% ch.)	0.72	0.41	0.64	0.46	2.27

At the table level, the first row of output for each of the series is set to be untransformed, while the second row will show the 1-period percentage change in the series. The table defaults have both rows set to perform frequency conversion using the Average then Transformed setting. In addition, we use Series Table Row Options dialog to override the second row transformation for PR, setting it to Transform then Average option.

The first four columns show the data in native frequency so the choice between Average then Transform and Transform then Average is irrelevant—each entry in the second row measures the 1-period (1-quarter) percentage change in the variable.

The 1-period percentage change in the last column is computed differently under the two methods. The Average then Transformed percentage change in GDP for 1996 measures the percentage change between the average value in 1995 and the average value in 1996. It is computed as:

$$100 \frac{1909.0 - 1816.3}{1816.4} = 5.10 \quad (12.1)$$

EViews computes this transformation using full precision for intermediate results, then displays the result using the specified number format.

The computation of the Transform then Average one-period change in PR for 1996 is a bit more subtle. Since we wish to compute measure of the annual change, we first evaluate the one-year percentage change at each of the quarters in the year, and then average the results. For example, the one-year percentage change in 1996Q1 is given by $100(1.09 - 1.03)/1.03 = 2.29$ and the one-year percentage change in 1996Q2s $100(1.10 - 1.07)/1.07 = 2.22$. Averaging these percentage changes yields:

$$100 \frac{1.09 - 1.07}{1.07} \frac{1.10 - 1.07}{1.07} \frac{1.11 - 1.08}{1.08} \frac{1.11 - 1.09}{1.09} = 2.27 \quad (12.2)$$

Note also that this computation differs from evaluating the average of the one-quarter percentage changes for each of the quarters of the year.

Other Menu Items

- **Edit+/-** allows you to edit the row (series) labels as well as the actual data in the table. You will not be able to edit any of the computed ranks and any changes that you make to the row labels will only apply to the dated data table view.

We warn you that if you edit a data cell, the underlying series data will also change. This latter feature allows you to use dated data tables for data entry from published sources.

If you want to edit the data in the table but wish to keep the underlying data unchanged, first Freeze the table view and then apply Edit to the frozen table.

- **Font** allows you to choose the font, font style, and font size to be used in the table.
- **Title** allows you to add a title to the table.
- **Sample** allows you to change the sample to display in the table.

Here is an example of a table after freezing and editing:

	1995				<u>1995</u>
Gross Domestic Product	1792.3	1802.4	1825.3	1845.5	1816.4
One-period % change	1.03	0.56	1.27	1.11	4.58
Price Level	1.07	1.07	1.08	1.09	1.08
One-period % change	0.80	0.49	0.52	0.55	2.55
	1996				<u>1996</u>
Gross Domestic Product	1866.9	1902.0	1919.1	1948.2	1909.0
One-period % change	1.16	1.88	0.90	1.52	5.10
Price Level	1.09	1.10	1.11	1.11	1.10
One-period % change	0.72	0.41	0.64	0.46	2.27

Graph

The Graph... menu item brings up the Graph Options dialog, which allows you to select various types of graphical display of the group. You can create graph objects by freezing these views. See [Chapter 13. "Graphing Data," beginning on page 435](#) for a discussion of techniques for creating and customizing the graphical display.

Descriptive Statistics

These views display the summary statistics of each series in the group. Details for each statistic are provided in ["Descriptive Statistics & Tests" on page 316](#)

- Common Sample computes the statistics using observations for which there are no missing values in any of the series in the group (casewise deletion of observations).
- Individual Samples computes the statistics using all nonmissing observations for each series (listwise deletion).

The two views produce identical results if there are no missing values, or if every series has missing observations for the same set of observations.

View	Proc	Object	Print	Name	Freeze	Sample	Sheet	Stats	Spec
				GDP		PR			
Mean				632.4190		0.514106			
Median				374.3000		0.383802			
Maximum				1948.225		1.110511			
Minimum				87.87500		0.197561			
Std. Dev.				564.2441		0.303483			
Skewness				0.845880		0.592712			
Kurtosis				2.345008		1.829239			
Jarque-Bera				24.68300		20.81933			
Probability				0.000004		0.000030			
Sum				113835.4		92.53909			
Sum Sq. Dev.				56988478		16.48625			
Observations				180		180			

Covariance Analysis

The covariance analysis view may be used to obtain different measures of association (covariances and correlations) and associated test statistics for the series in a group. You may compute measures of association from the following general classes:

- ordinary (Pearson product moment)
- ordinary uncentered
- Spearman rank-order
- Kendall's tau-a and tau-b

EViews allows you to calculate partial covariances and correlations for each of these general classes, to compute using balanced or pairwise designs, and to weight individual observations. In addition, you may display your results in a variety of formats and save results to the workfile for further analysis.


Performing Covariance Analysis

We consider the stock price example from Johnson and Wichern (1992, p. 397) in which 100 observations on weekly rates of return for Allied Chemical, Du Pont, Union Carbide, Exxon, and Texaco were examined over the period from January 1975 to December 1976 ("Stocks.WF1"). These data are in the group object G2 containing the series ALLIED, DUPONT, UNION.

To proceed, simply open the group object and select View/Covariance Analysis... to display the covariance dialog:

We will consider the various options in detail below. For now, note that by default, EViews will compute the unweighted ordinary (Pearson product moment) covariance for the data in the group, and display the result in a spreadsheet view.

The current sample of observations in the workfile, “1 100”, will be used by default, and EViews will perform listwise exclusion of cases with missing values to balance the sample if necessary.




The dialog box is titled "Covariance Analysis". It has several sections:

- Statistics:**
 - Method: Ordinary (dropdown)
 - ☒ Covariance, ☐ Correlation, ☐ SSCP, ☐ t-statistic, ☐ Probability | t | = 0
 - Layout: Spreadsheet (dropdown)
- Sample:**
 - 1 100 (text box)
 - ☒ Balanced sample (listwise deletion)
- Partial analysis:**
 - Series or groups for conditioning (optional): (empty text box)
- Options:**
 - Weighting: None (dropdown)
 - Weight series: (empty text box)
 - ☐ d.f. corrected covariances
 - Multiple comparison adjustments: None (dropdown)
 - Saved results basename: (empty text box)

Buttons: OK, Cancel

Click on OK to accept the defaults, and the group display changes to show the covariances between the variables in the group. The sheet header clearly shows that we have computed the covariances for the data. Each cell of the table shows the variances and covariances for the corresponding variables. We see that the rates of return are positively related, though it is difficult to tell at a glance the relative strengths of the relationships.



	ALLIED	DUPONT	EXXON
ALLIED	0.001614	0.000809	0.000438
DUPONT	0.000809	0.001217	0.000383
EXXON	0.000438	0.000383	0.000794

Statistics

Let us now consider some of the options in the dialog in greater detail. The first section of the dialog, labeled Statistics, controls the statistics to be calculated, and the method of displaying our results.

First you may use the Method combo to specify the type of calculations you wish to perform. You may choose between computing ordinary Pearson covariances (Ordinary), uncentered covariances (Ordinary (uncentered)), Spearman rank-order covariances (Spearman rank-order), and Kendall's tau measures of association (Kendall's tau).

The checkboxes below the combo box identify the statistics to be computed. Most of the statistics are self-explanatory, but a few deserve a quick mention


The statistic labeled SSCPrefers to the “sum-of-squared cross-products.” The Number of cases is the number of rows of data used in computing the statistics, while the Number of obs is the obviously the number of observationsemployed. These two values will differ only if frequency weights are employed. The Sum of weights will differ from the number of cases only if weighting is employed, and it will differ from the number of observations only if weights are non-frequency weights.

If you select Kendall's tau from the Method combo, the checkbox area changes to provide you with choices for a different set of covariance statistics. In addition to the previously offered number of cases and obs, and the sum of weights, EViews allows you to display Kendall's tau-a and tau-b, the raw concordances and discordances, Kendall's score statistic, and the probability value for the score statistic.


Turning to the layout options, EViews provides you with up to four display options: Spreadsheet, Single table, Multiple tables, and List. We have already seen the spreadsheet view of the statistics. As the names suggest, the two table views lay out the statistics in a table view; the single table will stack multiple statistics in a single “cell” of the table, while the multiple tables will place the table for the sec-

ond statistic under the table for the first statistic, etc. The list view displays each of the statistics in a separate column of a table, with the rows corresponding to pairs of variables. Note that the spreadsheet view is not available if you select multiple statistics for display.

In this example, we perform ordinary covariance analysis and display multiple statistics in a single table. We see that all of the correlations are positive, and significantly different from zero at conventional levels. Displaying the Correlation instead of Covariance makes it eas-



ier to see that the two chemical companies, Allied and DuPont are more highly correlated with each other than they are with the oil company Exxon.




Group: G2 Workfile: STOCKS::Stocks1

View Proc Object Print Name Freeze Sample Sheet Stats Spec

Covariance Analysis: Ordinary
Date: 08/15/09 Time: 17:39
Sample: 1 100
Included observations: 100

Correlation	ALLIED	DUPONT	EXXON
Probability	1.000000		
Cases	100		
ALLIED	1.000000		
DUPONT	0.576924	1.000000	
EXXON	0.386721	0.389519	1.000000

To compute Spearman rank-order correlations, simply select Spearman rank-order in the Method combo and choose the statistics you wish to compute. Spearman rank-order covariances is a nonparametric measure of correlation that may be thought of as ordinary covariances applied to rank transformed data. Here we display three Spearman results, Correlation, Probability, and Number of cases, arranged in multiple tables:



Group: G2 Workfile: STOCKS::Stocks1

View Proc Object Print Name Freeze Sample Sheet Stats Spec

Covariance Analysis: Spearman rank-order
Date: 08/15/09 Time: 17:41
Sample: 1 100
Included observations: 100

Correlation	ALLIED	DUPONT	EXXON
ALLIED	1.000000		
DUPONT	0.543630	1.000000	
EXXON	0.371183	0.304633	1.000000

Probability	ALLIED	DUPONT	EXXON
ALLIED	0.0000		
DUPONT	0.0000	0.0021	
EXXON	0.0001		0.0021

Cases	ALLIED	DUPONT	EXXON
ALLIED	100		
DUPONT	100	100	
EXXON	100	100	100

Note that the multiple table results make it easier to compare correlations across variables, but more difficult to relate a given correlation to the corresponding probability and number of cases.

A third major class of measures of association is based on Kendall's tau (see [Kendall's Tau" on page 400](#)). Briefly, Kendall's tau for two variables is based on the number of concordances and discordances between the orderings of the variables for all possible comparisons of observations. If the number of concordances and discordances are roughly the same, there is no association between the variables, relatively large numbers of concordances suggest a positive relationship between the variables, and conversely for relatively large numbers of discordances.

Here, we display output in list format, showing Kendall's tau-b, Kendall's D & C, and Probability :

		tau-b	Concord.	Discord.	Probability
ALLIED	ALLIED	1.000000	4913	0	-----
DUPONT	ALLIED	0.379806	3393	1520	0.0000
DUPONT	DUPONT	1.000000	4950	0	-----
EXXON	ALLIED	0.255122	3085	1827	0.0002
EXXON	DUPONT	0.211941	2999	1950	0.0018
EXXON	EXXON	1.000000	4949	0	-----

The results are similar to those obtained from ordinary and Spearman correlations, though the tau-b measures of association are somewhat lower than their counterparts.

Sample

EViews will initialize the edit field with the current workfile sample, but you may modify the entry as desired.

By default, EViews will perform listwise deletion when it encounters missing values so that all statistics are calculated using the same observations. To perform pairwise deletion of missing values, simply uncheck the Balanced sample (listwise deletion) checkbox. Pairwise calculations will use the maximum number of observations for each calculation.

Note that this option will be ignored when performing partial analysis since the latter is only performed on balanced samples


Partial Analysis

A partial covariance is the covariance between two variables while controlling for a set of conditioning variables.

To perform partial covariance analysis in EViews, simply enter a list of conditioning variables in the partial analysis edit field. EViews will automatically balance the sample, compute the statistics and display the results. Partial covariances or correlations will be computed for each pair of analysis variables, controlling for all of the variables in the conditioning set.

Consider the example from Matthews (2000) in which we consider the Pearson correlation between the number of stork breeding pairs and the number of births in 17 European countries. The data are provided in the workfile “Storks.WF1”.

The unconditional correlation coefficient of 0.62 for the STORKS and BIRTH_RATE variables is statistically significant, with a p-value of about 0.008, indicating that the numbers of storks and the numbers of babies are correlated.




Covariance Analysis: Ordinary
Date: 08/15/09 Time: 17:52
Sample: 1 17
Included observations: 17

Correlation	STORKS	BIRTH_RATE
Probability	1.000000	0.620265
Cases	17	17
		0.0079
		17

While some stork lovers may wish to view this correlation as indicative of a real relationship, others might argue that the positive correlation is spurious. One possible explanation lies in the existence of confounding variables or factors which are related to both the stork population and the number of births. Two possible factors are the population and area of the country.

To perform the analysis conditioning on the country area, select the statistics you wish to display, enter AREA in the partial analysis edit field, and press OK. The partial correlation falls to 0.27, with a statistically insignificant p-value of about 0.31.



Partial Covariance Analysis: Ordinary
Date: 08/15/09 Time: 17:53
Sample: 1 17
Included observations: 17
Partial analysis controlling for: AREA

Correlation	STORKS	BIRTH_RATE
Probability	1.000000	0.272773
Cases	17	17
		0.3067
		17

Options

EViews provides a variety of other options for calculating your measures of association and for saving results.

Weighting

When you specify weighting, you will be prompted to enter a different weighting method and the name of a weight series. There are five different weight choices: frequency, variance, standard deviation, scaled variance, and scaled standard deviation.

EViews will compute weighted means and variances using the specified series and weight method. In each case, observations are weighted using the weight series; the different weight choices correspond to different functions of the series and different numbers of observations.

See [“Weighting,” beginning on page 401](#) for details.

Degrees-of-freedom Correction

You may choose to compute covariances using the maximum likelihood estimator or using the unbiased (degree-of-freedom corrected) formula. By default, EViews computes the ML estimates of the covariances.

When you check d.f. corrected covariances, EViews will compute the covariances by dividing the sums-of-squared cross-products by the number of observations n less the number of conditioning elements k , where k equals the number of conditioning variables, including the mean adjustment term, if present. For example, if you compute ordinary covariances conditional on Z_1, Z_2, Z_3 , the divisor will be $n - 4$.

Multiple Comparison Adjustments

You may adjust your probability values for planned multiple comparisons using Bonferroni or Dunn-Sidak adjustments. In both of these approaches you employ a conservative approach to testing by adjusting the level of significance for each comparison so that the overall error does not exceed the nominal size.

The Bonferroni adjustment sets the elementwise size to

$$\alpha_{\text{elementwise}} = \alpha / m \quad (12.3)$$

where α is the specified (overall) size of the tests, and m is the number of tests performed. For the Dunn-Sidak adjustment, we set the elementwise size to

$$\alpha_{\text{elementwise}} = 1 - (1 - \alpha)^{1/m} \quad (12.4)$$

For details, see Sokal and Rohlf (1995, p. 228–240).

Saved Results

You may place the results of the covariance analysis into symmetric matrices in the workfile by specifying a Saved results basename. For each requested statistic, EViews will save the results in a sym matrix named by appending an identifier (“cov,” “corr,” “sscp,” “tstat,” “prob,” “taua,” “taub,” “score” (Kendall's score), “conc” (Kendall's concurrences), “disc” (Kendall's discordances), “cases,” “obs,” “wgts”) to the basename.

For example, if you request ordinary correlations, probability values, and number of observations, and enter “MY” in the Saved results basename edit field, EViews will output three sym matrices MYCORR, MYPROB, MYOBS containing the results. If objects with the specified names already exist, you will be prompted to replace them.

Details

The following is a brief discussion of computational details. For additional discussion, see Johnson and Wichern (1992), Sheskin (1997), Conover (1980) and Kendall and Gibbons (1990).

Ordinary and Uncentered Covariances

The sums-of-squared cross-products are computed using

$$SSCP_{X,Y} = \sum_i (X_i - \hat{m}_X)(Y_i - \hat{m}_Y) \quad (12.5)$$

where $\hat{m}_X$ and $\hat{m}_Y$ are the estimates of the means. For uncentered calculations, the mean estimates will be set to 0.

The covariances are computed by dividing the SSCP by the number of observations with or without a degrees-of-freedom correction:

$$\hat{J}_{X,Y} = \frac{\sum_i (X_i - \hat{m}_X)(Y_i - \hat{m}_Y)}{n - k} \quad (12.6)$$

where n is the number of observations associated with the observed X, Y pairs, and k is a degree-of-freedom adjustment term. By default EViews uses the ML estimator so that $k = 0$, but you may perform a degrees-of-freedom correction that sets k equal to the number of conditioning variables (including of the mean adjustment term, if present).

The correlation between the variables X and Y is computed from the following expression:

$$\hat{r}_{X,Y} = \frac{\hat{J}_{X,Y}}{\sqrt{\hat{J}_{X,X} \hat{J}_{Y,Y}}} \quad (12.7)$$

It is worth reminding you that in unbalanced designs, the numbers of observations used in estimating each of the moments may not be the same.

Spearman Rank-order Covariances

Spearman covariances are a nonparametric measure of association that is obtained by computing ordinary covariances on ranked data, where ties are handled using averaging. To compute the Spearman rank-order covariances and correlations, we simply convert the data to ranks and then compute the centered ordinary counterparts.

Textbooks often provide simplified expressions for the rank correlation in the case where there are no ties. In this case, Equation (12.7) simplifies to:

$$r_{X,Y} = \frac{6 \sum_i (R_{X_i} - R_{Y_i})^2}{n(n^2 - 1)} \quad (12.8)$$

where R returns the rank of the observation.

Kendall's Tau

Kendall's tau is a nonparametric statistic that, like Spearman's rank-order statistic, is based on the ranked data. Unlike Spearman's statistic, Kendall's tau uses only the relative orderings of ranks and not the numeric values of the ranks.

Consider the ranked data for any two observations i and j . We say that there is a concordance in the rankings if the relative orderings of the ranks for the two variables across observations are the same: $R_{X_i} < R_{X_j}$ and $R_{Y_i} < R_{Y_j}$ or $R_{X_i} > R_{X_j}$ and $R_{Y_i} > R_{Y_j}$. Conversely, we say that there is a discordance if the ordering of the X ranks differs from the ordering of the Y ranks: $R_{X_i} < R_{X_j}$ and $R_{Y_i} > R_{Y_j}$ or $R_{X_i} > R_{X_j}$ and $R_{Y_i} < R_{Y_j}$. If there are ties in the ranks of either the X or the Y pairs, we say the observation is neither concordant or discordant.

Intuitively, if X and Y are positively correlated, the number of concordances should outnumber the number of discordances. The converse should hold if X and Y are negatively related.

We may form a simple measure of the relationship between the variables by considering Kendall's score S , defined as the excess of the concordant pairs, C , over the discordant pairs, D . S which may be expressed as:

$$S_{X,Y} = \sum_{i,j} \text{sgn}(R_{X_i} - R_{X_j}) \text{sgn}(R_{Y_i} - R_{Y_j}) \quad (12.9)$$

where the sign function takes the values -1, 0, and 1 depending on whether its argument is negative, zero, or positive. Kendall's tau-a is defined as the average of the excess of the con-

cordant over the discordant pairs. There are $n(n-1)/2$ unique comparisons of pairs of observations that are possible so that:

$$t_a(X, Y) = \frac{S(X, Y)}{n(n-1)/2} \quad (12.10)$$

In the absence of tied ranks, $-1 \leq t_a \leq 1$, with $t_a = 1$ when all pairs are concordant and $t_a = -1$ when all pairs are discordant.

One disadvantage of t_a is that the endpoint values -1 and 1 are not reached in the presence of tied ranks. Kendall's tau-b t_b rescales t_a by adjusting the denominator of t_a to account for the ties:

$$t_b(X, Y) = \frac{S(X, Y)}{\sqrt{\left[\frac{n(n-1)}{2} - \sum_s \frac{t_s(t_s-1)}{2} \right] \left[\frac{n(n-1)}{2} - \sum_v \frac{u_v(u_v-1)}{2} \right]}} \quad (12.11)$$

where t_s are the number of observations tied at each unique rank of X , and u_v are the number of observations tied at each rank of Y . This rescaling ensures that $t_b(X, X) = 1$. Note that in the absence of ties, the summation terms involving t and u equal zero so that $t_a = t_b$.

It is worth noting that computation of these measures requires $n(n-1)/2$ comparisons, a number which increases rapidly with n . As a result, textbooks sometimes warn users about computing Kendall's tau for moderate to large samples. EViews uses very efficient algorithms for this computation, so for practical purposes, the warning may safely be ignored. If you find that the computation is taking too long, pressing the ESC break key may be used to stop the computation.

Weighting

Suppose that our weight series Z has m individual cases denoted by z_i . Then the weights and number of observations associated with each of the possible weighting methods are given by:

Method	Weights: w_i	Observations: n
Frequency	z_i	$\sum w_i$
Variance	z_i	m
Std. Dev.	z_i^2	m
Scaled Variance	$mz_i + \sum z_i$	$\sum w_i = m$
Scaled Std. Dev.	$mz_i + \sum z_i^2$	m

Frequency weighting is the only weighting allowed for Spearman's rank-order and Kendall's tau measures of association.

The weighted SSCP is given by

$$\text{WSSCP } X, Y = \sum_i w_i (X_i - \tilde{m}_X)(Y_i - \tilde{m}_Y) \quad (12.12)$$

where the X_i and Y_i are the original data or ranks (respectively), the $\tilde{m}$ are weighted means (or zeros if computing uncentered covariances), and the w_i are weights that are functions of the specified weight series.

If estimated, the weighted means of X and Y are given by:

$$\tilde{m}_X = \frac{\sum_i w_i X_i}{\sum_i w_i}, \quad \tilde{m}_Y = \frac{\sum_i w_i Y_i}{\sum_i w_i} \quad (12.13)$$

where n is the number of observations.

The weighted variances are given by

$$\tilde{s}^2_{X, Y} = \frac{\sum_i w_i (X_i - \tilde{m}_X)(Y_i - \tilde{m}_Y)}{n - k} \quad (12.14)$$

and the weighted correlations by

$$\tilde{r}_{XY} = \frac{\tilde{s}_{X, Y}}{\sqrt{\tilde{s}^2_{X, X} \tilde{s}^2_{Y, Y}}} \quad (12.15)$$

The weighted Kendall's tau measures are derived by implicitly expanding the data to accommodate the repeated observations, and then evaluating the number of concordances and discordances in the usual fashion.

Testing

The test statistics and associated p -values reported by EViews are for testing the hypothesis that a single correlation coefficient is equal to zero. If specified, the p -values will be adjusted using Bonferroni or Dunn-Sidak methods (see ["Multiple Comparison Adjustments,"](#) on page 398).

For ordinary Pearson and Spearman correlations, the t -statistic is computed as

$$t = \frac{r \sqrt{n - k - 1}}{\sqrt{1 - r^2}} \quad (12.16)$$

where r is the estimated correlation, and k is the number of conditioning variables, including the implicit mean adjustment term, if necessary. The p -value is obtained from a t -distribution with $n - k - 1$ degrees-of-freedom (Sheskin, 1997, p. 545, 598).

In the leading case of centered non-partial correlations, $k = 1$, so the degrees-of-freedom is $n - 2$. For centered partial correlations, $k = k_{\text{„}} - 1$ where $k_{\text{„}}$ is the number of non-redundant conditioning variables, so the degrees of freedom is given by $n - k_{\text{„}} - 2$.

The test of significance for Kendall's tau is based on a normal approximation using the continuity corrected z -statistic (Kendall and Gibbons, 1990, p. 65–66):

$$z = \frac{S - \text{sgn } S}{\sqrt{\text{var}(S)}} \quad (12.17)$$

where the variance is given by:

$$\text{var}(S) = S_1 + S_2 + S_3 \quad (12.18)$$

for

$$\begin{aligned} S_1 &= \frac{1}{18} n(n-1)(2n-5) - \sum_s Q_s t_s - 1 \quad 2t_s - 5 - \sum_v Q_v u_v - 1 \quad 2u_v - 5 \quad \textcircled{S} \\ S_2 &= \frac{1}{9n(n-1)(n-2)} \sum_s Q_s t_s - 1 \quad t_s - 2 \quad \textcircled{S} \sum_v Q_v u_v - 1 \quad u_v - 2 \quad \textcircled{S} \\ S_3 &= \frac{1}{2n(n-1)} \sum_s Q_s t_s - 1 \quad \textcircled{S} \sum_v Q_v u_v - 1 \quad \textcircled{S} \end{aligned} \quad (12.19)$$

where t_s are the number of observations tied at each unique rank of X and u_v are the number of observations tied at each rank of Y . In the absence of ties, Equation (12.18) reduces to the expression:

$$\text{var } S = \frac{1}{18} n(n-1)(2n-5) \quad (12.20)$$

usually provided in textbooks (e.g., Sheskin, 1997, p. 633).

Probability values are approximated by evaluating the two-tailed probability of z using the standard normal distribution. Note that this approximation may not be appropriate for small sample sizes; Kendall and Gibbons (1990) suggest that the approximation is not generally recommended for $n \leq 30$ (in the untied case).

Significance level values are currently not provided for partial Kendall's tau.

Partial Analysis

Let $W = X, Y$ be the set of analysis variables, and let Z be the set of conditioning variables.

For the ordinary and Spearman rank-order calculations, the joint sums of squares and cross-products for the two sets of variables are given by:

$$S = \begin{bmatrix} S_{ZZ} & S_{ZW} \\ S_{WZ} & S_{WW} \end{bmatrix} \quad (12.21)$$

EViews conditions on the Z variables by calculating the partial SSCP using the partitioned inverse formula:

$$S_{WW|Z} = S_{WW} - S_{WZ} S_{ZZ}^{-1} S_{ZW} \quad (12.22)$$

In the case where S_{ZZ} is not numerically positive definite, Z is replaced by a subset of Z formed by sequentially adding variables that are not linear combinations of those already included in the subset.

Partial covariances are derived by dividing the partial SSCP by $n - k$; partial correlations are derived by applying the usual correlation formula (scaling the partial covariance to unit diagonals).

For Kendall's tau computations, the partitioned inverse is applied to the corresponding matrix of joint Kendall's tau values. The partial Kendall's tau values are obtained by applying the correlation formula to the partitioned inverse.

N-Way Tabulation


This view classifies the observations in the current sample into cells defined by the series in the group. You can display the cell counts in various forms and examine statistics for independence among the series in the group. Select **View/N-Way Tabulation...** which opens the tabulation dialog.

Many of the settings will be familiar from our discussion of one-way tabulation in [“One-Way Tabulation” on page 332](#).

Group into Bins If

If one or more of the series in the group is continuous and takes many distinct values, the number of cells becomes excessively large. This option provides you two ways to automatically bin the values of the series into subgroups.

- **Number of values** option bins the series if the series takes more than the specified number of distinct values.



- Average count option bins the series if the average count for each distinct value of the series is less than the specified number.
- Maximum number of bins specifies the approximate maximum number of sub-groups to bin the series. The number of bins may be chosen to be smaller than this number in order to make the bins approximately the same size.

The default setting is to bin a series into approximately 5 subgroups if the series takes more than 100 distinct values or if the average count is less than 2. If you do not want to bin the series, unmark both options.

NA Handling

By default, EViews drops observations from the contingency table where any of the series in the group has a missing value. Treat NA as category option includes all observations and counts NAs in the contingency table as an explicit category.

Layout

This option controls the display style of the tabulation. The Table mode displays the categories of the first two series in $r \times c$ tables for each category of the remaining series in the group.

The List mode displays the table in a more compact, hierarchical form. The Sparse Labels option omits repeated category labels to make the list less cluttered. Note that some of the conditional χ^2 statistics are not displayed in list mode.

Output

To understand the options for output, consider a group with three series. Let (i, j, k) index the bin of the first, second, and third series, respectively. The number of observations in the (i, j, k) -th cell is denoted as n_{ijk} with a total of $N = \sum_i \sum_j \sum_k n_{ijk}$ observations.

- Overall% is the percentage of the total number of observations accounted for by the cell count.
- Table% is the percentage of the total number of observations in the conditional table accounted for by the cell count.
- Row% is the percentage of the number of observations in the row accounted for by the cell count.
- Column% is the percentage of the number of observations in the column accounted for by the cell count.

The overall expected count in the (i, j, k) -th cell is the number expected if all series in the group were independent of each other. This expectation is estimated by:

$$\hat{n}_{ijk} = \frac{C_{i,jk} \cdot N_{\cdot j}}{N_{\cdot j}} = \frac{C_{i,jk} \cdot N_{\cdot j}}{N_{\cdot j}} \quad (12.23)$$

The table expected count $\tilde{n}_{ijk}$ is estimated by computing the expected count for the conditional table. For a given table, this expected value is estimated by:

$$\tilde{n}_{ijk} = \frac{C_{i,jk} \cdot N_{k\cdot}}{N_{k\cdot}} = \frac{C_{i,jk} \cdot N_{k\cdot}}{N_{k\cdot}} \quad (12.24)$$

where $N_{k\cdot}$ is the total number of observations in the k table.

Chi-square Tests

If you select the Chi-square tests option, EViews reports χ^2 statistics for testing the independence of the series in the group. The test statistics are based on the distance between the actual cell count and the count expected under independence.

- Overall (unconditional) independence among all series in the group. EViews reports the following two test statistics for overall independence among all series in the group:

$$\text{Pearson } \chi^2 = \sum_{i,j,k} \frac{(\hat{n}_{i,j,k} - n_{i,j,k})^2}{n_{i,j,k}} \quad (12.25)$$

$$\text{Likelihood ratio } \chi^2 = 2 \sum_{i,j,k} n_{i,j,k} \log \frac{n_{i,j,k}}{\tilde{n}_{i,j,k}}$$

where n_{ijk} and $\tilde{n}_{ijk}$ are the actual and overall expected count in each cell. Under the null hypothesis of independence, the two statistics are asymptotically distributed χ^2 with $IJK - I - J - K - 1$ degrees of freedom where I, J, K are the number of categories for each series.

These test statistics are reported at the top of the contingency table. For example, the top portion of the tabulation output for the group containing LWAGE, UNION, and MARRIED in the workfile "Cps88.WF1" shows:

Tabulation of LWAGE and UNION and MARRIED

Date: 08/18/09 Time: 15:15

Sample: 1 1000

Included observations: 1000

Tabulation Summary

Variable	Categories
LWAGE	5
UNION	2
MARRIED	2
Product of Categories	20

<u>Test Statistics</u>	<u>df</u>	<u>Value</u>	<u>Prob</u>
Pearson X2	13	174.5895	0.0000
Likelihood Ratio G2	13	167.4912	0.0000

WARNING: Expected value is less than 5 in 40.00% of cells (8 of 20).

The three series LWAGE, UNION, and MARRIED, have 5, 2, and 2 categories, respectively. Note the WARNING message: if there are many cells with expected value less than 5, the small sample distribution of the test statistic under the null hypothesis may deviate considerably from the asymptotic χ^2 distribution.

- Conditional independence between series in the group. If you display in table mode, EViews presents measures of association for each conditional table. These measures are analogous to the correlation coefficient; the larger the measure, the larger the association between the row series and the column series in the table. In addition to the Pearson χ^2 for the table, the following three measures of association are reported:

$$\text{Phi coefficient} = \frac{\sqrt{\tilde{\chi}^2}}{\sqrt{N}} \quad (12.26)$$

$$\text{Cramers V} = \frac{\sqrt{\tilde{\chi}^2}}{\sqrt{\tilde{\chi}^2 + \min(r, c) - 1}} \cdot \frac{1}{\sqrt{N}} \quad (12.27)$$

$$\text{Contingency coefficient} = \frac{\sqrt{\tilde{\chi}^2}}{\sqrt{\tilde{\chi}^2 + N}} \quad (12.28)$$

where $\min(r, c)$ is the smaller of the number of row categories r or column categories c of the table, and N is the number of observations in the table. Note that all three measures are bounded between 0 and 1, a higher number indicating a stronger relation between the two series in the table. While the correlation coefficient only measures the linear association between two series, these nonparametric measures are robust to departures from linearity.

Table 1: Conditional table for MARRIED=0:

Count		UNION		Total
		0	1	
LWAGE	[0, 1)	0	0	0
	[1, 2)	167	8	175
	[2, 3)	121	44	165
	[3, 4)	17	2	19
	[4, 5)	0	0	0
Total		305	54	359
Measures of Association		Value		
Phi Coefficient		0.302101		
Cramer's V		0.302101		
Contingency Coefficient		0.289193		
<u>Table Statistics</u>		<u>df</u>	<u>Value</u>	<u>Prob</u>
Pearson X2		2	32.76419	0.0000
Likelihood Ratio G2		2	34.87208	0.0000

Note: Expected value is less than 5 in 16.67% of cells (1 of 6).

Bear in mind that these measures of association are computed for each two-way table. The conditional tables are presented at the top, and the unconditional tables are reported at the bottom of the view.


Tests of Equality

This view tests the null hypothesis that all series in the group have the same mean, median (distribution), or variance. All of these tests are described in detail in [“Equality Tests by Classification” on page 324](#)

The Common sample option uses only observations for which none of the series in the group has missing values.

As an illustration, we demonstrate the use of this view to test for groupwise heteroskedasticity. Suppose we use data for seven countries over the period 1950–1992 and estimate a pooled OLS model (see [Chapter 35. “Pooled Time Series, Cross-Section Data,” on page 565](#) of User’s Guide I). To test whether the residuals from this pooled regression are groupwise heteroskedastic, we test the equality of the variances of the residuals for each country.

First, save the residuals from the pooled OLS regression and make a group of the residuals corresponding to each country. This is most easily done by estimating the pooled OLS regression using a pool object and saving the residuals by selecting Proc/Make Residuals in the pool object menu or toolbar.



Next, open a group containing the residual series. One method is to highlight each residual series with the right mouse button, double click in the highlighted area and select Open Group. Alternatively, you can type show, followed by the names of the residual series, in the command window.

Select View/Tests of Equality..., and choose the Variance option in the Test Between Series dialog box.

Test for Equality of Variances Between Series

Date: 08/18/09 Time: 15:56

Sample: 1935 1954

Included observations: 20

Method	df	Value	Probability
Bartlett	9	496.0973	0.0000
Levene	(9, 190)	14.47574	0.0000
Brown-Forsythe	(9, 190)	9.566464	0.0000

Category Statistics

Variable	Count	Std. Dev.	Mean Abs.	Mean Abs.
			Mean Diff.	Median Diff.
IAR	20	15.16693	12.02575	11.98550
ICH	20	42.72556	32.89755	29.64650
IDM	20	1.718661	1.474400	1.335500
IGE	20	48.58450	40.96800	39.70000
IGM	20	309.5746	212.1080	192.1700
IGY	20	14.88117	13.04590	12.91000
IIB	20	34.94722	27.96830	25.88800
IUO	20	18.31569	14.13405	13.80250
IUS	20	125.3994	96.11750	95.28500
IWH	20	19.11019	14.92465	14.56250
All	200	216.8753	46.56641	43.72855

Bartlett weighted standard deviation: 108.6848

Here we see results for testing the equality of variances for investment by various firms using data in the workfile "Grunfeld_baltagi_pool.WF1". The test statistics providing strong evidence of the presence of firmwise heteroskedasticity, decisively rejecting the null hypothesis of equal variances.

Principal Components

Principal components analysis models the variance structure of a set of observed variables using linear combinations of the variables. These linear combinations, or components, may be used in subsequent analysis, and the combination coefficients, or loadings, may be used in interpreting the components. While we generally require as many components as vari-

ables to reproduce the original variance structure, we usually hope to account for most of the original variability using a relatively small number of components.

We may, for example, have a very large number of variables describing individual health status that we wish to reduce to a manageable set. By forming linear combinations of the observed variables we may achieve data reduction by creating a handful of measures that describe overall health (e.g., “strength,” “fitness,” “disabilities”). The coefficients in these linear combinations may be used to provide interpretation to the newly constructed health measures.

The principal components of a set of variables are obtained by computing the eigenvalue decomposition of the observed variance matrix. The first principal component is the unit-length linear combination of the original variables with maximum variance. Subsequent principal components maximize variance among unit-length linear combinations that are orthogonal to the previous components.

For additional details see Johnson and Wichern (1992).


Performing Principal Components

EViews allows you to compute the principal components of the estimated correlation or covariance matrix of a group of series, and to display your results in a variety of ways. You may display the table of eigenvalues and eigenvectors, display line graphs of the ordered eigenvalues, and examine scatterplots of the loadings and component scores. Furthermore you may save the component scores and corresponding loadings to the workfile.

As an illustration, we again consider the stock price example from Johnson and Wichern (1992) in which 100 observations on weekly rates of return for Allied Chemical, DuPont, Union Carbide, Exxon, and Texaco were examined over the period from January 1975 to December 1976 (“Stock.WF1”).

To perform principal components on these data, we open the group G1 containing the series and select View/Principal Components... to open the dialog:

The principal components dialog has two tabs. Here, we have selected the first tab, labeled Components. The second tab, labeled Calculation, controls the computation of the dispersion matrix from the series in the group. By default, EViews will perform principal components on the ordinary (Pearson) correlation matrix, but you may use the settings on this tab to modify the preliminary calculation. We will examine this tab in greater detail in ["Covariance Calculation" on page 417](#).



Viewing the Components

The Components tab is used to specify options for displaying the components or saving the eigenvalues and eigenvectors of the variances.

The Display box allows you to choose between showing the eigenvalues and eigenvectors in a tabular form, or displaying line graphs of the ordered eigenvalues, or scatterplots of the loadings, scores, or both (biplot). As you select different display methods, the remainder of the dialog will change to provide you with different settings.

Table

In the figure above, the Table display setting is chosen. There are two sets of fields that you may wish to modify.

First, EViews provides you with three settings for controlling the number of components to be displayed; the number displayed will be the minimum number satisfying any of the criteria. The Maximum number setting should be self-explanatory. The Minimum eigenvalue instructs EViews to only show results for components where the eigenvalue (variance) exceeds a threshold. The Cumulative proportion target tells EViews to retain the first m components such that the sum of their proportion of the variances

meets or exceeds the target proportion of the total variance. By default, the settings are chosen so that all components will be retained.

The Output fields allow you to save the eigenvalues and eigenvectors to the workfile. Simply enter a valid name in the corresponding field if you wish EViews to save your results.

If we leave the default settings as is and click OK, EViews will display a table of results.

Principal Components Analysis

Date: 08/18/09 Time: 15:58

Sample: 1 100

Included observations: 100

Computed using: Ordinary correlations

Extracting 5 of 5 possible components

Eigenvalues: (Sum = 5, Average = 1)

Number	Value	Difference	Proportion	Cumulative Value	Cumulative Proportion
1	2.856487	2.047368	0.5713	2.856487	0.5713
2	0.809118	0.269075	0.1618	3.665605	0.7331
3	0.540044	0.088697	0.1080	4.205649	0.8411
4	0.451347	0.108343	0.0903	4.656996	0.9314
5	0.343004	---	0.0686	5.000000	1.0000

Eigenvectors (loadings):

Variable	PC 1	PC 2	PC 3	PC 4	PC 5
ALLIED	0.463541	-0.240850	-0.613357	0.381373	-0.453288
DUPONT	0.457076	-0.509100	0.177900	0.211307	0.674981
UNION	0.469980	-0.260577	0.337036	-0.664098	-0.395725
EXXON	0.421677	0.525265	0.539018	0.472804	-0.179448
TEXACO	0.421329	0.582242	-0.433603	-0.381227	0.387467

Here we show the top two sections of the table. The header describes the sample of observations, the method used to compute the dispersion matrix, and information about the number of components retained (in this case, all five).

The next section summarizes the eigenvalues, showing the values, the forward difference in the eigenvalues, the proportion of total variance explained, etc. Since we are performing principal components on a correlation matrix, the sum of the scaled variances for the five variables is equal to 5. The first principal component accounts for 57% of the total variance ($2.856/5.00 = 0.5713$), while the second accounts for 16% ($0.809/5.00 = 0.1618$) of the total. The first two components account for over 73% of the total variation.

The second section describes the linear combination coefficients. We see that the first principal component (labeled "PC1") is a roughly-equal linear combination of all five of the stock returns; it might reasonably be interpreted as a general stock return index. The second principal component (labeled "PC2") has negative loadings for the three chemical firms

(Allied, du Pont and Union Carbide), and positive loadings for the oil firms (Exxon and Texaco). This loading appears to represent an industry specific component.

The third section of the output displays the calculated correlation matrix:


Ordinary correlations:

	ALLIED	DUPONT	UNION	EXXON	TEXACO
ALLIED	1.000000				
DUPONT	0.576924	1.000000			
UNION	0.508656	0.598384	1.000000		
EXXON	0.386721	0.389519	0.436101	1.000000	
TEXACO	0.462178	0.321953	0.425627	0.523529	1.000000

Eigenvalues Plots

You may elect to display line graphs of the ordered eigenvalues by selecting Eigenvalues plots in the Display portion of the main dialog. The dialog will change to offer you the choice of displaying plots of any of: the eigenvalues (scree plot), the eigenvalues difference, the cumulative proportion of variance explained. By default, EViews will only display the scree plot of ordered eigenvalues.

For the stock data, displaying the scree and cumulative proportion graphs yields the graph depicted here. The scree plot in the upper portion of the view shows the sharp decline between the first and second eigenvalues. Also depicted in the graph is a horizontal line marking the mean value of the eigenvalues (which is always 1 for eigenvalue analysis conducted on correlation matrices).



The lower portion of the graph shows the cumulative proportion of the total variance. As we saw in the table, the first two components account for about 73% of the total variation. The diagonal reference line offers an alternative method of evaluating the size of the eigenvalues. The slope of the reference line may be compared with the slope of the cumulative pro-

portion; segments of the latter that are steeper than the reference line have eigenvalues that exceed the mean.

Other Graphs (Variable Loadings, Component Scores, Biplots)

The remaining three graphs selections produce graphs of the loadings (variables) and scores (observations): the variable loadings plots (Variable loadings plot) produce component-wise plots of the eigenvectors (factor loading coefficients), allowing you to visualize the composition of the components in terms of the original variables; the scores plot (Component scores plot) shows the actual values of the components for the observations in the sample; the biplot (Biplots (scores & loadings)) combines the loadings and scores plots in one display.

We continue our example by displaying the biplot graph since it includes the options for both the loadings and scores plots. If we select the Biplots (scores and loadings) entry, the right side of the dialog changes to provide additional plot options.

Components to Plot

The top right portion of the dialog, labeled Components to plot, is where you will provide the basic specification for the graphs that you want to display.

First, you must provide a list of components to plot. Here, the default setting “1 2” instructs EViews to place the first component on the x-axis and the second component on the y-axis. You may reverse the order of the axes by reversing the indices.

Principal Components

Components | Calculation

Display

- Table
- Eigenvalues plots
- Variable loadings plots
- Component scores plots
- Biplots (scores & loadings)**

Scatterplots of observation scores with loadings axes.

Components to plot

Enter list or vector of two or more indices:

1 2

Multiple graphs: First vs. All

Scaling: Normalize loadings

Output

Eigenvalues vector:

Eigenvectors matrix:

Graph options

☒ Center graphs around zero

Obs. labels: Label outliers

Loadings axis scaling: Automatic

OK Cancel

You may add indices for additional components. When more than two indices are provided, the Multiple graphs setting provides choices for how you wish to process the indices. You may elect to plot the first listed component against the remaining components (First vs. All), to use successive pairs of indices to form plots (XY pairs), or to plot each component against the others (Lower triangular matrix).


The Scaling options determine the weights to be applied to eigenvalues in the scores and the loadings (see “[Technical Discussion](#),” beginning on page 418 for details). By default, the

loadings are normalized so the observation scores have norms proportional to the eigenvalues (Normalize loadings). You may instead choose to normalize the scores instead of the loadings (Normalize scores) so that the observation score norms are proportional to unity, to apply symmetric weighting (Symmetric weights), or to specify a user-supplied loading weight (User loading weight).

In the latter three cases, you will be prompted to indicate whether you wish to adjust the results account for the sample size (Adjust scores & loadings for sample size). By default, EVIEWS uses this setting and scales the loadings and scores so that the variances of the scores (instead of the norms) have the desired structure (see [“Observation Scaling” on page 421](#)). Setting this option may improve the interpretability of the plot. For example, when normalizing scores, the weight adjustment scales the results so that the Euclidean distances between observations are the Mahalanobis distances and the cosines of the angles between variables are the covariances.

Using the default settings and clicking on OK, EVIEWS produces the view:

The component scores are displayed as circles and the variable loadings are displayed as lines from the origin with variable labels. The biplot clearly shows us that the first component has positive loadings for all five variables (the general stock return index interpretation). The second component has positive variable loadings for the energy stocks, and negative loadings for the chemical stocks; when the energy stocks do well relative to the chemical stocks, the second specific component will be positive, and vice versa.



The scores labels show us that observation 3 is an outlier, with a high value for the general stock market index, and a relatively neutral value for the sector index. Observation 37 shows a poor return for the general market but is relatively sector neutral. In contrast, observation 20 is a period in which the overall market return was positive, with high returns to the energy sector relative to the chemical sector.

Graph Options

There are three additional options provided under Graph options . The first option is to Center graphs around zero . Unchecking this box will generally enlarge the graph within the frame at the expense of making it somewhat more difficult to quickly discern the signs of scores and loadings in a given dimension.

The Obs. labels combo allows you to choose the style of text labeling for observations. By default, EViews will Label outliers , but you may instead choose to Label all obs. or to display Symbols only . If you choose to label outliers, EViews will use a cutoff based on the specified probability value for the Mahalanobis distance of the observation from 0. The default is 0.1 so that labeled observations differ from the 0 with probability less than 0.1.

The last option, Loadings axis scaling , is available only for biplot graphs. Note that the observations and variables in a biplot will generally have very different data scales. Instead of displaying biplots with dual scales, EViews applies a constant scaling factor to the loadings axes to make the graph easier-to-read. Loadings axis scaling allows you to override the EViews default scale for the loadings in two distinct ways.

First, you may instruct EViews to apply a scale factor to the automatically chosen factor. This method is useful if you would like to stretch or shrink the EViews default axes. With the Loadings axis scaling set to Automatic , simply enter your desired adjustment factor. The automatically determined loadings will be scaled by this factor.

Alternatively, if you wish to assign an absolute scaling factor, select User-specified for the axis scaling, and enter your scale factor. The original loadings will be scaled by this factor.

Saving Component Scores

EViews provides easy-to-use tools for saving the principal components scores and scaled loadings matrices in the workfile. Simply select Proc/Make Principal Components... from the main group menu to display the dialog.

As with the main principal components view, the dialog has two tabs. The second tab controls the calculation of the dispersion matrix. The first describes the results that you wish to save.


The first option, **Scaling**, specifies the weights to be applied to eigenvalues in the scores and the loadings (see [Technical Discussion](#), beginning on [page 418](#) for details). By default, EViews will save the scores associated with normalized loadings (Normalize loadings), but you may elect to save normalized scores (Normalize scores), equal weighted scores and loadings (Symmetric weights), or user weighted loadings (User loading weight). The normalized loadings scores will have variances equal to the corresponding eigenvalues; the normalized scores will obviously have unit variance.

For the latter three selections, you are also given the option of adjusting the scores and loadings for the sample size. If **Adjust scores & loadings for sample size** is selected, the scores are scaled so that their variance rather than the sums-of-squares (norms) match the desired value. In this example, the sample variances of the component scores will equal 1.

Next, you should enter names for the score series, one name per component score you wish to save. Here we enter two component names, "Market" and "Industry," corresponding to the interpretation of our components given above. You may optionally save the loadings corresponding to the saved scores, eigenvalues, and eigenvectors to the workfile.

Covariance Calculation

The EViews routines for principal components allow you to compute the dispersion matrix for the series in a group in a number of ways. Simply click on the **Calculation** tab to display the preliminary calculation settings.



The Type combo allows you to choose between computing a Correlation or a Covariance matrix.

The Method combo specifies computation of Ordinary, Ordinary (uncentered), Spearman rank-order or Kendall's tau-a, or Kendall's tau-b measures. The Type selection combo is not applicable if you select Kendall's tau-a or Kendall's tau-b as your method.

The remaining settings should be familiar from the covariance analysis view ([“Covariance Analysis” on page 392](#)). You may, for example, specify the sample of observations to be used and perform listwise exclusion of cases with missing values to balance the sample if necessary. Or you can perform partial and/or weighted analysis.

Note that component scores may not be computed for dispersion matrices estimated using Kendall's tau-a and tau-b.

Technical Discussion

From the singular value decomposition, we may represent an $n \times p$ data matrix Y of rank r as:

$$Y = UDV^T, \quad (12.29)$$

where U and V are orthonormal matrices of the left and right singular vectors, and D is a diagonal matrix containing the singular values.

More generally, we may write:

$$Y = AB^T, \quad (12.30)$$

where A is an $n \times r$, and B is a $p \times r$ matrix, both of rank r , and

$$\begin{aligned} A &= n^{-b/2} U D^{1-a} \\ B &= n^{-b/2} V D^a \end{aligned} \quad (12.31)$$

so that $0 \leq a \leq 1$ is a factor which adjusts the relative weighting of the left (observations) and right (variables) singular vectors, and the terms involving b are scaling factors where $b \geq 0$, $a \in [0, 1]$. The basic options in computing the scores A and the corresponding loadings

B involve the choice of (loading) weight parameter a and (observation) scaling parameter b .

In the principal components context, let S be the cross-product moment (dispersion) matrix of Y , and perform the eigenvalue decomposition:

$$S = L L' L \quad (12.32)$$

where L is the $p \times p$ matrix of eigenvectors and L is the diagonal matrix with eigenvalues on the diagonal. The eigenvectors, which are given by the columns of L , are identified up to the choice of sign. Note that since the eigenvectors are by construction orthogonal, $L' L = L L' = I_m$.

We may set $U = Y L D^{-1}$, $V = L$, and $D = n L^{-1/2}$, so that:

$$\begin{aligned} A &= n^{b/2} Y L D^{-a} \\ B &= n^{-b/2} L D^a \end{aligned} \quad (12.33)$$

A may be interpreted as the weighted principal components scores and B as the weighted principal components loadings. Then the scores and loadings have the following properties:

$$\begin{aligned} A A' &= n^b D^{-a} L' Y' Y L D^{-a} = n^b n L^{-a/2} n L^{-a/2} = n^b n L^{1-a} \\ B B' &= n^{-b} D^a L' L D^a = n^{-b} n L^a \\ B B' &= n^{-b} L D^{2a} L' = n^{-b} L n L^a L' \end{aligned} \quad (12.34)$$

Through appropriate choice of the weight parameter a and the scaling parameter b , you may construct scores and loadings with various properties (see [“Loading Weights” on page 419](#) and [“Observation Scaling” on page 421](#)). EViews provides you with the opportunity to choose appropriate values for these parameters when displaying graphs of principal component scores and loadings and when saving scores and loadings to the workfile.

Note that when computing scores using [Equation \(12.33\)](#), EViews will transform the Y to match the data used in the original computation. For example, the data will be scaled for analysis of correlation matrices, and partialing will remove means and any conditioning variables. Similarly, if the preliminary analysis involves Spearman rank-order correlations, the data are transformed to ranks prior to partialing. Scores may not be computed for dispersion matrices estimated using Kendall's tau.

Loading Weights

At one extreme, we define the normalized loadings (also termed the form, or JK) decomposition where $a = b = 0$. The scores formed from the normalized loadings decomposition will have variances equal to the corresponding eigenvalues. To see this, substituting into [Equation \(12.33\)](#), and using [Equation \(12.30\)](#) we have $Y = JK$, where:

$$\begin{matrix} J & YL \\ K & L \end{matrix} \quad (12.35)$$

From Equation (12.34), the scores J and loadings K have the norms:

$$\begin{matrix} J & J & nL \\ K & K & I_p \end{matrix} \quad (12.36)$$

The rows of J are said to be in principal coordinates, since the norm of J is the diagonal matrix with the eigenvalues on the diagonal. The columns of K are in standard coordinates since K is orthonormal (Aitchison and Greenwood, 2002, p. 378). The JK specification has a row preserving metric (RPM) since the observations in J retain their original scale.

At the other extreme, we define the normalized scores (also referred to as the covariance or GH) decomposition where $\alpha = 1$. Then we may write $Y = GH$, where:

$$\begin{matrix} G & n^{-b} Y L D^{-1} \\ H & n^{-b} L D \end{matrix} \quad (12.37)$$

Evaluating the norms using Equation (12.34), we have:

$$\begin{matrix} G & G & n^b I_p \\ H & H & n^{-b} nL \\ HH & & n^{-b} L nL L & n^{1-b} S \end{matrix} \quad (12.38)$$

For this factorization, G is orthonormal (up to a scale factor) and the norm of H is proportional to the diagonal matrix with the n times the eigenvalues on the diagonal. Thus, the specification is said to favor display of the variables since the H loadings are in principal coordinates and the scores G are in standard coordinates (so that their variances are identical). The GH specification is sometimes referred to as the column metric preserving (CMP) specification.

In interpreting results for the GH decomposition, bear in mind that the Euclidean distances between observations are proportional to Mahalanobis distances. Furthermore, the norms of the columns of H are proportional to the factor covariances, and the cosines of the angles between the vectors approximate the correlations between variables.

Obviously, there are an infinite number of alternative scalings lying between the extremes. One popular alternative is to weight the scores and the loadings equally by setting $\alpha = 0.5$: This specification is the SQ or symmetric biplot, where $Y = SQ$;

$$\begin{matrix} S & n^b Y L D^{-1/2} \\ Q & n^{-b} L D^{1/2} \end{matrix} \quad (12.39)$$

Evaluating the norms of the scores S and loadings Q , we have:

$$\begin{aligned} S S &= n^b n L^{1/2} \\ Q Q &= n^{-b} n L^{1/2} \end{aligned} \quad (12.40)$$

so that the norms of both the observations and the variables are proportional to the square roots of the eigenvalues.

Observation Scaling

In the decompositions above, we allow for observation scaling of the scores and loadings parameterized by b . There are two obvious choices for the scaling parameter b .

First, we could ignore sample size by setting $b = 0$ so that:

$$\begin{aligned} A A &= n L^{1-a} \\ B B &= n L^a \end{aligned} \quad (12.41)$$

With no observation adjustment, the norm of the scores equals $n L^{1-a}$, the variance of the scores equals $L^{1-a} n^a$, and the norm of the variables equals n^a times the eigenvalues raised to the a power. Note that the observed variance of the scores is not equal to, but is instead proportional to L^{1-a} , and that the norm of the loadings is only proportional to L^a .

Alternately, we may set $b = a$, yielding:

$$\begin{aligned} A A &= n^a n L^{1-a} = n L^{1-a} \\ B B &= n^{-a} n L^a = L^a \end{aligned} \quad (12.42)$$

With this sample size adjustment, the variance of the scores equals L^{1-a} and the norm of the variables equals L^a .

Gabriel (1971), for example, recommends employing a principal components decomposition for biplots that sets $b = a = 1$. From [Equation \(12.34\)](#) the relevant norms are given by:

$$\begin{aligned} G G &= n I_p \\ H H &= L \\ H H &= S \end{aligned} \quad (12.43)$$

By performing observation scaling, the scores are normalized so that their variances (instead of their norms) are equal to 1. Furthermore the Euclidean distances between points are equal to the Mahalanobis distances (using S^{-1}), the norms of the columns of H are equal to the eigenvalues, and the cosines of the angles between the vectors equal the correlations between variables. Without observation scaling, these results only hold up to a constant of proportionality.

By default, EViews performs observation scaling, setting $b = a$. To remove this adjustment, simply uncheck the Adjust scores & loadings for sample size checkbox. Note that

when EViews performs this adjustment, it employs the denominator from the original dispersion calculation which will differ from n if any degrees-of-freedom adjustment has been applied.

Correlograms

Correlogram displays the autocorrelations and partial autocorrelations of the first series in the group. See ["Correlogram" on page 333](#), for a description of the correlogram view.

Cross Correlations and Correlograms

This view displays the cross correlations of the first two series in the group. The cross correlations between the two series x and y are given by,

$$r_{xy} = \frac{c_{xy}}{\sqrt{c_{xx}} \sqrt{c_{yy}}}, \text{ where } l = 0, -1, -2, \dots, T-1 \quad (12.44)$$

and,


$$c_{xy} = \begin{cases} \sum_{t=1}^T (x_t - \bar{x})(y_t - \bar{y}) & l = 0, 1, 2, \dots, T-1 \\ \sum_{t=1}^T (y_t - \bar{y})(x_{t-l} - \bar{x}) & l = 0, -1, -2, \dots, -T+1 \end{cases} \quad (12.45)$$

Note that, unlike the autocorrelations, cross correlations are not necessarily symmetric around lag 0.

The dotted lines in the cross correlograms are the approximate two standard error bounds computed as $\pm 2/\sqrt{T}$.

Long-run Covariance

You may compute estimates of the long-run covariance matrix of a group of series.




The discussion that follows assumes that you are familiar with the various issues and choices involved in computing a long-run covariance matrix. The technical description of the tools are given in [Appendix E. “Long-run Covariance Estimation,” on page 775](#) of User's Guide II.

To compute the (possibly row-weighted) long-run covariance matrix of the series in a group, open the Group object and select View/Long-run Covariance... from the toolbar or main menu. If you wish to compute the results for a particular sample, you should set the workfile sample accordingly.

By default, EViews will estimate the symmetric long-run covariance matrix using a non-parametric kernel estimator with a Bartlett kernel and a real-valued bandwidth determined solely using the number of observations. The data will be centered (by subtracting off means) prior to computing the kernel covariance estimator, but no other pre-whitening will be performed. The results will only be displayed in the series or group window.

You may use the dialog to change these settings. The dialog (here we show the dialog for a group object) is divided into three sections. The Basic options section is used to describe the covariance that you wish to compute and to specify an output matrix, if desired. The Whitening options section is used to define pre-whitening or VARHAC options. The Kernel options section describes the non-parametric kernel settings.



Basic Options

You may instruct EViews to compute a one-sided covariance by changing the Window combo from the Symmetric default to one of Lower (lags), Strict lower (lags), Upper (leads), Strict upper (leads). The “lower” methods only use covariances in which the rows correspond to contemporaneous values and the columns correspond to current and lagged data; the “upper” methods employ covariances where the columns correspond to current values and leads of the data. The “strict” long-run covariances exclude the contemporaneous covariance from the computation.

You may use the Remove means checkbox to indicate whether you wish to subtract off means (center your data) prior to computing the kernel covariance estimator. By default, EViews will remove the mean from each series in the group. To compute an uncentered long-run covariance, you should uncheck this box. If you do elect to center the data, you will be prompted for whether the covariance estimates should employ a d.f. Adjustment that accounts for the estimation of the mean values.

In addition, you may provide weights by entering a series expression in the Row weights edit field. Row weights are a convenient way of instructing EViews to compute the long-run covariance on data where the series in the group are weighted by a common element. A leading application occurs in the computation of White or Newey-West regression coefficient covariances, where the group contains the regressor data and the weights are the residuals. For example, if you have the regressor series X_1 , X_2 , and X_3 in your group, and the residuals are in the series RES, entering “RES” in the Row weights edit field instructs EViews to compute the long-run covariance of “ X_1*RES ”, “ X_2*RES ”, “ X_3*RES ”.

Lastly, you may elect to save your results in an EViews object. Simply enter a valid EViews object name in the Output matrix edit field. EViews will save symmetric long-run covariances in a sym object and one-sided covariances in a matrix object.

Whitening Options

The Whitening options section is used to define options for computing the VAR used in computing VARHAC or pre-whitened kernel estimation.

By default, EViews does not whiten the data before computing the long-run covariance. To enable whitening, you should change the lag specification combo box from None to one of Fixed, Auto - AIC, Auto - Schwarz, or Auto - Hannan-Quinn.

If you specify one of the automatic methods (Auto - AIC, Auto - Schwarz, Auto - Hannan-Quinn), you must specify the maximum number of lags in the Maximum lags edit field. You may provide the actual maximum value, or you may enter “*” to instruct EViews to use an observation-based maximum given by the integer portion of $T^{1/3}$ as suggested by Den Haan and Levin (1997).

If you specify a Fixed lag specification, you should enter the value in the Number of lags edit field.

Kernel Options

The Kernel options section is used to define settings for estimation of the long-run covariance of the original or pre-whitened data.

Kernel Shape

The Kernel combo is used to define the method for computing the long-run covariance. Choosing None tells EViews to compute the long-run covariance using only the contemporaneous covariance. (The VARHAC methodology, for example, uses a combination of pre-whitening and the None setting.) The remaining choices specify the shape of the kernel function. There are a large number of pre-defined kernel shapes from which you may choose, as well as the option to provide the name of a User-specified custom kernel shape vector.

If you choose to use a user-specified kernel, EViews will prompt you for the name of a vector object containing the kernel weights. The vector should contain the weights for the (auto)covariances for lags from 0 to the lag truncation value. For example, to specify user-weights that match a Bartlett kernel with bandwidth value of 4.0, you should provide a vector of length 4 with values (1.0, 0.75, 0.5, 0.25) or equivalently a vector of length 5 with values (1.0, 0.75, 0.5, 0.25, 0.0).

Bandwidth Specification

If you elect to use one of the pre-defined kernel shapes, EViews will prompt you to provide bandwidth information. By default, the kernel bandwidth is determined by the arbitrary observation-based Newey-West Fixed bandwidth rule. You may override the default choice by selecting either the Andrews Automatic, Newey-West Automatic settings for automatic optimal bandwidth selection, or the User-specified setting if you wish to provide a bandwidth value.

The Newey-West Automatic bandwidth selection method requires specification of a Lag selection parameter. You may enter a value for the number of lags in the edit field, or you may specify “*” to use an observation-based value given by the integer portion of $4 T^{1/5}$ where r_n depends on the properties of the selected kernel shape as given in [“Kernel Function Properties” on page 785](#) of User’s Guide II (see [“Newey-West Automatic Selection” on page 781](#) of User’s Guide II and Newey-West (1994) for discussion).

The User-specified bandwidth selection requires that you provide a bandwidth value. Simply enter the value as prompted in the Bandwidth value edit field.

Lastly, EViews does not restrict bandwidth values to be integers. Notably, the bandwidths obtained from the Newey-West fixed and the Andrews and Newey-West automatic methods are likely to be real valued. You may instruct EViews to use the integer portions of these bandwidths by checking the Truncate to integer checkbox.

Examples

To illustrate the use of the long-run covariance view of a group, we employ the HAC covariance matrix example taken from Stock and Watson (2007, p. 620, Column 1). In this example Stock and Watson estimate the dynamic effect of cold weather on the price of orange juice by regressing the percent change in prices on a distributed lag of the number of freezing degree days and a constant, and obtain a HAC estimator for the coefficient covariance matrix using a Bartlett kernel estimator with lag truncation of 7. While the HAC covariances may be obtained directly from the EViews equation object (see [“HAC Consistent Covariances \(Newey-West\)” on page 34](#) of User’s Guide I), here we will estimate the long-run covariance estimate of $X_t \hat{\epsilon}_t$ manually using the group long-run covariance view, and will use this estimate to derive the HAC coefficient covariance matrix.

First, open the workfile “Stockwat_620.WF1”, and notice that we have the equation object EQ_OLS which contains an estimated OLS equation (with conventional coefficient covariance and standard errors), and the group object XVARS which contains the regressors for the equation. We wish to compute the HAC coefficient covariance associated with the coefficient estimates in EQ_OLS using the group XVARS.

First, we need to obtain the residuals. Open EQ_OLS and click on Proc/Make Residual Series to display the Make Residuals dialog. Enter “RES” for the name of the residuals, then click on OK to save the regression residuals in the workfile.

Next, we will compute the symmetric long-run covariance of $X_t \hat{e}_t$. Double click on XVARs to open the group containing the regressors, then select View/Long-run Covariance... to display the dialog.

We must make a few changes to the default settings. To weight the regressors using the residuals, you must enter "RES" in the Row weights edit field. Uncheck the Remove means checkbox, since the $X_t \hat{e}_t$ should already have mean zero. Then, enter "LRCOV" in the Output matrix edit fields so that EViews will save the results in a sym matrix object.

The Stock-Watson example uses a Bartlett kernel with no pre-whitening, so we leave the Lag spec at the default None setting and the Kernel shape choice at the default Bartlett. We should, however, change the Bandwidth method to User-specified and enter "8" in the edit field to match the 7 lags employed by Stock and Watson. Click on OK to compute and save the results.

The long-run covariance estimates are displayed in the group window and saved in the LRCOV matrix in the workfile. To obtain the d.f. corrected HAC coefficient covariances (see, for example, Hamilton (1994, p. 282)), we issue the commands:

```
sym xxinv = @inverse(@inner(xvars))
scalar obs = eq_ols.@regobs
scalar df = eq_ols.@regobs - eq_ols.@ncoef
sym hac_direct = (obs / df) * obs * xxinv * lrcov * xxinv
```

The first line computes $X'X^{-1}$. The next two lines get the number of observations and the number of degrees-of-freedom. The last line computes the d.f. corrected sandwich estimator using the long-run covariance in LRCOV as the estimator of $E[X \hat{e} \hat{e}' X']$.

You may wish to verify that the estimate HAC_DIRECT matches the coefficient covariance matrix obtained using equation EQ_HAC (also provided in the workfile) estimated using the same HAC settings:

```
equation eq_hac.ls(cov=hac, covbw=8) 100*dlog(poj) xvars
sym hac_eq = eq_hac.@coefcov
```

Unit Root Test

This view carries out the Augmented Dickey-Fuller (ADF), GLS transformed Dickey-Fuller (DFGLS), Phillips-Perron (PP), Kwiatkowski, et. al. (KPSS), Elliot, Richardson and Stock (ERS) Point Optimal, and Ng and Perron (NP) unit root tests for whether the series in the group (or the first or second differences of the series) are stationary.

See [“Panel Unit Root Test” on page 391](#) of User’s Guide II for additional discussion.

Cointegration Test

This view carries out the Johansen, Engle-Granger, or Phillips-Ouliaris test for whether the series in the group are cointegrated or not. See [Chapter 38. “Cointegration Testing,” on page 685](#) of User’s Guide II


Granger Causality

Correlation does not necessarily imply causation in any meaningful sense of that word. The econometric graveyard is full of magnificent correlations, which are simply spurious or meaningless. Interesting examples include a positive correlation between teachers’ salaries and the consumption of alcohol and a superb positive correlation between the death rate in the UK and the proportion of marriages solemnized in the Church of England. Economists debate correlations which are less obviously meaningless.

The Granger (1969) approach to the question of whether x causes y is to see how much of the current y can be explained by past values of y and then to see whether adding lagged values of x can improve the explanation. y is said to be Granger-caused by x if x helps in the prediction of y , or equivalently if the coefficients on the lagged x ’s are statistically significant. Note that two-way causation is frequently the case; x Granger causes y and y Granger causes x .

It is important to note that the statement “ x Granger causes y ” does not imply that y is the effect or the result of x . Granger causality measures precedence and information content but does not by itself indicate causality in the more common use of the term.

When you select the Granger Causality view, you will first see a dialog box asking for the number of lags to use in the test regressions. In general, it is better to use more rather than fewer lags, since the theory is couched in terms of the relevance of all past information. You should pick a lag length, l , that corresponds to reasonable beliefs about the longest time over which one of the variables could help predict the other.



EViews runs bivariate regressions of the form:

$$\begin{aligned} y_t &= a_0 + a_1 y_{t-1} + \dots + a_l y_{t-l} + b_1 x_{t-1} + \dots + b_l x_{t-l} + e_t \\ x_t &= a_0 + a_1 x_{t-1} + \dots + a_l x_{t-l} + b_1 y_{t-1} + \dots + b_l y_{t-l} + u_t \end{aligned} \quad (12.46)$$

for all possible pairs of x , y series in the group. The reported F-statistics are the Wald statistics for the joint hypothesis:

$$b_1 = b_2 = \dots = b_l = 0 \quad (12.47)$$

for each equation. The null hypothesis is that x does not Granger-cause y in the first regression and that y does not Granger-cause x in the second regression.

We illustrate using data on consumption and GDP using the data in the workfile "Chow_var.WF1". The test results are given by:

Pairwise Granger Causality Tests
Date: 08/18/09 Time: 16:10
Sample: 1946Q1 1995Q4
Lags: 4

Null Hypothesis:	Obs	F-Statistic	Prob.
GDP does not Granger Cause CS	189	1.39156	0.2387
CS does not Granger Cause GDP		7.11192	2.E-05

For this example, we cannot reject the hypothesis that GDP does not Granger cause CS but we do reject the hypothesis that CS does not Granger cause GDP. Therefore it appears that Granger causality runs one-way from CS to GDP and not the other way.

If you want to run Granger causality tests with other exogenous variables (e.g. seasonal dummy variables or linear trends) or if you want to carry out likelihood ratio (LR) tests, run the test regressions directly using equation objects.

Label

This view displays the label information of the group. You can edit any of the field cells in the label view, except the Last Update cell which shows the date/time the group was last modified.

Name is the group object name as it appears in the workfile; you can rename your group by editing this cell. If you fill in the Display Name cell, EViews will use this name in some of the tables and graphs of the group view. Unlike object names, display names preserve case (allow upper and lower case letters) and may contain spaces.

See [Chapter 10. "EViews Databases," on page 267](#) for a discussion of the label fields and their use in database searches.

Group Procedures Overview

There are several procedures available for groups which generate new objects or data.

Make Equation

The Make Equation... proc opens an Equation Specification dialog box with the first series in the group listed as the dependent variable and the remaining series as the regressors, including a constant term "C". You can modify the specification as desired. See [Chapter 18. "Basic Regression Analysis," on page 5](#) of User's Guide II for details.

Make Factor

Make Factor... opens the factor analysis dialog with the correlation specification filled out with the series in the group. See [Chapter 39. "Factor Analysis," on page 705](#) of User's Guide II for details.

Make System

You may use the Make System... proc to make a system object. Simply select Make System... to open a system specification dialog. The dialog will be filled with the series in the group as dependent variables, and has edit fields that allow you to list common and equation specific regressors, instruments, and dependent variable transformations, if desired.

The screenshot shows the "Make System" dialog box. It has a title bar with the text "Make System" and a close button. The dialog is divided into several sections:

- Dependent variables:** A text box containing "gdp pr".
- Coefficient name:** A text box containing "C".
- Regressors and AR() terms:**
 - Common coefficients:** An empty text box.
 - Equation specific coefficients:** A text box containing "c".
- Instrument list:**
 - Common:** An empty text box.
 - Equation specific:** An empty text box.
- Option:** A section with a label "Dependent variable transformation" and a dropdown menu currently set to "NONE".

At the bottom right of the dialog are two buttons: "OK" and "Cancel".

Make Vector Autoregression

Make Vector Autoregression... opens an Unrestricted Vector Autoregression dialog box, where all series in the group are listed as endogenous variables in the VAR. See [Chapter 32. "Vector Autoregression and Error Correction Models," on page 459](#) of User's Guide II for a discussion of specifying and estimating VARs in EViews.

Resample


Resample... performs resampling on all of the series in the group. A description of the resampling procedure is provided in ["Resample" on page 344](#)

Make Principal Components

Make Principal Components... is used to save various intermediate results from principal components analysis. See ["Saving Component Scores" on page 416](#)

Make Whiten

You may use the Make Whiten... procedure from a group (or series) to use the results from a parametric VAR (or AR) model to filter the data. EViews offers whitening based on either a fixed lag specification, or an information criterion based auto-selected lag.



You may use the Lag specification combo to choose between a Fixed, user-specified number of lags on the VAR, or you may choose automatic lag-selection by choosing Auto - AIC , Auto - Schwarz , or Auto - Hannan-Quinn . In the Fixed case, EViews will prompt you for the number of lags to use; in the automatic selection case, you will be prompted for the maximum number of lags to use in selection. The default setting of "*" indicates use of an observation based maximum lag of $T^{1/3}$ suggested by Den Haan and Levin (1997).

You may use the Include constant checkbox to indicate whether or not to include a constant in the VAR, and you may specify Row weights in the corresponding edit field.

By default, EViews will save the results in series with the names given by those in the group with "_W" appended to the end. Information on the whitening procedure will be included


in the series label. If you would like to change the names, you can provide a list of series names or an alternate wildcard expression in the Output series edit field.

Lastly, you can instruct EViews to save a matrix containing the estimated coefficients from the VAR by entering a valid object name in the Output coef matrix edit field. The results will be saved in a matrix where each column represents the coefficients for the corresponding series in the group. The coefficients are ordered in the column by: constant (if present) followed by the lag 1 coefficient for each of the series in the group, in order, followed by the lag 2 coefficients, etc.

To illustrate the use of this tool, we use the data for industrial production (IP), money supply (M1), and the Treasury bill rate (TB3) in the workfile “Var1.WF1” used in [Chapter 32. “Vector Autoregression and Error Correction Models,” beginning on page 459](#). First set the sample to the entire workfile by entering the command

```
smpl @all
```

Next, create a group containing IP, M1, and TB3, name the group GROUP01, then click on Proc/Make Whitenened... to display the whitening dialog. Set the Lag specification combo to Auto - AIC, and enter “ABC” in the Output coef matrix edit field. Click on OK.



View	Proc	Object	Print	Name	Freeze	Default	Sort	Transpose	Edit +/-
obs		IP_W		M1_W		TB3_W			
1959M01		NA		NA		NA			
1959M02		NA		NA		NA			
1959M03		NA		NA		NA			
1959M04		NA		NA		NA			
1959M05		NA		NA		NA			
1959M06		NA		NA		NA			
1959M07		NA		NA		NA			
1959M08		-1.270547		0.299025		0.357210			
1959M09		0.304379		-0.618412		0.913382			
1959M10		-0.239094		-0.183514		0.217548			
1959M11		0.329422		0.439830		0.142489			
1959M12		2.204216		0.043035		0.588671			
1960M01		0.263078		0.607564		-0.243191			
1960M02		-0.891662		1.321452		-0.637435			
1960M03		-0.484898		0.675346		-0.026923			
1960M04		-0.380524		-0.366037		0.255600			
1960M05									


EViews displays a new untitled group containing the three whitened series IP_W, M1_W and TB3_W. In addition, the 22 –3 matrix object ABC contains the coefficients for the 7 lag VAR used to filter the data.

Note that the handling of lags differs slightly between the whitening procedure and VAR estimation. The whitening procedure does not use lagged values prior to the beginning of the computation sample, while the VAR estimator will use any available lags, even if they precede the estimation sample. In this case, the results for the whitening procedure will exactly match those of a VAR estimated for the sample from 1959M01 to 1995M04 since

there are no valid presample values, but this correspondence may not hold for samples starting after the beginning of the workfile.

Make Distribution Plot Data

Make Distribution Plot Data... may be used to output the graph data used to construct auxiliary kernel, nearest neighbor, and quantile-quantile graphs. See [“Auxiliary Graph Types” on page 512](#)



Simply select the desired graph type on the upper-left hand side of the dialog, set the relevant options on the right, choose a base name for the output, and if necessary, specify how to handle multiple sets of series in the group.

References

- Aitchison, J. and Greenacre, M. J. (2002). Biplots of compositional data. *Applied Statistics* 51, 375–392.
- den Haan, Wouter J. and Andrew Levin (1997). “A Practitioner’s Guide to Robust Covariance Matrix Estimation,” Chapter 12 in Maddala, G. S. and C. R. Rao (eds.), *Handbook of Statistics Vol. 15, Robust Inference* North-Holland: Amsterdam, 291–341.
- Gabriel, K. R. (1971). The biplot-graphic display of matrices with application to principal component analysis. *Biometrika*, 58, 453–467.
- Granger, C. W. J. (1969). “Investigating Causal Relations by Econometric Models and Cross-Spectral Methods,” *Econometrica*, 37, 424–438.
- Hamilton, James D. (1994). *Time Series Analysis* Princeton University Press.
- Johnson, Richard A., and Dean W. Wichern (1992). *Applied Multivariate Statistical Analysis*, Third Edition, Upper Saddle River, New Jersey: Prentice-Hall, Inc.
- Kendall, Maurice, and Jean Dickinson Gibbons (1990). *Rank Correlation Methods* Fifth Edition, New York: Oxford University Press.
- Matthews, Robert (2000). “Storks Deliver Babies ($p=0.008$)”, *Teaching Statistics* 22(2), 36–38.

Sheskin, David J. (1997). *Parametric and Nonparametric Statistical Procedures*. Boca Raton: CRC Press.

Sokal, Robert R. and F. James Rohlf (1995). *Biometry*. New York: W. H. Freeman and Company.

Chapter 13. Graphing Data

Constructing graphs from data is an important part of the process of data analysis and presentation. Results displayed in graphs are generally more concise and often more illuminating; one may be able to detect patterns and relationships in data that are not readily apparent from examining tables of summary statistics.

Accordingly, EViews provides an easy-to-use, full-featured set of tools for the graphical display of information. With EViews, you can quickly and easily display graphs of data, customize those graphs, and output the results so that they may be incorporated into your presentations.

There are many aspects of the graphing of data in EViews. This chapter describes the basics of graphing data in series and groups of series using the View/Graph... menu item. (Most of the graphs in this chapter may also be generated from vectors and matrices, but for brevity, we will speak mostly of series and groups).

Three types of graphs are described in this chapter:

- Observation graphs which show the data for each observation in the series or group. A line plot of the observations in a series or a scatterplot of observations for pairs of series in a group are examples of observation graphs.
- Analytical graphs where we display results obtained from analysis of the series or group data. You might, for example, show a histogram or a boxplot computed from the original data.
- Auxiliary graphs are analytical graphs that are not meant to stand alone, but rather are to be added to existing observation graphs. For example, we may display the linear regression or kernel fit line on top of a scatterplot. Strictly speaking, auxiliary graphs are not a graph type, but rather a modification of an existing observation plot.

A fourth class of graphs, categorical graphs, consists of observation or analytical graphs formed using data divided into categories defined by factor variables. Categorical graphs are described in [Chapter 14. "Categorical Graphs," beginning on page 523](#)

We do not consider here the specialized series and group routines that produce graphical output. For example, views of an equation produce graphs of the equation forecasts and residuals. Similarly, views of a model object that show graphs of simulation results, and the views of a state space object that show estimated states or signals. These graphs are described in the context of the specific views and procedures.

The remainder of this chapter is structured as follows. The first section offers a quick overview of the process of constructing a series or group graph view. The next two sections describe the process of constructing graphs from series and groups in somewhat greater depth. Next, we describe a handful of the most commonly performed graph view customizations. The final section provides detail on individual graph types.


Quick Start

All of the graph features described in this chapter may be accessed by selecting **View/Graph...** from a series or graph (or vector or matrix) object menu, or by double clicking on a series or group graph view.

For example, let us consider the example workfile “Housedebt.WF1”, which contains quarterly data on household debt and financial obligations from 1980 to 2006. The series DSR is an estimate of the debt service ratio representing the ratio of the total of mortgage and consumer debt payments to personal income.


We begin our example by opening DSR, selecting **View/Graph...** from the series menu and clicking on OK to accept the defaults. By default, EViews will display a simple (observation) line graph showing the data in the series.

Note that the titlebar of the window shows that we are looking at a view of the series DSR, and that the horizontal axis shows the dates associated with the current workfile sample range. The steep upward trend in the debt service ratio beginning in the early 1990s is readily apparent from the graph.



We can more closely examine the start of the trend by hovering the cursor over the data point we wish to identify. EViews will popup a box in the graph showing the observation label and value. Here, we see that the 1992Q4 value for DSR is 10.80.


Alternately, if you hover over any point inside the graph frame, EViews will display the location of that point in the statusline located in the lower left-hand corner of your EViews window.



We may change the graph type to show a histogram of the data by double-clicking on the graph area or by selecting View/Graph... to access the Graph Options dialog.


The graph options are broken into several categories, appearing on the left-hand side of the dialog. Make cer-

tain that you are displaying the Basic type page, then change the specific type to Distribution. Notice that there is a combo on the right-hand side that offers you choices on which type of distribution graph to produce. Since we want to display the default histogram, simply click on OK.



The view of the series will change to show a histogram of the data in the series.

The histogram is an example of an analytic graph in which the data are plotted against a data scale, not the workfile observation scale; note that the horizontal axis in the graph no longer corresponds to dates in the workfile, but instead represents intervals of data values observed from data included in the workfile sample. In this case, we show bars whose heights represent frequencies for the data intervals depicted on the horizontal axis.





Similarly you may display graphs for a group of series by opening the group, selecting View/Graph... and choosing an appropriate type.

First, open the group object GROUP01 in the workfile, then select View/Graph... from the group menu and click on OK to accept the defaults. By default, EViews will display line graphs of the two series within a single graph frame.

As before, we may change the graph to a histogram view by double-clicking on the graph or selecting View/Graph... to display the dialog.

Change the specific type to Distribution and click OK to accept the default settings.





The group view will change to show histograms of the data in the two series. Note that by default, the histograms are displayed in separate frames (we have rearranged the graphs horizontally for presentation by right-clicking on the graph and selecting Position and align graphs...; see [“Working with Multiple Graphs” on page 583](#)). Note also that each of the frames has its own vertical and horizontal axis scale.


Displaying other graph views is generally just as easy. Most graphs can be displayed with a few mouse clicks and a couple of keystrokes. In general, you can simply open the series or group object, display the graph dialog, select the graph type, set a few options if necessary, and click OK to produce acceptable results.

Graphing a Series

Up to this point we have examined graph views for series and groups constructed using default settings. We now consider the process of displaying graph views of a single series in a bit more depth.

Our discussion focuses on the selection of a graph type and setting of associated options. We consider the general features of selecting a graph type for the series, not on the particulars associated with each graph type. Details on the individual graph types are provided in [“Graph Types,” beginning on page 479](#).

To display the graph view of a single series, you should first select View/Graph... from the series menu to display the Graph Options dialog.



The Graph Options dialog has multiple pages that specify various settings for the graph view. The Basic type page depicted here is of central importance since it controls the graph you wish to display. The other dialog pages, which control various display characteristics of the graph, will be discussed below ([“Basic Customization,” beginning on page 459](#)).


Choosing a Type

On the left-hand side of the Basic type page, you will see the Graph type section where you will specify the type of graph you wish to display.

First, the General combo box allows you to switch between displaying a Basic graph of the data in the series, and displaying a Categorical graph constructed using the data divided into categories defined by factor variables. For now, we will stick to basic graphs; we defer the discussion of categorical graphs until [Chapter 14. “Categorical Graphs,” beginning on page 523](#)

Second, the Specific list box offers a list of the graph types that are available for use. You may select a graph type by clicking on its name. The default graph type is a Line & Symbol plot.

In most cases, these two settings are sufficient to identify the graph type. If, however, you select Distribution graph as your specific graph type, the right-hand side of the dialog will offer an option for choosing a specific distribution graph (note that the combo box for Orientation has been replaced by one labeled Distribution). The Options button allows you to customize the selected distribution graph, or to display more than one distribution graph in the frame (see [“Multiple Graph Types” on page 447](#)).



Similarly, if you select either Quantile - Quantile or Seasonal Graph as your specific type, the dialog will change to provide you with additional options. For theoretical quantile-quantile plots, you may use the Options button to specify a distribution or to add plots using different distributions. For seasonal graphs, there will be a combo box controlling whether to panel or overlay the seasons in the graph.

Details


The right-hand side of the dialog offers various options that EViews collectively labels Details. The options that are available will change with different choices for the Specific graph type. We have, for example, already mentioned the sub-type settings that are available when you select Distribution, Quantile-Quantile, or Seasonal Graph. We now consider the remaining settings.

Graph Data

The Graph Data combo specifies the data to be used in observation graphs. By default, EViews displays observation graphs that use Raw data, meaning that every observation will be plotted. The combo allows you to compute summary statistics (Means, Medians, etc.) for your data prior to displaying an observation graph. (Note: if we display an observation graph type using summary statistics for the data, the graph is no longer an observation graph since it no longer plots observations in the workfile. Such a graph is, strictly speaking, a summary graph that uses an observation graph type.)

It is worth noting that a summary statistic graph for a single series shows a single data point. For example, we see here the Line & Symbol graph for the mean of the debt service ratio series DSR in our example workfile ("Housedebt.WF1"). Since we are working with a single series, the graph displays data for a single point which EViews displays as a symbol plot.

One will almost always leave this setting at Raw data in the basic single series case. As we will see, the Graph data option is most relevant when plotting data for multiple series, or when plotting data that have been categorized by some factor.




Orientation

The Orientation combo allows you to choose whether to display observation graphs with the observations along the horizontal or the vertical axis. By default, EViews displays the graph with the observations along the horizontal axis (Normal - obs/time across bottom), but you may elect to display them on the vertical axis (Rotated - obs/time down left axis).


For example, bar graphs are sometimes displayed in rotated form. Using the workfile "EUPOP.WF1", we may display a rotated bar graph of the 1995 population (POP) for each of the 15 European Union members.

As an aside, it is worth mentioning here that graphs of this form, where observations have no particular ordering (unlike graphs involving time series data) sometimes order the bars by size.



While EViews does not allow you to change the order of data in a series view, you can reorder the observations in a graph object (frozen series view).

While displaying the bar graph view, simply click on the Freeze button to create a graph object, then press the right mouse button and select Sort... to display the sort dialog. Sorting on the basis of values of POP in ascending order yields the graph depicted on the right. Note that sorting reorders the data in the graph object, not the data in the original series POP.



Frequency

When plotting a line graph for a link series (see [Chapter 8. "Series Links," beginning on page 183](#)), the graph dialog changes to offer you the option of choosing to plot the data at the native frequency (the frequency of the source page), or at the frequency of the current workfile page (the frequency of the destination page).

By default, EViews will plot the data at the native frequency of the series. To plot the frequency converted data, you should select Plot links at workfile frequency.

Related discussion and examples may be found in ["Mixed Frequency Graphs" on page 452](#)

Note that when plotting links, the Frequency combo replaces the Orientation combo. To rotate the graph, you will need to manually assign the series to the bottom axes using the Axes & Scaling/Data scaling page of the dialog (["Axis Assignment" on page 463](#)).

Axis Borders

You may use the Axis borders combo to select a distribution graph to display along the axes of your graphs. For example, you may display a line graph with boxplots or kernel densities along the data (vertical) axis. By default, no axis graphs are displayed (None).

To illustrate, we use the workfile “Treasury2005c.WF1” containing data on 2005 daily market yields for U.S. Treasury securities at constant maturities. We display a line graph for 3-month maturities (TB03MTH) containing a histogram along the data axis.

Note the relationship between the bulges in the distribution and the quarter ends.


Sample Break & NA Handling

By default, an observation graph will leave “spaces” for observations containing missing values. If you look closely at the line graph of TB03MTH above, you may see a few gaps in the line corresponding to days the market was closed.

If there are missing values in your data, the Basic type page will change to offer you a choice for how to handle the missing values. You may close the gaps in your graph by checking the box labeled **Connect adjacent non-missing observations** or **Connect adjacent**.


Similarly, if you specify a sample that is non-contiguous, EViews will offer you choices on how to handle the gap in the observation scale. The default is to drop the excluded observations from the graph scale (**Drop excluded obs**), but you may instead choose to pad the graph with the excluded observations (**Pad excluded obs**). The final option, **Segment with lines**, is the same as **Drop excluded obs**, but with a vertical line drawn at the seams in the observation scale.

In this latter setting, **Connect adjacent** may be used to connect observations across both the seams and across missing values.



To illustrate, we again consider the TB03MTH series. First, set the workfile sample to exclude missing values for TB03MTH ("smpl if TB03MTH<>NA", and then select Segment with lines to produce a graph that highlights the location missing observations.


We see that there are 10 internal missing values in the series, with several, not-surprisingly, in the holiday rich fourth quarter of the year. Notice that the line depicting TB03MTH stops at the two sides of the segment; to connect the lines across the segment, you must select **Connect adjacent**.



Panel Options


When plotting observation graphs in workfiles with a panel data structure, the Basic type page offers additional options for how to use the panel structure. A Panel options section will be displayed containing a combo box that controls the panel portion of the display.

By default, EViews uses the Stack cross sections options, which simply stacks the data for each cross-section and plots the data without regard for panel structure. The resulting graph is an observation plot of the entire workfile. For example, a line graph for the series F in the Grunfeld-Baltagi data ("Grunfeld_Baltagi_Panel.WF1"), shows that there is considerable variation across cross-sections, with cross-section 3 in particular having high values:




Alternately, you may choose to display a line graph of the data for each cross-section in its own frame (Individual cross sections), or in a single frame (Combined cross sections).

The combined panel graph for the example panel is given by:



EViews also allows you to plot means plus standard deviation bounds (Mean plus SD bounds) or medians plus quantiles (Median plus quantiles) computed across cross-sections for every “period”. In the latter two cases, EViews will also prompt you for the number of SDs to use in computing the bounds, and the quantiles to compute, respectively.

The means plus/minus two standard deviations graph for the example data is given by:




Each observation in the time series for the mean represents the mean value of F taken across all cross-sections in the given period. The standard deviation lines are the means plus and minus two standard deviations, where the latter are computed analogously, across cross-sections for the period.

Multiple Graph Types


We have previously alluded to the fact that we may display multiple Distribution plots or multiple theoretical Quantile-Quantile plots in the same graph. It is easy, for example, to display a graph showing both a histogram of your series data and a fitted normal density curve, or to show Quantile-Quantile plots of your series against both a normal and an extreme value distribution.

To illustrate, we open the debt service ratio series DSR in the "Housedebt.WF1" workfile. We begin by selecting Distribution graph as our Specific type, and Histogram as our specific distribution type.

Next, click on the Options button to display the options page. Click on the Add button to add an additional distribution graph. EViews displays a new dialog prompting you to select from the list of distribution types that you may add to the histogram. To begin, we select Theoretical Density, then click on OK to add the element.



The dialog page changes to reflect your choice. The listbox on the left now shows that we have two different graph elements: the original Histogram, and the newly added Theoretical Distribution. You may select an element in the list box to show or modify the options for that element. Here we see the options for the Theoretical Distribution selection.




You may add additional elements by clicking on the Add button and selecting the desired graph type, or you may remove an element by selecting it in the listbox and pressing the Remove button.

For our example, we press the Add button again to add a Kernel Density graph to two existing elements.


Returning to the main graph page, you should note that when you have a graph with multiple types, the Distribution combo on the main page shows that you have a Custom graph (not depicted). Click on OK to display the specified graph.

EViews displays the fitted normal and kernel density estimates (in red and green, respectively) superimposed over the original histogram. Note that both the kernel density and histograms suggest that there are three distinct groups of observations for the debt service ratio.



Graphing Multiple Series (Groups)

EViews makes it easy to display graphs of the data in multiple series in a group object. Simply open the group object, select View/Graph... and fill out the dialog:



As with the single series dialog, the Graph Options dialog has multiple pages that specify various settings for the graph view. We again focus exclusively on the Basic type page. The other pages, which control various display characteristics of the graph, are described below ([“Basic Customization,” beginning on page 459](#)).

Choosing a Type

To select a graph type simply click on its name in the Specific type listbox. The options that you will see on this page will depend on the selected graph type. Some of the options (Orientation, Axis borders) have already been considered (see [“Details,” on page 441](#)), so we focus here on the remaining settings. To aid in our discussion we divide entries in the listbox into three classes:

- The first class consists of all of the graphs available in the series graph dialog (Line, Bar, Spike, Distribution, etc.). For this class, EViews will produce a graph of the specified type for each series in the group. Options will control whether to display the graphs in a single frame or in individual (multiple) frames.
- The second class of graphs use the multiple series to produce specialized observation plots of series data (Area Band, Mixed with Lines, Error Bar, High-Low (Open-Close), Pie).
- The final class produce pairwise plots of series data against other series data (Scatter, XY Line, XY Area, XY Bar). Options will be used to control how to use the different series in the group, and if relevant, whether to display the graph in a single or multiple frames. Note that these graphs are observation plots in the sense that data for

each observation are displayed, but unlike other observation graphs we have seen (e.g., line graphs), data are not plotted against workfile observation indicators.

We consider the settings for each of these classes in turn.

Single Series Graphs


Returning to our Treasury bill workfile ("Treasury2005c.WF1"), we first open the group GROUP01 containing the 1-month, 3-month, 1-year, and 10-year Treasuries, then click on View/Graph... to display the graph options dialog.

Multiple Series

When you select any of the individual series graph types in a group with more than one series, the right-hand side of the dialog changes to reflect your choice. In addition to the Graph data, Orientation, and Axis borders settings considered previously there will be a combo box, labeled Multiple series which controls whether to display: the individual series in a single frame (Single graph), the stacked individual series in a single frame (Stack in single graph), or the series in individual frames (Multiple graphs).

By default, EViews will display all of the series in the group in a single graph frame as depicted here. Each series is given a different color and a legend is provided so that you may distinguish between the various lines.


We see four distinct lines in the graph, each corresponding to one of the series in the group. Displaying the series in the same graph highlights a most notable feature of the Treasury rate data: the narrowing of the spread between yields at different maturities over the course of the year.



Setting the combo to Multiple graphs instructs EViews to display each of the series in its own graph, with the individual graphs arranged in a larger graph as shown here for an area graph. We have selected the Connect adjacent non-missing observations setting to remove gaps due to missing values.

Note that in contrast to the Single graph setting where each series


is plotted on the same scale, each graph is given a different vertical axis scale. This display emphasizes the individual variation in the series, but makes it more difficult to compare across series. Later, we will show how we may control the vertical axes scales ([“Axes & Scaling,” on page 462](#)).



The final combo setting, Stack in single graph, allows you to plot data that are sums of the series in the group. This method is available for most, but not all, individual graph types. The first graph element will be the first series plotted in the usual way; the second element will be the sum, for every observation, of the first series and the second. The third element will contain the sum of the first three series, and so forth.

We illustrate the stacked graph using data on newspaper advertising revenue data ("Newspapers.WF1"). The three series in the group object GROUP01 (CLASSIFIED, RETAIL, and NATIONAL), are the three components of TOTAL advertising revenue.


The height of the stacked bar for each observation shows the total amount of newspaper advertising revenue. We see that national advertising is by far the smallest component of advertising revenue and retail is the largest, though classified appears to be growing as a share of total revenue.



Graph Data

Earlier we saw that the Graph data combo allows you to display summary statistic graphs (Means, Medians, etc.) for your data ("Graph Data" on page 441). For graphs of a single series, displaying summary data may be of limited value since the graph will show a single summary value. For multiple series, the combo allows us to display graphs that compare values of the statistics for each of the series in the group.

Once again using the newspaper advertising revenue series in group GROUP01, we set the Graph data combo to Mean and display a bar graph with the multiple series displayed in a single frame. We see that the means of both RETAIL and CLASSIFIED advertising revenue are significantly greater than the average NATIONAL revenue.



Mixed Frequency Graphs

One important application of multiple series graphs involves displaying line graphs of mixed frequency data. You may, for example, have a workfile with two pages, one containing data sampled at a monthly frequency, and the other sampled at a quarterly frequency. EVIEWS


allows you to display line graphs of data from both pages in a single graph, with each series plotted at its native frequency.

To illustrate, we again use our Treasury bill workfile ("Treasury2005c.WF1"). We work with the group GROUP02 in the "Daily5" page, containing the series TB03MTH, AAA, and GDPCHG. TB03MTH is, as we have already seen, the 3-month T-bill series measured at a 5-day daily frequency.

The other series in the group are link series. (See [Chapter 8. "Series Links," beginning on page 183](#) for a discussion of links). AAA, which is linked from the Monthly workfile page, contains data on Moody's Seasoned Aaa Corporate Bond Yield. GDPCHG, which is linked from the Quarterly workfile page, measures the (annualized) quarterly percent change in GDP (in chained 2000 dollars). Both links convert the low frequency data to high using the constant-match average frequency conversion method.

Note that since the two link series are tied to data in other workfile pages, EViews has access to both the native (monthly and quarterly) and the converted (daily 5) frequencies for the AAA and GDPCHG. Accordingly, the main graph dialog for GROUP02, prompts you for whether you wish to plot your links using the native frequency data, or whether you wish to plot links using the workfile frequency (frequency converted) data.


We first display a line graph of the series in the group using the Plot links at native frequency setting. Since TB03MTH is sampled at the workfile frequency, this graph is a mixed frequency graph, with TB03MTH plotted at a daily-5 frequency, AAA plotted at a monthly frequency, and GDPCHG plotted at a quarterly frequency. To make it easier to see the different frequencies in the plot, we display AAA and GDPCHG using lines and symbols ("Lines and Symbols" on [page 476](#)), and we add vertical grid lines ("Frame" on [page 460](#)) to the graph.



Note that the GDPCHG line connects the four quarterly values of the series measured at its native frequency. The four points are each centered on the corresponding range of daily-5

dates. Similarly, the 12 monthly values of AAA are connected using line segments, with the individual points centered on the appropriate range of daily-5 values.

We may compare this graph to the same plot using the Plot links at workfile frequency setting. Here, all three series are plotted at the daily-5 frequency, with the AAA and GDPCHG series using the frequency converted values. Note that the graph simply uses the values that are displayed when you examine the link series in the spreadsheet view.



In contrast to the earlier graph, AAA and GDPCHG are displayed for each daily-5 date. Since the frequency conversion method for both series was to use a constant value, the graphs for AAA and GDPCHG are step functions with steps occurring at the native frequency of the links.


Specialized Graphs

The Area Band, Mixed with Lines, Error Bar, High-Low (Open-Close), and Pie graph types use multiple series in the group to form a specialized graph. Each specific type has its own set of options. For additional detail and discussion, see the description of the individual graph type in [“Observation Graphs,” beginning on page 480](#)

Pairwise Graphs

The final class of graphs use data for a given observation in pairs, plotting the data for one series against data for another series (Scatter, XY Line, XY Area, XY Bar).


For Scatter, XY Line, and XY Area graphs for groups containing exactly two series, there is no ambiguity about how to use the data in the group; there will be a single graph frame with the first series placed along the horizontal axis and the second series along the vertical axis. When there are more than two series, you will be prompted on how to use the multiple series to form data pairs and whether to display the graphs in a single or multiple frames.



Single graph - First vs. All

This setting forms graph pairs using the first series along the horizontal axis plotted against each of the remaining series along the vertical axis. The graph displays all of the graph pairs in a single frame.


We illustrate using a scatterplot of GROUP01, which contains our Treasury data at different maturities. The first series in the group is the 1-month Treasury rate, which is plotted against the remaining series in the group.



Single graph - Stacked

As the name suggests, this setting plots the first series against the remaining series in stacked form. Thus, the first series is plotted against the second series, against the sum of the second and third series, against the sum of the second through fourth series, and so forth.

We illustrate using our data on newspaper advertising revenue data ("Newspapers.WF1"). For GROUP01, we show the stacked XY graph that plots CLASSIFIED against the sum of RETAIL and NATIONAL.



Single graph - XY pairs

This setting forms pairs by using successive pairs of series in the group. The first series is paired with the second, the third with the fourth, and so on, with the first series in each pair placed on the horizontal axis, and the second series placed on the vertical axis. If the group contains an odd number of series, the last series will be ignored. The graph uses a single frame for all of the graph pairs.

Multiple graphs - First vs. All


Like Single graph - First vs. All, this setting plots the first series against the remaining series, but instead places each pair in an individual graph frame.

Multiple graphs - XY pairs

Like Single graph - XY pairs, this setting forms pairs by using successive pairs of series in the group, but places each pair in an individual graph frame.


We again illustrate using an XY line graph of the group object GROUP01 containing our Treasury data. The first series in the group is the 1-month Treasury rate, which is plotted against the remaining series in the group.

Note that each graph has its own data frame and vertical axis scale. In addition, we may manually set the vertical axes scales ([Axes & Scaling,](#) on page 462).



Scatterplot matrix


The Scatterplot matrix setting forms pairs using all possible pairwise combinations for series in the group and constructs a plot using the pair. If there are k series in the group, there will be a total of k^2 plots, each in its own frame.



Note that the frames of the graphs in the scatterplot matrix are locked together so that the individual graphs may not be repositioned within the multiple graph frame.

Lower triangular matrix

This setting constructs the same plots as Scatterplot matrix, but displays only the lower triangle elements consisting of the unique pairs of series not including the series against itself. There are a total of $k(k-1)/2$ distinct pairwise graphs, each displayed in its own frame.



Note that the frames of the graphs in the lower triangular matrix are locked together so that the individual graphs may not be repositioned within the multiple graph frame.


Fit Lines

EViews provides convenient tools for superimposing auxiliary graphs on top of your Scatter or XY line plot, making it easy to put regression lines, kernel fits, and other types of auxiliary graphs on top of your XY plots.

When you select Scatter or XY Line from the Specific type listbox, the right-hand side of the page changes to offer a Fit lines option, where you may add various types of fit lines to the graph as outlined in [“Auxiliary Graph Types,” beginning on page 512](#). You may also use the Options button to add additional auxiliary graphs. To illustrate, we use the familiar “Old Faithful Geyser” eruption time data considered by Simonoff (1996) and others (“Geyser.WF1”), and add both a regression line and a nearest neighbor fit relating eruption time intervals to previous eruption durations.

First, we open the group GROUP01 and select Scatter as our Specific type, then select Regression Line in the Fit lines combo to add a linear regression line. Next, click on the Options button to display the Scatterplot Customize page.


Click on the Add button to add an additional fit line to the existing graph. EViews displays a new dialog prompting you to select from the list of fit lines types that you may add to the scatterplot with regression line. We will select Nearest Neighbor Fit to be added to the existing graph. Click on OK to accept your choice.



You may elect to add additional elements by clicking on the Add button, or to remove an element by selecting it in the listbox and clicking on the Remove button.

Returning to the main graph page, we see that the Fit lines combo now reads Custom (not depicted) indicating that we are using multiple graph types.

Click on OK to accept the graph settings, and EViews displays the scatterplot with both the linear regression fit and the default LOW-ESS nearest neighbor fit superimposed on the observations. Note that since there are two lines in the graph, EViews provides legend information identifying each of the lines. We see the nearest neighbor fit has a slightly higher slope for lower values of INTERVAL and a lower slope at higher values of INTERVAL than the corresponding linear regression.



Basic Customization

EViews allows you to perform extensive customization of your graph views at creation time or after the view is displayed. You may, for example, select your graph type, then click on the other option groups to change the graph aspect ratio, the graph line colors and symbols, and the fill colors, then click on OK to display the graph. Alternately, you may double-click on an existing graph view to display the Graph Options dialog, change settings, then display the modified graph. And once a graph view is frozen, there are additional features for adding text, lines, and shading.

We defer a detailed discussion of graph customization to later chapters. Here we describe a handful of the most commonly performed graph view customizations.

You should be aware that some of the options that we describe are transitory and will be lost if you change the graph type. For example, if you set the symbol colors in a scatterplot and then change the graph to a line graph, the color changes will be lost. If you wish to make permanent changes to your graph, you should freeze the modified graph view or freeze the graph view and then make your change to the resulting graph object.

Frame

The Frame option group controls characteristics of the basic graph view window, including the frame appearance, colors in the graph not related to data, and the position of the data within the frame.

Color & Border

The Color & Border section of the Frame group contains two sets of options. The Color group controls fill and background colors, while the Frame border group modifies the graph frame itself.


Color

The Color group allows you to choose both the color inside the graph frame (Frame fill) and the background color for the entire graph (Background). You may also apply a fade effect to the frame color or background color using the corresponding combo boxes.

The final two settings are related to the behavior of graphs when they are printed or saved to file. The first option, Make background transparent for printing and file saving, should be used to ignore the background color when printing or saving the graph (typically, when printing to a black-and-white printer). Unchecking the last option, Use grayscale-no color, changes the display of the graph to grayscale, allowing you to see how your graph will look when output to a black-and-white device.

Here, we display a histogram of data on three month CD rate data for 69 Long Island banks and thrifts ("CDrate.WF1"). These data are used as an example in Simonoff (1996).

We have customized the graph by changing the color of the background (obviously not visible in black-and-white), and have applied a fade fill to the graph frame itself. The frame fill is light at the top and dark at the bottom.



Frame Border

The Frame border group controls the drawing of the graph frame. The Axes combo describes the basic frame type. The first entry in the combo, Labeled Axes, instructs EViews to draw a frame line for each axis that is used to display data in the graph. The last entry, none, instructs EViews not to draw a frame. The remaining combo entries are pictographs showing the positions of the frame lines. In this example, we will display a box frame.

Size & Indents

The Size & Indents section provides options for positioning and sizing the frame. The Frame size group controls the height and width of the graph, while Graph position in frame positions the data plot inside the graph.


Frame Size

The Frame size group is used to control the aspect ratio of your graph and the relative size of the text in the graph. (Note that you can also change the aspect ratio of the graph by click-and-dragging the bottom or right edges of the graph.)

The first two settings, Height in inches and Width, determine the graph frame size in virtual inches. You may specify the width in absolute inches, or you may specify it in relative terms. Here, we see that the graph frame is roughly 4 – 3 inches since the height is 3.00 inches and the width is 1.333 times the height.

Note that all text in graphs is sized in terms of absolute points (1/72 of a virtual inch), while other elements in the graph are sized relative to the frame size. Thus, reducing the size of the graph frame increases the relative size of text in the graph. Conversely, increasing the size of the graph frame will reduce the relative size of the text.

We can see the effect of changing both the aspect ratio and the absolute graph size using our example workfile “Housedebt.WF1”. We display a line plot of the data in GROUP01, with the Auto aspect ratio Default set to 3, and the Height in inches to 1. The resulting graph is now three times as wide as it is tall. Note also the increase in axis label and legend text size compared with the corresponding example in “Quick Start,” on page 436.



There is one additional checkbox, labeled Auto reduce frame size in multiple graphs to make text appear larger, which, when selected does as advertised. When displaying multiple graphs in a given frame size, there is a tendency for the text labels and legends to become small and difficult to read. By automatically reducing the frame size, EViews counteracts this undesired effect.

Position of graph in frame

The two combo boxes in Graph position in frame control the position of the plot within the graph frame. Note that different graph types use different default settings, but you may override them using the two combos. Using positive values for these settings can help insure that your data points are not obscured by drawing them on top of the axes scale lines.

Axes & Scaling

The Axes & Scaling option group controls the assignment of data to horizontal and vertical axes, the construction of the axis scales and labeling of the axes, and the use of tickmarks and grid lines.


This group is divided into sections based on the type of scale being modified. There are two different scale types: data scales, and workfile (observation) scales. When series data are assigned to a given axis, the axis is said to have a data scale, since the data for the series are plotted using that axis. Alternately, if observation identifiers are plotted along an axis, we say that the axis has a workfile or observation scale.

Some observation graphs (Line graphs, Bar graphs, etc.) have both data and observation scales, since we plot data against observation indicators from the workfile. Other observation graphs (Scatter, XY Line, etc.) have only data scales, since data for multiple series are plotted against each other. Similarly, analytic graphs (Histogram, Empirical CDF, etc.) have only data scales since the derived data are not plotted against observations in the workfile.

The first two sections in this group, Data scaling and Data axis labels, relate to settings for the data scales. The third section, Obs/Date axis, sets options for the workfile (observation) scales. The fourth section, Grid Lines, can be used to add or modify grid lines on any axis.

Data scaling

The Data scaling section allows you to arrange data among axes and set data scaling parameters for each axis.



Axis Assignment

The right-hand side of the dialog contains a section labeled Series axis assignment, which you may use to assign each series in the graph to an axis. The listbox shows each data element along with the current axis assignment. Here we see the assignment for a scatterplot where the first series is assigned to the bottom axis and the second series is assigned to the left axis.


To change the axis assignment, simply click on a graph element in the listbox, then click on one of the radio buttons to perform the desired assignment. Note that when you select an element, the top of the section shows information about the selected data series.

Note that the rules of graph construction imply that there are restrictions on the assignments that are permitted. For example, when plotting series or group data against workfile identifiers (as in a line graph), you may assign your data series to any combination of the left and right axes, or any combination of the top and bottom axes, but you may not assign data to both vertical and horizontal axes. Similarly, when plotting pairwise series data, you may not assign all of your series to a single axis, nor may you assign data to all four axes.

We have already seen one example of changing axis assignment. The `Orientation` combo on the Type page is essentially a shorthand method of changing the axis assignments to display the graph vertically or horizontally (see [“Orientation,” on page 442](#)).

A second common example of axis assignment involves setting up a dual scale graph, where, for example, the left hand scale corresponds to one or more series, and the right hand scale corresponds to a different set of series.

Once again working with GROUP01 in our debt service ratio dataset, we see the display of a dual scale line graph where the first line is assigned to the left axis, and the second line is assigned to the right.



When you specify a dual scale graph with series assigned to multiple axes, the bottom left-hand side of the dialog will change to offer you the choice to select the axis scales so that the lines do no overlap, or to allow the lines to overlap.

Selecting an Axis to Edit

The `Edit axis` combo at the top of the dialog is used to select a scale (left, right, top, bottom) for modification. When you select an entry, the remainder of the dialog will change to reflect the characteristics of the specified scale.

Defining Data Scales

The remainder of the Data scaling page allows you to specify properties of the data scale.

We have selected the left axis in our example, so we see the two relevant sections of the dialog labeled Left axis scaling method and Left axis scale endpoints .


Axis Scale

The Axis scaling method describes the method used in forming the selected axis scale. By default, EViews displays a linear scale, but you may instead choose: a linear scale that always includes the origin (Linear – force zero), a logarithmic scale (Logarithmic scaling), or a linear scale using the data standardized to have mean 0 and variance 1 (Normalized data) . If you select the Invert scale option, EViews will reverse the scale so that it ranges from high values to low.

You may use the Axis scale endpoints to control the range of data employed by the scale. If you select User specified, you will be prompted to enter a minimum and maximum value for the scale. Note that if either of these are within the actual data range, the graph will be clipped.


We illustrate log scaling and user-specified axis endpoints using the GDP series from our newspaper advertising revenue data (“Newspapers.WF1”) workfile. In addition to drawing the data with log scaling, we have set the endpoints for our vertical axis to 0 and 10,000 (the default endpoints are 4,000 and 10,000).

Note that EViews has chosen to place tickmarks at every 1,000 in the scale, leading to the unequal spacing between marks.



Labeling the Data Axis

The next section in the Axes & Scaling group is Data axis labels . This section contains options for all characteristics of the data axes which do not affect the scaling of the data.



Similar to the Edit axis combo box on the Data scaling page, you may use the combo box at the top of the Data axis labels page to select an axis to edit.

Axis Labels

You may suppress all labels for the selected axis by checking the Hide labels box.

If you do choose to display labels for the specified axis, you may use the Label angle combo to rotate your labels. Note that the values in the combo describe counterclockwise rotation of the labels, hence selecting 45 in the combo box rotates the axis labels 45 degrees counter-clockwise while selecting -30 rotates the labels 30 degrees clockwise.

Clicking on Axis Font brings up a font dialog allowing you to change the size and typeface of your labels.

Ticks and Lines

The Ticks & lines section controls the display of tick marks. The first combo box determines the placement of tickmarks: you may choose between Ticks outside axis, Ticks inside axis, Ticks outside & inside, and No ticks.

The Zero line checkbox controls whether or not to draw a horizontal or vertical line at zero along the specified axis. Note that it is possible to select Zero line for an axis scale that does not include the origin; in this case, the option has no effect.

Duplicating Axis Labels

For a graph with all data series assigned to one horizontal or one vertical axis (or, at most, one vertical and one horizontal in the case of an XY graph), the bottom left-hand side of the dialog offers you the choice to Label both axes. This option will duplicate the labels onto the corresponding empty axis. For example, for a graph with all series assigned to the left axis, you may elect to label the right axis with the same labels by checking this box.

Data Units & Labels


The Data units & label format group can be used to label your axis using scaled units or to customize the formatting of your labels.

- The Units combo box allows you to display your data using a different scale. You may choose between the default setting Native, Percent: .01, Thousands: 1e3, Millions: 1e6, Billions: 1e9, and Trillions: 1e12. For example, selecting Thousands: 1e3 will display the data in units of a thousand; it is equivalent to dividing the data by 1,000 before graphing. Similarly, selecting Percent: .01 effectively multiplies the data by 100 prior to display.
- The Decimal places combo specifies the number of digits to display after the decimal. In addition to the default Auto setting, you may choose any integer from 0 to 9.
- The Thousands separator option controls whether numbers employ separators to indicate thousands. By default, EViews will display a separator between thousands (e.g., "1,234" and "2,123,456", or "1.234" and "2.123.456" if Comma as decimal is selected), but you may uncheck the Thousands separator option to suppress the delimiter.
- The Comma as decimal option controls whether the comma is used as the decimal delimiter. If checked, the decimal and comma indicators will be swapped: the decimal indicator will be the comma instead of the period, and the thousands separator, if used, will be the period instead of the comma.
- By default, EViews will trim leading zeros in numbers displayed along the axis, but you may uncheck the default Trim leading zeros checkbox to display these zeros.
- In addition, you may provide a single character prefix and/or suffix for the numbers displayed along the axis.

For example, suppose that we have data that are expressed as proportions ("0.153"). To display your axis as percentages ("15.3%"), you may select Percent: .01 as the Units, and add "%" as the suffix.

Defining Observation Scales

The third option group under **Axes & Scaling** is **Obs/Date axis**. This page should be used to define all aspects of the workfile or observation scale.



For graphs which do not have a date axis, such as XY graphs, the **Axis assignment** combo box in the top left-hand corner of the page will read **Graph has no Obs/Date axis**, and any changes to the settings on this page will be irrelevant for the current graph type.

Rotating the Graph

If you are working with a graph which has a date axis, this combo box provides you with a shortcut for rotating the graph. You may select **Normal - Obs axis on bottom** or **Rotated - Obs axis on left**. Choosing the latter will move the date axis to the left-hand axis and reassign all remaining axes to the bottom axis. The combo box provides the most common options, assigning to either the left or bottom axis. Note that the same results may be accomplished using the **Series axis assignment** control on the **Data scaling** page, as discussed above.


Date Label Frequency

The **Observations to label** group controls the frequency with which labels are displayed on the axis. For workfiles with a date structure, you may choose between **Automatic selection**, **End-points only**, **Every observation**, **Custom (Step=One obs)** where you specify an anchor position and number of steps between labels, and other Custom settings based on a date frequency. Only the first four settings are available for workfile scales that do not have a date structure. Some of the dated custom set-

tings are not available for work files with low frequencies (e.g., Custom (Step = Quarter) is not available in annual workfiles).

When you select any of the custom settings, EViews offers you the Alignment date and Stepsedit fields where you will fill in an alignment position and a step size. EViews will place a label at the alignment position, and at observations given by taking forward (and backward steps) of the specified size.

We illustrate custom date labeling by specifying 20 year label intervals for our LOGVOL series from our stock data workfile ("NYSEVolume.WF1"), by putting "1900" in the Alignment date edit field, and by entering "20" in the Stepsfield.



Date Label Formatting


The Date format section allows you to select the method of forming labels for the date axis. You may use the combo to select the default Automatic , in which EViews will choose an appropriate format, you can select from alternatives that display strings made up of various parts of the dates, or you may select Custom, which allows you to specify a fully custom date format string. Depending on your choice, you will be prompted for additional formatting information. You may also use the End of period date labels checkbox to tell EViews to use the end of period date for an observation when constructing its label.

For example, using the default Automatic setting, EViews will provide automatic date formats using a default set of guidelines for displaying dates. If you would like to exert some control over the guidelines, you may click on the **Formats for Auto Labeling** button. This brings up the **Date Formats for Auto Label** dialog, in which you may specify your preferred formats without locking the graph to a specific date string.

Alternately, you may decide that you always want your labels to be formed using both the month and year of the observation. If you select **Month Year** from the combo, EViews will display an additional drop-down specifying how the month/year string is to be formatted. For date formats that include a year, click the **Use 4 digit year** checkbox to update all formats in the drop-down to a 4 digit display.

If you would like complete control over the display of your date strings, you should select **Custom**. The dialog will change to provide an edit field in which you should specify a date format using a standard EViews date format specifications in the **Format** edit field (see [“Date Formats,” on page 85](#) of the *Command and Programming Reference*).

If you would like EViews to continue to provide automatic date formats, but would prefer some control over its choices, leave the default Automatic setting and click the Formats for Auto Labeling button. This brings up the Date Formats for Auto Label dialog, in which you may specify your preferred formats without locking the graph to a specific date string.



The dialog box is titled "Date Formats for Auto Label" and contains a section for "Preferred date formats". It includes several dropdown menus for selecting date components and their formats:

- Year***: Set to "Auto". A note says: "*Keep at Auto for best automatic labeling".
- Quarter**: Set to "QR".
- Quarter Year**: Set to "YYYY[q]Q".
- Month**: Set to "[M]mm".
- Month Year**: Set to "YYYY[m]mm".
- Day**: Set to "dd".
- Day Month**: Set to "mm/dd".
- Day Month Year**: Set to "mm/dd/YY".
- Hour**: Set to "hh:MI".
- Minute**: Set to "hh:MI".

At the bottom right, there is a text box that says: "Automatic labeling will choose one or more of the selected formats to label dated axes." Below this are "OK" and "Cancel" buttons.

Observation scales without a date structure are always labeled using the Automatic setting.

Date Label Positioning

The Date label positioning group determines whether the labels are centered over period intervals, or whether they are placed at the beginning of the interval. You may change the setting in the combo box from the default Automatic label and tick placement to label the start or center of the period.

Label start of period - tick on obs instructs EViews to place the label at the beginning of the period, and the tick on the observation. If you select Center label on period - tick between obs, EViews places the ticks between observations and centers the label over the period.

The last option, Center label on period - trim space at axis ends, is essentially the same as the previous option, Center label on period - tick between obs, except that the empty space on either end of the date axis will be removed. The beginning of the first period and end of the last period will fall at the edges of the graph frame, taking into account any indent set in the Size & Indents page in the Frame option group.

Depending on the frequency of your graph, date labeling can be made clearer if we include a second row of labels. Checking the Allow two row date labels box allows EViews to utilize a second row of labels where appropriate. For example, daily data can be labeled first by month, with a second row of labels indicating the year.

Axis Labels

The Axis labels group on the Obs/Date axis page allows you to modify label characteristics such as angle and font for the time axis. These options are similar to those discussed above for data axis labels. However, on the time axis, you can also customize the text of the labels.

The top half of the group mimics the behavior of the controls found in the Axis labels group on the Data axis labels page.


The bottom half of the group allows you to specify custom observation axis labels. See [“Adding Custom Labels,” beginning on page 572](#) for further discussion.

Tick Marks

The combo box in the Tick marks section determines the placement of tickmarks: you may choose between Ticks outside axis, Ticks inside axis, Ticks outside & inside, and No ticks. The Allow minor ticks checkbox determines whether smaller ticks are placed between the major ticks.

Grid Lines

The final section of the Axes & Scaling group, Grid Lines, controls grid lines for all axes.



Data Scale Grid Lines

You may use the Data scale grid lines group to add grid lines to your graph by checking one or more of the four checkboxes. Left axis scale grid lines originate from the left vertical axis; those from the right correspond to the right vertical axis. Top and bottom grid lines are drawn from the corresponding horizontal axes.

Notice that the Bottom axis scale checkbox is disabled in the image to the right. This indicates that the date scale for our current graph is assigned to the bottom axis, so the Obs & Date axis grid lines group should be used to control grid lines for this axis.


Note that if an axis associated with a specified grid line is not in use, the corresponding grid line option will be ignored.

Date Axis Grid Lines

The Obs & Date axis grid lines group applies grid lines to the observation or date axis. The first option in the combo, No grid lines, is self explanatory. The second option, Automatic grid placement, allows EViews to place grid lines at intervals it deems appropriate for the given frequency and range.


The remaining Custom options in the combo box allow you to add grid lines at specified intervals, based on the frequency of your workfile. After specifying a step length in the combo, enter a value for the number of steps between grid lines in the Steps edit field.

For example, suppose we have data on monthly housing starts over the period 1990M01-1992M12 (a line graph of series HS in the workfile "House.WF1"). When we turn on grid lines and select Automatic grid placement, EViews opts to draw a grid line at the end of each year.



However, we might like the grid lines to show a bit more granularity. You may change the grid setting to Custom (Step = Month) and enter “2” in the Steps field. EViews then draws a graph with a grid line every other month.

Similarly, if we change the grid setting to Custom (Step = Quarter) and enter “2” in the Steps field, EViews will now display the graph with a grid line drawn semi-annually.




Grid Line Attributes

You may modify the appearance of grid lines in the Line attributes group. Use the Pattern combo to select a line pattern, the Width combo to modify the grid line width, and the Color combo to update the line color. The Draw grid lines on top option can be useful for filled graph types, such as bars or areas. Note that all grid lines will be modified with these settings.

Legend

The next main category in the graph options dialog is Legend. This section provides control over the text, placement, and appearance of the legend.



Legend Characteristics

You may elect to show or hide the legend and modify its appearance in the Characteristics group.

The first checkbox, Display legend , provides the most important option: to show or hide the legend. Click the checkbox to override EViews' default setting. Note that for single series graphs, the default is to hide the legend.

EViews attempts to display the legend entries in a visually appealing layout. To modify the number of columns, change the Legend Columns combo box from the default Auto setting. Select an integer between 1 and 5, and EViews will rearrange the legend entries with the corresponding number of columns and rows.

By default, EViews draws a box around legends. You may elect not to enclose the legend in a box by unchecking the Legend in Box checkbox. If a box is to be drawn, you may select the Box fill color and a box Frame color using the two color selectors.

Legend Placement

The legend may be positioned anywhere on the graph using the options presented in the Placement section. EViews provides a few common positions in the drop-down menu: Bottom Center , Bottom Left , Bottom Right , Left , Right , in addition to the User option. All locations are relative to the graph frame.

If User is selected, edit fields for the X and Y location are enabled. Note that the origin (0, 0) is the top left corner of the graph frame, and the coordinates are in units of virtual inches.

Individual graphs are always 4 x 3 virtual inches (scatter diagrams are 3 x 3 virtual inches) or a user-specified size, regardless of their current display size. It is often much easier to position the legend by dragging it to the desired location on the graph and not being concerned with its coordinates.

Note that if you place the legend using the User option, the relative position of the legend may change if you change the graph frame size. This does not include changing its size on the screen, but may occur if its size in virtual inches is changed via the Size & Indents section of the Frame options.

Legend Font

Click the Legend Font button to open the Font dialog and modify the text font and color.

Legend Text

To modify text shown in the legend, use the Edit legend entries section of the Legend page. Simply click on the text you wish to edit in the second column of the listbox, and alter the legend text in the edit field.

Lines and Symbols

For many graph types, the Lines & Symbols section under the Graph Elements group permits you to display your graph using lines only, lines and symbols, or symbols alone. In addition, you may specify various line and symbol attributes (color, line pattern, line width, symbol type and size).

To change the settings for your graph, click on the Lines & Symbols section under the Graph Elements group to show the line attributes. In the Attributes section you will see a list of the graph elements that you may change. Click on an element in the right-hand side of the dialog to access its settings, then use the comboboxes to change its characteristics.

The Line/Symbol use combo determines the combination of lines and symbols used to display the selected element. You should change the Line/Symbol use combo to Line & Symbol to display both lines and symbols, or Symbol only to suppress the lines. The corresponding Color, Line pattern, Line width, Symbol, and Symbol size combos control the characteristics of the selected element. Note that the settings will sometimes have no


effect on the graph (e.g., symbol choice if you are only displaying lines; line pattern if you are only displaying solid lines).

For the most part, the settings are selfexplanatory; simply change the symbol and line use, size, and color of a graph element and the preview region will change to reflect your choices. Click on Apply or OK to apply your selections.

There are two Symbol choices that deserve explicit mention. The last two entries in the combo specify that the symbol should be the observation label from the workfile (the first entry uses the observation label itself; the second choice also includes a small circle with an attached text label). In some cases, these labels will be the dates, in other cases they will be integer values (1, 2, 3, ...), and in others, they will be text labels corresponding to the observations in the workfile. You may use this setting to display identifiers for each point in the observation graph.

We illustrate this choice by displaying a scatterplot of the Matthews (2000) data on stork breeding pairs and number of births (“Storks.WF1”).

Observation labels are displayed in the graph so that we may identify the data associated with each observation in the workfile. The graph shows immediately that the upper right-hand corner outlier is Turkey, and that, among others, Polish, Spanish, and Romanian storks have relatively low productivity.



Once you have selected observation labels from the Symbol combo, you can modify their font attributes by clicking on the Font button in the Observation Label section on the left-hand side of the dialog. This button brings up a Font dialog, where you can set the font style, font size, and color of the observation labels.

The Pattern use section of the dialog requires a bit of discussion. By default, this option is set to Auto choice, meaning that EViews graphs will use different line pattern settings depending on whether you are out-putting to a color or a black and white device; lines will be solid when shown on color devices (like your monitor), but will print with a pattern

on a black-and-white printer. You may instead select **Solid always** or **Pattern always** so that the pattern of lines in the two types of devices always match.


The effect of different choices for this setting are shown in the **Attributes** section of the dialog, which shows what your graph elements will look when output to both types of devices. Our line graph example above uses the **Pattern always** setting so that the second and third lines are dashed when displayed on both color and black-and-white devices (for related preview tools, see [“Color & Border” on page 460](#)).

At times, you may notice that the data line in your line graph does not look perfectly smooth. To allow EViews to use a smoothing algorithm when drawing the line, make sure anti-aliasing is enabled. In the **Anti-aliasing** groupbox, selecting **Auto** will allow EViews to use anti-aliasing when it determines that doing so will make a visible difference. This choice is dependent primarily on the number of data points. To force anti-aliasing on or off when drawing lines, select **On** or **Off**, respectively.

If you wish to perform curve fitting on your data, you may use the **Interpolation** options at the bottom of the page. Select from **Linear** interpolation or a cardinal spline of varying degrees: **Mild**, **Medium**, or **Full**.

Fill Areas

You may use the **Fill Areas** section under the **Graph Elements** group to specify a fill color, gray shade (black-and-white representation of the fill color), or to add hatching to the fill region. The fill colors are used in graphs involving bars, areas, and area bands.




In the Brush edit section, simply click on one of the entries on the right to select the fill whose characteristics you wish to change (there are two in this example and the first is selected), then use the combo boxes to alter the color, gray shade, and hatching as desired.

Note that the Color settings are used for fills that are displayed on a color device; the Gray shade combo controls the fill display when displayed on black-and-white devices. The preview and selection area on the right shows the characteristics of the fill element in both settings (for related preview tools, see [“Color & Border” on page 460](#)).

Additional options for Fill Areas

There are a few additional options for graphs with filled areas in the Bar-Area-Pie section of the Graph Elements group.



The Bar graphs section allows you to add value labels to bars, in addition to shading and a 3D appearance. These options are described in [“Bar” on page 481](#).

You may choose to outline or not outline the fill regions for various fill types using the Outline fill areas in checkboxes. Here we see that Bars and Areas will be outlined but Area Bands will not.

Clicking Label pies in the Pie graphs group adds or removes observation labels from each pie in a pie graph.

Graph Types

The following is a description of the basic EViews graph types. We divide these graph types into three classes: observation graphs that display the values of the data for each observa-

tion; analytical graphs that first summarize the data, then display a graphical view of the summary results; auxiliary graphs, which are not conventional graph types, per se but which summarize the raw data and display the results along with an observation graph of the original data.

The discussion for each type is limited to a basic overview of each graph type and does not discuss many of the ways in which the graphs may be customized (e.g., adding histograms to the axes of line graphs or scatterplots;), nor does it describe the many ways in which the graphs are displayed when using multiple series or categorizations (e.g., stacking; see [“Basic Customization,” beginning on page 459](#)).


Observation Graphs

Observation graphs display the values of the data for each observation in the series or group. Some observation graphs are used for displaying the data in a single series (Line & Symbol, Area, Bar, Spike, Dot Plot, Seasonal Graphs), while others combine data from multiple series into a graph (Area Band, Mixed with Lines, Error Bar, High-Low(-Open-Close), Scatter, XY Line, XY Bar, XY Area, Pie).

Line & Symbol

The line and symbol plot is a simple plot of the data in the series against observation identifiers. The plot shows data values as symbols, lines, or both symbols and lines.

To display a line and symbol plot for a single series or for each series in a group, select **View/Graph...** from the series or group menu to bring up the main Graph Options dialog, which will automatically open to the Basic type page. Then choose **Line & Symbol** in the Specific listbox.



By default, EViews will display the data in the series using a line. To illustrate, we use the workfile “Treasury2005c.WF1” containing data on 2005 daily market yields for U.S. Treasury securities at constant maturities. The default line graph for the 3-month maturity series TB03MTH is depicted. If you look closely, you may be able to see gaps corresponding to holidays.


You may display your graph symbols alone, or using lines and symbols by clicking the **Lines & Symbols** section in the Graph Elements option group, and changing the desired

attributes ([“Lines and Symbols” on page 476](#)). There are other settings for controlling color, line pattern, line width, symbol type, and symbol size that you may modify.

Area

Area graphs are observation graphs of a single series in which the data for each observation in the series is plotted against the workfile indicators. Successive observations are connected by a line, with the area between the origin and the line filled in.

To display an area graph of a single series or each series in a group, you should select View/Graph... from the series or group menu to display the Graph Options dialog, and then select Area in the Specific listbox.




Our illustration depicts the area graph of the deviations of the 3-month Treasury bill series TB03MTH (“Treasury2005c.WF1”) around the mean. Note that positive and negative regions use the same fill color, and that we have connected adjacent non-missing observations by checking the box labeled Connect adjacent non-missing observations.

Bar

The bar graph uses a bar to represent the value of each observation in a single series.

Bar graphs may be displayed for a single series or each series in a group by selecting View/Graph... from the series or group menu, and clicking Bar in the Specific listbox.

Our illustration shows a bar graph for the series TOTAL (from the workfile “Newspapers.WF1”) containing annual data on total advertising expenditures for the years 1985 to 1999.



Bar graphs are effective for displaying information for relatively small numbers of observations; for large numbers of observations, bar graphs are indistinguishable from area graphs since there is no space between the bars for successive observations.

You may add numeric value labels to your bars by double clicking on the bar to display the graph dialog, selecting the Bar-Area-Pie section in the Graph Elements option group, and select either Label above bar, or Label in bar in the Bar graphs section of the dialog page. EViews will add a label showing the height of the bar, provided that there is enough space to display the label.


You may use the drop-down menu to apply fade effects to your bars.

By default, EViews displays the Solid color bars, but you may instead choose to display 3D rounded bars, Fade: dark at zero, Fade: light at zero. The latter two entries fade the bars from light to dark, with the fade finishing at the zero axis. Note that at press time, fades are not supported when exporting graphs to PostScript.

Moreover, while we discourage you from doing so, you may also use the Fill Areas page to remove the spacing and/or the outlines from the bars.

Here, we see the bar graph for the TOTAL newspaper advertising expenditures for the years 1997 to 1999, with value labels placed above the bar, and 3D rounded bars. It is worth pointing out that we restrict the sample to the three years, as the labels are not large enough to be visible when displaying lots of bars.


The Fill Areas section in the Graph Elements option group may be also used to change the basic characteristics of the fill area (color, gray shading, hatching, etc.). See “Fill Areas,” on page 478 for details.



Area Band

The area band graph is used to display the band formed by pairs of series, filling in the area between the two. While they may be used in a number of settings, band graphs are most often used to display forecast bands or error bands around forecasts.

You may display an area band graph for any group object containing two or more series. Select **View/Graph...** from the group menu, and then choose **Area Band** in the **Specific** listbox. The **Fill Areas** and **Lines & Symbols** dialogs under the **Graph Elements** group may be used to modify the characteristics of the lines and shades in your graph.




EViews will construct bands from successive pairs of series in the group. If there is an odd number of series in the group, the final series will, by default, be plotted as a line.

Our example of the area band graph uses data from the Federal Reserve Bank of Philadelphia's Survey of Professional Forecasters ("Forecast_unemp.WF1"). UNEMP_MAX and UNEMP_MIN contain the high and low one-quarter ahead forecasts of the unemployment rate for each period in the workfile; UNEMP_MEAN contains the mean values over the individual forecasts. To construct this graph, we create a group GROUP01 containing (in order), the series UNEMP_MAX, UNEMP_MIN, and UNEMP_MEAN. Note that reversing the order of the first two series does not change the appearance of the graph.

Spike

The spike plot uses a bar to represent the value of each observation in a single series. Spike plots are essentially bar plots with very thin bars. They are useful for displaying data with moderate numbers of observations; settings where a bar graph is indistinguishable from an area graph.

To display a spike plot for a single series or for each series in a group, select **View/Graph...** from the series or group menu, and then choose **Spike** in the **Specific** listbox.




Our illustration shows a spike graph for the annual total newspaper advertising expenditure data in the series **TOTAL** in "Newspapers.WF1". It may be directly compared with the bar graph depiction of the same data (see "[Bar](#)" on page 481).

Note that for large numbers of observations, the spike graph is also indistinguishable from an area graph.

Mixed with Lines

This graph type combines a bar, spike, area, or area band graph with line graphs. The mixed graph displays multiple series in single graph, with the first series shown as a bar, spike, or area graph, or with the first two series displayed as an area band graph, with the remaining series depicted using lines.

To display a mixed plot, you must have with a group object containing two or more series. Select **View/Graph...** from the group menu, and then choose **Mixed with Lines** in the **Specific** listbox.



When you select **Mixed with Lines**, the right-hand side of the page changes to offer a **First series** option, where you will choose between **Bar**, **Spike**, **Area**, and **Area Band**. This setting determines whether the first series in the group will be displayed as a bar, spike, or area graph, or whether the first two series will be used to form an area band graph. The default setting is **Bar**.

Our illustration uses data from our newspaper advertising example ("Newspapers.WF1"). The data in **GROUP01** are displayed as **Mixed with Lines** graph, with the **First series** combo on the right-side of the dialog set to **Bar**.


Dot Plot

The dot plot is a symbol only version of the line and symbol graph ("**Line & Symbol**" on [page 480](#)) that uses circles to represent the value of each observation. It is equivalent to the **Line & Symbol** plot with the lines replaced by circles, and with a small amount of indenting to approve appearance.

Dot plots may be displayed for a single series or each series in a group by selecting **View/Graph...** from the series or group menu, and clicking **Dot Plot** in the **Specific** listbox.

Symbol options may be accessed using the **Lines & Symbols** dialog under the **Graph Elements** group.

Dot plots are often used with cross-section data. For example, using the series **POP** in the workfile "EUPOP.WF1", we may produce a dot plot of the 1995 population of each of the 15 European Union members (as of 1995). With a bit of effort we can see that Germany is the clear population outlier.




Dot plots are sometimes rotated so that the observations are on the vertical axis, often with horizontal gridlines. EViews provides easy to use tools for performing these and other modifications to improve the appearance of this graph ("**Orientation**," on [page 442](#) and "**Grid Lines**," on [page 472](#)).

Error Bar

The error bar graph is an observation graph designed for displaying data with standard error bands. As with the related area band graph, error bars are most often used to display forecast intervals or error bands.

The graph features a vertical error bar connecting the values for the first and second series. If the first series value is below the second series value, the bar will have outside half-lines. The optional third series is plotted as a symbol.




You may display an error bar graph for any group object containing two or more series; the error bar will use data for, at most, the first three series. To display an error bar graph, View/Graph... from the group menu, and then choose Error Bar in the Specific listbox.

Our illustration shows an error graph for the forecasting data in the group GROUP01 in "Forecast_unemp.WF1". It may be directly compared with the area band graph of the same data ("[Area Band](#)" on page 483).

High-Low (Open-Close)

The High-Low (Open-Close) is an observation graph type commonly used to display daily financial data. As the name suggests, this chart is commonly used to plot the daily high, low, opening and closing values of asset prices.

The graph displays data for two to four series. Data from the first two series (the high-low values) will be connected as a vertical line. If provided, the third series (the open value) is drawn as a left horizontal half-line, and the fourth series (the close value) is drawn as a right horizontal half-line.



You may display a high-low graph for any group object containing two or more series. To display an high-low graph, View/Graph... from the group menu, and then choose High-Low (Open-Close) in the Specific listbox. Data for up to four series will be used in forming the graph.


We illustrate this graph type using daily stock price data for Hewlett-Packard (ticker HPQ) for the month of August, 2006 ("HPQ.WF1"). We display the graph for data in the group GROUP01 containing the series HIGH, LOW, OPEN, and CLOSE.

Scatter

A scatterplot is an observation graph of two series in which the values of the second series are plotted against the values of the first series using symbols. Scatterplots allow you to examine visually the relationship between the two variables.

We may display a scatterplot of a group containing two or more series by selecting View/Graph... from the main menu, and then selecting Scatter in the Specific listbox.

Our illustration uses data from the Harrison and Rubinfeld (1978) study of hedonic pricing ("Harrison_Panel.WF1"). The data consist of 506 census tract observations on 92 towns in the Boston.




We focus on the variables NOX, representing the average annual average nitrogen oxide concentration in parts per hundred million, and MV, representing the log of the median value of owner occupied houses (MV). We form the group SCATTER containing NOX and MV, with NOX the first series in the group since we wish to plot it on the horizontal axis. The scatter shows some evidence of a negative relationship between air pollution and house values.

Note that EViews provides tools for placing a variety of common graphs on top of your scatter (see ["Auxiliary Graph Types," beginning on page 512](#)).

XY Line

An XY line graph is an observation graph of two series in which the values of the second series are plotted against the values of the first series, with successive points connected by a line.

XY line graphs differ from scatterplots both in the use of lines connecting points and in the default use of a 4:3 aspect ratio.



To display a XY line graph we first open a group containing two or more series, then select View/Graph... main menu, and then choose XY Line in the Specific listbox.

As with the scatterplot, EViews provides tools for placing a variety of common graphs on top of your XY line graph (see [“Auxiliary Graph Types,” beginning on page 512](#)).

Our illustration uses data on unemployment rates and inflation for the U.S. from 1996 through 2000. Following the discussion in Stock and Watson (2007), we plot the change in the inflation rate against the previous period's unemployment rate; to make it easier to see the ordering of the observations, we have turned on observation labeling ([“Lines and Symbols” on page 476](#)).


XY Area

The XY area graph is an observation graph of two series in which the values of the second series are plotted against the values of the first series. In contrast with the scatterplot, successive points are connected by a line, and the region between the line and the zero horizontal axis is filled. Alternately, one may view the XY area graph as a filled XY line graph (see “XY Line”).

To display a XY area graph we first open a group containing two or more series, then select View/Graph... from the main menu, and then choose XY Area in the Specific listbox.


We may customize the graph by changing display characteristics using the Lines & Symbols and Fill Areas dialogs under the Graph Elements dialog group.

Our illustration of the XY area graph uses data on U.S. unemployment as discussed in “XY Line,” on page 488. Note that the example graph is not particularly informative as XY area graphs are generally employed when the values of the data in the X series are monotonically increasing. For example, XY area graphs are the underlying graph type that EViews uses to display filled distribution graphs.



XY Bar (X-X-Y triplets)

XY bar graphs display the data in sets of three series as a vertical bar. For a given observation, the values in the first two series define a region along the horizontal axis, while the value in the third series defines the vertical height of the bar. While technically an observation graph since every data observation is plotted, this graph is primarily used to display summary results. For example, the XY bar is the underlying graph type used to display histograms (“Histogram,” on page 493).



Our illustration uses the XY bar graph to create a variable width histogram for the 3-month Treasury security data from "Treasury2005c.WF1". We first use Proc/Generate by Classification... to divide the series into categories defined by the intervals [2.25, 2.5), [2.5, 3), [3, 3.9), [3.9, 4.5). The classified series is given by TB03MTH_CT. The frequency view of this series is given by:

Tabulation of TB03MTH_CT
Date: 10/05/06 Time: 12:54
Sample: 1/03/2005 12/30/2005
Included observations: 250
Number of categories: 4

Value	Count	Percent	Cumulative	
			Count	Percent
[2.25, 2.5)	22	8.80	22	8.80
[2.5, 3)	86	34.40	108	43.20
[3, 3.9)	97	38.80	205	82.00
[3.9, 4.5)	45	18.00	250	100.00
Total	250	100.00	250	100.00


Next, we use the data in this table to create a matrix. We want to use a matrix instead of a series in the workfile since we want each row to correspond to a bin in the classification. Accordingly, we create a 4 $\times$ 3 matrix VARWIDTH where the first column contains the low limit points, the second column contains the high limit points, and the last column contains the number of observations that fall into the interval.

To display the XY bar graph shown in the example illustration, select View/Graph... from the matrix main menu, and then choose XY Bar (X-X-Y triplets) in the Specific listbox.

Pie

This graph is an observation graph where each observation is pictured as a pie chart, with the wedges of the pie representing the series value as a percentage of the group total. (If a series has a negative or missing value, the series value will be dropped from the calculation for that observation.)

Pie graphs are available for groups containing two or more series. To display the graph, select View/Graph... from the group menu, and then select Pie in the Specific list-box.



You may choose to label each pie with an observation number. To change the setting from the default value, select the Bar-Area-Pie dialog from the Graph Elements group, and select or unselect the Label pies option in the Pie graphs section of the page.

Our illustration uses the newspaper advertising revenue data ("Newspapers.WF1"). The three series in GROUP01, CLASSIFIED, RETAIL, and NATIONAL, are the three components of TOTAL advertising revenue. Each pie in the graph shows the relative proportions; retail is the dominant component, but its share has been falling relative to classified.

Seasonal Graphs

Seasonal graphs are a special form of line graph in which you plot separate line graphs for each season in a regular frequency monthly or quarterly workfile.

To display a seasonal graph for a single series or for each series in a group, select View/Graph... from the series or group menu, and then choose Seasonal Graph in the Specific listbox. Note that if your workfile does not follow a monthly or quarterly regular frequency, Seasonal Graph will not appear as a specific graph type.


When you select Seasonal Graph, the right-hand side of the page changes to provide a Seasonal type combo containing two options for displaying the graph. The first option, Paneled lines & means, instructs EViews to divide the graph into panels, each of which will contain a time series for a given season. If, for example, we have a monthly work-

file, the graph will be divided into 12 panels, the first containing a time series of observations for January, the second containing a time series for February, etc. The second option, Multiple overlaid lines , overlays the time series for each season in a single graph, using a common date axis.

To see the effects of these choices, we consider two examples of seasonal graphs. The EViews workfile “Starts_cust.WF1” contains Census Bureau data on monthly new residential construction in the U.S. (not seasonally adjusted) from January 1959 through August 2006. We will consider the series TOTAL containing data on the total of new privately owned housing starts (in thousands) for the subsample from January 1990 through August 2006.


We first display a Paneled lines & means seasonal graph for the series TOTAL. Note that the graph area is divided into panels, each containing a time series for a specific month. The graph also contains a set of horizontal lines marking the seasonal means.

It is easy to see the seasonal pattern of housing starts from this graph, with a strong reduction in housing starts during the fall and winter months. The mean of January starts is a little over 120 thousand units, while the mean for May starts is around 180 thousand.



We may contrast this form of the seasonal graph with the Multiple overlaid lines form of the seasonal graph. The differences in the individual time series lines provide a different form of visual evidence of seasonal variation in housing starts. The overlaid form of the seasonal graph makes it easier to compare values for a given period.

Here, we see that January values for housing starts are roughly two-thirds of their summer counterparts.



Analytical Graph Types


Analytical graphs are created by first performing data reduction or statistical analysis on the series or group data and then displaying the results visually. The central feature of these graphs is that they do not show data for each observation, but instead display a summary of the original data.

The following is a brief summary of the characteristics of each of these graph types. Unless otherwise specified, the examples use data on three month CD rate data for 69 Long Island banks and thrifts ("CDrate.WF1"). These data are used as an example in Simonoff (1996).

Histogram

The histogram graph view displays the distribution of your series in bar graph form. The histogram divides the horizontal axis into equal length intervals or bins, and displays a count or fraction of the number of observations that fall into each bin, or an estimate of the probability density function for the bin.


To display a histogram for a single series or for each series in a group, select **View/Graph...** from the series or group menu, then select **Distribution** from the **Specific** listbox. The right-hand side of the dialog will change to show **Distribution** options. Select **Histogram** from the drop-down (the default).



(Note that specialized tools also allow you to place histograms along the axes of various graph types.)

When you select **Histogram**, EViews displays an **Options** button that opens the **Distribution Plot Customize** dialog. This dialog allows you to customize your histogram estimate or to add additional distribution graphs. You may, for example, add a fitted theoretical distribution plot or kernel density to the histogram.

Adding additional graph elements may be done using the Add button in the Added Elements section of the dialog. As you add elements, they will appear in the list-box on the left. You may select any graph element to display its options on the right-hand side of the page. In this example, there is only the single histogram graph element (which is selected), and the dialog shows the options for that histogram.



First, the Scaling combo box lets you choose between showing the count of the number of observations in a bin (Frequency), an estimate of the density in the bin (Density), and the fraction of observations in each bin (Relative frequency). The density estimates are computed by scaling the relative frequency by the bin width so that the area in the bin is equal to the fraction of observations.

Next, Bin Width and Anchor specify the construction of the bin intervals. By default, EViews tries to create bins that are defined on “nice” numbers (whole numbers and simple fractions). These estimates do not have any particular statistical justification.


Simple data based methods for determining bin size have been proposed by a number of authors (Scott 1979, 1985a; Silverman 1986; Freedman-Diaconis 1981). The supported methods all choose a bin width h that minimizes the integrated mean square error of the approximation (IMSE) using the formula, $h = a \hat{\sigma} N^{-1/3}$:

- Normal (Sigma): $a = 3.49, \hat{\sigma} = s$
- Normal (IQR): $a = 3.49, \hat{\sigma} = \text{IQR} / 1.34$
- Silverman: $a = 3.49, \hat{\sigma} = \min(s, \text{IQR} / 1.34)$
- Freedman-Diaconis: $a = 2.0, \hat{\sigma} = \text{IQR}$

where s is the sample standard deviation, IQR is the interquartile range, and N is the number of observations.

For our example data, displaying a density histogram of the CDRATE data using the Normal (Sigma) bin-width method shows a histogram with considerably fewer bins and modified vertical axis scaling. One could argue that the shape of the CDRATE distribution is more apparent in this plot, at the cost of detail on the number of observations in easily described categories.

It is well-known that the appearance of the histogram may be sensitive to the choice of the anchor (see, for example, Simonoff and Udina, 1997). By default, EViews sets the anchor position for bins to 0, but this may be changed by entering a value in the Anchor edit box.




The Right-closed bin intervals checkbox controls how observations that equal a bin endpoint are handled. If you select this option, observations equal to the right-endpoint of a bin will be classified as being in the bin, while observations equal to the left-endpoint will be placed in the previous bin.

By default, EViews provides the minimum legend information sufficient to identify the graph elements. In some instances, this means that no legend is provided; in other cases, the legends may be rather terse. The Legend labels combo box allows you to override this setting; you may elect to display a short legend (Short), to display detailed information (Detailed), or to suppress all legend information (None).

Histogram Polygon

Scott (1985a) shows that the histogram polygon (frequency polygon), which is constructed by connecting the mid-bin values of a histogram with straight lines, is superior to the histogram for estimating the unknown probability density function.

To display a histogram polygon for a single series or for each series in a group, select **View/Graph...** from the series or group menu, then select **Distribution** from the **Specific** listbox. Then choose **Histogram Polygon** from the **Distribution** options on the right-hand side.



We use the default settings to display the frequency polygon for the three-month CD rate data. The EViews defaults, which were designed to generate easy to interpret histogram intervals, undersmooth the data.


You may control the computation of the histogram polygon by clicking on the **Options** button, and filling out the resulting dialog. In addition to all of the options described in [“Histogram” on page 493](#), you may instruct EViews to display the fill the area under the polygon by clicking on the **Fill area** checkbox.

Note that the data based methods for determining bin size differ from those for the frequency polygon. The bandwidth is chosen as in the frequency polygon with $h = 2.15$ for the Normal (Sigma), Normal (IQR), and Normal (Silverman) methods, and $h = 1.23$ for Freedman-Diaconis. The constant factor in the Freedman-Diaconis is a crude adjustment that takes the histogram value for h and scales it by the ratio of the normal scaling factors for the frequency polygon and the histogram ($2.15 / 3.49$).

Histogram Edge Polygon

Jones, et al. (1998) propose a modification of the frequency polygon that joins the bin right-edges by straight lines. This modification generates a smoothed histogram that improves on the properties of the frequency polygon.

To display a edge polygon, select View/Graph... from the series or group menu, then select Distribution from the Specific listbox. Then choose Histogram Edge Polygon from the Distribution drop-down to the right.



The default edge frequency graph for the CDrate data is displayed here. The EViews defaults, which were designed to generate easy to interpret histogram intervals, appear to undersmooth the data.


You may control the computation of the histogram polygon by clicking on the Options button, and filling out the resulting dialog. All of the options are described in ["Histogram Polygon" on page 496](#)

Note that the data based methods for determining bin size generate different bin widths than those for the frequency polygon. The bandwidth is chosen as in the histogram and frequency polygon with a 1.50 for the Normal (Sigma), Normal (IQR), and Normal (Silverman) methods, and a 0.86 for Freedman-Diaconis.

Average Shifted Histogram

The average shifted histogram (ASH) is formed by computing several histograms with a given bin width but different bin anchors, and averaging these histograms (Scott, 1985b). By averaging over shifted histograms, the ASH minimizes the impact of bin anchor on the appearance of the histogram.

Scott (1985b) notes that the ASH retains the computational simplicity of the histogram, but approaches the statistical efficiency of a kernel density estimator. EViews computes the frequency polygon version of the ASH, formed by connecting midpoints of the ASH using straight lines.



To compute an ASH, select **View/Graph...** from the series or group menu, then select **Distribution** from the **Specific** listbox. Then choose **Average Shifted Histogram** from the **Distribution** drop-down to the right.

The default ASH for the Long Island CD rate data is displayed above. The EViews defaults, which were designed to generate easy to interpret histogram intervals, undersmooth the data.

When you select **Average Shifted Histogram**, EViews displays an **Options** button that opens the **Distribution Plot Customize** dialog allowing you to customize your ASH or to add additional distribution graphs (see [“Histogram” on page 493](#) for a discussion of the latter topic).

Almost all of the settings on the right-hand side of the dialog are familiar from our discussion of histograms.

The only new setting is the edit box for the Number of shift evaluations . This setting controls the number of histograms over which we average. By default, EViews will compute 25 shifted histograms.

Kernel Density


The kernel density graph displays a kernel density estimate of the distribution of a single series. Heuristically, the kernel density estimator is an adjusted histogram in which the “boxes” the histogram are replaced by “bumps” that are smooth (Silverman, 1986). Smoothing is done by putting less weight on observations that are further from the point being evaluated. Specifically, the kernel density estimate of a series X at a point x is estimated by:

$$f(x) = \frac{1}{Nh} \sum_{i=1}^N K\left(\frac{x - X_i}{h}\right) \quad (13.1)$$

where N is the number of observations, h is the bandwidth (or smoothing parameter) and K is a kernel weighting function that integrates to one.


To compute and display a kernel density estimate for a single series or for each series in a group, select View/Graph... from the series or group menu, then choose Distribution in the Specific listbox. The right-hand side of the dialog page will change to provide a Distribution combo box prompting you to choose a distribution graph. You should select Kernel Density .

(Note also that specialized tools allow you to place kernel density plots along the axes of various graph types.)



The default kernel density estimate for the CD rate data (see “Histogram” on page 493) is depicted above.

When you select Distribution/Kernel Density , EViews displays an Options button that opens the Distribution Plot Customize dialog. This dialog allows you to customize your kernel density estimate, or to add additional distribution graphs. You may, for example, choose a different kernel function, or a different bandwidth, or you may add a histogram or fitted theoretical distribution plot to the graph.



Adding additional graph elements may be done using the Add button in the Added Elements section of the dialog.

The Specification section of the dialog allows you to specify your kernel function and bandwidth selection:

- Kernel . The kernel function is a weighting function that determines the shape of the bumps. EViews provides the following options for the kernel function K:

Epanechnikov (default)	$\frac{3}{4} (1 - u^2) I(u \leq 1)$
Triangular	$(1 - u) I(u \leq 1)$
Uniform (Rectangular)	$\frac{1}{2} I(u \leq 1)$
Normal (Gaussian)	$\frac{1}{\sqrt{2\pi}} \exp\left(-\frac{1}{2}u^2\right)$
Biweight (Quartic)	$\frac{15}{16} (1 - u^2)^2 I(u \leq 1)$
Triweight	$\frac{35}{32} (1 - u^2)^3 I(u \leq 1)$
Cosinus	$\frac{9}{4} \cos\left(\frac{\pi}{2}u\right) I(u \leq 1)$

where u is the argument of the kernel function and I is the indicator function that takes a value of one if its argument is true, and zero otherwise.

- **Bandwidth** . The bandwidth h controls the smoothness of the density estimate; the larger the bandwidth, the smoother the estimate. Bandwidth selection is of crucial importance in density estimation (Silverman, 1986), and various methods have been suggested in the literature. The Silverman option (default) uses a data-based automatic bandwidth:

$$h = 0.9kN^{-1/5} \min(s, IQR/1.34) \quad (13.2)$$

where N is the number of observations, s is the standard deviation, and IQR is the interquartile range of the series (Silverman 1986, equation 3.31). The factor k is a canonical bandwidth-transformation that differs across kernel functions (Marron and Nolan 1989; Härdle 1991). The canonical bandwidth-transformation adjusts the bandwidth so that the automatic density estimates have roughly the same amount of smoothness across various kernel functions.

To specify a bandwidth of your choice, click on the User Specified option and type a nonnegative number for the bandwidth in the corresponding edit box. Although there is no general rule for the appropriate choice of the bandwidth, Silverman (1986, section 3.4) makes a case for undersmoothing by choosing a somewhat small bandwidth, since it is easier for the eye to smooth than it is to unsmooth.

The Bracket Bandwidth option allows you to investigate the sensitivity of your estimates to variations in the bandwidth. If you choose to bracket the bandwidth, EViews plots three density estimates using bandwidths $0.5h$, h , and $1.5h$.

The remaining options control the method used to compute the kernel estimates, the legend settings, and whether or not to fill the area under the estimate:

- **Number of Points** . You must specify the number of points M at which you will evaluate the density function. The default is $M = 100$ points. Suppose the minimum and maximum value to be considered are given by X_L and X_U , respectively. Then $f(x)$ is evaluated at M equi-spaced points given by:

$$x_i = X_L + i \frac{X_U - X_L}{M-1} \quad \text{for } i = 0, 1, \dots, M-1. \quad (13.3)$$

EViews selects the lower and upper evaluation points by extending the minimum and maximum values of the data by two (for the normal kernel) or one (for all other kernels) bandwidth units.


- **Method** . By default, EViews utilizes the Linear Binning approximation algorithm of Fan and Marron (1994) to limit the number of evaluations required in computing the density estimates. For large samples, the computational savings are substantial.

The Exact option evaluates the density function using all of the data points for each X_j , $j = 1, 2, \dots, N$ for each x_i . The number of kernel evaluations is therefore of order $O(NM)$, which, for large samples, may be quite time-consuming.

Unless there is a strong reason to compute the exact density estimate or unless your sample is very small, we recommend that you use the binning algorithm.

- **Legend labels.** This combo box controls the information placed in the legend for the graph. By default, EViews uses a minimalist approach to legend labeling; information sufficient to identify the estimate is provided. In some cases, as with the kernel density of a single series, this implies that no legend is provided. You may elect instead to always display a short legend (Short), to display detailed kernel choice and bandwidth information (Full), or you may elect to suppress all legend information (None).
- **Fill area.** Select this option if you wish to draw the kernel density as a filled line graph.

This density estimate for the CD rate data seems to be oversmoothed. Simonoff (1996, chapter 3) uses a Gaussian kernel with bandwidth 0.08. To replicate his results, we fill out the dialog as follows: we select the Normal (Gaussian) kernel, specify a bandwidth of 0.08, select the Exact evaluation method (since there are only 69 observations to evaluate the kernel), select Detailed from Legend labels, and check the Fill area checkbox.




This density estimate has about the right degree of smoothing. Interestingly enough, this density has a trimodal shape with modes at the “focal” numbers 7.5, 8.0, and 8.5. Note that the shading highlights the fact that the kernel estimates are computed only from around 7.45 to around 8.85.

Theoretical Distribution

You may plot the density function of a theoretical distribution by selecting View/Graph... from the series or group menu, and choosing Distribution in the Specific listbox. The right-hand side of the dialog page will change to provide a Distribution combo box prompting you to choose a distribution graph. You should select Theoretical Distribution.

By default, EViews will display the normal density function fit to the data.



The Options button may be used to display the Distribution Plot Customize dialog. As with other distribution graphs, the left-hand side of the dialog may be used to add distribution graphs to the current plot (e.g., combining a histogram and a theoretical distribution).

The right-hand side of the dialog allows you to specify the parametric distribution that you wish to display. Simply select the distribution

of interest from the drop-down menu. The small display window will change to show you the parameterization of the specified distribution.

You can specify the values of any known parameters in the edit field or fields. If you leave any field blank, EViews will estimate the corresponding parameter using the data contained in the series.

The Estimation Options provides control over iterative estimation, if relevant. You should not need to use these settings unless the graph indicates failure in the estimation process.


Most of the options are self-explanatory. If you select User-specified starting values , EViews will take the starting values from the C coefficient vector.

Empirical CDF

The empirical CDF graph displays a plot of the empirical cumulative distribution function (CDF) of the series. The CDF is the probability of observing a value from the series not exceeding a specified value r :

$$F_x(r) = \Pr(x \leq r)$$

To display the empirical CDF, you should select View/Graph... from the series or group menu, choose Distribution in the Specific listbox, and select Empirical CDF in the Distribution combo.



By default, EViews displays the empirical CDF for the data in the series along with approximate 95% confidence intervals. The confidence intervals are based on the Wilson interval methodology (Wilson, 1927; Brown, Cai and Dasgupta, 2001).

Clicking on the Options button displays a dialog that allows you to specify the method for computing the CDF, to turn on or off the displaying of confidence intervals, to specify the size of the confidence interval, and to control the display of legend entries.

The Quantile Method combo controls the method of computing the CDF. Given a total of N observations, the CDF for value r is estimated as:

Rankit (default)	$r - 1 \div N$
Ordinary	$r \div N$
Van der Waerden	$r \div (N + 1)$
Blom	$(r - 3 \div 8) \div (N + 1 \div 4)$
Tukey	$(r - 1 \div 3) \div (N + 1 \div 3)$
Gumbel	$(r - 1) \div (N - 1)$

See Cleveland (1994) and Hyndman and Fan (1996). By default, EViews uses the Rankit method, but you may use the combo to select a different method.

Empirical Survivor


The empirical survivor graph of a series displays an estimate of the probability of observing a value at least as large as some specified value r :

$$S_x(r) = \Pr(x \geq r) = 1 - F_x(r)$$

To display the empirical survivor function, select View/Graph... from the series or group menu, choose Distribution in the Specific listbox, and select Empirical Survivor in the Distribution combo.

By default, EViews displays the estimated survivor function along with a 95% confidence interval (Wilson, 1927; Brown, Cai and Dasgupta, 2001).

See [“Empirical CDF” on page 504](#) for additional discussion and a description of the dialog brought up by the Options button.




Empirical Log Survivor

The empirical log survivor graph for a series displays the log of the probability of observing a value at least as large as some specified value r .

To display the empirical log survivor function, select View/Graph... from the series or group menu, choose Distribution in the Specific listbox, and select Empirical Log Survivor in the Distribution combo.

By default, EViews displays the logarithm of the estimated survivor function along with a 95% confidence interval (Wilson, 1927; Brown, Cai and Dasgupta, 2001).



See [“Empirical Survivor” on page 505](#) for additional discussion and a description of the dialog brought up by the Options button.

Empirical Quantile


This graph type plots the empirical quantiles of the series against the associated probabilities. The quantile is the inverse function of the CDF; graphically, the quantile can be obtained by flipping the horizontal and vertical axis of the CDF.

For $0 \leq q \leq 1$, the q -th quantile x_q of x is a number such that:

$$\Pr(x \leq x_q) \geq q$$

$$\Pr(x \leq x_q) \leq 1 - q$$

The graph plots the values of x_q against q .




To display the empirical quantile plot, select View/Graph... from the series or group menu, choose Distribution in the Specific listbox, and Empirical Quantile in the Distribution combo.

By default, EViews displays the empirical quantiles along with approximate 95% confidence intervals obtained by inverting the Wilson confidence intervals for the CDF (Wilson, 1927; Brown, Cai and Dasgupta, 2001).

See [“Empirical Survivor” on page 505](#) for a description of the dialog brought up by clicking the Options button.

Quantile-Quantile (Theoretical)

Theoretical quantile-quantile plots are used to assess whether the data in a single series follow a specified theoretical distribution; e.g. whether the data are normally distributed (Cleveland, 1994; Chambers, et al. 1983). If the two distributions are the same, the QQ-plot should lie on a straight line. If the QQ-plot does not lie on a straight line, the two distributions differ along some dimension. The pattern of deviation from linearity provides an indication of the nature of the mismatch.



To display the theoretical quantile-quantile plot, select View/Graph... from the series or group menu, choose Quantile - Quantile in the Specific listbox, and select Theoretical in the Q-Q graph combo to the right.

By default, EViews displays the QQ-plot comparing the quantiles of the data with the quantiles of a fitted normal distribution.

The Options button may be used to display the Quantile-Quantile Plot Customize dialog. The left-side of this graph may be used to add additional QQ-plots to the current plot, allowing you to compare your data to more than one theoretical distribution.

The right-hand side of the dialog allows you to specify the parametric distribution that you wish to display. See [“Theoretical Distribution” on page 503](#) for a discussion of these settings.

Quantile-Quantile Plot Customize

Added Elements

- Theoretical Q-Q

Specification

Distribution: **Logistic**

$$f(x|\mu, s) = \left(\frac{1}{s}\right) e^{(x-\mu)/s} (1 + e^{(x-\mu)/s})^{-2}$$

μ

s

Enter number or expression for parameter, or leave blank to estimate value

Quantile Method: **Rankit (Cleveland)**

Options

☒ Display fit line

Legend labels: **Default**

Estimation Options

Max Iterations: **500** Convergence: **1e-07**

Starting Coef Values: **EViews supplied**


OK **Cancel**

In addition, the customize page offers you several methods for computing the empirical quantiles. The options are explained in the section [“Empirical CDF” on page 504](#); the choice should not make much difference unless the sample is very small.

Lastly, the Display fit line checkbox provides you with the option of plotting a regression line through the quantile values.

Quantile-Quantile (Symmetry)

An alternative form of the quantile-quantile (QQ)-plot examines the symmetry of the data directly by comparing each quantile value with the corresponding upper-tail quantile value. You may think of this procedure as plotting the distance to points above the median against the distance to the corresponding point below the median (Cleveland, et al. 1983, p. 17). The resulting QQ-symmetry plot has the property that the more symmetric are the data, the closer are the points to the 45 degree line.



To display the quantile-quantile symmetry plot, select View/Graph... from the series or group menu, choose Quantile - Quantile in the Specific listbox, and select Symmetry in the Q-Q graph combo to the right.


Our example uses the workfile “CDrate.WF1”, for which we have plotted the symmetry of the series CDRATE. The default QQ-symmetry plot shows that the data is highly asymmetric.

The Options button may be used to display the Quantile-Quantile Plot Customize dialog. The settings offered in this dialog are limited; you may choose whether to display the 45 degree line and may modify the legend settings.

Quantile-Quantile (Empirical)

The empirical quantile-quantile (QQ)-plot plots the quantiles of one series against the quantiles of a second series (Cleveland, 1994; Chambers, et al. 1983). If the distributions of the two series are the same, the QQ-plot should lie on a straight line.

To display the empirical quantile-quantile plot for a group with two or more series, select View/Graph... from the group menu, choose Quantile - Quantile in the Specific listbox, and select Empirical in the Q-Q graph combo.



Our illustration uses the example workfile "Housedebt.WF1", containing quarterly data on household debt and financial obligations from 1980 to 2006. We show here the default QQ-plot for the debt service ratio series DSR against the financial obligation ratio series FOR_TOTAL.

The settings accessed through the Options button are limited; you may specify a computation method, choose whether to display the fit line, and modify the legend settings. These settings are discussed in "Theoretical Distribution" on page 503 and "Quantile-Quantile (Theoretical)" on page 507.


Note that unlike other distribution graphs, EVIEWS does not allow you to add additional QQ-plots for a given pair of series; rarely will the choice of Quantile Method generate enough of a difference to make such a plot useful.

Boxplot

A boxplot, also known as a box and whisker diagram, summarizes the distribution of a set of data by displaying the centering and spread of the data using a few primary elements (McGill, Tukey, and Larsen, 1978).

The box portion of a boxplot represents the first and third quartiles (middle 50 percent of the data). These two quartiles are collectively termed the hinges, and the difference between them represents the interquartile range, or IQR. The median is depicted using a line through the center of the box, while the mean is drawn using a symbol.

The inner fences are defined as the first quartile minus $1.5 \times \text{IQR}$ and the third quartile plus $1.5 \times \text{IQR}$. The inner fences are typically not drawn in boxplots, but graphic elements known as whiskers and staples show the values that are outside the first and third quartiles, but within the inner fences. The staple is a line drawn at the last data point within (or equal to) each of the inner fences. Whiskers are lines drawn from each hinge to the corresponding staple.




Data points outside the inner fence are known as outliers. To further characterize outliers, we define the outer fences as the first quartile minus $3.0 \times \text{IQR}$ and the third quartile plus $3.0 \times \text{IQR}$. As with inner fences, outer fences are not typically drawn in boxplots. Data between the inner and outer fences are termed near outliers, and those outside the outer fence are referred to as far outliers. A data point lying on an outer fence is considered a near outlier.

A shaded region or notch may be added to the boxplot to display approximate confidence intervals for the median (under certain restrictive statistical assumptions). The bounds of the shaded or notched area are defined by the median $\pm 1.57 \times \text{IQR} / \sqrt{N}$ where

N is the number of observations. Notching or shading is useful in comparing differences in medians; if the notches of two boxes do not overlap, then the medians are, roughly, significantly different at a 95% confidence level. It is worth noting that in some cases, most likely involving small numbers of observations, the notches may be bigger than the boxes.


Boxplots are often drawn so that the widths of the boxes are uniform. Alternatively, the box widths can be varied as a measure of the sample size for each box, with widths drawn proportional to N , or proportional to the square root of N .



To display a boxplot for a single series or for each series in a group, select **View/Graph...** from the series or group menu, and then choose **Boxplot** in the Specific listbox.


(Note that specialized tools allow you to place boxplots along the axes of various graph types.)

The default boxplot for the three month CD rate data is presented here. Note that since we are displaying the boxplot for a single series, EViews changes the aspect ratio of the graph so that it is taller than it is wide. Typically, boxplots are displayed for multiple series; the aspect ratio will adjust accordingly.



In addition to the **Orientation** option on the main page which allows you to rotate your boxplots, you may specify a number of display options in the **BoxPlots** dialog under the **Graph Elements** group.

The left-hand side of the **BoxPlot** dialog allows you to show or hide specific elements of the boxplot, to control the box widths, and to modify the appearance of the notching and shading.



In the right-hand portion

of the dialog, you may customize individual elements of your graph. Simply select an element to customize in the **Element** listbox or click on the depiction of a boxplot element in the **Preview** window, and then modify the **Color**, **Line pattern**, **Line/Symbol width**, and **Symbol** type as desired. Note that each boxplot element is represented by either a line or a symbol; the dialog will show the appropriate choice for the element that you have selected.

The Preview window will change to display the current settings for your graph. You may also click on elements within the Preview window to select them in the Element listbox, if you find this easier. To revert to the original graph settings, click on Undo Page Edits.

Auxiliary Graph Types

EViews can construct several analytical graphs that are only meant to be added to observation graphs; we term these graphs auxiliary graphs. Strictly speaking, auxiliary XY graphs should not be thought of as a distinct graph type, but rather as a class of modifications that may be applied to an observation plot.


At present, auxiliary graphs may be added on top of scatterplots and XY line graphs. When either Scatter or XY Line is selected in the Specific listbox, the right-hand side of the graph dialog changes to offer the Fit lines combo box, where you can select one of the auxiliary types to be added to the graph. If you wish to add additional auxiliary graphs or if you wish to customize the settings of your specified type, you should click on the Options button to display additional settings.

The following is a brief summary of the characteristics of each of these graph types. For illustration purposes, the examples generally use the familiar “Old Faithful Geyser” eruption time data considered by Simonoff (1996) and many others (“Geyser.WF1”). These data provide information on 222 eruption time intervals and previous eruption durations for the Old Faithful Geyser in Yellowstone National Park.

Regression Line

This graph uses data from two series, displaying the fit of a bivariate regression of the second series on the first series x , and a constant. If desired, you may automatically perform various transformations of your data prior to performing the regression.

Our example uses the geyser data and considers the relationship between previous eruption length, and the interval to the next eruption. We create a group GROUP01 where the first series, LENGTH, rep-




resents the duration of the previous eruption, and the second series, INTERVAL, measures the interval between eruptions.

In our illustration, the regression line is drawn on top of the scatterplot of points for the geyser data. Clearly there is a positive relationship between length of eruption and the time until the next eruption.

Clicking on the Options button displays the Scatterplot Customize dialog. The left-hand side of the dialog may be used to add additional auxiliary graphs; simply click on the Add button and select the type of element you wish to add.

The right-hand side of the dialog contains options specific to the selected element. In this case, we see the options for the regression line selection.

First, you may specify transformations of your dependent and independent variables using the radio buttons. The following transformations are available for the bivariate fit:



None	y	x
Logarithmic	$\log y$	$\log x$
Inverse	$1/y$	$1/x$
Power	y^a	x^b
Box-Cox	$y^a - 1/a$	$x^b - 1/b$
Polynomial	—	$1, x, x^2, \dots, x^b$

where you specify the parameters a and b in the edit field. Note that the Box-Cox transformation with parameter zero is the same as the log transformation.

- If any of the transformed values are not available, EViews returns an error message. For example, if you take logs of negative values, non-integer powers of nonpositive values, or inverses of zeros, EViews will stop processing and issue an error message.

- If you specify a high-order polynomial, EViews may be forced to drop some of the high order terms to avoid collinearity.

Next, you may instruct EViews to perform robustness iterations (Cleveland, 1993). The least squares method is very sensitive to the presence of even a few outlying observations. The Robustness Iterations option carries out a form of weighted least squares where outlying observations are given relatively less weight in estimating the coefficients of the regression.

For any given transformation of the series, the Robustness Iteration option carries out robust fitting with bisquare weights. Robust fitting estimates the parameters a , b to minimize the weighted sum of squared residuals,

$$\sum_{i=1}^N r_i (y_i - a - x_i b)^2 \quad (13.4)$$

where y_i and x_i are the transformed series and the bisquare robustness weights are given by:

$$r_i = \begin{cases} 1 - e_i^2 / 36m^2 & \text{for } |e_i| \leq m \\ 0 & \text{otherwise} \end{cases} \quad (13.5)$$

where $e_i = y_i - a - x_i b$ is the residual from the previous iteration (the first iteration weights are determined by the OLS residuals), and m is the median of $|e_i|$. Observations with large residuals (outliers) are given small weights when forming the weighted sum of squared residuals.

To choose the number robustness iterations, click on the check box for Robustness Iterations and specify an integer for the number of iterations.

Lastly there is an option controlling the amount of information provided in legends. The EViews default displays a minimum of legend information; this default may be overridden using the Legend labels combo box. In particular, if you wish to see the coefficients of your fitted line you should select Full. (Note that coefficient information is not available for some transformations).

Kernel Fit

Using data from two series, this kernel fit displays the local polynomial kernel regression fit of the second series y on the first series x . Extensive discussion may be found in Simonoff (1996), Hardle (1991), Fan and Gijbels (1996).

Both the nearest neighbor fit ("Nearest Neighbor Fit," on [page 517](#)), and the kernel regression fit are nonparametric regression methods that fit local polynomials. The two differ in how they define "local" in the choice of bandwidth.

The effective bandwidth in nearest neighbor regression varies, adapting to the observed distribution of the regressor. For the kernel fit, the bandwidth is fixed but the local observations are weighted according to a kernel function.


Local polynomial kernel regressions fit Y at each value x , by choosing the parameters b to minimize the weighted sum-of-squared residuals:

$$\min_x \sum_{i=1}^N (Y_i - b_0 - b_1 x - X_i - \dots - b_k x - X_i)^2 K \left(\frac{x - X_i}{h} \right) \quad (13.6)_1$$

where N is the number of observations, h is the bandwidth (or smoothing parameter), and K is a kernel function that integrates to one. Note that the minimizing estimates of b will differ for each x .


The default settings compute the local linear fit using the Epanechnikov kernel and an arbitrary, rule of thumb bandwidth rule. For efficient purposes, the kernel fit is evaluated using the linear binning method proposed by Fan and Marron (1994).

Our example shows the default kernel fit line drawn on top of the geyser scatterplot data. As with the regression line there is a positive relationship between the length of eruption and the time until the next eruption. There does appear to be some flattening of the slope of the relationship for long durations, suggesting that there may be a different model for short and long duration times.



You may click on the Options button to display the Scatterplot Customize dialog. As always, the left-hand side of the graph may be used to add additional auxiliary graphs, while the right-hand side of the dialog provides options for the kernel fit.

You will need to specify the form of the local regression (Nadaraya-Watson constant, Linear, Polynomial), the kernel function, the bandwidth, and other options to control the fit procedure.



Regression

Here, you will specify the order of the polynomial k to fit at each data point. The Nadaraya-Watson option sets $k = 0$ and locally fits a constant at each x . Local Linear sets $k = 1$ at each x . For higher order polynomials, mark the Local Polynomial option and type in an integer in the field box to specify the order of the polynomial.

Kernel

The kernel is the function used to weight the observations in each local regression. Definitions are provided in the discussion of “Kernel Density,” beginning on page 499.

Bandwidth

The bandwidth h determines the weights to be applied to observations in each local regression. The larger the h , the smoother the fit. By default, EViews arbitrarily sets the bandwidth to:

$$h = 0.15 (X_U - X_L) \quad (13.7)$$

where $X_U - X_L$ is the range of X .

To specify your own bandwidth, mark User Specified and enter a nonnegative number for the bandwidth in the edit box.

The Bracket Bandwidth option fits three kernel regressions using bandwidths $0.5h$, h , and $1.5h$.

For nearest neighbor (variable) bandwidths, see [“Nearest Neighbor Fit,” on page 517](#).

Number of grid points

You must specify the number of points M at which to evaluate the local polynomial regression. The default is $M = 100$ points; you can specify any integer in the field. Suppose the range of the series X is $[X_L, X_U]$. Then the polynomial is evaluated at M equi-spaced points:

$$x_i = X_L + i \cdot \frac{X_U - X_L}{M - 1} \quad \text{for } i = 0, 1, \dots, M - 1 \quad (13.8)$$

Method


Given a number of evaluation points, EViews provides you with two additional computational options: exact computation and linear binning.

The Linear Binning method (Fan and Marron, 1994) approximates the kernel regression by binning the raw data X_j fractionally to the two nearest evaluation points, prior to evaluating the kernel estimate. For large data sets, the computational savings may be substantial, with virtually no loss of precision.

The Exact method performs a regression at each x_i , using all of the data points X_j, Y_j , for $j = 1, 2, \dots, N$. Since the exact method computes a regression at every grid point, it may be quite time consuming when applied to large samples. In these settings, you may wish to consider the linear binning method.

Nearest Neighbor Fit

The nearest neighbor fit displays local polynomial regressions for two series with bandwidth based on nearest neighbors. Briefly, for each data point in a sample, we fit a locally weighted polynomial regression. It is a local regression since we use only the subset of observations which lie in a neighborhood of the point to fit the regression model; it may be weighted so that observations further from the given data point are given less weight.




This class of regressions includes the popular Loess (also known as Lowess) techniques described by Cleveland (1993, 1994). Additional discussion of these techniques may be found in Fan and Gijbels (1996), and in Chambers, Cleveland, Kleiner, Tukey (1983).

The default settings estimate a local linear regression using a bandwidth of 30% of the sample. The estimates use Tricube weighting, and Cleveland subsampling of the data.

Our illustration shows results that are broadly similar to the results for the kernel fit. There is a positive relationship between the length of eruption and the time until the next eruption, with evidence of flattening of the slope of the relationship for long durations.

Clicking on the Options button displays the Scatterplot Customize dialog. The left-hand side of the dialog may be used to add additional auxiliary graphs, while the right-hand side of the dialog provides options for the nearest neighbor fit.

You will need to specify the form of the local regression, the bandwidth, and other options to control the fit procedure.



Specification

For each point in the sample selected by the Evaluation Method option, we compute the fitted value by running a local regression using data around that point. The Specification option determines the rules employed in identifying the observations to be included in each local regression, and the functional form used for the regression.

Polynomial degree specifies the degree of polynomial to fit in each local regression.

Bandwidth span determines which observations should be included in the local regressions. You should specify a number a between 0 and 1. The span controls the smoothness of the local fit; a larger fraction a gives a smoother fit. The fraction a instructs EViews to include the $\lfloor aN \rfloor$ observations nearest to the given point, where $\lfloor aN \rfloor$ is $100a$ % of the total sample size, truncated to an integer.

If you mark the Bracket bandwidth span option, EViews displays three nearest neighbor fits with spans of $0.5a$, a , and $1.5a$.

Note that this standard definition of nearest neighbors implies that the number of points need not be symmetric around the point being evaluated. If desired, you can force symmetry by selecting the **Symmetric neighbors** option. **Symmetric Neighbors** forces the local regression to include the same number of observations to the left and to the right of the point being evaluated. This approach violates the definition, but arguably not the spirit, of nearest neighbor regression. Differences between the two approaches will show up where the data are thin (there are relatively few observations in the region).

Weighting

Local Weighting (Tricube) weights the observations of each local regression. The weighted regression minimizes the weighted sum of squared residuals:

$$\sum_{i=1}^N w_i (y_i - a - x_i b_1 - x_i^2 b_2 - \dots - x_i^k b_k)^2. \quad (13.9)$$

The tricube weights w_i are given by:

$$w_i = \begin{cases} 1 - \left| \frac{d_i}{d_{[aN]}} \right|^3 & \text{for } \left| \frac{d_i}{d_{[aN]}} \right| \leq 1 \\ 0 & \text{otherwise} \end{cases} \quad (13.10)$$

where $d_i = |x_i - x|$ and $d_{[aN]}$ is the $[aN]$ -th smallest such distance. Observations that are relatively far from the point being evaluated get small weights in the sum of squared residuals. If you turn this option off, each local regression will be unweighted with $w_i = 1$ for all i .

Robustness Iterations iterates the local regressions by adjusting the weights to downweight outlier observations. The initial fit is obtained using weights w_i , where w_i is tricube if you choose **Local Weighting** and 1 otherwise. The residuals e_i from the initial fit are used to compute the robustness bisquare weights r_i as given in ["Regression Line," beginning on page 512](#). In the second iteration, the local fit is obtained using weights $w_i r_i$. We repeat this process for the user specified number of iterations, where at each iteration the robustness weights r_i are recomputed using the residuals from the last iteration.

Note that LOESS/LOWESS is a special case of nearest neighbor fit, with a polynomial of degree 1, and local tricube weighting. The default EViews options are set to produce LOWESS fits.

Options

You should choose between computing the local regression at each data point in the sample, or using a subsample of data points.

- **Exact (full sample)** fits a local regression at every data point in the sample.

- Cleveland subsampling performs the local regression at only a subset of points. You should provide the size of the subsample M in the edit box.

The number of points at which the local regressions are computed is approximately equal to M . The actual number of points will depend on the distribution of the explanatory variable.

Since the exact method computes a regression at every data point in the sample, it may be quite time consuming when applied to large samples. For samples with over 100 observations, you may wish to consider subsampling.


The idea behind subsampling is that the local regression computed at two adjacent points should differ by only a small amount. Cleveland subsampling provides an adaptive algorithm for skipping nearby points in such a way that the subsample includes all of the representative values of the regressor.

It is worth emphasizing that at each point in the subsample, EViews uses the entire sample in determining the neighborhood of points. Thus, each regression in the Cleveland subsample corresponds to an equivalent regression in the exact computation. For large data sets, the computational savings are substantial, with very little loss of information.

Orthogonal Regression

The orthogonal regression fit displays the line that minimizes the orthogonal (perpendicular) distances from the y data to the fit line. This graph may be contrasted with the regression fit ([“Regression Line,” beginning on page 512](#)) which displays the line that minimizes the sum of squared vertical distances from the data to the corresponding fitted y values on the regression line.

Apart from adding other auxiliary graphs, the only option for orthogonal regression is the Legend labels combo box. If you wish to see the properties of your fitted line you should select Full. EViews will display the mean of X , the mean of Y and the estimated angle parameter.




Confidence Ellipse

The confidence ellipse for a pair of series displays the confidence region around the means (Johnson and Wichern 1992, p. 189).

By default, EViews displays the 95% confidence ellipse around the means, computed using the F-distribution with 2 and $N - 2$ degrees-of-freedom.

Our illustration shows the default confidence ellipse around the means of the geyser data. The effect of the positive correlation between the length of eruption and time until next eruption is apparent in the oval shape of the region.



Pressing the Options button opens a dialog that allows you to specify additional auxiliary graphs to be added, or to modify the ellipse options.

The edit field at the top of the dialog is where you will enter the probabilities for which you wish to compute confidence regions. If you wish to compute more than one, simply provide a space-delimited list of values or put them in a vector and enter the name of the vector.

The 'Scatterplot Customize' dialog box has two main sections: 'Added Elements' and 'Specification'. In the 'Added Elements' section, 'Confidence Ellipse' is listed. In the 'Specification' section, the 'Confidence levels' field contains '0.95'. Under 'Compute probabilities using:', the 'F-distribution' radio button is selected. In the 'Options' section, the 'Legend labels' dropdown is set to 'Default'. 'Add' and 'Remove' buttons are located below the 'Added Elements' list, and 'OK' and 'Cancel' buttons are at the bottom.

Next, you may change the method of computing the interval to use the χ^2 distribution instead of the F-distribution.

Lastly, you may use the Legend labels combo box to change the amount of information provided. If you select Full, EViews will always display both the probability associated with each ellipse as well as the distribution used to compute values.

References

- Brown, Lawrence D., T. Tony Cai, and Anirban DasGupta (2001). "Interval Estimation for a Binomial Proportion," *Statistical Science* 16(2), 101-117.
- Chambers, John M., William S. Cleveland, Beat Kleiner, and Paul A. Tukey (1983). *Graphical Methods for Data Analysis*, Murray Hill, NJ: Wadsworth & Brooks/Cole Publishing Company.
- Cleveland, William S. (1993). *Visualizing Data*, Summit, NJ: Hobart Press.
- Cleveland, William S. (1994). *The Elements of Graphing Data*, Summit, NJ: Hobart Press.
- Conover, W. J. (1980). *Practical Nonparametric Statistics*, 2nd edition, New York: John Wiley & Sons.
- Fan, J. and I. Gijbels (1996). *Local Polynomial Modelling and its Applications*, London: Chapman & Hall.
- Fan, J. and J. S. Marron (1994). "Fast Implementations of Nonparametric Curve Estimators," *Journal of Computational and Graphical Statistics* 3, 35-56.
- Freedman, David and Persi Diaconis (1981). "On the Histogram as a Density Estimator: L_2 Theory," *Zeitschrift für Wahrscheinlichkeitstheorie und verwandte Gebiete*, 57, 453-476.
- Hyndman, R. J. and Fan, Y. (1996). "Sample Quantiles in Statistical Packages," *American Statistician*, 50(4), 361-365.
- Härdle, Wolfgang (1991). *Smoothing Techniques with Implementation in S*, New York: Springer Verlag.
- Johnson, R. A., and D. W. Wichern (1992). *Applied Multivariate Statistical Analysis*, Third Edition, Upper Saddle River, New Jersey: Prentice-Hall, Inc.
- Jones, M. C., M. Samiuddin, A. H. Al-Harbey, and T. A. H. Maatouk (1998). "The Edge Frequency Polygon," *Biometrika*, 85(1), 235-239.
- Marron, J. S. and D. Nolan (1989). "Canonical Kernels for Density Estimation," *Statistics and Probability Letters* 7, 191-195.
- McGill, R., J.W. Tukey, and W. Larsen (1978). "Variations of Boxplots," *The American Statistician*, 32(1), 12-16.
- Scott, David W. (1979). "On Optimal and Data-Based Histograms," *Biometrika*, 66(3), 605-610.
- Scott, David W. (1985a). "Frequency Polygons: Theory and Application," *Journal of the American Statistical Association*, 80(390), 348-354.
- Scott, David W. (1985b). "Average Shifted Histograms: Effective Nonparametric Density Estimators in Several Dimensions," *The Annals of Statistics* 13(3), 1024-1040.
- Silverman, B. W. (1986). *Density Estimation for Statistics and Data Analysis*, London: Chapman & Hall.
- Simonoff, Jeffrey S. (1996). *Smoothing Methods in Statistics*, New York: Springer-Verlag.
- Simonoff, Jeffrey S. and Frederic Udina (1997). "Measuring the Stability of Histogram Appearance When the Anchor Position is Changed," *Computational Statistics & Data Analysis*, 23, 335-353.
- Stock, James H. and Mark W. Watson (2007). *Introduction to Econometrics*, Boston: Pearson Education, Inc.
- Wilson, Edwin B. (1972). "Probably Inference, the Law of Succession, and Statistical Inference," *Journal of the American Statistical Association* 22(158), 209-212.

Chapter 14. Categorical Graphs

Suppose that you have a sample of individuals in the United States, with information on employment, earnings, and various demographic variables. Among other things, you may wish to:

- Display a bar plot comparing the mean incomes of individuals living in each state.
- Produce a scatterplot of wages and hours worked, where the subset of males is drawn using one plotting symbol, and the subset of females uses a different symbol.
- Show wage–education profiles for both male and female workers.
- Draw histograms and boxplots of wages for union and non-union workers in different industries.

These graphs are all examples of categorical graphs. Categorical graphs are observational or analytical graphs formed using subsets of the data, where the subsets are defined using the values of one or more categorical conditioning variables (which we refer to as factors). In the examples above, state of residence, gender, years of education, and union status are factors that are used to form subsets of the data, which we then use to construct the graph.

Constructing these graphs by hand can be a difficult and time-consuming process. Fortunately, EViews provides powerful tools for constructing categorical graphs directly from your data. With these tools, you may quickly and easily define your categorization, specify the graph you wish to construct, and describe the basic graph layout; additional options provide detailed control over layout and labeling of the graph, if necessary.

The remainder of this chapter describes the construction of categorical graphs of data from a series or group object using the View/Graph... menu item.

Illustrative Examples

Starting from the premise that the most useful method of documenting categorical graphs is to work through examples, we begin by describing the construction of a few representative cases. We divide these examples into two broad categories: graphs which display categorical summaries of the data, and graphs which display the raw data with category-identifying information.

Since there is considerable detail in many of the example graphs, we have saved the graphs and then imported them directly into the manual, rather than using the usual screen capture approach.

Category Summaries

Perhaps the most common form of categorical graph involves the display of summary information computed for subsets of observations. For this type of categorical graph, we plot summaries based on the classification, not the original data.

We consider three examples of summary graphs: the first example involves simple plots of descriptive statistics computed for each group; the second example produces line plots from categorical descriptive statistics; the third example constructs analytical graphs for each factor level (category).

Descriptive Statistics


The simplest categorical graph compares values for descriptive statistics for observations in each category.

For our first set of examples, we employ the workfile “Gulfcoast.WF1” which contains demographic information for counties located in the Gulf Coast region of the United States. The workfile consists of 234 observations; 117 counties measured at two different periods (July 2005 and January 2006). The latter measurement is from a special assessment taken by the Census Bureau to measure the impact of hurricanes Rita and Katrina on population in the region.

The series POP contains data on the population in each county (in thousands). The series YEAR identifies the period associated with each observation, while STATE_NAME and COUNTY_NAME are categorical series that identify the observation at the state and county level, respectively.

We begin by constructing a summary graph comparing total population in the two periods. There are three parts to specifying this graph.

First, open the series POP and select View/Graph... to display the graph dialog, which should automatically open to the Basic type




group. Select Categorical graph from the General dropdown and Bar from the Specific type in the middle of the dialog to identify the main graph type.

Next, select Sums in the Graph data combo on the right-hand side of the dialog. This setting instructs EViews to plot the sum of POP computed for each subset of the data.


Lastly, we enter “YEAR” in the Within graph edit field. EViews will construct categories using the two unique values in YEAR (YEAR=2005 and YEAR=2006), and will display the summary statistics within a single graph frame.

Click on OK to accept the settings. EViews will display a bar graph showing the total population for each year, computed by taking sums of POP over all 117 counties in the region for the given year. We see that total population in the first year was roughly 12 million, and that the total population in the region falls by roughly 250,000 over the periods.



To gain additional insight into the composition of the population change, we may construct a categorical graph showing the sums of POP categorized using both YEAR and STATE_NAME. Double click on the graph window to display the dialog, edit the Within graph edit field to read “YEAR STATE_NAME”, and click on OK to display the updated graph.

EViews computes the total population for each distinct combination of YEAR and STATE_NAME, and displays bar graphs of the results in a single graph frame. Note that the set of bars for YEAR=2005 are displayed first, followed by the bars for YEAR=2006. Also note that the bars for a given STATE_NAME are assigned the same color (e., the bars for “Alabama” in the two years are both blue, the bars for “Louisiana” are both red, etc.) to facilitate comparison across years.




The ordering of the bars in the graph follows the order in which the categorical variables were

entered; the factors entered first vary more slowly than later factors (for an apparent excep-


tion to the rule, see [“Line Graphs” on page 528](#)). Since YEAR is the first factor in the list, it varies more slowly, i.e., the values for STATE_NAME are grouped within a given year.

While this particular ordering of bars has its merits, grouping by STATE_NAME makes more sense here since presumably, we want to compare population values for a given state across the two years. Rearranging the factor specification so that STATE_NAME precedes YEAR in the Within graph list, we now display the graph with the bars grouped by state.

It is considerably easier to visually assess the change in state populations. Not surprisingly, we see that the bulk of the population decrease occurs in Louisiana, and to a lesser extent Mississippi. Texas experiences population growth over the period, in part due to relocations from neighboring states.



Up to this point we have displayed our categorical graphs within a single graph frame. To display graphs for each category in a separate frame, you should enter the factor name in the Across graphs edit field. For example, to display a graph comparing state population across years with each state in its own frame, we enter YEAR in the Within graphs and STATE_NAME in the Across graphs edit fields. Click on OK to display the graph. (We have rearranged the graph so that all four frames appear on a single line by right-clicking on the graph and selecting Position and align graphs... ; see [“Working with Multiple Graphs” on page 583](#))




Note that by default, the multiple graph frames employ common vertical axes scales. This feature facilitates comparison of the series sums across states in different frames.


To turn off this feature, select View/Graph... or double-click on the graph to open the Graph Options dialog, then select **Categorical options** under the Graph Type group on the left-hand side of the dialog.

The Categorical options dialog permits control of settings for category

definitions and labels, as well as axis scaling. We will have much more to say about the category and label settings later (["Factor Display Settings," on page 543](#)). For now, we focus on the Axis scales section.

You will use the Selected factor list box to select the factor whose properties you wish to modify. In this case, we want each state to have its own scale, so we click on **STATE_NAME**, and select **Individual axes scales**. Click on **OK** to accept the changes and display the modified graph.





Each graph frame now has its own axis scale, making it easier to see the year-to-year changes, but more difficult to compare the changes across states. While the common scaling made it difficult to determine whether Alabama experienced an increase or decrease in population, the individually scaled graphs clearly show a small reduction in population in that state over the two years.

Line Graphs

One special case of categorical summary plots involves examining line graphs constructed from the summary statistics. While there is a general correspondence to the graphs described in [“Category Summaries” on page 524](#) there are some important differences in the specification of these graphs which require some discussion.


We illustrate these techniques using data from the Panel Study of Income Dynamics (Cornwell and Rupert 1988), as discussed by Baltagi (2001). The data (provided in “Wages.WF1”) consist of wage and demographic information for 595 individuals taken over 7 years from 1976–1982. For our purposes, we focus on three binary factors: FEM, a (0, 1) indicator for whether the individual is male (FEM=0) or female (FEM=1), UNION, a (0, 1) indicator for whether the wage is set by union contract, and EXPER, a measure of the number of years of full-time work experience.

Suppose, for example that we wish to examine the earnings-experience profiles for all of the individuals in our sample. Our approach will be to compute the average earnings at each experience level and then to display a line graph connecting the mean values. Note that a key feature of EXPER is that it is numeric (cardinal), so that it does make sense to draw a line between summary values computed at different experience levels.

First, open the log-wage series LWAGE and select View/Graph... to display the graph dialog. Then, select Categorical graph from the General dropdown in the middle of the dialog and Line & Symbol from the Specific list to identify the main graph type.

Next, select Means in the Graph data combo on the right-hand side of the dialog to compute the means of LWAGE for each of our categories.

Lastly enter "EXPER" in the Within graph edit field and click on OK to accept the settings. EViews will display the average earnings-experience profile computed across all of the observations in the workfile as depicted. The profile is generated by computing the mean of LWAGE for each level of the factor variable EXPER and plotting the category means against the category values using a line graph. Note that there is a dropoff in the profile at around 30 years of experience.



You may notice that the horizontal axis labels showing the category identifiers in this graph are not very attractive (e.g., "EXPER=20"). We will use the Categorical options page to modify these labels.


Double-click on the graph to open the Graph Options dialog, then select Categorical options under the Graph Type group on the left-hand side.

Since we want to change the labeling of the categories defined by levels of experience, we select **EXPER** in the Selected factor listbox. The settings of interest are in the section labeled **Category labels**.


The **Contents** combo box provides three settings for the category labels. The default setting, **Automatic**, lets EViews choose the labels. In this example, **Automatic** is equivalent to the second setting, **Factor name & value**, where we form labels using both the name of the factor (“**EXPER**”) and the value of the factor (“**20**”). In this case, we want to display only the factor value so you should select **Factor value only**. Click on **OK** to accept the updated graph settings.

The factor labels in the graph are shorter and slightly easier to read now that they omit the factor name and use only the factor value.

If desired, you may make two additional customizations of the display by double-clicking on the horizontal axis to bring up the **Obs/Date axis dialog** page, and setting the **Observations** to label to **Custom**, starting at 0, with steps of 5. This setting automatically rotates the labels to horizontal. Then go to the **Grid Lines** group, also under the **Axes & Scaling** section, to turn on vertical gridlines. Select **Automatic** grid placement from the **Obs & Date axis grid lines** group, and click **OK**.




Next, suppose that we wish to compute separate profiles for males and females and to place them in different graph frames. Simply double-click on the graph to display the **Graph Options** dialog, and enter “**FEM**” in the **Across graphs** edit field. Click on **OK**, and EViews will display the two wage-experience profiles in separate graph frames. (Note that we have again rearranged the graphs so that they are next to each other by right-clicking on the graph and selecting **Position** and **align graphs...**. We will rearrange many of the following graph examples in this manner.)



The shapes of the two graphs suggests that the bulk of the dropoff in the overall profile comes from the steep decline in the profile for women at 30 years of experience. (Note that the factor label and interval settings were retained when we added the FEM factor.)

Suppose instead that we wish to display the separate profiles in a single frame. Double click on the graph to bring up the dialog and move "FEM" from the Across graphs to the Within graphs edit field so that the latter reads "EXPER FEM". The resulting graph shows the wage-experience profile for both males and females in the same graph frame.

The order in which we enter the factors in this latter example requires some discussion. The rule-of-thumb is that factors should be entered from slowest varying to fastest varying, so that the values for the second factor are grouped within the first factor, and values for the third factor are grouped within the second factor, and so forth.



In this case, however, the first series, EXPER, appears to vary more rapidly than the second series, FEM (the variation in EXPER for a given level of FEM using a line), despite preceding it in the list of within series. The apparent reversal of ordering arises from the combined effect of two simple rules: (1) the slowest varying factor is placed along the observation


axis, and (2) line graphs connect data along the observation axis. Since we want to draw lines connecting levels of EXPER along the observation axis, it is entered first in the list.

We describe various implications of the rules for specifying factors in greater depth in [“Specifying Factors,” on page 540](#). For now, it is probably sufficient to note that the specified ordering is probably the most natural way of describing the problem since we would probably refer to this graph as displaying the “wage-experience profile, conditional on gender.”

Analytical Graphs

You may display categorical graphs where, in place of computing simple descriptive statistics such as the mean or sum, we construct an analytic graph (Distribution, Quantile-Quantile, Boxplots) for each subset of observations.

We begin our example with a simple categorical histogram of the log-wage series from the PSID data described above ([“Line Graphs” on page 528](#)). Consider first a simple example showing a histogram of LWAGE with FEM as an across factor. The procedure is straightforward: select Categorical graph and Distribution for the Graph type from the middle of the dialog, select Histogram for the Distribution type, and place FEM in the across list. Click on OK and EViews will display the two histograms in individual graph frames.



If desired, you may change the multiple graph axis scaling to allow for individual scales as described in [“Descriptive Statistics,” beginning on page 524](#).

Next, we consider slightly more complicated examples involving multiple series and multiple factors. We begin by displaying kernel density plots of two series, LWAGE and EXPER, using FEM as a within factor and UNION as an across factor. First, create a group containing LWAGE and EXPER, then select View/Graph... from the group menu to display the graph dialog. From this point, constructing our example graph is a four step process:


- First, select Categorical graph and Distribution as the Graph type.
- Select Kernel Density from the Distribution drop-down.
- Enter “FEM” in the Within graph edit field, and “UNION” in the Across graph field.
- Select First across factor (the default) in the Treat multiple series in the Group object combo.

The last setting, which is displayed only when graphing multiple series, may appear to be a bit obscure, but the basic idea is really quite simple.

Each series in the group may be viewed as a subset of the data in the workfile. Accordingly, we may define an implicit “series factor,” which we denote @SERIES, that divides the workfile data into subsets corresponding to series. In our example, data in the first series of our group are said to be in the category defined by “@SERIES=LWAGE” while data in the second series are in category “@SERIES=EXPER”.

Since @SERIES is a factor, we may choose to have it vary within or across graphs. If it varies within graphs, data for both LWAGE and EXPER will be displayed in a single frame; if it varies across graphs, data for the two series will be displayed in different graph frames. (The choice between plotting the multiple series data in a single graph or in multiple graphs may sound familiar since it corresponds to the Multiple series option for basic graphs; see [“Multiple Series” on page 450.](#))

The Treat multiple series combo box allows us to insert the implicit @SERIES factor at the beginning or the end of the list of within or across factors. By default, EViews treats @SERIES as the first across factor (most slowly varying across factor), but you may move it to the end of the across list or the beginning or end of the within list.




The current example specifies @SERIES as the fit, and UNION as the second across factor. Since @SERIES varies more slowly, values of UNION will be grouped within @SERIES. We see the effect of this grouping since the first two frames are for data where “@SERIES=LWAGE” paired with “UNION=0” and “UNION=1”, respectively, followed by “@SERIES=EXPER” for the two union values.

Similarly, we may display a categorical boxplot with FEM, UNION and @SERIES as within graph factors.

First, double click on the graph, being careful to select the entire graph, to display the dialog and change the Specific graph type to Boxplot. Next, move the UNION factor to the end of the Within graph edit field, and change the multiple series combo to Last within factor.

The resulting graph displays eight boxplots in a single graph frame. The implicit factor @SERIES has been placed at the end of the within list so that it varies fastest. We see that

LWAGE and EXPER are displayed for each level of FEM and UNION, that the levels of UNION vary within each level of the first factor FEM.



Identifying Categories

The second major type of categorical graph displays the raw data along with category identifying information.

We consider four representative examples of these graphs: a scatterplot, a spike plot, a line plot, and a dot plot. The first two examples, which involve multiple observations in each category, use the Raw Data setting for the Graph data combo; the last example, where there is a single observation in each category, uses the special Unique values – error if not identical setting.

Raw Data

We consider here two categorical graphs that employ the Raw Data setting in the Graph data combo. As you might expect given the name of the setting, these graphs all display the underlying (raw) data in the series.

One commonly employed raw data categorical graph is a scatterplot where observations in each category are displayed with a different symbol. Our first two examples use data in the



workfile “Mpg.WF1” on EPA reported miles-per-gallon and engine size (displacement) for a subset of 2006 model year automobiles.

We construct a categorical scatterplot of city miles-per-gallon (CITY_MPG) against engine size (DISPLACEMENT), using the number of cylinders (NUMB_CYL) in the engine as a within factor. First, create a group containing DISPLACEMENT and CITY_MPG. Simply specify Categorical graph and Scatter as the Graph type, leave the Graph data setting at Raw data, and enter “NUMB_CYL” in the Within graph edit field. To draw a set of linear regression lines through the points in each class, set the Fit lines combo to Regression line.

The resulting graph uses color and symbol choice to identify categories. Since we have selected Raw data, every valid observation in the sample is displayed using category specific colors and symbols. Not surprisingly, we see that engines with greater numbers of cylinders have a larger displacement. More interestingly, there appears to be a weaker relationship between DISPLACEMENT

and CITY_MPG for cars as the number of cylinders increases, though the two high MPG outliers may be unduly influential in that comparison.

We may compare this categorical graph to one in which we treat NUMB_CYL as an across factor:




Here, each set of raw data points is displayed in its own graph frame, using common axis scaling. The points all use the same color and symbol since the graph frame titles are sufficient to identify the group displayed in the frame.

Our second example uses categorical raw data graphs to explore differences in the regression fit of CITY_MPG to DISPLACEMENT. We first estimate the linear regression of CITY_MPG on DISPLACEMENT then save the residuals from this equation to the series MPG_RESID. Note that the equation results in EQ01 assume a common slope coefficient on DISPLACEMENT; the scatterplots above suggest that this assumption is not valid.


Equation: EQ01 Workfile: MPG::Untitled1				
View	Proc	Object	Print	Name
Freeze	Estimate	Forecast	Stats	Resids
Dependent Variable: CITY_MPG				
Method: Least Squares				
Date: 08/07/09 Time: 13:27				
Sample: 1 468				
Included observations: 468				
Variable	Coefficient	Std. Error	t-Statistic	Prob.
C	29.55137	0.512806	57.62685	0.0000
DISPLACEMENT	-3.075824	0.138943	-22.13728	0.0000
R-squared	0.512582	Mean dependent var	18.75641	
Adjusted R-squared	0.511536	S.D. dependent var	4.911689	
S.E. of regression	3.432788	Akaike info criterion	5.308887	
Sum squared resid	5491.359	Schwarz criterion	5.326615	
Log likelihood	-1240.280	Hannan-Quinn criter.	5.315863	
F-statistic	490.0591	Durbin-Watson stat	1.594655	
Prob(F-statistic)	0.000000			

As further evidence that the equation assumptions are not valid, we display a categorical bar plot of MPG_RESID using NUMB_CYL as the within factor. This graph shows each value of MPG_RESID, with observations in different classes drawn using different colored bars.

While it may be a bit difficult to see in the printed black-and-white form of the graph, the size of the equation residuals appears to be negatively related to the number of cylinders; in particular, almost all of the very large positive residuals are for 4-cylinder vehicles. The correlation between residuals and number of cylinders suggests that, at the very least, number of cylinders is an omitted variable in the equation. Note that EViews shows only observation indices since there is insufficient space to show observation labels.



The visual comparison of residuals for cars with different numbers of cylinders may be facilitated by treating NUMB_CYL as an across factor:



The negative relationship between number of cylinders and the size of residuals is readily apparent in this graph. Note that since there are fewer observations plotted in each of the graph frames, EViews switches to showing some of the observation labels from the workfile.

Unique Values

Our final example uses the Unique values – error if not identical data setting.

We again employ the workfile “Gulfcoast.WF1” containing population information for counties in the Gulf Coast region of the United States. For this example, we restrict ourselves to displaying values for counties in Louisiana by setting the sample to only include observations where the STATE_NAME = “Louisiana”.

We display the percentage change in population for counties in Louisiana in 2005 and 2006 using a categorical dot plot. The categorical plot uses the factors COUNTY_NAME and YEAR, with YEAR entered last in the within list since we want to compare population values in the two years for a each county.

A slightly customized version of the graph is depicted here. The filled circles represent the proportionate changes in population in 2006; the open circles represent the 2005 changes. We see that there is a large disparity in the effect of the hurricanes across counties, with three counties: St. Bernard, Orleans, Plaquemines, and to a lesser extent Cameron and Jefferson bearing the brunt of the impact.


Constructing this particular graph is straightforward, requiring only a few steps.

First, we display the graph dialog for PDIFF and set the Graph Type to Categorical graph and Dot Plot, and choose Rotated – obs axis on left from the Orientation dropdown.

Since we want to plot a graph grouping different years for each county together, we enter "COUNTY_NAME YEAR" in the Within graphs edit field.

Next, despite the fact that we wish to plot every observation in the sample, we set the Graph data setting to Unique values – error if not identical. Note that this is a change from previous examples where we used the Raw data setting.

This latter choice requires a bit of discussion. Since we are displaying a plot of every observation (every county and period) in the sample, you might at first think of selecting Raw



data for this setting. Recall, however, that using Raw data will produce a plot with each observation identified in some way as belonging to a category. In this case, since every observation is in a different category (county and period), selecting Raw data will produce a dot plot that uses a separate row and symbol for every observation. This is obviously not the desired effect.

Selecting Unique values – error if not identical tells EViews that (using the default settings in the Categorical options dialog) despite the fact that we are plotting every observation, we want to plot both year values for a single COUNTY_NAME on a single row, and that we want to use unique graph elements across years, but not across counties. Thus, different YEAR observations are given different symbols within a county, but the set of symbols used to identify the two years is the same across different counties.

If all of this seems rather abstract or mysterious, we will examine this issue in greater depth in [“Specifying Factors,” on page 540](#). For now, you may follow a simple rule-of-thumb: if your factors define groups containing only one observation each, you generally should select Unique values – error if not identical to obtain the desired graph.

Lastly, we use the Size & Indents dialog under the Frame section to change the height and aspect ratio to 6 and 0.50, respectively. Then use the Grid Lines dialog under Axes & Scaling to turn on horizontal gridlines by selecting Custom from Obs & Date axis grid lines, with a Step of 1. In addition, we employ the Data axis labels dialog, also under Axes & Scaling, to display the bottom axis scale in Units of Percent, with a “%” suffix, and to draw a zero line.

Specifying Factors

Categorical graphs use factor variables to define subsets of data. In the simplest case, a categorical graph is based on a single factor variable containing a small number of discrete values; subsets of the data are defined for observations with each of these values. In this basic setting, specifying the factors for the graph involves little more than providing the name of the factor variable and indicating whether it should vary within or across graph frames.

More complicated situations can be constructed involving multiple factors or non-categorical factor variables. These cases raise a number of issues associated with how to define the categories for the factor and how to organize the subsets of the data for display. How these issues are resolved has a profound impact on the appearance of the categorical graph.

Accordingly, the factor specification for a categorical graph may involve much more than simply providing a list of factors. While the EViews defaults will generally produce the desired graph, you may need to customize the factor specification in more complicated settings. The remainder of this section outlines the default rules that EViews uses for specifying and organizing factors, and describes rules for customizing the factor specification.

Defining a Factor Categorization

In most cases, you will specify a factor variable that contains a small number of discrete values. These discrete values will be used to define a set of categories associated with the factor.

Suppose, for example, that we have the factor variable, FEM, indicating whether the individual is a 0 (Male) or 1 (Female). The two distinct values 0 and 1 will be used to define the categories for the factor and each individual in a sample will be categorized on the basis of whether they are 0 or 1.


You may also specify a factor variable that is non-categorical, or one with a large number of distinct values. For example, suppose you propose the use of the series INCOME, which measures individual incomes, as a factor variable. The use of this variable creates difficulties since income does not have a small number of categories; indeed, every observation will be in its own category.

By default, EViews tries to avoid this situation by analyzing each factor to determine whether it appears to be categorical or continuous. If EViews determines that the variable is continuous, or if there is a large number of categories associated with the factor, EViews will define a new categorization by automatically binning the factor into five categories defined by the quintiles of the series.

You may override the EViews default categorization settings using the Categorical options dialog under the Graph Type section (note that this dialog is only available when Categorical graph has been selected for the Graph type). Simply select the factor whose options you wish to change in the left-side list box, then select the desired entry in the Binning combo box. The default setting, Automatic, uses Quantile bins if there are a large number of distinct values for the factor, and No binning otherwise. You may choose either of the latter two methods directly, or tell EViews to create Value bins by grouping data on the basis of equal width intervals. For both Quantile bins and Value bins, EViews will prompt you for the number of bins to use. The default number of bins is 5.

For example, we again consider the workflow “Mpg.WF1” which reports EPA reported miles-per-gallon and engine size (displacement) for 468 automobiles. We first display the categorical bar graph of the mean of CITY_MPG using the categorical variable DISPLACEMENT as a within factor.


There are 35 distinct values in the DISPLACEMENT series. EViews automatic binning settings allow DISPLACEMENT to be used as an unbinning factor.



By default, EViews attempts to label all 35 categories in the resulting graph. The graph may be a bit busy for some tastes, even if we only show the factor levels. One alternative is to display a binned version of this graph where we define categories based on intervals of the DISPLACEMENT values.

Click on Categorical options under Graph Type in the main dialog, select DISPLACEMENT in the left-hand side list box, then change the Binning combo to Value bins. For these settings, EViews will create a factor using (at most) 5 equal-width bins based on the values of DISPLACEMENT. Click on OK to accept the options.

The resulting graph shows that EViews categorizes observations into one of four DISPLACEMENT ranges: [0, 2), [2, 4), [4, 6), [6, 8). The mean MPG for cars with engine size under 2 liters is roughly 29, while the mean value for engines from 6 to 8 liters is under 14. While the negative relationship between engine size and miles-per-gallon can be seen in the earlier graph, it is more apparent in the binned version.



It is worth noting that binning on the basis of custom thresholds is not directly supported in graphs. If you wish to define custom bins, you should use the series classification Proc to define a new categorical variable (see [“Stats by Classification” on page 318](#) for details), and then use the new variable as your factor.

Factor Display Settings

Having defined factor categories for one or more factors, there are several basic settings that will control the appearance of your graph: whether to display factor levels within or across graph frames, the ordering of factor levels, the ordering of multiple factors, and for summary graphs, the assignment of graph elements to factor levels and the method of labeling factor categories.

Within vs. Across

You should enter your factor names in the Within graph and Across graphs edit lists on the main graph options page. Each level of a factor entered in the Across graphs factor list will be displayed in a separate graph frame, while levels of factors in Within graph will be displayed in single frames.

In addition, if you are plotting multiple series in a group, you will be prompted for whether to treat the different series as an across or a within factor, and to specify the factor ordering (whether the factor should be placed at the beginning or end of the list).

A number of the case studies in “[Illustrative Examples](#),” beginning on page 523 demonstrate the effects of these choices.


Factor Levels Ordering

By default, EViews orders the categories formed from each factor from lowest to highest value. Categories formed from numeric values will be sorted numerically while categories formed from alphanumeric factors will be sorted alphabetically. The order of categories is then used in constructing the graph.

To change the ordering of levels for a given factor, click on **Categorical options** to display the options dialog, select a factor in the left-hand side list box, then change the Display order combo from the default Ascending to Descending.

We may, for example, modify our categorical graph for CITY_MPG using the binned values of DISPLACEMENT. Double click on the graph to open the main graph dialog, click on **Categorical options** to show the options dialog, and change the display order.

Note that changing the ordering of the levels changes the order in which they are displayed in the graph. The categories for DISPLACEMENT now start at the largest level for the factor and continue on through the smallest.



Multiple Factor Ordering

You may specify more than one factor variable, thereby forming a set of categories defined by each combination of the distinct factor values. In this case, the order in which the factors vary has an important effect on the final display.

Suppose, in addition to the FEM variable, you have a second factor variable UNION representing whether the individual is in “Union” or “Non-union” employment. Then the four categories for these two factors are: { (“Male,” “Non-union”), (“Male,” “Union”), (“Female,” “Non-union”), (“Female,” “Union”) }.

Note that in this list, we have arranged these factors so that:

Order	FEM	UNION
1	"Male"	"Non-union"
2	"Male"	"Union"
3	"Female"	"Non-union"
4	"Female"	"Union"

with the "Male" categories coming first, followed by the "Female" categories, and with the UNION status categories varying within the FEM categories. We say that the FEM factor varies more slowly in this ordering than the UNION category since the latter varies within each level of FEM.

Alternately, we can reverse the ordering so that the FEM factor varies more rapidly:

Order	FEM	UNION
1	"Male"	"Non-union"
2	"Female"	"Non-union"
3	"Male"	"Union"
4	"Female"	"Union"

so that the GENDER values vary for each level of UNION.

We may extend this notion of ordering to more than two categories. Suppose we have a third factor, YEAR, representing the year the individual is observed, with three distinct values 1980, 1981, and 1982. Then if FEM varies most slowly, UNION next most slowly, and YEAR most rapidly, we have:

Order	FEM	UNION	YEAR
1	"Male"	"Non-union"	1980
2	"Male"	"Non-union"	1981
3	"Male"	"Non-union"	1982
4	"Male"	"Union"	1980
5	"Male"	"Union"	1981
6	"Male"	"Union"	1982
7	"Female"	"Non-union"	1980
8	"Female"	"Non-union"	1981
9	"Female"	"Non-union"	1982
10	"Female"	"Union"	1980

11	"Female"	"Union"	1981
12	"Female"	"Union"	1982

The first three cells correspond to {"Male," "Non-union"} workers in each of the three years, while the first six cells correspond to the "Male" workers for both union and non-union workers in each of the three years.

When specifying factors in the main Graph Options page, you will enter the factors in the Within graph or Across graphs list. Within each list, factor s should be ordered from slowest to fastest varying. Factors listed in the Across graphs list are always more slowly varying than those in the Within graphs list since each across graph category is displayed in a separate graph frame.

The first example in this section uses the ordering:

fem union

so that FEM varies more slowly than UNION. The second example reverses the ordering of the two factors so that UNION varies more slowly:

union fem

The last example orders the factors so that FEM varies most slowly, and YEAR most rapidly:

fem union year

Various examples of the effect of reversing the ordering of factors are provided in ["Illustrative Examples," beginning on page 523](#)

Assigning Graph Elements to Categories

One of the most important decisions you will make a within categorical summary graph is choosing the elements for displaying data for different categories. While EViews provides you with reasonable defaults, there are useful features for customizing these choices that you may find useful.


(The choices described in this section are not relevant for non-summary categorical graphs specified by selecting Raw data in the Graph data combo on the main graph dialog).

To understand the basic issues involved in these choosing graph elements, we must first divide our within factors into two groups: primary and secondary factors Primary within factors are a subset of most slowly moving factors whose levels share common graph elements (e.g., colors, line patterns, shades). The remaining secondary factors display different levels with different graphic elements.

You may think of the primary factors as defining the set of categories that yield summary "observations" so that they are arrayed along the axis, with the secondary factors defining subsets within these categories (much in the same way that one may draw minor ticks

between the major ticks on a graph axis). We then apply the general rule that primary factors share common graph elements across levels, while secondary factors use different graph elements for different categories. The interpretation of primary factors as being categories displayed the axis with secondary factors specified as subsets of the primary factors is an important one that we will explore further.

As is often the case, some examples will best illustrate the basic ideas. We return to the earlier example of constructing a binned categorical graph for mean of CITY_MPG divided into ranges of DISPLACEMENT. We begin by displaying a bar graph showing the categorical means:



On the left is the graph using default settings where DISPLACEMENT is treated as a primary factor, while on the right is a graph with DISPLACEMENT treated as a secondary factor. Note that on the left, the levels of the primary factor DISPLACEMENT use the same graph element (bar color), while on the right, the levels of the secondary factor DISPLACEMENT use different bar colors.

Before examining examples of the more complex settings, let us first see how we modify the default settings of the graph on the left to obtain the graph on the right. Click on Categorical options to display the options dialog. At the bottom of the dialog is the descriptively titled Within graph category identification which provides control over the assignment to major and minor factor categories, and as we will see later, the labeling of these categories.


As the name suggests, the verbosely labeled combo box Give common graphic elements (lines, bars, colors, etc.) to categories for factors

up to and including , selects the set of factors are to be given common graphic elements. Since the primary factors must be the most slowly varying factors, assigning factors to the primary and secondary groups is the same as choosing a cutoff such that factors up to and including the cutoff are primary factors, and factors following the cutoff are secondary factors. The combo box effectively draw a line separating the two groups of factors.

In the single factor case setting, the combo default is set so that factor is primary so that all graph elements are common; in this example, the combo is set to `DISPLACEMENT`. The graph above on the left, with all bars displayed using the same color, shows the default setting. Changing the combo to read `None` indicates that there are no primary factor, only the single secondary factor, as in the graph with different colored bars on the right.

While informative, our bar graph example hides one very important difference between the two graphs. Recall that one interpretation of the difference between primary and secondary factors is that the levels of the primary factors are placed along the axis, with secondary factors defining subsets within these major categories. In our example, there are four distinct categories along the axis in the left bar graph and only one category on the axis in the right graph. The different numbers of categories along the axis is hidden in bar graphs; since the latter always offset bars drawn for different categories it is difficult to tell the difference between the primary and secondary factor categories.

We may see the importance of this difference when switching from a bar graph to a dot plot:




In the graph on the left, `DISPLACEMENT` is a primary factor so that each level of the factor is displayed as a separate “observation” along the axis using a common symbol and color for the dot. In the graph on the right, `DISPLACEMENT` is a secondary factor that is displayed

using different symbols and colors for each level of the primary factor. Since there is no primary factor in this case there is only a single observation on the axis, and all four symbols are lined up on that single observation.

For a slightly more complicated example, we again use the “Wages.WF1” workfile containing information on log wages for a sample of 4165 individuals. We will use the three series FEM, UNION, and YEAR as within factors, entered in that order, and will display a dot plot of the means for this categorization using the default settings.


For more than one within factor, the default is to designate only the last listed factor as a secondary factor. At the default setting, the combo box in our example is set to UNION so that FEM and UNION are primary factors for the graph, while YEAR is as secondary factor.



The resulting graph, shown on the left, has several notable features. First, the four distinct categories formed from the primary factors FEM and UNION are each assigned to the graph axis. Within each level of the primary factors, we see distinct symbols representing the various levels of the secondary YEAR factor. Lastly, the set of symbols is common across primary factor levels (e.g., all four of the “YEAR=1976” symbols are blue circles).

Changing the combo box to FEM produces the graph on the right. Since FEM is the sole primary factor, EVIEWS assigns the two levels for FEM to the graph axis, with the remaining factors treated as secondary factors.

For our next example, we consider the group object GROUP01 containing the series EXPER and LWAGE. We display scatterplots of the categorical means for these two series given the three within factors FEM, UNION, and YEAR, along with regression fit lines.



The scatterplot on the left uses the default setting so that FEM and UNION are primary categories, and YEAR is a secondary category. Mean values are plotted for each category, with different symbols used for different levels of YEAR. Following the principal that primary factors define observations, regression fit lines are computed for each level of the secondary category across levels of the primary factor. Thus, the fit line for YEAR=1977 shows the regression fit obtained using the four mean values of LWAGE and EXPER in the categories defined by levels of FEM and UNION.


In contrast, setting the combo to YEAR so that all factors are primary yields the plot on the right. All of the points use the common symbols, and the fit line is fitted across all of the primary factor levels.

The basic principle here is that if you wish to draw fit lines for summary statistics across categories, those categories should be specified as primary factors.

Parenthetically, we are now in a position to explain the apparently anomalous ordering of factors in our wage-experience profiles above (["Line Graphs," on page 528](#)). Recall that the displaying separate average wage-experience profiles for men and women in a single graph frame required that we use the within factor list "EXPER FEM" despite the fact that EXPER appears to vary more rapidly than FEM.

An examination of the default settings for the graph reveals that EXPER is a primary factor, while FEM is a secondary factor. Since the levels of EXPER are observation identifiers that are displayed along the axis, line graphs connect the EXPER levels, making it appear that EXPER varies rapidly, even though the points are with FEM varying for each level of EXPER.

Here, we see the dot plot corresponding to the earlier line graph. FEM clearly varies more rapidly as both the FEM=0 and FEM=1 points are plotted for each level of EXPER. The line graph version of this graph simply connects points across observations (experience levels) for each level of FEM and turns off the symbols, making it appear as though EXPER is varying more rapidly.



Our last example ties together all of the various concepts. Suppose that we were to plot the average log wage against year using FEM and UNION as our factors. There are two distinct approaches to constructing this graph. In the first approach, we specify a single observation scale using YEAR and draw four different wage-year profiles, one for each category formed by FEM and UNION. In the second approach we adopt a “panel” style graph in which divide the factor scale into two panels, with the first panel representing a YEAR scale for males, and the second panel representing a YEAR scale for females. We show the two cases below:




The graph on the left specifies the within factor list as “Y EAR FEM UNION”, with YEAR the sole primary factor, and FEM and UNION the secondary factors. The axis scale uses YEAR to identify observations, and for each secondary factor category draws a line connecting the observations for that category. In contrast, the graph on the right uses the within factor list “FEM YEAR UNION”, with FEM and YEAR as the primary factors. The axis scale uses FEM and YEAR for observations, with YEAR varying for each level of FEM, and for each level of the secondary factor connects the lines across the observations for each factor. Note that EViews knows not to connect lines across levels of the FEM factor.

(Note: we have customized the graph on the right slightly by freezing the graph, and turning on Segment with lines in the Sample breaks section of the Basic type page.

The rule-of-thumb to remember here is that the factor that you wish to connect using a line graph or XY line graph, should be specified as the last primary factor. Specifications with one primary factor will have a set of lines for each secondary factor category; specifications with more than one primary factor will be displayed in paneled form.

Factor Labeling

By default, EViews will label factor levels in summary graphs using some combination of axis labels and legend entries. For line graphs and XY graphs, the EViews choices are the only possible way to identify the levels. For other types of summaries, we may choose to display the bulk of the label information along the axis, or we may choose to display most of the information in legend entries.



Both of the graphs displayed here are summary bar graphs of LWAGE categorized by YEAR, FEM and UNION. In the graph on the left, we display all of the category information using two-level labels along the axis, while in the graph on the right, we display the information using a single level axis label combined with legend entries.

By default, EViews will, if possible, place the category information along the axis. You may choose to override this default using the Categorical options dialog. At the bottom of the options dialog, in the Within graph category identification section, there is a combo box which allows you to choose between the default, Maximize use of axis labels, or the alternative, Maximize use of legends, which encourages the use of legend information. The graph on the left above was obtained using the default setting, while the graph on the right was obtained by encouraging the use of legend information.

We emphasize again that this combo box does not affect the category labeling for Line & Symbol, Scatter, and XY Line plots.

Part III. Customizing Output

EViews objects (series, groups, equations, and so on) display their view and (sometimes) procedure output in the form of graphs, tables, and text. You may, for example, display the descriptive statistics of a set of series, or the regression output from an equation as a table, or the impulse responses from a VAR as a graph. We will term these displays object views

While object views may be customized in a variety of ways, they are generally transitory; when you close the object and subsequently redisplay or switch between views, many of the customized settings are lost. And in cases where the views are dynamic, the view is regenerated automatically when the underlying object or the active sample changes, resulting in the loss of any custom settings.

Fortunately, you may preserve the current object view, along with any customization, so that it does not change when the object changes. We refer to this action as freezing the view. Freezing a view will create a new output object containing a “snapshot” of the current contents of the view window. The type of object created when you freeze a view depends on the original view—freezing a graphical view creates a graph object, freezing a tabular view creates a table object, and freezing a text view creates a text object.

Graph, table, and text objects form the basis of presentation output, and EViews provides sophisticated tools for customizing the appearance of these objects. EViews also offers a spool object which allows you to manage collections of output objects. Spool objects may be used for creating a log of the output created during a project or an EViews session, or for gathering together graph, table, and text output for a presentation.

The following chapters describe the use of graph objects, table objects, and spool objects in greater detail, showing how you may use these objects to form presentation output:

- [Chapter 15. “Graph Objects,” beginning on page 557](#) describes the creation and customization of graph objects.
- [Chapter 16. “Table and Text Objects,” beginning on page 589](#) describes the creation and customization of tables and text objects.
- [Chapter 17. “Spool Objects,” beginning on page 601](#) describes the use of spool objects to manage collections of output objects.

Chapter 15. Graph Objects

In [Chapter 13. “Graphing Data,” on page 435](#) and [Chapter 14. “Categorical Graphs,” beginning on page 523](#) we described in detail EViews tools for producing graphical displays of your data. The topics considered range from simple observation line graphs, to analytical graphs such as histograms, to even more complex categorical graphs.

These graphical displays are what we term graph views since they are simply a different way of viewing the data in the underlying data object. While graph views may be customized in a variety of ways, they are generally transitory; when you close the series or group object and subsequently redisplay or switch views, many customized settings are lost. And in cases where the views are dynamic, the view is regenerated automatically when the underlying object or the active sample changes, resulting in the loss of any custom settings.

Fortunately, you may create a graph object by freezing a graph view. Freezing a view will create a new graph object containing a “snapshot” of the current graph view, allowing you to perform permanent customization of the graphical output. Graphs may also be placed into a spool object along with table and text objects for use in custom presentations (see [Chapter 17. “Spool Objects,” on page 601](#)).


This remainder of this chapter describes the options available for customizing the appearance of a graph object. This chapter does not offer a comprehensive examination of all of the possible customizations you may perform; we encourage you to experiment with various settings to see the effect on your output.

Creating Graph Objects

Graph objects are usually created by freezing an object view. Simply press the Freeze button in an object window containing a graph view.

It is important to keep in mind the distinction between a graphical view of an object such as a series or a group, and a graph object created by freezing that view.

For example, suppose you wish to create a graph object containing a line graph of the series LPASSENGER from the workfile “Airline.WF1”. To display the line graph view of the series, select View/Graph... from the LPASSENGER series menu and select Line & Symbol from the list-box in the middle of the dialog. Notice the “Series: LPASSENGER” designation in the window titlebar that shows this is a view of the series object.



You may customize this graph view in any of the ways described in [“Customizing a Graph” on page 26](#) but many of these changes will be lost when the view is redrawn, e.g. when the object window is closed and reopened, when the workfile sample is modified, or when the data underlying the object are changed. If you would like to keep a customized graphical view, say for presentation purposes, you should create a graph object from the view.

Freezing a Graph View

To create a graph object from the view, click on the Freeze button. EViews opens the Auto Update Options dialog, prompting you to choose whether to make your new graph updating, and if so, to specify a few update options. Let’s discuss the difference between an updating and a non-updating frozen graph.

Selecting Off - Graph is frozen and does not update will create an untitled graph object containing a snapshot of the view. (This option mimics the behavior of the Freeze button in EViews prior to version 7.) The data has been copied from the

series and is stored in its current state in the graph object. Changes to the series data will not affect the graph.


Alternately, choosing Manual - Update when requested or type is changed or Automatic - Update whenever update condition is met will create an updating graph. This means that the underlying graph data is still tied to the original series, so when the series values change, the graph has the opportunity to update as well.

The choice between Manual and Automatic is based on when you would like the graph to respond to changes in the data. Selecting Manual allows you to control when the updates occur. The graph will remain the same until you push the Update button on the graph toolbar, or until the graph type is changed. Choose Automatic if you'd like EViews to keep the graph current with changes to the underlying data.

Whether you are working with a manually or automatically updating graph, you can specify how you would like changes in the data or workfile sample to affect the graph when it is updated. Selecting either Manual or Automatic will enable the Update condition section of the dialog. If you'd like the graph to plot over a constant sample that may or may not match the current sample of the workfile, select the first option, Update when underlying data changes using the sample. Enter the desired sample in the edit field, or simply accept the current default sample. The graph will now only update data that fits within the specified sample period. In addition, changes to data outside of this sample period will not trigger an update for automatically updating graphs.

Alternately, select Update when data or the workfile sample changes to accept all changes to the data and workfile sample when the graph is updated. Note this means that a change in the workfile sample will be reflected in the graph, whereas the Update when underlying data changes using the sample option keeps the graph sample constant unless you change it in the main Graph Options dialog.

For example, let's look at freezing the line graph view of the series LPASSENGER. The workfile contains monthly data from 1949 through 1960. First, we'll concentrate on a portion of the data by changing the workfile sample period to 1949 through 1952. Then freeze this view, selecting Automatic updating and Update when underlying data changes using the sample: in the Update condition group. Leave the default sample in the




edit field to restrict the graph to changes within the first few years of the workfile data. Click OK to create an untitled graph object.

Now, let's see how changes to the series data affect the frozen graph. If we change the value at 1949M01, we'll see the graph plotting the new value. However, modifying the value at 1956M01 has no effect on the graph, since this date is outside the graph's sample range.

The real difference between the two options in the Update condition group can be seen when we modify the workfile sample. Since we have specified an update sample for the current graph, changes to the workfile sample will not have an effect on the graph.

Alternately, if we had selected **Update** when data or the workfile sample changes in the **Auto Update Options** dialog when freezing the graph, we would see different behavior. Create a graph with the second **Update** condition, and then expand the workfile sample back to 1949 through 1960. Once updated, the graph will expand its sample to match that of the workfile.




Don't worry if you're not sure which choice to make for any of these options. You can always make changes after the graph has been created from the main **Graph Options** dialog, under the **Graph Updating** section (["Graph Updating" on page 581](#)). Even if you've chosen to create a non-updating graph, you can always switch the graph to update from this dialog, provided the original series or group still exists in the workfile.

Now, let's talk about the graph objects we've been creating.

Here, the titlebar shows that we have an untitled graph object. Notice also that since we are working with a graph object, the menu bar provides access to a new set of views and procedures which allow you to further modify the contents of the graph object.

As with other EViews objects, the UNTITLED graph will not be saved with the workfile. If you wish to store the frozen graph object in your workfile, you must name the graph object; press the Name button and provide a name.



There's one other thing to notice in the titlebar. A graph with updating turned off will have a green icon in the upper left-hand corner, while a graph with updating turned on will have an orange icon. These colored icons will also be seen in the workfile window, once the graph has been named. You may also verify (or modify) the updating status using the Graph Updating section of the graph options dialog ("[Graph Updating](#)" on page 581).

Combining Graphs

You may also create a graph object by combining two or more existing named graph objects. Simply select all of the desired graphs and then double click on any one of the highlighted names. EViews will create a new, untitled graph, containing all of the selected graphs. An alternative method of combining graphs is to select Quick/Show... and enter the names of the graphs.

Note that combined graphs may not be made auto-updating.

Customizing Graphs

EViews allows you to perform extensive customization of your graph object. You may add text, lines and shades, edit or remove existing elements such as legends or titles, or change a wide variety of display settings for the graph.

A graph object is made up of a number of elements: the plot area, the axes, the graph legend, and possibly one or more pieces of added text or shading. To select one of these elements for editing, simply click in the area associated with it. A blue box will appear around the selected element. Once you have made your selection, you can click and drag to move the element around the graph, or double click to bring up a dialog of options associated with the element.

Alternatively, you may use the toolbar or the right mouse button menus to customize your graph. For example, clicking on the graph and then pressing the right mouse button brings up a menu containing entries for customizing, copying and saving the graph.

Adding and Editing Text


You may customize a graph by adding one or more lines of text anywhere in the graph. Adding text can be useful for labeling a particular observation or period, or for adding titles or remarks to the graph. To add new text, simply click on the AddText button in the graph object toolbar or select Proc/Add text... from the main graph menu.

To modify an existing text object, simply double click on the object. The Text Labels dialog will be displayed.

Enter the text you wish to display in the large edit field. Spacing and capitalization (upper and lower case letters) will be preserved. If you want to enter more than one line, press the Enter key after each line.

- The Justification options determine how multiple lines will be aligned relative to each other.
- Font allows you to select a font and font characteristics for the text.
- Text in Box encloses the text in a box.
- Box fill color controls the color of the area inside the text box.
- Frame color controls the color of the frame of the text box.

The first four options in Position place the text at the indicated (relative) position outside the graph. You can also place the text by specifying its coordinates. Coordinates are set in virtual inches, with the origin at the upper left-hand corner of the graph.



The X-axis position increases as you move to the right of the origin, while the Y-axis increases as you move down from the origin. The default sizes, which are expressed in virtual inches, are taken from the global options, with the exception of scatter diagrams, which always default to 3 –3 virtual inches.

Consider, for example, a graph with a size of 4 –3 virtual inches. For this graph, the X=4, Y=3

position refers to the lower right-hand corner of the graph. Labels will be placed with the upper left-hand corner of the enclosing box at the specified coordinate.


You can change the position of text added to the graph by selecting the text box and dragging it to the position you choose. After dragging to the desired position, you may double click on the text to bring up the Text Labels dialog to check the coordinates of that position or to make changes to the text. Note that if you specify the text position using coordinates, the relative position of the text may change when you change the graph frame size.

Adding Lines and Shades

You may draw lines or add a shaded area to the graph. From a graph object, click on the Lines/Shade button in the toolbar or select Proc/Add shading.... The Lines & Shading dialog will appear.

Select whether you want to draw a line or add a shaded area, and enter the appropriate information to position the line or shaded area horizontally or vertically. EViews will prompt you to position the line or shaded area by providing an observation or data value.


You should also use this dialog to choose a line pattern, width, and color for the line or shaded area, using the drop down menus.



When adding a line, you may check **Draw line on top** to instruct EViews to draw the line after drawing the data. This can be useful with filled in areas, such as area or bar graphs.

If you check the **Apply color...** checkbox, EViews will update all of the existing lines or shades of the specified type in the graph.

Here we have drawn a vertical shaded area defined by the dates 1953M01 and 1957M07:




To modify a single existing line or shaded area, simply double click on it to bring up the dialog.


Sorting Graphs

Selecting **Sort...** from the **Proc** menu or the right mouse-button menu from the brings up the **Sort Order** dialog. Providing one or more sort keys will reorder the observations in the graph on the basis of the values of the keys. You may choose to reorder the data in ascending or descending values of the keys.

Note that sorting reorders the data in the graph object, not the underlying data in the original series or matrices.

Sorting the graph in ascending order yields:






Notice that EViews displays as much axis label information as possible since the observations are no longer described using a single timescale. Note also that the existing shade is associated with observation numbers and remains in the sorted graph, albeit with a very different interpretation.

Removing Graph Elements

To remove a graph element, simply select the element and press the **Delete** key. Alternately, you may select the element and then press the **Remove** button on the graph toolbar. For example, to remove the vertical axis in your graph simply click on the axis. A border will appear around the axis indicating that it is selected.




Simply press Delete or click on the Remove button to delete the scale.

(Double clicking will open the Graph Options dialog and will show the settings for the vertical axis.)

You may also remove legends, as well as any text, lines or shading which have been added to the graph.

Graph Options


The main Graph Options dialog controls the basic display characteristics of your graph. The dialog may be opened by selecting Options... from the right mouse menu. You may also double click anywhere in the graph window to bring up the Graph Options dialog. If you double-click on an applicable graph element (the legend, axes, etc.), the dialog will open to the appropriate page.



Here we have double clicked on the graph's legend, so the dialog opens to the Legend section. First, note the tree structure on the left-hand side of the dialog. EViews offers a lot of graph options, and to make them more accessible, they have been broken up and organized into groups. Within each group, you will find specific sets of options. Let's go through these groups one at a time.

Graph Types

The Graph Type section allows you to change the graph type. Begin by selecting a type from the Basic type page:



The listbox on the left-hand side of the page provides access to the fundamental graph types. The graph types that are available depend on whether the graph uses data from a single series (or column of data, e.g., a vector) or more than one series (or more than one column of a matrix). For example, the Area Band, Mixed with Lines, and High-Low (Open-Close), Scatter, XY Line, and XY Area types are only available for graphs containing multiple series or matrix columns.

Depending on the nature of your graph, there are a number of additional settings that may be displayed on the right-hand side of the Basic type page:


- **Multiple series** – When plotting line, bar, or area graphs with multiple series, EViews displays an option for producing a stacked graph. Simply select **Stack lines, bars, or areas** to display a stacked graph (see [“Single Series Graphs,” beginning on page 450](#) for details).
- **XY series handling** – In cases where there is potential ambiguity concerning the handling of multiple series in XY graphs (Scatter, XY Line, XY Area, XY Bar), EViews will display a combo box prompting you for whether you want to plot the data using **First vs. All** or using **XY pairs** (see [“Pairwise Graphs” on page 454](#) for discussion).
- **Mixed - First series type** – The mixed graph displays multiple series in a single graph frame, with the first series shown as a bar, spike, or area graph, or with the first two series displayed as an area band graph with the remaining series depicted using lines.

If you select **Mixed with Lines** as your graph type, the dialog will change to offer you a choice for the graph type for the first series type. The default setting is **Bar**. See [“Mixed with Lines” on page 484](#).

- **Sample Breaks & NA Handling** – If your data involve sample breaks or missing values, EViews will display additional settings allowing you to control the appearance of your graph. See [“Sample Break & NA Handling” on page 444](#) for further discussion.

Categorical graphs


If you have selected **Categorical graph** from the **General** drop-down on the **Basic type** page, a **Categorical options** page will also be available under the **Graph Type** section:



For a discussion of categorical graphs and use of the **Categorical options** page, see [Chapter 14. “Categorical Graphs,” on page 523](#)

Frame & Size

The **Frame & Size** section controls basic display characteristics of the graph, including color usage, framing style, indent position, and grid lines.




For discussion of each of these settings, see ["Frame" on page 460](#).

Axes and Scales

To change or edit axes, select the appropriate page from the **Axes & Scaling** group. The first two sections in this group, **Data scaling** and **Data axis labels**, relate to settings for the data scales. The third section, **Obs/Date axis**, sets options for the workfile (observation) scales. The fourth section, **Grid Lines**, can be used to add or modify grid lines on any axis.

Depending on its type, a graph can have up to four axes: left, bottom, right, and top. Each series is assigned an axis as displayed in the upper right listbox on the **Data scaling** page:




You may change the assigned axis by first highlighting the series and then clicking on one of the available axis buttons. For example, to plot several series with a common scale, you should assign all series to the same axis. To plot two series with a dual left-right scale, assign the two series to different axes. To edit characteristics of an axis, select the desired axis from the drop down menu at the top of the dialog.

Adding Custom Labels

EViews offers one of two methods for add custom labels depending on the type or status of the graph and the workfile structure.

In the Obs/Date axis dialog , you will see either a button or an edit field at the bottom of the Axis labels group.




For graphs that are actively updated, such as a graph view or a frozen graph with updating turned on, an edit field will be displayed. Entering an alpha or series name in the field instructs EViews to label each observation with the text or value of the alpha or series. The labels are updated as the values of the alpha or series change. To remove the labels and return to EViews default labels, leave this field blank.

The second approach to adding custom labels allows you to use alpha or numeric series values in a static fashion. The labels are initialized with the current values in the series, but will not be updated if the underlying data change. You may also choose to initialize labels of this type with observation numbers, or simply leave them blank and assign your own text. The labels may be edited as you please, and your changes will not be replaced when the graph is refreshed or the type is changed.

This static method of labeling is used for a graph whose data is no longer changing, such as a frozen graph with updating off. If stored labels can be used, you will see the **Add custom obs labels** or **Edit custom obs labels** button in place of the edit field.

To initialize the labels, click the **Add custom obs labels** button to bring up the **Axis label initialize** dialog. Select either **Standard observations labels (dates)**, **Observation numbers (taken from the workfile)**, **Uninitialized (empty strings)**, or **Series in workfile**, providing an alpha or series name if you chose the latter. Click on **OK** to accept your selection.

A dialog will open allowing you to edit the label associated with each observation. Here we have initialized the custom labels with the workfile labels.



If you wish to return to the default axis labels, click the Remove Labels button in the Edit custom obs labels dialog. All custom labels will be deleted and replaced with the default labels.

EViews does its best to preserve labels you have assigned to a Graph. For example, say you have created a graph view and assigned labels based on an alpha series in the workfile. When you're ready to turn off updating and obtain a snapshot of the current graph, EViews will hold on to the labels from the alpha series. you may now move the graph to a different workfile page or delete the alpha series completely, and the graph labels will be preserved.



See [“Axes & Scaling” on page 462](#) for additional detail.

Legend

To edit the graph legend characteristics, select the **Attributes** page of the Legend group.

You may change the basic characteristics of the legend (number of columns, enclose it in a box with specified fill and frame color, change the font, and change the placement) using the settings on the top half of the **Attributes** page.

Use the bottom half of the dialog to change the legend text. Simply click on the specified item in the list box, and then click in the edit field and alter the text.




Note that if you place the legend using user-specified (absolute) positions, the relative position of the legend may change if you change the graph frame size.

Lines and Symbols

The Lines & Symbols page under the Graph Elements group provides you with control over the drawing of all lines and symbols corresponding to the data in your graph.


The current line and symbol settings will be displayed in the listbox on the right-hand side of the dialog. You may choose to display lines, symbols, or both, and you can customize the color, width, pattern, and symbol usage. Once you make your choices, click on Apply to see the effect of the new settings.



See "[Lines and Symbols](#)" on [page 476](#) for additional detail.


Fill Areas

The Fill Areas page under the Graph Elements group allows you to control the display characteristics of your area, bar, or pie graph. Here, you may customize the color, shading, and hatching pattern of the graph elements.



Bar-Area-Pie


The Bar-Area-Pie page under the Graph Elements group provides additional options for bar, area, or pie graphs. You may add data labels to bar graphs, as well as modify the bars visually by adding shading or a 3D appearance. You may also specify if fill areas should be outlined.



[“Fill Areas” on page 478](#) provides additional discussion.

Boxplots

The final page of the Graph Elements group, Boxplots, provides control over all elements of a boxplot. As with the line and fill area dialogs, these options are only applicable if you have chosen boxplot as your graph type.



The left-hand side of the dialog

allows you to select which boxplot elements should be visible, and to specify which method should be used to display the confidence interval. On the right-hand side of the dialog, you may modify the characteristics of each boxplot element individually. Each element may have a unique color, symbol, line pattern, or width.


See "[Boxplot](#)" on page 509 for a discussion of boxplots.

Templates

Having put a lot of effort into getting a graph to look just the way you want it, you may want to use the same options in another graph. EViews allows you to use any named graph as a template for a new or existing graph. You may think of a template as a graph style that can be applied to other graphs.

In addition, EViews provides a set of predefined templates that you may use to customize the graph. These predefined templates are not associated with objects in the workfile, and are always available. The EViews templates provide easy-to-use examples of graph customization that may be applied to any graph. You may also find it useful to use the predefined templates as a foundation for your own graph template creation.

To update a graph using a template, double click on the graph area to display the Graph Options dialog, and click on Apply template under the Templates & Objects group. Alternatively, you may right mouse click, and select Templates... to open the desired page of the dialog.




On the left-hand side of the dialog you will first select your template. The left-hand list box contains a list of the EViews predefined templates. The right-hand box contains a list of all of the named graphs in the current workfile page. In this dialog, we have selected the graph object GRAPH01 for use as our graph template.


If you select one of the templates, you will be given the choice of applying the Bold, Wide, or English labels modifiers to the base template. As the name suggests, the Bold modifier changes the settings in the template so that lines and symbols are bolder (thicker, and larger) and adjusts other characteristics of the graph, such as the frame, to match. The Wide modifier changes the aspect ratio of the graph so that the horizontal to vertical ratio is increased.

The English labels modifier changes the base template's settings for auto labeling the date axis. When English labels are applied, labels using month formatting will default to English month names. For example, with English labels turned on, the axis may read: "Jan", "Feb", "Mar", while otherwise it may read: "M1", "M2", "M3".

Applying the Midnight template to the example graph yields:



Applying Midnight with the Bold and Wide modifiers selected yields:




You may reset the dialog by clicking on the Undo Page Edits button prior to clicking on OK.

When you click on the OK or Apply button, EViews will immediately update all of the basic graph settings described in ["Graph Options" on page 567](#), including graph size and aspect ratio, frame color and width, graph background color, grid line options, and line, symbol, and filled area settings.

In contrast to the basic graph settings which are always updated when you click on OK or Apply, the effects of using the template on the characteristics of existing text, line, and shade objects in the graph is controlled by the choices on the right-hand side of the dialog. There are three possibilities:

- Do not apply template to existing text & line/shade objects – instructs EViews to use the text, line, and shade attributes in the template or template graph only for the purpose of updating the default settings in the graph. If you select this option and select Apply, subsequently added text, line, and shades will use the updated settings, but existing objects will retain their existing characteristics.
- Apply template settings to existing text & line/shade objects – will update both the settings for existing text, line, and shade objects, and the defaults used for newly added objects.
- Replace text & line/shade objects with those of the template graph – will first remove any added text label, line, or shading objects in the existing graph, and then copy to the graph any such objects in the template.

If you have a template graph that you wish to apply to graphs in other workfiles, you may add it to the global template list so it will be accessible from any workfile. Click on Manage templates under the Templates & Objects group. The listbox in the top middle of the dialog shows all existing global templates, including the EViews predefined templates. These templates are stored globally and may be accessed from any workfile. The listbox on the bottom of the dialog shows all named graphs in the current workfile page that have not already been added to the predefined template list.



To add a graph to the predefined template list, select it from the listbox on the bottom and click the Add button. The graph will then move into the predefined list on the top of the dialog and will be removed from the list on the bottom. Before clicking the Add button, you

may wish to give the graph template a different name by editing its name in the edit field to the right of the listbox.

Similarly, to remove a graph from the predefined list, select it from the listbox on the top of the dialog and click the Remove button. This will remove the graph from the template list, but will not affect the graph object itself. Note that the EViews predefined templates cannot be removed.

Objects

Also under the Templates & Objects group, the Object options dialog allows you to control the default characteristics of new text, shade, or line drawing objects later added to the graph, or to update the characteristics of the existing objects.

You may select colors for the shade, line, box, or text box frame, as well as line patterns and widths, and text fonts and font characteristics.

By default, when you apply these changes to the graph object options, EViews will update the default settings in the graph, and will


use these settings when creating new line, shade, or text objects. Any existing lines, shades or text in the graph will not be updated. If you wish to modify the existing objects to use the new settings, you must check the Apply to existing line/shade objects and Apply to existing text objects boxes prior to clicking on the OK button.

Note that you may change the default settings for any of these options by selecting Options/ Graphics Defaults... from the main EViews menu. Any new graph views or objects will use the updated options as the default settings.


See [“Adding and Editing Text” on page 563](#) and [“Adding Lines and Shades” on page 564](#)

Graph Updating

For graphs which may still be tied into underlying data, you will be offered the opportunity to specify auto updating settings. The Graph Updating section allows you to change options



for how and when the graph is updated when its underlying data changes or the workfile sample is modified.



See “Freezing a Graph View” on page 558 for details.

Modifying Multiple Graphs

Some views are made up of multiple graphs. Like single graph views, these multiple graph views may be turned into graph objects by freezing. For example, the impulse response view of a VAR can display multiple graphs in a single view.

You may also create a graph object containing multiple graphs by combining existing named graph objects. Simply select the desired graphs and then double click on any one of the highlighted names. An alternative method of combining graphs is to select Quick/Show... and enter the names of the graphs.

There are two ways to work with a multiple graph. You may change the settings for the multiple graph as a whole, or you may work with an individual graph component of the multiple graph.


Working with Multiple Graphs

EViews makes it easy to work with all of the graphs in a multiple graph. Simply select Proc from the graph menu or click on the background of the graph and display the right mouse-button menu. EViews will display a menu prompting you for additional choices.

Note that selecting Proc will display a menu with additional options related to auto updating of graphs. See [“Freezing a Graph View” on page 558](#) for a discussion of graph updating.

These menu items set options that apply to all graphs in the graph object.

- Copy to clipboard... copies the graph to the clipboard.
- To set a common graph attribute to all graphs, select Options on all graphs... . EViews will display the multiple graph version of the Graph Options dialog, with each page initialized using the settings for the first of the multiple graphs. Here we see the dialog open to the Color & Border page of the Frame & Size section:




Click on OK to accept and apply the changes to each of the graphs.

- Each single graph in a multiple graph can be freely positioned by dragging the graph. Alternately, you may wish to align graphs in columns and control the overall spacing between graphs; for quick positioning all of your graphs, select Position and align graphs... to open the graph alignment dialog.

You may choose the number of columns and blocksize, as well as the horizontal and vertical spacing around individual graphs.

Here, we instruct EViews to display the graphs in blocks of 5, positioned using 3 columns per row. In this example, the first row of a block will contain 3 columns while the second row will have 2 columns; the pattern is repeated as necessary. If the specified blocksize is less than the number of columns, the “effective” blocksize will be the smallest multiple of the blocksize greater than the number of columns. Specified 3 columns with a blocksize of 2 is equivalent to 3 columns with a blocksize of 4.



Note also that when the dialog opens, the current spacing settings will be specified in the manual alignment edit fields. To have EViews automatically reposition the graphs (which may be useful if, for example, you have changed aspect ratios or font settings), select Automatic and click on OK.

- If all of your graphs share a common axis, you can draw lines or add shading to each graph in the object, by selecting Add lines & shading to all graphs... See [“Adding Lines and Shades” on page 564](#)
- Selecting Add text... allows you to annotate your multiple graph. Note that adding an item to the multiple graph differs from adding it to an individual graph since it will not move as you move individual graphs within the multiple graph. See [“Adding and Editing Text” on page 563](#).
- Selecting Templates... allows you to apply a template graph to each individual graph in your multiple graph or to reset the graph to use the global defaults. See [“Templates” on page 577](#) for a discussion of templates.
- Save graph to disk... brings up the File Save dialog, as described in [“Saving Graphs to a File” on page 586](#).

Working with Individual Graphs

You may change the options for a single graph within a multiple graph in the usual fashion by double clicking on the single graph to display its options dialog.

You can also perform various operations on individual graphs. Click on the individual graph and EViews will confirm the selection by surrounding the graph with a blue border. SelectProc or right mouse click to display a menu that combines the individual and multiple graph choices.

Most of the menu items are taken from the multiple graph menu, and apply to the entire graph. For example, selecting Copy to clipboard... allows you to copy the entire graph to the clipboard, not the individual graph.

The middle set of items provide tools for working with the selected graph. You may use these to change options, to add lines and shading, to sort the data, or to extract or remove the selected graph.

Printing Graphs


Clicking on the Print button on the graph view or graph object window toolbar will open the Print dialog, allowing you to override the various global settings for graph printing.

The top section of the Print dialog may be used to select a printer and print options, or to redirect the print job to an RTF file, graph object, or spool object (see [“Print Setup” on page 637](#)).

Most of the remaining options are self-explanatory. If you wish to print your graph in color using your color printer, make certain that the Print in color box is checked. Conversely, if you are printing to a black and white printer, you should make certain that this box is not checked so that EViews will substitute line patterns for colors.

Make background transparent should be used to ignore the background color of the graph (typically used when printing to a black-and-white printer).


See [“Print Setup” on page 637](#) for additional details.



Copying Graphs to the Clipboard

You can incorporate an EViews graph view or object directly into a document in your Windows word processor. First, you should activate the object window containing the graph you wish to move by clicking anywhere in the window (the titlebar of the object window should change to a bright color). Then click on **Edit/Copy** on the EViews main menu; the **Graph Metafile** dialog box appears. The default settings in this dialog are taken from the global defaults.

You can copy the graph to the Windows clipboard in Windows metafile (WMF) or enhanced metafile (EMF) formats. You can request that the graph be in color and that its background be transparent (ignore the background color of the graph). We recommend that you copy graphs in black-and-white unless you will be printing to a color printer.



Once you copy a graph to the clipboard, you may then switch to your word processor and paste the graph into your document. Standard programs such as Microsoft Word will give you a graph which can be sized, positioned, and modified within the program. You can also paste graphs into drawing programs, and make further modifications before pasting into your word processor or other software.

You may choose to hide this copy dialog for subsequent operations by unchecking the **Display this dialog...** box. Copying will then always use the default settings, without prompting. If you wish to change the default settings, or to turn on or off the display of the copy dialog, you may go to the **Exporting** page of the global Graph options (**Options/Graphics Defaults...**).

Saving Graphs to a File

EViews allows you to save your graphs to a file in a variety of popular graphics formats (Windows Metafile, PostScript, bitmap, GIF, JPEG, PNG).

Simply select **Proc** from the graph menu or click on the background of the graph and display the right mouse-button menu, then select **Save graph to disk...** to bring up the **Graphics File Save** dialog.

In the top portion of the dialog, you should provide the name of the file you wish to create. EViews will automatically append an extension of the proper type to the name (here, “.EPS” since we are saving an Encapsulated PostScript file).


Next, select the File type , and any options associated with the output type. You may select Metafile - Win 3.1 , Enhanced Metafile , Encapsulated Post-

Script, Bitmap , Graphics Interchange Format (also known as GIFs), Joint Photographic Experts Group (better known as JPEGs), or Portable Network Graphics (PNGs). You may elect to save the graph in color or not, whether to make the background transparent, and, for PostScript files, elect to include a bounding box or choose the graph orientation.

Lastly, you should select the Output graph size . The size may be specified in inches, centimeters, printer points, pi cas, or pixels. If the Lock aspect ratio checkbox is selected, changes to the Width or the Height will generate corresponding changes in the other dimension. If you wish to scale your graph in a non-proportionate fashion, you should uncheck this box.

When saving raster images (bitmap, GIF, JPEG, PNG) with sizes expressed in anything but pixels, EViews offers an additional setting, Dots per Inch , which specifies the output resolution. The total number of pixels written in the output file will depend on both the number of inches and the number of dots per inch. If, for example, you export a 5 by 4 inch GIF at 300 dots per inch, the final output file will be 1500 by 1200 pixels. At 100 dots per inch, the output file will be 500 by 400 pixels.

The default graph file saving options may be set in the global options dialog by selecting Options/Graphics Defaults.... and opening the Exporting page (see [“Graphics Defaults” on page 639](#)).



Graph Commands

For those of you who wish to automate these procedures, for example to produce a regular report, EViews allows you to perform extensive graph customization from the command line or using programs.

See [Chapter 2. “Working with Graphs,” on page 21](#), and [“Graph” on page 182](#) in the Command and Programming Reference for additional detail.

Chapter 16. Tabland Text Objects

Table and text objects form the basis of presentation output for, and EViews provides sophisticated tools for customizing the appearance of these objects.

Table Objects

Freezing views that contain formatted text or numbers that are aligned in columns or rows produces table objects. The following sections describe the basics of working with table objects, including creating, formatting, printing, and exporting of tables.

Creating Tables

In EViews, a table may be an object view or a table object. Table views are object views that contain formatted text or numbers that are aligned in columns and rows. Examples of table views are the spreadsheet views of a series and the estimation output views of an equation. There are a limited set of customizations that are available for table views.

A table object is an independent object that contains formatted text or numbers. Table objects may be created directly, by issuing a table declaration, or indirectly, by freezing a table view. As with graph objects, table objects are “not live” in the sense that they do not reflect the current contents of the underlying object, but are based instead upon the contents of the object at the time the object was frozen. Table objects also allow for a full set of customizations.

While many of the features described here apply to both table views and table objects, the remainder of our discussion focuses on customization of table objects. Working with table views is described elsewhere (see, for example [“Changing the Spreadsheet Display” on page 82](#)).

Table Basics

The most basic operations in a table involve selecting cells and editing cell values.

Selecting Cells

Selecting one or more cells is one of the most common tasks in working with table views and table objects. For the most part, you will find that cell selection works as it does everywhere else in Windows, but a brief review may prove useful.

The simplest selection is for a single cell. Simply click on the cell you wish to select. If the table is not in edit mode, the cell will be shaded. If the table is in edit mode, the cell will be surrounded by a black border, and the contents of the cell will be displayed in the table edit window.

For the selection of multiple cells, EViews uses the concept of an anchor cell to determine a selection region. The anchor cell is used to mark the start of the selection region and is used to indicate how a selection will change as you move the mouse or use key-strokes.

When edit mode is off, the anchor cell is marked as the cell with the black square in one of the four corners of the cell. When edit mode is on, the anchor cell is marked with a black border around the cell. You may toggle between edit mode on and edit mode off by clicking on the Edit +/- button on the object toolbar, or alternatively, by right mouse clicking and selecting Edit +/- .

The easiest way to highlight a region is to (left) click in a cell to set an anchor point, then, while holding down the mouse button, move the mouse to select additional cells. In addition, cell selection shortcuts allow you to select rows and columns by clicking on row and column headers, and to select rectangular regions by clicking on a cell to set an anchor cell, then SHIFT-click to select the rectangular region defined by the anchor and ending cells. You may enter CTRL-A to select all of the cells in a table.

Some of the more frequently used selection tools include:

To select	Action
Text in a cell	If edit mode is turned on, select the cell, double-click in it, and then select the text in the cell. Or select the cell and then select the text in the edit field.
A single cell	Click the cell, or use the arrow keys to move the anchor cell.
A range of cells	Click the first cell of the range, and then drag to the last cell. Or click in a cell to set the anchor, then SHIFT-click in the last cell you wish to include. Or set the anchor, and then SHIFT and press the arrow keys until desired cells are selected.
All cells in a table	Click the corner cell shared by the column and row header (the corner cell is not visible in some output views). Or press CTRL+A.
An entire row	Click the row heading.
An entire column	Click the column heading.

Adjacent rows or columns	Click and drag across the row or column headers. Or select the first row or column; then hold down SHIFT and click the last row or column heading.
More or fewer cells than the current selection	Hold down SHIFT and click the last cell you want to include in the new selection. The rectangular range between the active cell and the cell you click becomes the new selection. Or hold down SHIFT and press the arrow keys until selection is correct.

Note that row and column header selection is not always available in table views since the headers are not always displayed. For example, the estimation output view of an equation is a table that does not contain header lines. Freezing the view creates a table object that allows for cell selection using the visible headers.

Editing Cell Values

To enter or change the data in a table, you must first display the table edit window by enabling edit mode, and selecting a cell to be modified. Here, we see a table that is in edit mode, with the contents of the A1 cell displayed in the edit window just below the toolbar.

To modify the contents of the cell, simply type in the edit window. Alternately, you may double click in the cell to edit the contents. EVIEWS will then allow you to edit the cell in place.

You may provide either alphanumeric or numeric input. If your text may be interpreted as a number, EVIEWS will interpret the input and store the value as

a number. Since the table value is stored as a number it may later be formatted using the numeric formatting tools. You may, for example, change the display of the number to scientific notation, or you may display numbers with 4 digits of precision (see [“Content Formatting” on page 593](#)).

Note that you may enter numeric expressions and have EVIEWS evaluate them prior to placing them in the table. To evaluate a numeric expression into a cell, type “=” before the expression. For example, entering the text “=4*5” will result in a cell value of “20”. Entering an invalid numeric expression will set the cell to a numeric NA.

	A	B	C	D	E
1	LS // Dependent Variable is UNEMP				
2	Date: 02/08/95 Time: 11:20				
3	Sample: 1958:1 1981:4				
4	Included observations: 96				
5	Convergence achieved after 12 iterations				
6					
7	Variable	Coefficient	Std. Error	T-Statistic	Prob.
8					
9	C	4.341774	1.491847	2.910334	0.0046
10	DMR	-5.784553	1.758724	-3.289063	0.0014
11	SIG	2.199932	1.104584	1.991638	0.0495
12	SIG(-1)	2.881466	1.063034	2.710605	0.0081
13	AR(1)	0.786288	0.160852	4.888275	0.0000
14	ΔP(2)	0.153912	0.155971	0.986991	0.3261
15					

This latter example raises a minor issue associated with entering missing values into a table. If the text “NA” is entered into a table cell, the cell value will be set to the string “NA”, not to the missing value NA. To enter a numeric missing value, you should enter the string “=NA” into the cell. We point out that the choice between entering the “NA” string or the NA value into a cell has consequences for auto-justification, or when saving values to a file.

Basic Customization

You may perform basic customization of a table object by attaching a title, by adding or hiding the grid lines, or by resizing the rows or columns.

Table Title

To add a header title to the top of a table object, you should select Proc/Title... from the table menu, or you may click on the Title button on the toolbar. EViews will display a dialog prompting you to enter your title. When you enter text in this dialog, EViews displays a header title at the top center of the table. Note that the table title is different from the table name, which provides the object name for the table in the workfile.

To remove the table title, display the title dialog, then delete the existing title.

Grid Lines

To toggle on or off the grid marking the cells in the table object, click on the Grid+/- button on the table toolbar, or select Proc/Grid +/- from the main table menu.

Resizing Columns and Rows

Column widths may easily be resized in both table views and in table objects. Simply place your cursor over the separator lines in the column header. When the cursor changes to the two-sided arrow, click and drag the column separator until the column is the desired size. If you wish to resize more than one column to the same size, first select the columns you wish to resize, then drag a single column separator to the desired size. When you release the mouse button, all of the columns will be resized to the specified size.

Row heights may only be resized in table objects. Place your cursor over the separator lines in the row header and drag the separator until the row is the desired height. If you wish to resize more than one row, first select the rows you wish to resize, then drag a separator to the desired size. All of the rows will be resized to the specified size.

Double clicking a column/row edge in the header will resize the row or column to the minimum height or width required so that all of the data in that row or column is visible.

Table Cell Customization

EViews provides considerable control over the appearance of table cells, allowing you to specify content formatting, justification, font face, size, and color, cell background color and borders. Cell merging and annotation are also supported.

Cell Formatting

You may select individual cells, ranges of cells, or the entire table, and apply various formatting tools to your selection. To format the contents of a set of cells, first make certain that the table is in edit mode. Next, select a cell region, then click on CellFmt in the toolbar, or right mouse click within the selected cell region and select Cell Format... EViews will open the Table Options dialog containing three tabs: Format, Font/Color, and Borders/Lines.


Content Formatting

The Format tab allows you to apply display formats to the contents of cells in table objects. Formatting of table objects may be cell specific, so that each cell may contain its own format.

You may also modify the display of numeric values, set column widths and row heights, and specify the justification and indentation.

Bear in mind that changing the height of a cell changes the height of the entire row and changing the width of a cell changes the width of the column. Column widths are expressed in unit widths of a numeric character, where the character is based on the default font of the table at the time of creation. Row height is measured in unit heights of a numeric character in the default font.


For additional discussion of content and cell formatting, see the related discussion in ["Changing the Spreadsheet Display" on page 82](#)



Fonts and Fill Color

The **Font/Color** tab allows you to specify the font face, style, size and color for text in the specified cells. You may also add **strikeout** and **underline** effects to the font. This dialog may also be used to specify the background fill color for the selected cells.

Where possible, the **Sample** window displays a preview of the current settings for the selected cells. In cases where it is impossible to display a preview (the selected cells do not have the same fonts, text colors, or fill colors) the sample text will be displayed as gray text on a white background.




Note also that EViews uses the special keyword **Auto** to identify cases where the selection region contains more than one text or fill color. To apply new colors to all of the selected cells, simply select a **Text** or **Fill** color and click on **OK**.

Borders and Lines

The last tab, labeled **Borders/Lines**, is used to specify borders and lines for the selected table cells.

Simply click on any of the **Presets** or **Border** buttons to turn on or off the drawing of borders for the selected cells, as depicted on the button. As you turn on and off border lines, both the buttons and the display on the right will change to reflect the current state of your selections. Note also that there is a checkbox allowing you to draw double horizontal lines through the selected cells.



It is worth noting that the appearance of the **Borders/Lines** page will differ slightly depending on whether your current selection contains a single cell or more than one row or column of cells. In this example, we see the dialog for a selection consisting of multiple rows and columns. There are three sets of buttons in the **Border** section for toggling both the row and column borders. The first and

last buttons correspond to the outer borders, and the second button is used to set the (between cell) inner border.

If there were a single column in the selection region, the Border display would only show a single column of “Cell Data”, and would have only two buttons for modifying the outer vertical cell borders. Similarly, if there were a single row of cells, there would be a single row of “Cell Data”, and two buttons for modifying the outer horizontal cell borders.

Cell Annotation

Each cell of a table object is capable of containing a comment. Comments may be used to make notes on the contents of a cell without changing the appearance of the table, since they are hidden until the mouse cursor is placed over a cell containing a comment.

To add a comment, select the cell that is to contain the comment, then right mouse click and select Insert Comment... to open the Insert Cell Comment dialog. Enter the text for your comment, then click OK. To delete an existing comment, just remove the comment string from the dialog.

If comment mode is on, a cell containing a comment will be displayed with a small red triangle in its upper right-hand corner. When the cursor is placed over the cell, the comment will be displayed.

If comment mode is off, the red indicator will not be displayed, but the comment will still appear when the cursor is placed over the cell.

	A	B	C	D	E	F
1	LS // Dependent Variable is UNEMP					
2	Date: 02/08/95 Time: 11:20					
3	Sample: 1958:1 1981:4					
4	Included observations: 96					
5	Convergence achieved after 12 iterations					
6						
	Variable	Coefficient	Std. Error	T-Statistic	Prob.	
9	C	4.341774	1.404047	2.910334	0.0046	
10	DMR	-5.784553	1.730724	-3.289063	0.0014	
11	SIG	2.199932	1.104584	1.991638	0.0495	
12	SIG(-1)	2.881466	1.063034	2.710605	0.0081	
13	AR(1)	0.786288	0.160852	4.888275	0.0000	
14	AR(2)	0.153942	0.155971	0.986991	0.3264	
15						

Use the Comments+/- button in the tool bar to toggle comment mode on and off. Note that the red triangle and comment text will not be exported or printed.

Cell Merging

You may merge cells horizontally in a table object. When cells are merged, they are treated as a single cell for purposes of input, justification, and indentation. Merging cells is a useful tool in customizing the look of a table; it is, for example, an ideal way of centering text over multiple columns.

To merge several cells in a table row, simply select the individual cells you wish to merge, then right click and select Merge Cell +/- . EViews will merge the cells into a single cell. If the selected cells already contain any merged cells, the cells will be returned to their original state (unmerged).


Here, we begin by selecting the two cells B1 and C1. Note that B1 is the anchor cell, as indicated by the edit box surrounding the cell, and that B1 is center justified, while C1 is right justified.

If we right mouse click and select Merge Cell +/- , the two cells will be merged, with the merged cell containing the contents and formatting of the anchor cell B1. If you wish C1 to be visible in the merged cell, you must alter the selection so that C1 is the anchor cell.


We see that the B1 and C1 cells are merged, as indicated by the large selection rectangle surrounding the merged cells.

Bear in mind that the C1 cell has not been cleared; its contents have merely been hidden behind B1 in the merged cell. Editing the value of the merged cells will replace the value in the cell B1, but has no effect on hidden cells, in this case C1.

If the merged cell is selected, toggling Merge Cell +/- will unmerge the cell so that cells are returned to their original form. The contents of C1 will once again be visible and may be modified using any of the table display formatting tools.



	A	B	C	D	E
1	obs	GDP			
2					
3	1952Q1	87.875	444.80		
4	1952Q2	88.125	444.70		
5	1952Q3	89.625	447.73		
6	1952Q4	92.875	461.50		
7	1953Q1	94.625	470.65		
8	1953Q2	95.550	474.33		
9	1953Q3	95.425	471.85		
10	1953Q4	94.175	464.55		
11	1954Q1	94.075	462.48		
12	1954Q2	94.200	462.13		
13	1954Q3	95.450	467.23		
14					




	A	B	C	D	E
1	obs	GDP			
2					
3	1952Q1	87.875	444.80		
4	1952Q2	88.125	444.70		
5	1952Q3	89.625	447.73		
6	1952Q4	92.875	461.50		
7	1953Q1	94.625	470.65		
8	1953Q2	95.550	474.33		
9	1953Q3	95.425	471.85		
10	1953Q4	94.175	464.55		
11	1954Q1	94.075	462.48		
12	1954Q2	94.200	462.13		
13	1954Q3	95.450	467.23		
14					

Printing Tables

To print a table object, click on the Print button on the table tool bar or select View/Print... from the main EViews menu to display the Print dialog.

The top section of the Print dialog may be used to select a printer and print options, or to redirect the print job to an RTF file, text file, table object, or spool object (see [“Print Setup” on page 637](#)).




You may use the remainder of the dialog to scale all of the text in the table, to select the orientation of the table (Portrait or Landscape), to draw or not draw a box around the table, and to include or not include the table headers in the print job.

If you have selected a range of cells in the table, the Print range section of the dialog will offer you choice of printing the entire table or only printing the current selection.

Copying Tables to the Clipboard

You may copy-and-paste a table to the Windows clipboard, from which you may paste the table contents into your favorite spreadsheet or word processing software.

Simply select the cells that you wish to copy and then choose Edit/Copy from the EViews main menu, or Copy from the right mouse button menu. The Copy Precision dialog box will open, providing you with the option of copying the numbers as they appear in the table, or at their highest internal precision.



After you make a choice, EViews will place the table on the clipboard in Rich Text Format (RTF), allowing you to preserve the formatting information built into the table. Thus, if you copy-and-paste a table from EViews into Microsoft Word or another program which supports RTF, you will create a nicely formatted table containing your results.

To paste the clipboard contents into another application, switch to the destination application and select Edit/Paste. Note that some word processors provide the option of pasting the contents of the clipboard as unformatted files. If you wish to paste the table as unformatted text, you should select Edit/Paste Special.


Saving Tables to a File

EViews allows you to save your table objects in several file formats: Comma Separated Value (CSV), tab-delimited text (ASCII), Rich Text Format (RTF), or a Web page (HTML) file.

To save the table to disk, with the table window active or with table cells selected, right mouse click or select **Proc**, then select **Save table to disk...** to bring up the **Table File Save** dialog. The dialog displays default values from the global settings.

In the top portion of the dialog, you should provide the name of the file you wish to create. EViews will automatically append an extension of the proper type to the name (here, “.HTM” since we are saving a Web HTML file), and will prepend the default path if an explicit path is not provided.

Next, select the **File type**. You may select Comma Separated Value, Tab Delimited Text-ASCII, Rich Text Format, or Web page. The options section of the dialog allows you to save the entire table or only those cells that are currently selected, and, for HTML file output, to scale the table size.



You may also specify options for how numbers are to be treated when written. You may specify a **Number format** so that numbers are written **As displayed** in the table, or using **Full precision**. In addition, you may change the text used to write missing values.

Table Commands

EViews provides tools for performing extensive table customization from the command line or using programs. See [“Table” \(p. 596\)](#) in the **Command and Programming Reference** for additional details.

Text Objects

Some output views have no formatting and are simple displays of text information. Examples are representations of an equation and results from X-11 seasonal adjustment. If you freeze one of these views, you will create a text object.

You can also create a blank text object by selecting **Object/New Object.../Text** in the main EViews menu or by simply typing “text” in the command window. Text objects may be used whenever you wish to capture textual data that does not contain any formatting information.

Printing of text objects follows the same procedure and offers the same options as printing a table object; see ["Printing Tables" on page 597](#).

Chapter 17. Spool Objects


EViews offers a spool object that is capable of holding multiple tables, graphs, text, and spools, allowing you to form collections of output objects. You may find spools to be useful for organizing results, for example, for creating a log of the results for a project or an EViews session, or perhaps for gathering output for a presentation.

In addition to being an output object container, spool objects provide easy-to-use tools for working with the objects in the spool. Among other things, you may manage (add, delete, extract, rearrange, hide) or customize (resize, space and indent, title and comment, and edit) the spool and the individual objects in a spool.

Creating a Spool

To create a spool object in a workfile, you may select `Object\New Object\Spool` from the workfile menu, optionally enter a name in the `Name for object` edit field, and click on `OK`. Alternately, you may simply enter the declaration command `spool` followed by an optional name in the command window, then press `ENTER`.

Spools may also be created by printing from an EViews object to a non-existent spool. You may simply redirect the print output of an object you wish to add to the spool (see [“Adding Objects”](#), below).



Here we see the spool view of an empty, unnamed spool object. As depicted here, the default is to display the contents of the spool using two panes. The left pane is the tree pane

which shows a tree-structure listing of the objects contained in the spool. You may use the tree pane to navigate quickly from object to object. The right pane is the main output pane which shows the actual output view objects.

You may select and drag the separator between the two panes to change their relative sizes, and you may use the Tree +/- on the toolbar to show and hide the tree pane. Note that hiding the tree pane provides you with a larger main window display area, but makes a number of spool management and customization tasks somewhat more difficult.

Managing the Spool

Most of your time using a spool will be spent managing the output objects contained in the spool. EViews provides easy-to-use tools for the Δ of the basics tasks like adding, deleting, extracting, and rearranging objects, as well as more advanced operations such as hiding objects and flattening portions of the tree.

Adding Objects

You may add an output object to a spool using any of the three primary methods: printing to the spool, copy-and-pasting objects, using the spool append procedure.

Printing to a Spool

Perhaps the easiest approach is to redirect the printing of the your object output into a spool object. You may, for example, display the estimation results for an equation, or perhaps the histogram view of a series, and “print” the output directly into a spool. Note that this method does not require you to freezing the original object view to create a separate output object.

To redirect your print job into the spool, simply click on Print from the object toolbar, or select File/Print... from the main EViews menu. In the Print dialog that opens, you should set the Destination to Redirect, specify Spool object as the redirect target, and then specify the name of the spool to which you wish to print. If you specify a spool object that does not exist, a new spool with the specified name will be created and a copy of your object will be added to it.

The screenshot shows the 'Print' dialog box in EViews. The 'Destination' section has two radio buttons: 'Printer' (unselected) and 'Redirect' (selected). The 'Redirect' option has a dropdown menu showing 'Spool object' and a text field for 'Spool Name' containing 'SPOOL01'. There is a 'Properties' button next to the printer option and a 'Clear File' button next to the spool name field. The 'Text/Table options' section includes a 'Text size' dropdown set to 'Normal - 100%', a 'Percent' input field set to '60', and an 'Orientation' dropdown set to 'Portrait'. The 'Print range' section has two radio buttons: 'Entire Table/Text' (selected) and 'Current Selection'. The 'Table options' section has two checkboxes: 'Box around tables' and 'Include headers', both of which are unchecked. At the bottom are 'OK' and 'Cancel' buttons.

Click on OK to continue. EViews will add an output object containing the contents of the object window to the spool object.

If you wish to send all subsequent print jobs to the spool object, you may use the main File/Print Setup... dialog or the [output](#) command to change the default print destination to your spool (see [“Print Setup” on page 637](#) and [output \(p. 287\)](#) of the Command and Programming Reference). Then you may simply display your view, then click on Print and OK to send the output to the spool object.

Copy-and-Paste to a Spool


Alternately, objects may be copied from the workfile window and pasted into an existing spool object. Simply select the objects you wish to copy in the workfile window and press CTRL-C or select Edit/Copy from the main or the right-button menus. Next display the spool object window, and paste into the main object pane by pressing CTRL-V, or selecting Edit/Paste from the main or right mouse-button menus.

EViews will append copies of output (graph, table, text, and spool) objects directly into the spool; for other types of objects, EViews will append copies of the frozen default views. For example, if you copy-and-paste a series, EViews will add a copy of the default spreadsheet view to the spool.

We emphasize that the objects contained in a spool are frozen copies of the original objects. The objects in the spool are independent of the source objects so that changes made to either the copy or the original will not have an effect on the other.


Appending to a Spool

Lastly, you may select Proc/Append/Existing Object from the menu of an existing spool object. You will be prompted by a dialog where you can enter the names of the objects to be added and commands for displaying the desired output windows in a space delimited list. Here, for example, we instruct EViews to display the default spreadsheet view for GDP, a line graph for GDP, and as a Wald test for “c(1)=0” in equation EQ01, and to save the results for each of these three views into the spool.



Note that when adding multiple outputs you should make certain to separate the names and commands by spaces. If necessary, you should enclose the text in double quotes, if, for example, the command statement includes spaces as in the Wald example above.

Click on OK to continue. The tree pane of the spool now shows the three object names and types, while the main output pane allows you to view the objects. You may scroll the window between output objects by clicking on the icon in the tree pane or by using the scrollbar on the right-hand side of the output pane.



Note that the newly added objects are all given names that are variations on the name “UNTITLED”. You may wish to provide more descriptive names (see [“Naming Objects” on page 606](#)).


Click on Name and enter MYSPOOL to name the spool object.

Embedded Spools

Spool objects may contain other spool objects. Nested spools allows you to categorize or group output objects within a spool.

There are two ways to add a spool object to an existing spool. First, if the spool you wish to add exists in your workfile then you may insert it into a spool as you would any other object using print, copy-and-paste, or the append proc as described in [“Adding Objects” on page 602](#)


Second, you may add a new (empty) spool object to the spool by selecting Proc/Append/New Spool ... and entering a space separated list of one or more names for the new spools. The names given to spools must be valid EViews names. EViews will create and append a new spool for each specified name. If there are duplicate names in the spool, the new spools will be named using the next available name.



Suppose, for example, we have the namedspool object MYSPPOOL, which contains three output objects (A1, A2, and A3). We next create a new, UNITITLED spool object containing the output object B1. Lastly, we append MYSPPOOL, and its three output objects by copying-and-pasting MYSPPOOL into the UNITITLED main object pane.

The contents of MYSPPOOL are added to the end of the spool object. The copy of the spool object, shown with the spool icon, is assigned the name UNITITLED01.

The tree entry for UNITITLED01 is shown here in open fashion,



ion, with the three output objects in the embedded spool displayed in the branch of the tree. Clicking on B1 in the root of the tree scrolls the output window so that B1 is displayed in the main output pane; clicking on A1 in the UNITITLED01 branch of the tree scrolls to the A1 output object from MYSPPOOL. As with all tree structures, you may click on the tree icon next to UNITITLED01 to open or collapse the display of the branch.

It is worth noting that the embedded spool object is a full-fledged output object inside the parent spool. Thus, selecting an embedded spool and performing operations such as naming, commenting, hiding, indenting, resize, etc. applies to the embedded spool object, and not to the objects inside the embedded spool. The most important implication of this fact is that if you wish to change the properties of the objects within an embedded spool, you must display the embedded spool in edit mode so that you can access its settings and its individual elements ([“Editing Objects in a Spool” on page 616](#)), or you must first move the object out of the spool, or you may flatten or move all of the objects out of the embedded spool ([“Flattening a Spool” on page 611](#)).


For example, the easiest way to turn on comments for all of the objects within the embedded spool in the example above is to double click on UNITITLED01 in the tree pane to activate edit mode, then to modify its display settings by clicking on the Comments +/- button. By placing the embedded spool in edit mode, we gain access to its display settings; if instead we pressed Comments +/- in standard mode, we would activate comments for

the objects in the parent spool only. (See [“Editing Objects in a Spool,”](#) on page 616 for additional discussion).

Naming Objects

To rename an output object in the spool, select the object name in the tree pane or select the output object in the main output page, then right mouse-click and select Name.... EViews will display the Object Title dialog.

Note that the dialog may also be called up by double-clicking on the name of the object, if visible, in the main object window (see [“Display Properties”](#) on page 613 for a discussion of name display settings).



Simply enter a new, valid EViews name in the Object Name field, and if desired a display name in the optional Display Name field. The display name allows you to provide a more descriptive label that may be employed in place of the object name in the tree pane view when displaying object names.


Since all spool output objects will, by default, be named using some variant of “UNTITLED”, we recommend that if you have spools with more than a few objects, you assign them more descriptive object or display names.

Adding Comments

Comments may be added to objects, allowing you to annotate individual objects in the spool. To add a comment to an object or to change the existing comment, select the object of interest, then choose the right button menu item Comment... to bring up the Insert Object Comment dialog.

The dialog may also be called up by double-clicking on the comment for an object, if visible, in the main

object window (see [“Display Properties”](#) on page 613 for a discussion of comment display settings).



Enter your comment or edit the existing comment and click on OK to add it to the object.

Hiding Objects


After creating a spool with objects of various types, you may wish to view a subset of the objects. You may hide objects either individually or by type (tables, graphs, or text).

Hiding Individual Objects

You may hide or show objects individually using a variety of methods. The easiest method is to select an object in the spool using the tree pane or the main window, and select Show/Hide from either the Proc or right mouse-button menus to toggle the item between hidden and visible.

Note that hiding an embedded spool hides all of the objects in the embedded spool.

Objects that are hidden do not appear in the main window; if, however, the spool settings are to display titles or comments ([“Display Properties” on page 613](#)), the object title or comments will still be visible.



GDP	
Last updated: 09/09/97 - 15:35	
Display Name: gross domestic product	
1952Q1	87.87500
1952Q2	88.12500
1952Q3	89.62500
1952Q4	92.87500
1953Q1	94.62500
1953Q2	95.55000
1953Q3	95.42500
1953Q4	94.17500
1954Q1	94.07500
1954Q2	94.20000
1954Q3	95.45000
1954Q4	97.36375
1955Q1	100.7250
1955Q2	102.8250
1955Q3	104.9250
1955Q4	106.6000
1956Q1	107.2750


The icon for hidden objects will be grayed out in the tree pane. Here, we see that the UNTITLED01 table object in the main branch of the spool is hidden.


An alternate method requires that object title display be turned on. Click the Properties button to bring up the Spool Properties dialog, and check the Show Names checkbox. When titles are displayed, the main window

will contain a box containing a “+” or “–” alongside the name of the objects in the spool. Clicking on the box will toggle the object between being hidden and visible. In this example, clicking on the “–” symbol will hide UNTITLED01.

Hiding Types of Objects

In some cases it is desirable to hide objects of a specific type. Objects can be hidden by type by selecting Proc/Hide and choosing All, Tables, Graphs, or Text. Conversely, to show hidden objects of a specified type select Proc/Show.






Resizing Objects

You may use the spool object to override the sizes of individual output objects.

The default is for graph objects to be displayed at a fixed size while tables and text objects are displayed at their native sizes. This implies that all graphs are displayed with the same width, whatever the size of the individual graph, while tables and text objects are displayed using the widths and font sizes specified in the individual object.



There are two different ways of using the spool to change the display size for an object. But before you are allowed to alter the display size of an object you must make certain that its display mode is set to Variable Width or Variable Width w/ Limit (see ["Display Modes" on page 615](#) for details).

First, you may select the object in the tree pane or by clicking on the object in the main window. Press the right mouse-button and select Properties... to open the Object Properties dialog. Enter the desired Width in the edit field and click on OK. EViews will resize the object, maintaining the original aspect ratio. Font sizes in the object will be scaled accordingly.

Alternately, if the frame for an object is displayed in the output window, you may drag the border to resize the object (see [“Display Properties” on page 613](#) for a discussion of border display settings).

Note that resizing the object does not alter the native size of the object. You may at any time select an object, right-click, and choose `Reset size` to return an individual object to its native size. Or, you may use the spool object to reset the display of all of your objects to their native sizes (see [“Display Modes,” on page 615](#)).

Indenting Objects

To change the indentation of an object you should first select the object in the tree pane or by clicking on the object in the main window. Press the right mouse-button and select `Properties...` to open the Object Properties dialog. Enter the desired indentation in the Horizontal and Vertical edit fields, and click on `OK` to continue.

Note that the indentation values set in the `Indent in inches` section dialog will be added to any margins set for the spool.

Removing Objects

To remove an object from a spool select the object then press the `Delete` key or select `Remove` from the right mouse-button menu. EViews will prompt you for whether you wish to continue. Click on `OK` to proceed.

Note that if you remove a spool object, you will remove it and all of the objects contained in the spool. If you wish to retain some of the nested objects you must move them outside of the embedded spool ([“Rearranging Objects” on page 610](#)) prior to deleting the spool. Alternately, you may simply delete a subset of objects within the embedded spool.


Extracting Objects

You may copy, or extract, an object in a spool into the work file. To extract an object, simply highlight the object, and then select `Extract` from the right mouse-button menu, or click on `Proc/Extract`. EViews will create an untitled output object in the workfile containing a copy of the object in the spool.

Rearranging Objects

Suppose, for example, that you have placed a number of output objects in the spool, but they are not in the desired order for your presentation. You may reorder objects in the spool using the tree pane to move objects (one at a time) to different positions in the spool.


To move an object, you should select it in the tree pane and drag it to the desired position. A horizontal black bar will indicate the object's new location when the mouse button is released. If the destination is an embedded spool, EVIEWS will move the object into the embedded spool.



Note that objects may easily be moved into and out of embedded spool objects. In our example, we move the table object UNTITLED03 from the embedded spool UNTITLED02 into the top level of the spool, just below UNTITLED01.

In some cases, moving objects into or out of an embedded spool will cause an object name conflict. In these cases, EVIEWS will display a dialog prompting you to provide a new unique name (a new name will be suggested), along with an optional display name which may be used in the tree view.


As noted in the dialog, display names need not be unique.




Flattening a Spool

You may move all of the objects out of an embedded spool by flattening the spool. Flattening moves out all of the output objects in an embedded spool (including objects in any spools embedded in the embedded spool) and then deletes the now empty spool.

Select the name of the embedded spool you wish to flatten in the tree pane, then click on Proc/Flatten All or press the right mouse-button and select Flatten. EVIEWS will replace the spool with all of the output objects in the spool.



In our example, we select the spool object UNTITLED02, and use the right mouse-button to select Flatten. EViews will replace UNTITLED02 with all of its child output objects, renaming the objects as necessary to avoid name conflict.




In this example, UNTITLED01 and UNTITLED02 have automatically been renamed in order to resolve the name conflict resulting from flattening the spool.

Customizing the Spool

The spool object provides several options for customizing the display of object elements in the spool.

Display Properties

Press the Properties button in the tool bar to bring up the Spool Properties dialog which allows you to set the basic display properties for the spool object:



General Settings


The General Settings section of the dialog allows you to show and hide various parts of the spool.

- The Show Borders option allows you to display a frame around each of the output objects in the main spool window. Dragging the border of an object will resize that object (see [“Resizing Objects” on page 609](#)).
- The Show Names and Use Display Names checkboxes control the display of names in the main output window. Object name labels for each object are displayed if Show Names is checked; the display names are used in place of the object name if Use Display Names is checked (see [“Naming Objects” on page 606](#)).
- The Show Comments checkbox of this dialog determines whether individual object comments are displayed (see [“Adding Comments” on page 606](#)).
- Show Table Titles controls whether to display the table objects using their own titles.

Note that the Show Borders, Show Names and Show Comments settings may be accessed directly from the spool object toolbar. For example, clicking on the Names +/- button is the same as checking or unchecking the corresponding box in the Spool Properties dialog.

The last option, Show Table Titles, requires some discussion. In EViews, table objects have titles which generally differ from the name given the table in the spool. When Show Table


Titles is checked (the default), the title of each table will be displayed. If we also turn on Show Names, we see that the object name in the spool is “untitled02” and the table title is “GDP”:



The screenshot shows a software window titled "Spool: UNTITLED" with a menu bar (View, Proc, Object, Properties, Print, Name, Freeze, 100%, Tree+/-, Borders+/-, Names+/-, Comment) and a toolbar. On the left, a tree view shows "untitled01", "untitled02" (selected), and "untitled03". The main area displays the content of "untitled02", which is a table titled "GDP". Above the table, it says "Last updated: 09/09/97 - 15:35" and "Display Name: gross domestic product". The table contains 16 rows of quarterly data.

GDP	
Last updated: 09/09/97 - 15:35	
Display Name: gross domestic product	
1952Q1	87.87500
1952Q2	88.12500
1952Q3	89.62500
1952Q4	92.87500
1953Q1	94.62500
1953Q2	95.55000
1953Q3	95.42500
1953Q4	94.17500
1954Q1	94.07500
1954Q2	94.20000
1954Q3	95.45000
1954Q4	97.36375
1955Q1	100.7250
1955Q2	102.8250
1955Q3	104.9250
1955Q4	106.6000

Next, we turn table titles off, which hides the “G DP” table title. Note here that the first line of the object display is now the update date:



The screenshot shows the same software window as before, but the table title "GDP" is no longer visible. The first line of the object display is now the update date "Last updated: 09/09/97 - 15:35". The table content remains the same.

Last updated: 09/09/97 - 15:35	
Display Name: gross domestic product	
1952Q1	87.87500
1952Q2	88.12500
1952Q3	89.62500
1952Q4	92.87500
1953Q1	94.62500
1953Q2	95.55000
1953Q3	95.42500
1953Q4	94.17500
1954Q1	94.07500
1954Q2	94.20000
1954Q3	95.45000
1954Q4	97.36375
1955Q1	100.7250
1955Q2	102.8250
1955Q3	104.9250
1955Q4	106.6000
1956Q1	107.2750

Names/Comments Font

Click on the Font button to bring up a dialog for setting the font size, color, and family for text in displayed names and comments.

Vertical Spacing

The Vertical Spacing edit field controls the amount of vertical space placed between output objects in the spool.

Margins

The Use Margins checkbox controls whether the spool will display the contents of the output window with vertical and horizontal margin padding. If you wish to provide spool margins, you should select this option and enter values for the size of the vertical and/or horizontal margins.

Note that this setting controls margins for the spool object itself. Margins for individual objects may be adjusted by selecting an object, right mouse clicking, and selecting Properties... (see ["Indenting Objects," on page 610](#)). Individual object margins are specified relative to the margins for the spool object.

Display Modes


When you bring an output object into a spool, EViews copies the original output object at its original size; we term this the native object size. Subsequent editing of the object in the spool may change this native size (see ["Editing Objects in a Spool" on page 616](#)).

The spool object allows you to display objects at sizes that differ from the native sizes. By separating the display size of the object in the spool from the native object size, EViews permits customizing the display of objects without requiring manual editing of the native size in each output object.

By default, EViews displays graph objects in a spool using a uniform width while table and text objects are displayed in using their native widths and font sizes. This default setting allows for a relatively uniform appearance for the objects in the spool.

You may alter the display settings for the spool to allow graphs and tables to be displayed at different sizes. Click on Proc/Display Modes... to bring up the Display Modes dialog.

The top portion of the dialog offers Graph Settings that control the display size of graph objects in the spool. The Mode combo box allows you to choose between various settings:



- The default **Fixed Width** setting fixes the spool display sizes for graphs at a uniform width, as specified in the **Width Limit (inches)** edit field.
- **Variable Width** displays the graphs at the native sizes, but permits individual customization as described in [“Resizing Objects” on page 609](#)
- **Variable Width w/ Limit** displays graph objects in their native widths so long as they do not exceed the specified limit, otherwise the display size is adjusted accordingly. You may customize the display sizes of individual objects.

The **Table/Text Settings** portion of the dialog provides similar control over tables and text objects (though **Fixed Width** is not available for tables). For table and text objects, the default is to use **Variable Width**, but you may use the combo to change the settings to **Variable Width with limit**. If a table or text object is resized, the font will be scaled accordingly.

You may, after performing individual display sizing ([“Resizing Objects” on page 609](#)) decide that you wish to revert to the original native sizes; selecting **Reset objects to native width**, and clicking on **OK** will set all of the objects in the spool to use their native sizes.


Editing Objects in a Spool

In most cases, you may customize an object in a spool. Changes to an output object in edit mode are equivalent to editing the object in its own window.

To make changes to the object you must first place the spool in edit mode. Simply double click on the object in either the tree or the output panes to put the spool in edit mode. Alternatively, you may select the object you wish to edit, right-click, and choose **Edit**.

When a spool is placed in edit mode, EViews will display the object being edited using the full width of the window. The toolbar will change to show the options for the edit object, instead of those for the spool object. In addition there be a new region, just below the toolbar, showing the object and display names for the edit object, as well as a **Close** button that saves any modifications, turns off edit mode, and returns you to the standard spool window.


For example, edit mode for a graph object will show the graph in the main display, along with options for customizing the graph. Here we see a spool in edit mode showing the toolbar for a graph object. Clicking on Options or double clicking on the graph brings up the standard Graph Options menu allowing you to perform extensive customization of the graph. Similarly, the Proc menu and toolbar buttons may be used to add text, line shading, or to apply template options (see “Graph Options,” on page 567).



Similarly, editing a table in the spool allows you to perform extensive customization of the table. If a table is placed in edit mode, you will be able to perform all of the standard table editing operations, including row and column resizing, setting font sizes and styles, formatting cells, adding borders, titles, or comments, or simply changing the contents of a cell (see “Basic Customization,” on page 592 and “Table Cell Customization,” on page 593).

	A	B	C	D	E
1	Wald Test:				
2	Equation: EQ01				
3					
4	Test Statistic	Value	df	Probability	
5					
6	t-statistic	40.75850	159	0.0000	
7	F-statistic	1661.255	(1, 159)	0.0000	
8	Chi-square	1661.255	1	0.0000	
9					
10					
11	Null Hypothesis Summary:				
12					
13	Normalized Restriction (= 0)	Value	Std. Err.		
14					
15	C(1)	1.312383	0.032199		
16					
17	Restrictions are linear in coefficients.				
18					
19					
20					

One important case of object editing involves editing an embedded spool object. When you double click on an embedded spool object or select it, right-click, and choose Edit, EViews changes the spool display to show the embedded spool in edit mode:



Edit mode for the embedded spool is visually similar to standard mode for an arbitrary spool. There are only two visual cues that we are in edit mode in a parent object. First, just below the toolbar is the standard edit mode line containing the Close button and the description of the object name. Second, the icons for the objects B1 and UNTITLED01 are now grayed-out in the tree window, indicating that they may not be selected.

Indeed, working with an embedded spool object in edit mode is identical to working with a spool object in standard mode; you may perform all of the operations in this chapter using the embedded spool and its elements. Clicking on the Properties button brings up the Spool Properties dialog which allows you to set display options for the selected spool. You may, for example, use the properties dialog to increase the vertical spacing or to display table titles for objects within the embedded spool. Since we are editing the embedded spool, changes in the spool in edit mode have no impact on the objects and settings in the parent spool. (See also ["Embedded Spools,"](#) on page 604.


Once you are done editing your object, you should click on the Close button to save all of your object changes and to return to the standard display mode.

Printing a Spool

To print the spool object, simply click on the **Print** button on the toolbar or select **File/Print...** from the main EViews menu to display the **Print** dialog.

The top section of the **Print** dialog may be used to select a printer and print options, or to redirect the print job to an RTF file, text file, table object, text file, or spool object (see [“Print Setup” on page 637](#)).

The remainder of the dialog offers various printing options specific to spool objects.



Print Mode

You may use the **Print mode** combo to specify where page breaks are to be used in your print job. There are three possible modes (**Print to fit**, **Continuous**, and **Individual**). If you select **Print to fit**, objects will not, unless larger than a page, be split across pages. In **Continuous** mode, objects in the spool will be printed successively and page breaks will occur when the bottom of a page has been reached. **Individual** mode prints the spool with a page break after every object. Note that whatever the print mode setting, graph objects are never split across pages.

If the spool contains embedded (child) spools, you will be provided with an additional option for whether to treat the embedded spool as a single output object or to treat it as a set of individual objects. In practical terms, this choice is equivalent to deciding between printing the contents of embedded spools in continuous mode (single object) or printing the objects in the spool using the selected print mode (multiple objects). To employ the latter method, you should check the box labeled **Apply print mode to child spools**.

To demonstrate the effects of selecting this option, assume we have a parent spool containing a table and an embedded spool which contains two graph objects. Suppose that we set the **Print mode** to **Individual**, and check the **Apply print mode to child spools** option. The resulting print job will generate three pages of output: a page for the table, and one for each of the individual graphs. Unchecking the option would (if the graphs both fit on a single page), generate two pages of output: one for the table, and a second for both graphs.

Size and Position

You may use the Spool size combo to specify a custom size for printing. For example, selecting Custom and entering 80 in the Percent edit field will scale the contents of the spool to 80% of the full size prior to printing.

You may use the Child size to determine the relative size of child objects. Selecting Native Dimensions prints the objects in the spool at their native sizes so that they will appear as they would if printed individually, outside of the spool. If instead you select Screen proportional, EViews will print the objects in the spool in the same proportions as the spool display window. All sizing customization in the spool will be used.

The positions of objects on the page is controlled using the Justification combo. Choosing Left or Center will force all objects to print on the left side or the center of the page. Center graphs only will left-justify table and text objects, and center graph objects.

Labeling

You may use the Object Labels section of the dialog to control whether to print titles and comments in the spool. Selecting the respective checkbox check will print the additional information along with the output object. These settings are especially useful if you turn on the titles and comments in the spool display, but do not wish to include them in your printed output, or vice versa.


Saving a Spool

You may save the contents of a spool object to disk. Click on Proc/Save spool to disk... to display the save dialog.

The File Type combo box may be used to change between saving a Text file (*.txt) or a Rich Text Format RTF file (*.rtf). Note that if you specify a text file, any graphs in the spool will not be written to the file.

In the top portion of the dialog, you may provide the name of the file you wish to create. EViews will automatically append an extension of the proper type to the name and will prepend the default path if an explicit path is not provided.

The Object labels section of dialog may be used to specify whether the titles and comments should be written to the output file. By default, neither titles nor comments are saved in the output file.



Appendix A. Global Options

EViews employs user-specified default settings in many operations. You may, for example, set defaults for everything from how to perform frequency conversion between workfile pages of different frequency, to which font to use in table output, to line color and thickness in graphs, to how to compute derivatives in nonlinear estimation routines.

These default options may, of course, be overridden when actually performing an operation. For example, you may have specified a default conversion of data from monthly to quarterly data by averaging observations, but may choose to use summing when performing a specific conversion. Similarly, you may instruct EViews to use the color red for the first line in newly created graphs, and then change the color in a specific graph.

The Options Menu

The Options menu in the main toolbar allows you to define the default behavior for many of the operations in EViews. Most options are found within the General Options... and Graphics Defaults... menu items.


General Options

When you click the General Options... menu item, EViews brings up the Global Options dialog. This dialog is broken up into many sections which are accessible using the tree on the left-hand side of the dialog. We discuss briefly the options within each of these sections. In some cases, additional detail is provided in the corresponding sections of the manual.

Window Appearance

EViews provides a number of color themes to modify the appearance of your EViews environment.

In the Window colors groupbox, you may select from a variety of basic themes, including Light Blue, Silver, and EViews Classic. You can let the background and status bar follow this color theme, or choose a different color from the Background & status bar dropdown.




Not surprisingly, the Caption bar & borders combo may be used to choose the visual style of your caption bar and borders. The Default setting is for EViews to draw the caption bars and borders using colors to match the current theme in a style to match your operating system (either Windows XP or Windows Vista/Windows 7). You may instead choose EViews rounded or Vista style to have EViews choose a style independent of your operating system. If you have modified your operating system settings for window borders and text, and wish to have the operating system draw the caption and borders you should select Operating system drawn.

Most windows in EViews have a row of buttons along the top, called the button bar. To hide these buttons on all windows, uncheck Display button bars on the top right of the dialog.

Window Behavior

The Window behavior page controls the display characteristics of various types of EViews output.



The settings are divided into broad groupings:

- The Warn On Close section in the upper left-hand corner of the dialog instructs EViews to provide a warning message when you close an untitled object. You may choose to set warnings for various object types. By default, EViews warns you that closing an unnamed object without naming it will cause the object to be deleted. Along with the warning, you will be given an opportunity to name the object. If you turn the warning off, closing an untitled window will automatically delete the object.
- Allow Only One Untitled specifies, for each object type, whether to allow multiple untitled objects to be opened at the same time. If only one is allowed, creating a new untitled object will cause any existing untitled object of that type to be deleted automatically. Setting EViews to allow only one untitled object reduces the number of windows that you will see on your desktop.


If you elect to allow only one untitled object, we strongly recommend that you select Warn on Close. With this option set, you will be given the opportunity to name and save an existing untitled object, otherwise the object will simply be deleted.

- Keyboard Focus controls where the keyboard cursor is placed when you change views or windows. As the label suggests, when you select Command Window, the keyboard focus will go to the command window following a change of view. This setting is most useful if you primarily use EViews via the command line. Choosing Active Window will cause the focus to go to the active window following a change of view. You will find this setting useful if you wish to use keystrokes to navigate between and to select items in various windows. Note that whatever the default setting, you may always change the keyboard focus by clicking in the command window, or by clicking in the active window.

- **File open on double click** controls the whether to use an existing EViews session or or to launch an additional session when opening an EViews associated file. Selecting **Open in existing EViews session (when possible)** means that when using Windows to open an EViews file, say by double clicking, selecting an EViews file from the start menu, or opening as an email attachment, the file will open in an already running copy of EViews, if available.

Fonts


The Fonts section allows you to change the default font styles and sizes for various sets of windows and objects. Select the type of object for which you want to change the font from the dropdown at the top of the dialog and modify the font settings below. For example, to set the default font face and size to be used in table objects and table views of objects, select **Spreadsheets & Table defaults** and modify the settings below the dropdown.



Frequency Conversion

The Frequency conversion dialog within the **Series and Alphas** section allows you to set the default frequency conversion methods for both up and down conversion, and the default method of displaying dates.

The default frequency conversion method tells EViews how to convert data when you move data to lower or higher frequency workfiles. The frequency conversion methods and use of default settings are discussed in detail in [“Reading EViews Data using Other Applications,”](#) beginning on page 112



Series Auto Labels

You may elect to have EViews keep a history of the commands that created or modified a series as part of the series label. You can choose to turn this option on or off in the History in labels dialog within the Series and Alphas section.


Note that the series label may be viewed by selecting View/Label in a series window, or at the top of a series spreadsheet if the spreadsheet defaults are set to display labels ([Spreadsheet Layout](#) on page 626).

Alpha Truncation

Note that EViews alpha series automatically resize as needed, up to the truncation length.

To modify the alpha series truncation length, select Alpha Truncation from the Series and Alphas section, and enter the desired length. Subsequent alpha series creation and assignment will use the new truncation length.

You should bear in mind that the strings in EViews alpha series are of fixed length, so that the size of each observation is equal to the length of the longest string. If you have a series with all short strings, with the exception of one very long string, the memory taken up by the series will be the number of observations times the longest string size.




The maximum string length is 1,000 characters.

Spreadsheet Layout

The options in the Layout dialog within the Spreadsheets section control the default spreadsheet view settings of series, group, and table objects. The defaults are set using these option settings when the object is first created.

In the Series spreadsheets portion of the dialog, you may set the display format and choose to display the spreadsheet in one or multiple columns, with or without object labels and header information. In addition, you may choose to have edit mode turned on or off by default.



Below this section are the Group spreadsheet options for sample filtering, transposed display, and edit mode.


Frozen tables allows you to modify whether edit mode is on or off by default.

You may set the Spreadsheet display order to ascending or descending from the drop-down in the upper-right corner of the dialog.

Spreadsheet Data Display

The Data display dialog within the Spreadsheets section provides other default spreadsheet options.

On the top portion of the dialog are display settings that apply to all numeric and text spreadsheet displays. You may specify the default Numeric display to be used by new objects. The settings allow you to alter the numeric formatting of cells, the number of digits to be displayed, as well as the characters used as separators and indicators for negative numbers. Similarly, you may choose the default Text justification and Indentation for alphanumeric display.




We emphasize the fact that these display options only apply to newly created series or group objects. If you subsequently alter the defaults, existing objects will continue to use their own settings.

Workfile Storage Defaults

The Workfile Save dialog in the Data storage section allows you to specify storage precision and compression options for your saved workfiles, and to specify whether or not to create backup workfiles when overwriting existing files on disk.

The Series storage portion of the dialog controls whether series data are stored in saved workfiles in single or double precision. Note that workfiles saved in single precision will be converted to double precision when they are loaded into memory.



In addition, you may elect to save your workfiles in compressed format on disk by checking the Use compression setting. Note that compressed files are not readable by versions of EViews prior to 5.0, and that they do not save memory when using the workfile, as it is uncompressed when loaded into memory. Compressed workfiles do, however, save disk space.


You should uncheck the Prompt on each Save checkbox to suppress the workfile save dialog on each workfile save.

In addition, you may specify whether EViews should keep backup copies of workfiles when saving over an existing file. If selected, the automatic backup copy will have the same name as the file, but with the first character in the extension changed to “~”.

Database Storage Defaults

You may also control the default behavior of EViews when moving data into and out of databases using the Database Store and Database Fetch dialogs within the Data storage section. These dialogs control the behavior of group store and fetch (see [“Storing a Group Object”](#)


and [“Fetching a Group Object”](#) on page 279), and whether data are stored to databases in single or double precision.



Date Representation

The Date representation dialog controls the format for dates in sample processing, and in workfile and various object views. For daily and weekly data, you can set the default to American (Month/Day/Year) or you may switch to European notation (Day/Month/ Year), where the

day precedes the month. You may also specify your quarterly or monthly date display to use the Colon delimiter or a Frequency delimiter character based on the workfile frequency (“q” or “m”). The latter has the advantage of displaying dates using an informative delimiter (“1990q1” vs. “1990:1”).




See also [“Free-format Conversion Details” on page 102](#) in the Command and Programming Reference for related discussion.

Estimation Defaults

You can set the global defaults for the maximum number of iterations, convergence criterion, and methods for computing derivatives in the Estimation options dialog.

These settings will be used as the default settings in iterative estimation methods for




equation, log likelihood, state space, and system objects. Note that previously estimated EViews objects that were estimated with the previous default settings will be unchanged, unless reestimated. See [“Setting Estimation Options” on page 751](#) for additional details.

When the Display settings option is checked, EViews will produce additional output in the estimation output describing the settings under which estimation was performed.

Programs

The first page of the Programs section provides some general options for running EViews programs. You can stop a program from running after exceeding a specified number of errors by entering the error count in Maximum allowable errors before halting.



You may also use this dialog to specify whether EViews should keep backup copies of program files when saving over an existing file. The backup copy will have the same name as the file, but with the first character in the extension changed to “~”.


If the checkbox labeled Version 4 compatible variable substitution is selected, EViews will use the variable substitution behavior found in EViews 4 and earlier versions. EViews 5 changed the way that substitution variables are evaluated in expressions. You may use this checkbox to use Version 4 substitution rules. See [“Version 4 Compatibility Notes” on page 119](#) for additional discussion.

In addition, you may modify the Display Settings to change the display of text and editing behavior in program files.

If Use syntax coloring is selected, basic programming keywords, strings, and comments will be displayed in color. You may also Enable word wrap in programs.

The two controls on the right-hand side control auto-indenting and tab size settings. The Tab size (in spaces) edit box lets you set how many characters a tab will use in the program editor. The Indent combo lets you specify the type of automatic indenting that the program editor will use. Auto on means that EViews will attempt to automatically apply a single tab for lines of code that are inside a program statement (“For/Next”, “If/Endif”, “While/Wend”), or inside a subroutine. Note that the single tab will be applied on top of any tabbing that was already in place. Auto on w/completion means that EViews will apply automatic indenting, and will also automatically close any program statement. For example EViews will automatically add “Next” to the start of the next line when you finish a line starting with “For”. Auto off means no automatic indenting will be employed.

The Runtime settings dialog in the Programs section specifies whether, by default, EViews runs programs in Verbose mode, listing commands in the status line as they are executed, or whether it uses Quiet mode, which suppresses this information. EViews will run faster in quiet mode since the status line display does not need to be updated.




This default may always be overridden from the Run Program dialog, or by using the option “q” in the run statement, as in:

```
run(q) myprogram
```

For details, see “Executing a Program,” beginning on page 107 of the Command and Programming Reference

External Program Interface

The External program interface entry allows you to specify the default case to use when creating destination objects in MATLAB or R using the xput command. The defaults may be overridden by specifying the “case=lower” or “case=upper” option in the



xopen command or by specifying an explicit destination name using the “name=” option in the xput command.

You may also use the COM ProgID section of the dialog to specify the default Programmatic IDs (ProgIDs) used when instantiating a MATLAB or R COM server. The ProgID is used to indicate the version of MATLAB or statconnDCOM to which EViews connects when you issue an xopen command. Each combo will contain values found in the Windows registry on your system that were entered when you installed MATLAB and statconnDCOM. You may choose from entries in the combos, or type in a specific ProgID for EViews to use when opening a MATLAB or R session. The default settings may be overridden by specifying “progid=” in the xopen command.

For details on these settings see [xopen](#) (p. 383) and [xput](#) (p. 385) in the Command and Programming Reference or the whitepapers [Using EViews COM Automation Client for MATLAB](#) and [Using EViews COM Automation Client for R](#).


Network Proxy Server

Some EViews features (such as automatic update, registration) require internet access. If internet access is only available on your network via a proxy server, you may provide EViews with your proxy server settings.

Simply click on Network proxy server to display the relevant dialog and enter your settings. Note that valid proxy server setting values generally take the form:

servername:8080

where servername represents the name (or IP address) of the proxy server and 8080 is replaced by the actual port number to be employed.




If Microsoft Internet Explorer has previously setup properly with a proxy server on the current machine, you can click the Auto detect from IE button to import the current settings into EViews.

File Locations

This selection allows you to set the default working directory, and the locations of the .INI file, database registry and alias map, and the temp directory.


The dialog also reports, but does not allow you to alter, the location of your EViews executable.



Note that the default working directory may also be changed via the File Open and File Save or File Save As dialogs, or by using the `cd` command.

Advanced System Options

You may use the Advanced system options dialog to set memory allocation and expression evaluation options. Unless there is a specific reason for changing settings, we strongly recommend that you use the default EViews settings



Memory Allocation

The top portion of the dialog allows you to adjust the EViews memory allocation settings.

By default, EViews allows a maximum of 4 million observations per series. You may use the combo box to increase or decrease this limit.

The total memory available for all EViews objects is limited by the maximum address space per application. Standard Windows XP systems allow for 2GB of address space, but may be configured to use 3GB (using the /3GB switch). Windows XP x64 systems allow for 4GB of address space per application. Note that if the amount of physical memory available is less than the address space in use, available disk space will be used as virtual memory, which will significantly degrade performance.

EViews reserves a portion of this address space for auxiliary purposes. This memory is used by the operating system, DLLs, external database drivers, and by EViews when creating objects. Reducing the size of the reserved space will increase the amount of address space available for holding observations, but will decrease the total number of objects allowed in EViews, and may lead to instability caused by out-of-memory conditions.

By default, EViews increases the speed of evaluation by first compiling expressions to machine code. The pre-compiled code executes more rapidly, but the compilation procedure and evaluation requires additional memory. You may uncheck this setting to use the slower, memory efficient method of evaluation.

Multi-Processor Use


The Multi-processor/Multi-core use section may be used to define the maximum number of threads you would like to allow EViews to use when processing statistical calculations. EViews treats processors and cores symmetrically, and does not include hyper-threaded processors. In general, we recommend leaving this setting at Auto.

When set to Auto, EViews detects the number of cores in your system and attempts to use all of them. You may override this setting for up to eight threads. This allows you to increase the number of threads EViews uses to beyond the physical number of cores. We have not found this to be effective, but, in principle, it could improve performance with hyper-threading. If you require more processing power for other applications, you may wish to limit the number of threads EViews uses by setting this number below the physical number of cores. This is guaranteed to work with Intel processors, and, to our knowledge, should work with other brands of processors as well.

You may click on the Reset to EViews Defaults button to return to the default settings.

Graphics Defaults

These options control how a graph appears when it is first created. The great majority of these options are explained in considerable detail in [“Graph Options,” beginning on page 567](#).



Additional dialog pages are provided for specifying the default settings for use when saving graphs to file (Exporting) and for handling sample breaks, missing values, and panel data structures (Samples & Panel Data).

Default settings for color and background transparency may be set in the Frame & Size/ Color & Border entry of the Graph Options dialog.

The Quick fonts section lets you set multiple graph font settings all at once. You can change the font face, style and size for all axes, legends text objects and observation labels in a single step.

See [“Basic Customization,” beginning on page 459](#) and [Chapter 15. “Graph Objects,” on page 557](#).

Database Registry

The Database Registry... settings are described in detail in [“The Database Registry” on page 281](#)

EViews Auto-Update from Web

QMS occasionally releases patches to the EViews program, and we strongly recommend that you keep your copy of EViews as up-to-date as possible.


EViews includes an automatic updating feature that can check for new updates every day, and install any update that may be available. The automatic update feature can be disabled from the Options/EViews Auto-Update from Web item in

your main EViews menu. You can also manually check for updates from within EViews at any time by selecting Check now... under the EViews Auto-Update from Web menu item, or by selecting EViews Update from the Help menu.

You may also check for updates to the EViews program or for updates to supplementary components such as the EViews documentation or sample data and programs, by visiting the Download section of the EViews website (www.eviews.com).

Print Setup

The Print Setup options (File/Print Setup... on the main menu) determine the default print behavior when you print an object view.




The top of the Print Setup dialog provides you with choices for the destination of printed output.

You may elect to send your output directly to the printer by selecting the **Printer** radio button. The drop down menu allows you to choose between the printer instances available on your computer, and the **Properties** button allows you to customize settings for the selected printer.

Alternatively, you may select **Redirect** so that EViews will redirect your output. There are three possible settings in the drop down menu: **RTF file**, **Text file (graphs print)**, **Frozen objects**, and **Spool object**:

- If you select **RTF file**, all of your subsequent print commands will be appended to the RTF file specified in **Filename** (the file will be created in the default path with an “.RTF” extension). You may use the **Clear File** button to empty the contents of the existing file.
- If you select **Text file (graphs print)**, all printed text output will be appended to the text file specified in **Filename** (the file will be created in the default path with a “.TXT” extension). Since graph output cannot be saved in text format, all printing involving graphs will still be sent to the printer. Spools will send all text and table output to the file, and will ignore all graph output.
- **Frozen objects** redirects print commands into newly created graph or table objects using the specified **Base Object name**. Each subsequent print command will create a new table or graph object in the current workfile, naming it using the base name and an identifying number. For example, if you supply the base name of “OUT”, the first print command will generate a table or graph named OUT01, the second print command will generate OUT02, and so on.
- Selecting **Spool object** sends subsequent print commands into a spool object in the workfile. Spool objects allow you to create collections of frozen object output (see [Chapter 17](#), “[Spool Objects](#),” on page 601 for details).



The screenshot shows a dialog box titled "Destination". It has two radio buttons: "Printer:" and "Redirect:". The "Printer:" button is selected, and the printer name "HP LaserJet 2200 on Ne00:" is shown in a dropdown menu next to it. There is a "Properties" button to the right of the printer name. The "Redirect:" button is also selected, and a dropdown menu next to it shows "RTF file". Below these, there is a "Filename:" label followed by a text box containing "c:\eviews\data\aa.rtf". To the right of the text box is a "Clear File" button.

The other portions of the **Print Setup** dialog set various default settings for spool, graph, and table printing.

The Graph defaults section has settings for printing in portrait or landscape mode, scaling the size of the graph, positioning the graph on the page, and choosing black and white or color printing. For example, the Orientation combo allows you print graphs in Portrait or Landscape orientation. Similarly, you may use the Graph size combo to scale all graphs by a fixed percentage when printing. Note that some graph settings are not relevant when redirecting output, so that portions of the dialog may be grayed out.

See ["Printing Graphs" on page 585](#) for details.

The Text/Table defaults allow you adjust settings for printing tables and text objects. You may use the Orientation combo allows you print graphs in Portrait or Landscape orientation, Similarly, you may use the Graph size combo to scale all text by a fixed percentage when printing. Some of these options are not available when redirecting output.

See ["Printing Tables" on page 597](#) for details.

The Spool defaults portion of the dialog includes settings specific to printing spool. You may use the Print mode combo and Apply print mode to child spools checkbox to specify where page breaks are to be used, the Object labels section to print or suppress titles and comments, or the Child size, Justification, and Size combos to size and position the output.

See ["Printing a Spool" on page 619](#) for details.

We remind the user that this dialog only specifies the default settings for printing. You may override any of these settings when printing a particular job using the Print dialog or the print command.

Index

(Key: I = User's Guide I; II = User's Guide II)

Symbols

.DB? files [I:272](#)
.EDB file [I:268](#)
.RTF file [I:597](#)
.WF1 file [I:54](#)
?
 pool cross section identifier [II:570](#)
@all [I:93](#)
@cellid [II:621](#)
@clear [I:158](#)
@count [I:151](#)
@crossid [II:620](#)
@elem [I:134](#)
@eqnq [I:140](#)
@expand [I:152](#), [II:28](#)
@first [I:93](#)
@firstmax [II:626](#)
@firstmin [II:626](#)
@ingrp [II:570](#)
@isna [I:140](#)
@last [I:93](#)
@lastmax [II:626](#)
@lastmin [II:626](#)
@map [I:179](#)
@neqna [I:140](#)
@obsid [II:622](#)
@obsnum
 panel observation numbering [II:622](#)
@ranks [I:138](#)
@seriesname [I:151](#)
@unmap [I:179](#)
@unmaptxt [I:180](#)
~, in backup file name [I:55](#), [I:631](#)

Numerics

1-step GMM
 single equation [I:71](#), [II:76](#)
2sls (Two-Stage Least Squares) [I:55](#), [II:62](#)

diagnostics [II:78](#)
dropped instruments [II:78](#)
in systems [II:421](#)
instrument orthogonality test [II:79](#)
instrument summary [II:78](#)
J-statistic [II:58](#)
nonlinear [II:62](#)
nonlinear with AR specification [II:63](#)
order condition [II:57](#)
panels [II:650](#)
rank condition [II:57](#)
regressor endogeneity test [II:79](#)
residuals [II:58](#)
system estimation [II:449](#)
weak instruments [II:80](#)
weighted in systems [II:421](#), [II:449](#)
weighted nonlinear [II:63](#), [II:74](#)
with AR specification [II:59](#), [II:91](#)
with MA specification [II:61](#)
with pooled data [II:609](#)
3sls (Three Stage Least Squares) [I:421](#), [II:450](#)

A

Abort key [I:10](#)
Across factors [I:543](#)
Active window [I:74](#)
Add factor [II:511](#), [II:524](#)
Add text to graph [I:563](#)
Adding data [I:241](#)
ADF
 See also [Junit root tests](#).
Adjusted R-squared
 for regression [II:13](#)
Advanced database query [I:285](#)
AIC [II:771](#)
 See also [Akaike criterion](#).
Akaike criterion [II:15](#), [II:771](#)
 for equation [II:15](#)
Alias [II:513](#)
 database [I:282](#)
 OBALIAS.INI file [I:293](#)
 object [I:291](#)
Almon lag [II:24](#)

- Alpha series [I:160](#)
 - additional views [I:166](#)
 - declaring and creating [I:160](#)
 - maximum length [I:161](#), [I:625](#)
 - spreadsheet view [I:166](#)
 - truncation [I:161](#), [I:625](#)
- Analysis of variance [I:325](#)
 - by ranks [I:327](#)
- Analytical derivatives [II:767](#)
 - logl [II:360](#)
- Analytical graphs [I:493](#)
- And operator [I:94](#), [I:134](#)
- Anderson-Darling test [I:330](#)
- Andrew's automatic bandwidth [II:780](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - system GMM [II:452](#)
- Andrews test [II:258](#), [II:298](#)
- Andrews-Quandt breakpoint test [II:172](#)
- ANOVA [I:325](#)
 - by ranks [I:327](#)
- Appending data [I:241](#)
- AR Roots (VAR) [II:462](#)
- AR specification
 - estimation [II:89](#)
 - forecast [II:126](#)
 - in 2SLS [II:59](#)
 - in ARIMA models [II:93](#)
 - in nonlinear 2SLS [II:63](#)
 - in nonlinear least squares [II:44](#)
 - in pool [II:588](#)
 - in systems [II:424](#)
 - terms [II:97](#)
- AR(1)
 - coefficient [II:86](#)
 - Durbin-Watson statistic [II:86](#)
 - estimation [II:90](#)
- AR(p) [II:86](#)
 - estimation [II:90](#)
- ARCH [II:195](#)
 - See also GARCH.
 - correlogram test [II:158](#)
 - LM test [II:162](#)
 - multivariate [II:422](#)
 - system [II:422](#)
- ARCH test [II:162](#)
- ARCH-M [II:197](#)
- Area band graph [I:483](#)
- Area graph [I:481](#)
- AREMOS data [I:304](#)
- ARIMA models [II:93](#)
 - Box-Jenkins approach [II:94](#)
 - correlogram [II:106](#)
 - diagnostic checking [II:104](#)
 - difference operator [II:95](#)
 - frequency spectrum [II:108](#)
 - identification [II:94](#)
 - impulse response [II:107](#)
 - roots [II:105](#)
 - specification [II:95](#)
 - starting values [II:101](#)
 - structure [II:104](#)
- ARMA terms [II:97](#)
 - in models [II:546](#)
 - seasonal [II:97](#)
 - testing [II:159](#)
 - using state spaces models for [I:496](#)
- ARMAX [II:496](#)
- Artificial regression [II:163](#), [II:188](#)
- ASCII file
 - export [I:112](#)
 - import [I:108](#), [I:129](#)
 - open as workfile [I:40](#)
- Asymptotic test [II:139](#)
- Augmented Dickey-Fuller test [II:384](#)
 - See also Unit root tests.
- Augmented regression [II:176](#)
- Auto tab indent [I:631](#)
- Autocorrelation [I:334](#), [II:14](#)
 - robust standard errors [II:32](#)
- Autocorrelation test
 - VAR [II:464](#)
- Automatic bandwidth selection
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:779](#)
- Automatic variable selection [II:46](#)
- Autoregressive spectral density estimator [II:389](#)
- Auto-search
 - database [I:283](#)
- Auto-series [I:145](#)

- forecasting [II:131](#)
- generate new series [I:145](#), [I:280](#)
- in estimation [I:149](#)
- in groups [I:149](#)
- in regression [I:280](#)
- with database [I:279](#)
- Auto-updating graph [I:558](#)
- Auto-updating series [I:155](#)
 - and databases [I:158](#)
 - converting to ordinary series [I:158](#)
- Auxiliary graphs [I:512](#)
- Auxiliary regression [II:159](#), [II:162](#)
- Average log likelihood [II:252](#)
- Average shifted histogram [I:498](#)
- Axis [I:462](#)
 - assignment [I:463](#)
 - characteristics [I:465](#), [I:468](#)
 - custom obs labels [I:572](#)
 - data ticks and lines [I:466](#)
 - date labels [I:472](#)
 - date ticks [I:472](#)
 - duplicating [I:467](#)
 - format [I:467](#)
 - labels [I:465](#), [I:466](#), [I:467](#)
 - remove custom date labels [I:574](#)
 - scale [I:468](#)
- B**
- Backcast
 - in GARCH models [II:201](#)
 - MA terms [II:102](#)
- Backup files [I:54](#), [I:631](#)
- Balanced data [II:576](#)
- Balanced sample [II:587](#)
- Band-Pass filter [I:371](#)
- Bandwidth
 - Andrews [II:452](#), [II:780](#)
 - automatic selection See Automatic bandwidth selection
 - bracketing [I:501](#), [I:517](#), [I:518](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - kernel - technical details [II:778](#)
 - kernel graph [I:501](#), [I:516](#)
 - local regression [I:518](#)
 - long-run covariance estimation [I:425](#)
 - Newey-West (automatic) [II:453](#), [II:781](#)
 - Newey-West (fixed) [II:452](#)
 - robust standard errors [II:34](#)
 - selection in system GMM [II:429](#), [II:452](#)
- Bar graph [I:481](#)
- Bartlett kernel [II:452](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:777](#)
- Bartlett test [I:329](#)
- Baxter-King band-pass filter [I:371](#)
- BDS test [I:337](#), [II:411](#)
- Bekker standard errors [II:65](#)
- Berndt-Hall-Hausman (BHHH). See Optimization algorithms.
- Bias proportion [II:122](#)
- BIC [II:771](#)
 - See also Schwarz criterion.
- Bin width
 - histograms [I:494](#)
 - See also Binning
- Binary dependent variable [II:247](#)
 - categorical regressors stats [II:255](#)
 - error messages [II:254](#)
 - estimation [II:249](#)
 - estimation statistics [II:252](#)
 - expectation-prediction table [II:256](#)
 - fitted index [II:261](#)
 - forecasting [II:261](#)
 - goodness-of-fit [II:258](#)
 - interpretation of coefficient [II:251](#)
 - log likelihood [II:248](#)
 - predicted probabilities [II:262](#)
 - residuals [II:261](#)
 - response curve [II:262](#)
 - views [II:255](#)
- Binary estimation
 - dependent variable frequencies [II:255](#)
 - perfect predictor [II:254](#)
- Binary file [I:40](#)
- Binning [I:501](#), [I:515](#), [I:517](#)
 - categorical graphs [I:541](#)
 - classifications [I:319](#), [I:404](#)
- Binomial sign test [I:323](#)
- Blom [I:504](#)
- BMP [I:586](#)

- Bohman kernel
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:777](#)
- Bonferroni [I:398](#)
- Bootstrap [I:344](#)
- Box-Cox transformation [I:513](#)
- Box-Jenkins [II:94](#)
- Boxplot [I:509](#)
 - as axis [I:443](#)
- Break [I:10](#)
- Breakpoint test
 - Chow [II:170](#)
 - factor [II:155](#)
 - GMM [II:82](#)
 - Quandt-Andrews [II:172](#)
 - unequal variance [II:186](#)
 - unknown [II:172](#)
- Breitung [II:397](#)
- Breusch-Godfrey test [II:87](#) , [II:159](#)
- Breusch-Pagan test [II:161](#)
- Brown-Forsythe test [I:329](#)
- Broyden's method [II:552](#) , [II:760](#)
- By-group statistics [I:318](#) , [II:627](#) , [II:635](#)
- C
- C
- coef vector [II:6](#)
- constant in regression [II:6](#)
- Cache [I:308](#)
- Cancel
 - keystroke [I:10](#)
- Canonical cointegrating regression [II:221](#) , [II:228](#)
- Categorical graphs [I:523](#)
 - See also [Graphs](#).
 - analytical [I:532](#)
 - binning [I:541](#)
 - category summaries [I:524](#)
 - descriptive statistics [I:524](#)
 - factor display settings [I:543](#)
 - factor labeling [I:552](#)
 - factor ordering [I:544](#)
 - factors [I:540](#)
 - identifying categories [I:535](#)
 - line [I:528](#)
 - specifying factors [I:540](#)
 - summaries [I:524](#)
- Categorical regressor statistics [I:255](#) , [II:278](#)
- Causality
 - Granger's test [I:429](#)
- Cell
 - annotation [I:595](#)
 - formatting [I:593](#)
 - merging [I:595](#)
 - selection [I:589](#)
- Censored dependent variable [II:273](#)
 - estimation [II:274](#)
 - expected dependent variable [II:279](#)
 - fitted index [II:279](#)
 - forecasting [II:279](#)
 - goodness-of-fit tests [II:280](#)
 - interpretation of coefficient [II:278](#)
 - log likelihood [II:274](#)
 - residuals [II:278](#)
 - scale factor [II:278](#)
 - specifying the censoring point [II:275](#)
 - views [II:278](#)
- Census X11
 - historical [I:358](#)
 - limitations [I:358](#)
 - using X12 [I:351](#)
- Census X12 [I:349](#)
 - seasonal adjustment options [I:350](#)
- CGARCH [II:211](#)
- Change default directory [I:66](#)
- Chi-square
 - independence test in tabulation [I:406](#)
 - statistic for Wald test [II:148](#)
 - test for independence in n-way table [I:407](#)
 - test for the median [I:327](#)
- Cholesky factor
 - in VAR impulse responses [II:469](#)
 - in VAR normality test [II:465](#)
- Chow test
 - breakpoint [II:170](#)
 - forecast [II:174](#)
 - n-step forecast [II:180](#)
 - one-step forecast [II:180](#)
- Christiano-Fitzgerald band-pass filter [I:371](#)
- Classification
 - from series [I:339](#)

- Classification table
 - binary models [II:256](#)
 - ordered models [II:270](#)
 - sensitivity [II:257](#)
 - specificity [II:257](#)
- Cleveland subsampling [I:520](#)
- Clipboard [I:586](#)
- Close
 - EViews [I:10](#)
 - object [I:623](#)
- Clustering
 - by cross-section [II:608](#), [II:611](#), [II:612](#)
 - by period [II:607](#), [II:611](#), [II:612](#)
- Cochrane-Orcutt [II:60](#), [II:92](#)
- Coef (coefficient vector)
 - default [II:6](#)
 - update from equation [II:19](#)
- Coefficient
 - common (pool) [II:588](#)
 - covariance matrix [II:17](#)
 - covariance matrix of estimates [II:18](#)
 - cross-section specific (pool) [II:588](#)
 - diagnostics [II:140](#)
 - elasticity at means [II:140](#)
 - estimated from regression [II:11](#)
 - maximum number in default [II:270](#)
 - recursive estimates [II:181](#)
 - regression [II:11](#)
 - restrictions [II:8](#)
 - scaled [II:140](#)
 - setting initial values [II:43](#), [II:751](#)
 - standard error [II:12](#)
 - standardized [II:140](#)
 - tests [II:140](#), [II:146](#)
 - variance decomposition [II:144](#)
 - vectors of [II:20](#)
- Coefficient restrictions [II:369](#)
 - cross-equation [II:424](#)
- Coefficient uncertainty [II:531](#), [II:540](#), [II:550](#)
- Cointegrating regression [II:219](#)
 - equation specification [II:222](#)
- Cointegration [II:685](#)
 - Hansen instability test [II:239](#)
 - panel [II:640](#), [II:698](#)
 - Park added variable test [II:242](#)
 - pooled data [II:582](#)
 - regression [II:219](#)
 - residual tests [II:234](#), [II:694](#)
 - restrictions [II:481](#), [II:692](#)
 - test [II:234](#), [II:694](#)
 - test critical values [II:688](#), [II:703](#)
 - VAR [II:685](#)
- Collinearity [II:23](#)
 - coefficient variance decomposition [II:144](#)
 - test of [II:143](#), [II:144](#)
 - variance inflation factors [II:143](#)
- Color
 - EViews application [I:621](#)
 - graph frame [I:460](#)
 - printing in [I:585](#)
 - tables [I:594](#)
- Column width [I:592](#)
- Command window [I:7](#)
 - history of [I:8](#)
- Commands
 - history of [I:8](#)
- Comments [I:76](#)
 - spool [I:606](#)
 - tables [I:595](#)
- Common sample [I:139](#)
- Communalities [II:710](#)
- Comparison operators
 - with missing values [I:139](#)
- Comparisons [I:134](#)
- Component GARCH [II:211](#)
- Component plots [I:414](#)
- Conditional independence [I:407](#)
- Conditional standard deviation
 - display graph of [II:205](#)
- Conditional variance [II:193](#), [II:195](#), [II:196](#)
 - forecast [II:206](#)
 - in the mean equation [II:197](#)
 - make series from ARCH [II:207](#)
- Confidence ellipses [I:521](#), [II:140](#)
- Confidence interval [II:140](#)
 - ellipses [II:140](#)
 - for forecast [II:120](#)
 - for stochastic model solution [II:548](#)
- Constant
 - in equation [II:6](#), [II:12](#)
 - in ordered models [II:268](#)
- Contingency coefficient [I:407](#)
- Continuously updating GMM
 - single equation [II:71](#), [II:76](#)

- Contracting data [I:244](#)
- Convergence criterion [II:753](#) , [II:763](#)
 - default setting [I:630](#)
 - in nonlinear least squares [II:43](#) , [II:46](#)
 - in pool estimation [II:591](#)
- Convert
 - panel to pool [I:251](#)
 - pool to panel [I:257](#)
- Copy [I:244](#)
 - and paste [I:77](#) , [I:597](#)
 - by link [I:245](#)
 - by value [I:246](#)
 - command [I:117](#)
 - data [I:110](#)
 - data cut-and-paste [I:103](#)
 - database [I:293](#)
 - graph [I:586](#)
 - objects [I:77](#)
 - pool objects [II:568](#)
 - table to clipboard [I:597](#)
 - to and from database [I:275](#)
 - to spool [I:603](#)
- Correlogram [I:333](#) , [I:336](#) , [II:87](#)
 - ARMA models [II:106](#)
 - autocorrelation function [I:334](#)
 - cross [I:422](#)
 - partial autocorrelation function [I:335](#)
 - Q-statistic [I:335](#)
 - squared residuals [II:158](#) , [II:205](#)
 - VAR [II:464](#)
- Count models [II:287](#)
 - estimation [II:287](#)
 - forecasting [II:291](#)
 - negative binomial (ML) [II:289](#)
 - Poisson [II:288](#)
 - QML [II:289](#)
 - residuals [II:291](#)
- Covariance
 - matrix, of estimated coefficients [II:17](#)
 - matrix, systems [II:434](#)
- Covariance analysis [I:392](#)
 - details [I:399](#)
- Covariance proportion [II:122](#)
- Cragg-Donald [II:80](#)
- Cramer's V [I:407](#)
- Cramer-von Mises test [I:330](#)
- Create
 - database [I:269](#)
 - dated data table [I:384](#)
 - factor [II:706](#)
 - graph [I:557](#)
 - group [I:89](#) , [I:150](#)
 - link [I:197](#)
 - objects [I:71](#)
 - page [I:57](#)
 - series [I:82](#) , [I:141](#)
 - spool [I:601](#)
 - table [I:589](#)
 - text object [I:598](#)
 - workfile [I:34](#)
- Cross correlation [I:422](#)
- Cross correlogram [I:422](#)
- Cross section
 - pool identifiers [II:567](#)
 - specific series [II:569](#)
 - summaries [II:629](#)
 - SUR [II:607](#)
- Cross-equation
 - coefficient restriction [II:420](#) , [II:424](#)
 - correlation [II:421](#) , [II:422](#)
 - weighting [II:420](#)
- CSVI [I:598](#)
- C-test [II:79](#)
- Cubic
 - frequency conversion method [I:118](#)
- CUE (continuously updating GMM) See Continuously updating GMM
- Cumulative distribution [I:504](#)
 - computation [I:504](#)
- Cumulative statistics
 - functions [I:137](#)
- Customization
 - graphs [I:459](#)
- CUSUM
 - sum of recursive residuals test [II:178](#)
 - sum of recursive squared residuals test [II:179](#)
- D
- Daniell kernel
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:777](#)

Data

- appending more [I:241](#)
- cut and paste [I:105](#), [I:110](#)
- enter from keyboard [I:101](#)
- export [I:110](#), [I:111](#)
- Federal Reserve Economic data [I:303](#)
- FRED [I:303](#)
- import [I:105](#)
- irregular [I:213](#)
- keyboard entry [I:103](#)
- pool [II:572](#)
- regular [I:213](#)
- remove [I:244](#)
- structure [I:213](#)

Database

- alias [I:282](#)
- auto-search [I:283](#)
- auto-series [I:281](#)
- cache [I:308](#)
- copy [I:293](#)
- copy objects [I:275](#)
- create [I:269](#)
- data storage precision [I:629](#)
- default [I:272](#)
- default in search order [I:283](#)
- delete [I:293](#)
- delete objects [I:277](#)
- display all objects [I:270](#)
- export [I:275](#)
- fetch objects [I:273](#)
- field [I:286](#)
- foreign formats [I:295](#)
- frequency in query [I:288](#)
- group storage options [I:629](#)
- link [I:274](#), [I:275](#), [I:307](#)
- link options [I:309](#)
- maintenance [I:293](#)
- match operator in query [I:287](#)
- open [I:269](#)
- packing [I:293](#)
- queries [I:283](#)
- rebuild [I:295](#)
- registry [I:636](#)
- rename [I:293](#)
- rename object [I:277](#)
- repair [I:294](#)
- sharing violation [I:270](#)
- statistics [I:294](#)

- store objects [I:272](#)
- test integrity [I:294](#)
- using auto-updating series with [I:158](#)
- window [I:269](#)

Database registry [I:281](#), [I:636](#)

Datastream [I:297](#)

Date pairs [I:92](#)

Date series [I:166](#)

Dated data table [I:383](#)

- create [I:384](#)
- formatting options [I:388](#)
- frequency conversion [I:387](#)
- row options [I:389](#)
- table options [I:384](#)
- transformation methods [I:386](#)

Dates

- default display format [I:629](#)
- display format [I:166](#)
- format in a spreadsheet See [Display format](#)
- global options [I:624](#)
- match merging using [I:189](#)

Default

- database [I:9](#), [I:272](#)
- database in search order [I:283](#)
- directory [I:9](#), [I:634](#)
- set directory [I:65](#)
- setting global options [I:621](#)
- update directory [I:65](#)
- window appearance [I:621](#)

Delete

- database [I:293](#)
- graph element [I:566](#)
- objects from database [I:277](#)
- observation in series [I:88](#)
- page [I:65](#)
- series using pool [II:584](#)
- spool objects [I:610](#)

Delimiters [I:123](#)

Demonstration

- estimation [I:21](#)
- examining data [I:16](#)
- forecasting [I:27](#)
- getting data into EViews [I:13](#)
- specification test [I:23](#)

Den Haan and Levin [II:782](#)

Dependent variable

- no variance in binary models [II:254](#)

- Derivatives [II:754](#) , [II:766](#)
 - checking [II:366](#)
 - default methods [I:630](#)
 - description [II:767](#)
 - in equation [II:18](#)
 - in logl [II:360](#)
 - in system [II:434](#)
 - saving in series [II:770](#)
- Description
 - field in database query [I:289](#)
- Descriptive statistics [I:135](#)
 - balanced sample (pool) [II:580](#)
 - by classification [I:318](#)
 - by group [I:318](#)
 - categorical graphs of [I:524](#)
 - common sample (group) [I:392](#)
 - common sample (pool) [II:580](#)
 - cross-section specific [II:581](#)
 - for a series [I:321](#)
 - graphs of [I:524](#)
 - group [I:391](#)
 - individual samples (group) [I:392](#)
 - individual samples (pool) [II:580](#)
 - pooled [II:580](#)
 - series [I:316](#)
 - stacked data [II:581](#)
 - tests [I:321](#)
 - time period specific [II:581](#)
- Deselect all [I:72](#)
- Deterministic regressors [II:223](#)
- DFBetas [II:183](#)
- DFGLS [II:385](#)
- Dickey-Fuller test [II:384](#)
 - See also [Junit](#) root tests.
- Difference from moving-average [I:363](#)
- Difference operator [I:135](#) , [I:136](#) , [II:95](#)
 - seasonal [I:137](#) , [II:96](#)
- Display filter [I:50](#) , [I:213](#)
- Display format [I:83](#)
 - group [I:89](#)
- Display mode
 - spools [I:615](#)
- Display name
 - field in database query [I:289](#)
- distdata [I:374](#)
- Distribution
 - empirical distribution function tests [I:330](#)
 - tests [I:330](#)
- Distribution plot [I:503](#)
 - save data [I:374](#)
- DOLSSeeDynamic OLS (DOLS)
- Doornik and Hansen factorization matrix [II:465](#)
- Dot plot [I:485](#)
- Drag and drop
 - existing file onto a new workfile [I:63](#)
 - existing file onto an existing workfile [I:63](#)
 - into a model [II:516](#)
 - series into a group [I:90](#)
 - within the same workfile [I:117](#)
- Drag(ging)
 - text in graph [I:564](#)
- DRI database
 - DRIpro [I:306](#)
 - frequency [I:310](#)
 - illegal names [I:309](#)
 - object alias [I:291](#)
 - queries [I:311](#)
 - shadowing of object names [I:292](#)
 - troubleshooting [I:311](#)
- DRIBase database [I:297](#)
- DRIPro link [I:297](#)
- Dual processor [I:635](#)
- Dummy variables [I:152](#)
 - as binary dependent variable [II:247](#)
 - as censoring point in estimation [II:276](#)
 - automatic creation [II:28](#)
 - generating pool series dummies [II:579](#)
 - pools [II:579](#)
 - using @GROUP to create pool dummies [I:579](#)
- Dunn-Sidak [I:398](#)
- Durbin-Watson statistic [II:86](#)
 - demonstration [I:24](#)
 - for regression [II:14](#)
 - lagged dependent variable [II:87](#)
- Durbin-Wu-Hausman test [II:79](#)
- Dynamic forecasting [II:124](#)
- Dynamic OLS (DOLS) [II:221](#) , [II:230](#)
- Dynamic panel data [II:651](#)
- E
 - Easy query [I:284](#)
 - Economy.com [I:304](#)
 - EcoWin database [I:298](#)

-
- Edit
 - group [I:90](#)
 - series [I:87](#) , [I:381](#)
 - table [I:591](#)
 - EGARCH [II:209](#)
 - See also [GARCH](#)
 - EGLS (estimated GLS) [II:589](#) , [II:607](#) , [II:649](#)
 - EHS test [II:79](#)
 - Eigenvalues
 - factor analysis [II:719](#)
 - plots [I:413](#)
 - Elasticity at means [II:140](#)
 - Elliot, Rothenberg, and Stock point optimal test [II:387](#)
 - See also [Unit root tests](#).
 - Embedded spools [I:604](#)
 - EMF [I:586](#)
 - Empirical CDF
 - graph [I:504](#)
 - Empirical distribution tests [I:330](#)
 - Empirical quantile graph [I:506](#)
 - Empirical survivor graph [I:505](#)
 - End field [I:288](#)
 - Endogeneity [II:187](#)
 - test of [II:79](#)
 - Endogenous variables [II:55](#)
 - in models [II:511](#)
 - Engle-Granger cointegration test [II:694](#)
 - Enhanced metafile [I:586](#)
 - Enterprise Edition [I:297](#) , [I:298](#) , [I:302](#) , [I:304](#)
 - Epanechnikov kernel [I:500](#)
 - Equality tests [I:324](#)
 - groups [I:408](#)
 - mean [I:325](#)
 - median [I:327](#)
 - variance [I:329](#)
 - Equation [II:5](#)
 - add to model [II:516](#)
 - automatic dummy variables in [II:28](#)
 - coefficient covariance matrix [II:17](#)
 - coefficient covariance scalar [II:16](#)
 - coefficient standard error vector [II:17](#)
 - coefficient t-statistic scalar [II:17](#)
 - coefficient t-statistic vector [II:17](#)
 - coefficient vector [II:17](#) , [II:20](#)
 - command string [II:17](#)
 - create [II:5](#)
 - derivatives [II:18](#)
 - estimating in models [II:515](#)
 - gradients [II:18](#)
 - procedures [II:19](#)
 - regression coefficients [II:11](#)
 - regression summary statistics [II:13](#)
 - residuals [II:19](#)
 - results [II:11](#)
 - retrieve previously estimated [II:20](#)
 - r-squared [II:13](#)
 - sample string [II:17](#)
 - saved results [II:16](#)
 - scalar results [II:16](#)
 - specification [II:6](#)
 - specification by list [II:6](#)
 - specify by formula [II:7](#)
 - specify with non-default coefs [II:9](#)
 - specify with restrictions [II:8](#)
 - specify without dependent variable [II:8](#)
 - specifying a constant [II:6](#)
 - store [II:20](#)
 - text representation [II:17](#)
 - t-statistic [II:12](#)
 - update time [II:17](#)
 - vector and matrix results [II:17](#)
 - views [II:17](#)
 - Error bar graph [I:486](#)
 - Estimation [II:9](#)
 - AR specification [II:89](#)
 - as part of model [II:515](#)
 - auto-series [I:149](#)
 - behavior [II:763](#)
 - binary dependent variable [II:249](#)
 - censored models [II:274](#)
 - collinearity [II:21](#)
 - convergence [II:763](#)
 - convergence problems [II:754](#)
 - count models [II:287](#)
 - demonstration [I:21](#)
 - derivative computation options [II:754](#)
 - derivatives [II:766](#)
 - failure to improve [II:754](#)
 - for pool [II:586](#)
 - GMM [II:67](#)
 - log likelihood [II:362](#)
 - logl [II:362](#)
 - missing data [II:10](#)
 - multi-equation [II:420](#)

- near singular matrix problems [II:753](#)
- nonlinear least squares [II:40](#)
- options [II:751](#)
- ordered models [II:267](#)
- output [II:11](#)
- panel
- problems in convergence [II:752](#)
- residuals from equation [II:20](#)
- sample [II:9](#)
- sample adjustment [II:10](#)
- single equation methods [II:9](#)
- starting values [II:751](#)
- state space [II:491](#) , [II:501](#)
- systems [II:420](#) , [II:428](#)
- truncated models [II:283](#)
- two-stage least squares [II:55](#)
- VAR [II:460](#)
- VEC [II:478](#)
- Evaluation order [I:132](#)
 - logl [II:359](#)
- EViews
 - auto-update [I:11](#) , [I:637](#)
- EViews Databases [I:267](#)
- EViews Enterprise Edition [I:298](#) , [I:302](#) , [I:303](#) , [I:304](#)
- EViews Forum [I:11](#)
- Examining data
 - demonstration [I:16](#)
- Excel
 - reading EViews data in [I:113](#)
- Excel Add-in [I:113](#)
- Excel file
 - importing data into workfile [I:105](#)
 - opening as workfile [I:40](#)
 - opening as workfile demo [I:13](#)
- Exogenous variable [II:55](#)
 - uncertainty [II:540](#) , [II:551](#)
- Exogenous variables
 - in models [II:511](#)
- Expectation-prediction table
 - binary models [II:256](#)
 - ordered models [II:270](#)
- Expectations consistency in models [II:542](#)
- Expected dependent variable
 - censored models [II:279](#)
 - truncated models [II:285](#)
- Expected latent variable

- censored models [II:279](#)
- truncated models [II:285](#)
- Exponential GARCH (EGARCH) [II:209](#)
 - See also [GARCH](#)
- Exponential smoothing [I:364](#) , [I:369](#)
 - See also [Smoothing](#).
 - double [I:365](#)
 - Holt-Winters additive [I:367](#)
 - Holt-Winters multiplicative [I:366](#)
 - Holt-Winters no seasonal [I:367](#)
 - single [I:365](#)
- Export [I:111](#) , [I:265](#)
 - database [I:275](#)
 - pool data [II:584](#)
 - to ASCII files [I:112](#)
 - to spreadsheet files [I:112](#)
- Expression [I:131](#)
 - for database fields [I:287](#)
 - parentheses [I:132](#)
- Extreme value
 - binary model [II:250](#)
 - censored dependent variable models [II:275](#)

F

- Factor analysis [II:705](#)
 - background [II:736](#)
 - communalities [II:710](#)
 - creation [II:706](#)
 - data members [II:721](#)
 - details [II:736](#)
 - eigenvalues [II:719](#)
 - example [II:721](#)
 - goodness of fit [II:717](#) , [II:741](#)
 - graph scores [II:715](#)
 - loading views [II:718](#)
 - method [II:707](#) , [II:709](#)
 - method details [II:738](#)
 - model evaluation [II:741](#)
 - PACE [II:709](#)
 - procedures [II:720](#)
 - reduced covariance [II:718](#)
 - rotation [II:712](#)
 - rotation (theory) [II:743](#)
 - scaling [II:711](#)
 - score estimation [II:713](#)
 - See also [Factor object](#).
 - specification [II:706](#)
 - theory of [II:736](#)

- views [II:716](#)
- Factor and graph layout options [I:547](#)
- Factor breakpoint test [II:155](#)
- Factor display settings [I:543](#)
- Factor object
 - Kaiser's measure of sampling adequacy [II:720](#)
 - See also [Factor analysis](#).
- Factset [I:302](#)
- Fair-Taylor model solution [II:541](#)
- FAME database [I:302](#)
- Federal Reserve Economic Data [I:303](#)
- Fetch [I:80](#)
 - from database [I:273](#)
 - from pool [II:584](#)
- fetch [I:117](#)
- Fields in database [I:286](#)
 - description [I:289](#)
 - display_name [I:289](#)
 - end [I:288](#)
 - expressions [I:287](#)
 - freq [I:288](#)
 - history [I:289](#)
 - last_update [I:289](#)
 - last_write [I:289](#)
 - name [I:287](#)
 - remarks [I:289](#)
 - source [I:289](#)
 - start [I:288](#)
 - type [I:287](#)
 - units [I:289](#)
- File
 - open session on double click [I:624](#)
- Files
 - default locations [I:634](#)
- Filter
 - Hodrick-Prescott [I:369](#)
 - state space models [I:488](#)
- FIML [II:422](#)
- First derivative methods [II:757](#)
- Fisher-ADF [II:400](#)
- Fisher-Johansen [II:703](#)
- Fisher-PP [II:400](#)
- Fit lines (graph) [I:458](#)
- Fitted index
 - binary models [II:261](#)
 - censored models [II:279](#)
 - truncated models [II:285](#)
- Fitted probability
 - binary models [II:261](#)
- Fitted values
 - of equation [II:18](#)
- Fixed effects
 - pool [II:589](#)
 - pool description [II:604](#)
 - test [II:672](#)
- Fixed variance parameter
 - negative binomial QML [II:291](#)
 - normal QML [II:290](#)
- Flatten
 - spools [I:611](#)
- FMOLS See [Fully modified OLS \(FMOLS\)](#)
- Fonts
 - defaults [I:624](#)
 - tables [I:594](#)
 - text in graph [I:563](#), [I:581](#)
- Forecast
 - AR specification [II:126](#)
 - auto-series [II:131](#)
 - backcasting [II:126](#)
 - binary models [II:261](#)
 - by exponential smoothing [I:369](#)
 - censored models [II:279](#)
 - Chow test [II:174](#)
 - conditional variance [II:206](#)
 - count models [II:291](#)
 - demonstration [I:27](#)
 - dynamic [II:124](#), [II:491](#)
 - equations with formula [II:130](#)
 - error [II:119](#)
 - evaluation [II:121](#)
 - example [II:114](#)
 - expressions and auto-updating series [II:130](#)
 - fitted values [II:118](#)
 - from estimated equation [II:111](#)
 - innovation initialization in models [II:543](#)
 - interval [II:120](#)
 - lagged dependent variables [II:123](#)
 - MA specification [II:126](#)
 - missing values [II:118](#)
 - models [II:520](#)
 - nonlinear models [II:136](#)
 - n-step ahead [II:490](#)
 - n-step test [II:180](#)
 - one-step test [II:180](#)
 - ordered models [II:272](#)

- out-of-sample [II:117](#)
- PDLs [II:136](#)
- smoothed [II:491](#)
- standard error [II:120](#), [II:133](#)
- state space [II:490](#)
- static [II:125](#)
- structural [II:125](#)
- system [II:435](#)
- truncated models [II:285](#)
- VAR/VEC [II:480](#)
- variance [II:119](#)
- with AR errors [II:126](#)
- Foreign data
 - open as workfile [I:13](#)
- Format
 - tables [I:593](#)
- Formula
 - forecast [II:130](#)
 - implicit assignment [I:143](#)
 - normalize [I:144](#)
 - specify equation by [II:7](#)
- Forward solution for models [II:540](#)
- Frame [I:460](#)
 - size [I:461](#)
- FRED [I:303](#)
- Freedman-Diaconis [I:494](#)
- Freeze [I:78](#)
 - create graph from view [I:557](#)
- Freq
 - field in database query [I:288](#)
- Frequency (Band-Pass) filter [I:371](#)
- Frequency conversion [I:77](#), [I:78](#), [I:116](#), [I:624](#)
 - dated data table [I:387](#)
 - default settings [I:120](#)
 - DRI database [I:310](#)
 - links [I:203](#)
 - methods [I:117](#)
 - panels [I:195](#)
 - propagate NAs [I:118](#)
 - undated series [I:120](#)
 - using links [I:193](#)
- Frequency spectrum [II:108](#)
- Frequency zero spectrum estimation [II:388](#)
- F-statistic [II:148](#), [II:153](#)
 - for regression [II:15](#)
- F-test
 - for variance equality [I:329](#)

- Full information maximum likelihood [II:422](#)
- Fully modified OLS (FMOLS) [II:221](#), [II:223](#)

G

- GARCH [II:195](#)
 - ARCH-M model [II:197](#)
 - asymmetric component model [II:212](#)
 - backcasting [II:201](#)
 - component models (CGARCH) [II:211](#)
 - estimation in EViews [II:198](#)
 - examples [II:203](#)
 - exponential GARCH (EGARCH) [II:209](#)
 - GARCH(1,1) model [II:195](#)
 - GARCH(p,q) model [II:197](#)
 - initialization [II:201](#)
 - Integrated GARCH (IGARCH) [II:208](#)
 - mean equation [II:199](#)
 - multivariate [II:375](#)
 - Power ARCH (PARCH) [II:210](#)
 - procedures [II:206](#)
 - robust standard errors [II:202](#)
 - test for [II:162](#)
 - threshold (TARCH) [II:208](#)
 - variance equation [II:199](#)
- Gauss file [I:40](#)
- Gauss-Newton [II:758](#)
- Gauss-Seidel algorithm [II:552](#), [II:759](#)
- Generalized error distribution [II:209](#)
- Generalized least squares [See GLS](#)
- Generalized linear models [II:297](#)
 - quasi-likelihood ratio test [II:291](#)
 - robust standard errors [II:297](#)
 - variance factor [II:297](#)
- Generalized method of moments, [See GMM](#).
- Generalized residual
 - binary models [II:261](#)
 - censored models [II:279](#)
 - count models [II:292](#)
 - ordered models [II:272](#)
 - score vector [II:262](#)
 - truncated models [II:285](#)
- Generate series [I:141](#)
 - by command [I:144](#)
 - dynamic assignment [I:143](#)
 - for pool [II:578](#)
 - implicit assignment [I:143](#)
 - implicit formula [I:143](#)

- using samples [I:142](#)
- Geometric moving average [I:149](#)
- GiveWin data [I:304](#)
- Glejser heteroskedasticity test [II:162](#)
- GLM (generalized linear model) [II:297](#)
 - standard errors [II:297](#)
- Global optimum [II:753](#)
- GLS
 - detrending [II:385](#)
 - pool estimation details [II:605](#)
 - weights [II:649](#)
- GMM [II:67](#) , [II:450](#)
 - bandwidth selection (single equation) [II:76](#)
 - bandwidth selection (system) [II:429](#)
 - breakpoint test [II:82](#)
 - continuously updating (single equation) [II:71](#) , [II:76](#)
 - diagnostics [II:78](#)
 - dropped instruments [II:78](#)
 - estimate single equation by [II:67](#)
 - estimate system by [II:422](#)
 - HAC weighting matrix (single equation) [II:76](#)
 - HAC weighting matrix (system) [II:451](#)
 - instrument orthogonality test [II:79](#)
 - instrument summary [II:78](#)
 - iterate to convergence (single equation) [II:71](#) , [II:76](#)
 - J-statistic (single equation) [II:68](#)
 - kernel options (single equation) [II:76](#)
 - kernel options (system) [II:429](#)
 - multi-equation [II:422](#)
 - N-step (single equation) [II:71](#) , [II:76](#)
 - one-step (single equation) [II:71](#) , [II:76](#)
 - panels [II:651](#)
 - prewhitening option (single equation) [II:76](#)
 - prewhitening option (system) [II:430](#) , [II:453](#)
 - regressor endogeneity test [II:79](#)
 - robust standard errors [II:72](#)
 - system [II:450](#)
 - tests [II:78](#)
 - user-specified weight matrix [II:76](#)
 - weak instruments [II:80](#)
 - White weighting matrix (single equation) [II:76](#)
 - White weighting matrix (system) [II:451](#)
 - Windmeijer standard errors [II:73](#)
- Godfrey heteroskedasticity test [II:161](#)
- Goldfeld-Quandt [II:757](#)
- Gompit models [II:250](#)
- Goodness-of-fit
 - adjusted R-squared [II:13](#)
 - Andrews test [II:258](#) , [II:298](#)
 - factor analysis [II:717](#)
 - forecast [II:121](#)
 - Hosmer-Lemeshow test [II:258](#) , [II:298](#)
 - R-squared [II:13](#)
- Gradients [II:763](#)
 - details [II:763](#)
 - in equation [II:18](#) , [II:434](#)
 - in logl [II:365](#)
 - saving in series [II:766](#)
 - summary [II:764](#)
- Granger causality test [I:428](#)
 - VAR [II:463](#)
- Graph
 - align multiple [I:583](#)
 - analytical graphs [I:493](#)
 - area band [I:483](#)
 - area graph [I:481](#)
 - automating [I:587](#)
 - auto-updating [I:558](#)
 - auxiliary graphs [I:512](#)
 - average shifted histogram [I:498](#)
 - axis borders [I:443](#)
 - axis control [I:571](#)
 - axis label format [I:467](#)
 - axis See also [Axis](#).
 - background color [I:570](#)
 - background printing [I:570](#)
 - bar graph [I:481](#)
 - basic customization [I:459](#)
 - border [I:570](#)
 - boxplot [I:509](#)
 - categorical [I:570](#)
 - categorical See also [Categorical graphs](#).
 - color settings [I:570](#)
 - combining [I:562](#)
 - combining graphs [I:562](#)
 - confidence ellipse [I:521](#)
 - coordinates for positioning elements [I:563](#)
 - copying [I:586](#)
 - creating [I:557](#) , [I:558](#)
 - custom obs labels [I:572](#)
 - customization [I:562](#)
 - customize axis labels [I:467](#)
 - customizing lines and symbols [I:575](#)
 - data option [I:441](#)

- date label format [I:469](#)
- date label frequency [I:468](#)
- date label positioning [I:471](#)
- dot plot [I:485](#)
- drawing lines and shaded areas [I:564](#)
- empirical CDF [I:504](#)
- empirical log survivor [I:505](#)
- empirical quantile [I:506](#)
- empirical survivor [I:505](#)
- error bar [I:486](#)
- fill areas [I:478](#)
- first vs. all [I:455](#)
- fit lines [I:458](#)
- font [I:563](#)
- font options [I:581](#)
- frame [I:460](#)
- frame border [I:461](#)
- frame color [I:460](#)
- frame fill [I:570](#)
- freeze [I:557](#)
- freezing [I:558](#)
- frequency [I:443](#)
- grid lines [I:570](#)
- groups [I:448](#)
- high-low-open-close [I:486](#)
- histogram [I:493](#)
- histogram edge polygon [I:497](#)
- histogram polygon [I:496](#)
- identifying points [I:437](#)
- indentation [I:570](#)
- kernel density [I:499](#)
- kernel regression [I:515](#)
- legend [I:474](#)
- legend font [I:476](#)
- legend options [I:574](#)
- legend placement [I:475](#)
- legend settings [I:574](#)
- legend text [I:476](#)
- line formats [I:476](#)
- line graph [I:480](#)
- link frequency [I:443](#)
- location [I:462](#)
- means [I:441](#)
- merging multiple [I:72](#)
- mixed frequency data [I:452](#)
- mixed line [I:484](#)
- modifying [I:567](#)
- multiple graph options [I:583](#)

- multiple series option [I:450](#)
- nearest neighbor regression [I:517](#)
- non-consecutive observations [I:570](#)
- observation graphs [I:480](#)
- observations to label [I:468](#)
- orientation [I:442](#)
- orthogonal regression [I:520](#)
- pairwise data [I:454](#)
- panel data [II:635](#)
- panel data options [I:445](#)
- pie [I:491](#)
- place text in [I:563](#)
- position [I:462](#), [I:583](#)
- print in color [I:585](#)
- printing [I:585](#)
- quantile-quantile [I:507](#), [I:508](#), [I:509](#)
- raw data [I:441](#)
- regression line [I:512](#)
- remove custom date labels [I:574](#)
- remove element [I:566](#)
- remove elements [I:566](#)
- rotate [I:442](#)
- rotation [I:468](#)
- sample break plotting options [I:570](#)
- saving [I:586](#)
- scale [I:468](#)
- scatter [I:487](#)
- scatterplot matrix [I:456](#)
- scores [II:715](#)
- seasonal [I:491](#)
- series [I:439](#)
- series view [I:316](#)
- settings for multiple graphs [I:582](#)
- shade options [I:581](#)
- size [I:461](#)
- sorting [I:565](#)
- sorting observations [I:565](#)
- spike [I:484](#)
- stacked [I:455](#)
- symbol graph [I:480](#)
- symbols [I:476](#)
- templates [I:577](#)
- text justification [I:563](#)
- text options [I:581](#)
- theoretical distribution [I:503](#)
- type [I:440](#), [I:449](#), [I:479](#), [I:568](#)
- update settings [I:559](#)
- XY area [I:489](#)

- XY bar [I:489](#)
- XY line [I:488](#)
- XY pairs [I:455](#)
- Grid lines [I:472](#)
 - table [I:592](#)
- Grid search [II:759](#)
- Group [I:150](#), [I:379](#)
 - add member [I:379](#)
 - adding series [I:380](#)
 - adding to [I:90](#)
 - auto-series [I:149](#)
 - create [I:89](#), [I:150](#)
 - display format [I:89](#)
 - display type [I:83](#)
 - edit mode default [I:627](#)
 - edit series [I:381](#)
 - editing [I:90](#)
 - element [I:151](#)
 - graph view [I:391](#)
 - graphing [I:448](#)
 - make system of equations [I:430](#)
 - number of series [I:151](#)
 - pool [II:570](#)
 - rearranging series [I:380](#)
 - row functions [I:152](#)
 - spreadsheet view [I:380](#)
 - spreadsheet view defaults [I:627](#)
 - summaries [I:383](#)
- Group into bins option [I:319](#), [I:404](#)
- Groupwise heteroskedasticity [I:408](#)
- Gumbel [I:504](#)
- H
- HAC
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - robust standard errors [II:32](#), [II:34](#)
 - system GMM [II:452](#)
- Hadri [II:398](#)
- Hannan-Quinn criterion [II:771](#)
 - for equation [II:15](#)
- Hansen instability test [II:239](#)
- Harvey heteroskedasticity test [II:162](#)
- Hat matrix [II:183](#)
- Hatanaka two-step estimator [II:92](#)
- Hausman test [II:187](#), [II:674](#)
- Haver Analytics Database [I:303](#)
- Help [I:10](#)
 - EViews Forum [I:11](#)
 - help system [I:11](#)
 - World Wide Web [I:11](#)
- Heteroskedasticity
 - binary models [II:265](#)
 - cross-sectional details [II:606](#)
 - groupwise [I:408](#)
 - of known form [II:36](#)
 - period details [II:606](#)
 - robust standard errors [II:32](#)
 - tests of [II:161](#)
 - White's test [II:163](#)
 - wizard [II:164](#)
- Heywood cases [II:712](#)
- Hide
 - objects in spool [I:607](#)
- High frequency data [I:37](#)
- High-low-open-close graph [I:486](#)
- Hildreth-Lu [II:92](#)
- Histogram [I:316](#)
 - as axis [I:443](#)
 - average shifted graph [I:498](#)
 - bin width [I:494](#)
 - edge polygon graph [I:497](#)
 - graph [I:493](#)
 - normality test [II:158](#)
 - polygon graph [I:496](#)
 - save data [I:374](#)
 - variable width [I:490](#)
- History
 - command window [I:8](#)
 - field in database query [I:289](#)
- Hodrick-Prescott filter [I:369](#), [I:371](#)
- Holt-Winters
 - additive [I:367](#)
 - multiplicative [I:366](#)
 - no-seasonal [I:367](#)
- Hosmer-Lemeshow test [II:258](#), [II:298](#)
- HTML [I:598](#)
 - open page as workfile [I:40](#)
 - save table as web page [I:598](#)
- Huber/White standard errors [II:297](#)
- Hypothesis tests
 - See also [Test](#).
 - ARCH [II:162](#)
 - Bartlett test [I:329](#)

BDS independence [I:337](#), [II:411](#)
binomial sign test [I:323](#)
Brown-Forsythe [I:329](#)
chi-square test [I:327](#)
Chow breakpoint [II:170](#)
coefficient based [II:140](#)
coefficient p-value [II:12](#)
CUSUM [II:178](#)
CUSUM of squares [I:179](#)
demonstration [I:23](#)
descriptive statistic tests [I:321](#)
distribution [I:330](#)
F-test [I:329](#)
Hausman test [II:187](#)
heteroskedasticity [II:161](#)
irrelevant or redundant variable [II:154](#)
Kruskal-Wallis test [I:327](#)
Levene test [I:329](#)
mean [I:321](#)
median [I:323](#)
multi-sample equality [I:324](#)
nonnested [II:189](#)
normality [II:158](#)
omitted variables [II:153](#)
Ramsey RESET [II:175](#)
residual based [II:157](#)
Siegel-Tukey test [I:329](#)
single sample [I:321](#)
stability test [II:169](#)
unit root [I:336](#), [II:379](#)
unknown breakpoint [II:172](#)
Van der Waerden test [I:323](#), [I:328](#)
variance [I:322](#)
Wald coefficient restriction test [II:146](#)
White heteroskedasticity [II:163](#)
Wilcoxon rank sum test [I:327](#)
Wilcoxon signed ranks test [I:323](#)

I

Icon [I:69](#)

Identification

- Box-Jenkins [II:94](#)
- GMM [II:68](#)
- nonlinear models [II:45](#)
- structural VAR [II:476](#)

Identity

- in model [II:512](#)
- in system [II:425](#)

If condition in samples [I:93](#)

IGARCH [II:208](#)

Im, Pesaran and Shin [II:399](#)

Import data [I:101](#)

- for pool objects [II:572](#)
- from ASCII [I:108](#), [I:122](#)
- from spreadsheet [I:106](#)
- See also Foreign data.
- using a pool object [II:576](#)

Impulse response [II:467](#)

- See also VAR.
- ARMA models [II:107](#)
- generalized impulses [II:469](#)
- standard errors [II:468](#)
- structural decomposition [II:469](#)
- transformation of impulses [II:469](#)
- user specified impulses [II:469](#)

Incorrect functional form [II:163](#), [II:176](#)

Indentation

- spools [I:610](#)

Independence test [I:337](#), [II:411](#)

Index

- fitted from binary models [II:261](#)
- fitted from censored models [II:279](#)
- fitted from truncated models [II:285](#)

Individual sample [I:139](#)

Influence statistics [II:183](#)

Information criterion

- Akaike [II:15](#), [II:771](#)
- Hannan-Quinn [II:771](#)
- Schwarz [II:15](#), [II:771](#)

Innovation [II:86](#)

Insert

- observation [I:88](#)

Insertion point [I:7](#)

Installation [I:5](#)

Instrumental variable [II:55](#)

- dropped instruments [II:78](#)
- for 2SLS with AR specification [II:60](#)
- for nonlinear 2SLS [II:63](#)
- identification (single equation) [II:57](#)
- identification (systems) [II:427](#)
- in systems [II:425](#)
- order condition [II:57](#)
- rank [II:58](#)
- summary of [II:78](#)
- tests [II:78](#)

- using PDL specifications [II:25](#)
 - weak [II:64](#)
 - weak instruments [II:80](#)
 - with pooled data [II:609](#)
 - Integer dependent variable [II:287](#)
 - Integrated series [II:379](#)
 - Integrity (database) [I:294](#)
 - Intercept in equation [II:6](#) , [II:12](#)
 - Interpolate [I:346](#)
 - Intraday data [I:37](#)
 - in samples [I:95](#)
 - Invalid date identifiers [I:237](#)
 - Inverted AR roots [II:92](#) , [II:99](#)
 - Inverted MA roots [II:99](#)
 - Irregular data [I:213](#)
 - Irrelevant variable test [II:154](#)
 - Iterate to convergence GMM
 - single equation [II:71](#) , [II:76](#)
 - Iteration [II:753](#)
 - failure to improve message [II:754](#)
 - in models [II:555](#)
 - in nonlinear least squares [II:43](#)
- ## J
- Jarque-Bera statistic [I:318](#) , [II:158](#) , [II:206](#)
 - in VAR [II:464](#)
 - JPEG [I:586](#)
 - J-statistic
 - 2sls [II:58](#)
 - GMM [II:68](#)
 - panel equation [II:668](#)
 - J-test [II:189](#)
- ## K
- Kaiser's measure of sampling adequacy [II:720](#)
 - Kaiser-Guttman [II:737](#)
 - Kalman filter [II:489](#)
 - Kao panel cointegration test [II:701](#)
 - K-class [II:63](#)
 - estimation of [II:65](#)
 - Kendall's tau [I:392](#)
 - theory [I:400](#)
 - Kernel
 - cointegrating regression [II:231](#)
 - functions [II:777](#)
 - GMM estimation [II:76](#)
 - graph [I:516](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - system GMM HAC [II:429](#) , [II:452](#)
 - technical details [II:777](#)
 - Kernel density graph [I:499](#)
 - save data [I:374](#)
 - Kernel functions [I:500](#)
 - Kernel regression [I:515](#)
 - save data [I:374](#)
 - Keyboard
 - data entry [I:101](#)
 - focus option [I:623](#) , [I:624](#)
 - Keyboard focus [I:623](#)
 - Klein model
 - GMM [II:76](#)
 - LIML [II:66](#)
 - Kolmogorov-Smirnov test [I:330](#)
 - KPSS unit root test [II:387](#)
 - Kruskal-Wallis test [I:327](#)
 - Kullback-Leibler [II:771](#)
 - Kurtosis [I:318](#)
 - Kwiatkowski, Phillips, Schmidt, and Shin test [II:387](#)
- ## L
- Label
 - SeeLabel object
 - Label object [I:77](#)
 - automatic update option [I:625](#)
 - capitalization [I:76](#)
 - Lag
 - dynamic assignment [I:143](#)
 - exclusion test [II:463](#)
 - forecasting [II:123](#)
 - panel data [II:623](#)
 - series [I:135](#)
 - Lag length
 - VAR [II:463](#)
 - Lag structure
 - VAR [II:462](#)
 - Lagged dependent variable
 - and serial correlation [II:85](#)
 - Durbin-Watson statistic [II:87](#)
 - Lagged series in equation [II:7](#)
 - Lagrange multiplier

- test for serial correlation [II:87](#)
- Large sample test [II:139](#)
- Last_update
 - field in database query [I:289](#)
- Last_write
 - field in database query [I:289](#)
- Latent variable
 - binary model [II:248](#)
 - censored models [II:273](#)
 - ordered models [II:266](#)
- Lead
 - series [I:135](#)
- Least squares
 - panels [II:648](#)
 - See also [Equation.](#)
 - See also [OLS.](#)
- Levene test [I:329](#)
- Leverage plots [II:182](#)
- Levin, Lin and Chu [II:396](#)
- Likelihood [II:14](#)
- Likelihood specification [II:364](#)
- Lilliefors test [I:330](#)
- Limit points [II:269](#)
 - censored dependent variables [II:275](#)
 - make covariance matrix [II:272](#)
 - make vector [II:272](#)
 - non-ascending [II:270](#)
- Limited dependent variable [II:247](#)
- Limited information maximum likelihood (LIML)
 - See [LIML](#)
- LIML [II:63](#)
 - Bekker standard errors [II:65](#)
 - dropped instruments [II:78](#)
 - estimation of [II:65](#)
 - instrument summary [II:78](#)
 - linear objective [II:64](#)
 - minimum eigenvalue [II:64](#), [II:67](#)
 - nonlinear objective [II:64](#)
 - weak instruments [II:80](#)
- Line drawing [I:564](#)
- Line graph [I:480](#)
- Linear
 - frequency conversion method [I:118](#)
- Link [I:183](#)
 - basic concepts [I:183](#)
 - breaking [I:210](#)
 - create by command [I:204](#)
 - create by copy-and-paste [I:77](#)
 - creation [I:197](#)
 - frequency conversion [I:193](#), [I:203](#)
 - match merging [I:184](#)
 - modifying [I:209](#)
 - to databases [I:274](#), [I:275](#)
 - working with [I:207](#)
- Linked equations in models [II:530](#)
- List
 - specifying equation by [II:6](#)
- Ljung-Box Q-statistic [I:335](#)
 - serial correlation test [II:87](#)
- LM test
 - ARCH [II:162](#)
 - auxiliary regression [II:159](#), [II:766](#)
 - serial correlation [II:87](#), [II:159](#)
- Lo and MacKinlay variance ratio test [II:402](#)
- Load
 - workfile [I:56](#)
- Loadings [II:718](#)
- Local optimum [II:753](#)
- Local regression [I:518](#)
- Local weighting option [I:519](#)
- LOESS [I:518](#), [I:519](#)
- Log likelihood
 - See also [Logl.](#)
 - average [II:252](#)
 - censored models [II:274](#)
 - exponential [II:290](#)
 - for binary models [II:248](#)
 - for regression (normal errors) [II:14](#)
 - negative binomial [II:289](#)
 - normal [II:290](#)
 - ordered models [II:267](#)
 - Poisson model [II:288](#)
 - restricted [II:252](#)
 - truncated models [II:283](#)
- Logical expression [I:134](#)
 - in easy query [I:285](#)
- Logit models [II:250](#)
- Logl [II:355](#)
 - analytical derivatives [II:360](#)
 - convergence [II:366](#)
 - derivatives [II:360](#)
 - errors [II:367](#)
 - estimation [II:362](#)
 - examples [II:369](#)

- gradients [II:365](#)
- limitations [II:368](#)
- order of evaluation [II:359](#)
- parameters [II:358](#)
- specification [II:357](#)
- starting values [II:362](#)
- step size [II:361](#)
- troubleshooting [II:367](#)
- views [II:364](#)
- Long name [I:76](#)
 - for series [I:338](#)
- Long-run covariance [II:775](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - group [I:422](#)
 - series [I:336](#)
 - technical discussion [II:775](#)
- Long-run variance
 - See [Long-run covariance](#)
- LOWESS [I:518](#), [I:519](#)
- LR statistic [II:153](#), [II:252](#), [II:281](#), [II:282](#), [II:291](#)
- QLR [II:295](#)
- M
- MA specification
 - backcasting [II:102](#)
 - forecast [II:126](#)
 - in ARIMA models [II:93](#)
 - in model solution [II:543](#)
 - in two stage least squares [II:61](#)
 - terms [II:97](#)
- Mann-Whitney test [I:327](#)
- Marginal significance level [II:12](#), [II:139](#)
- Marquardt [II:758](#)
- Match merge [I:184](#)
 - by date [I:189](#)
 - many-to-many [I:187](#)
 - many-to-one [I:186](#)
 - one-to-many [I:185](#)
 - panels [I:191](#)
 - using links [I:184](#)
- Match operator in database query [I:287](#)
- Maximum
 - number of observations [I:635](#)
- Maximum likelihood
 - full information [II:422](#)
 - quasi-generalized pseudo-maximum likelihood [II:294](#)
 - quasi-maximum likelihood [II:289](#)
 - See also [Logl](#)
 - user specified [II:355](#)
- McFadden R-squared [II:252](#)
- Mean [I:317](#)
 - equality test [I:325](#)
 - hypothesis test of [I:321](#)
- Mean absolute error [II:121](#)
- Mean absolute percentage error [II:121](#)
- Mean equation (GARCH) [II:199](#)
- Measurement equation [II:488](#)
- Measurement error [II:55](#), [II:176](#)
- Median [I:317](#)
 - equality test [I:327](#)
 - hypothesis test of [I:323](#)
- Memory allocation [I:634](#)
- Memory, running out of [I:634](#)
- Menu [I:74](#)
 - objects [I:75](#)
- Merge [I:77](#)
 - See [Match merge](#)
 - graphs [I:72](#)
 - into panel workfiles [II:634](#)
 - store option [I:273](#)
- Metafile
 - save graph as Windows metafile. [I:586](#)
- Micro TSP
 - opening workfiles [I:265](#)
- Minimum discrepancy [II:739](#)
- Missing values [I:139](#)
 - forecasting [II:118](#)
 - handling in estimation [II:10](#)
 - in frequency conversion [I:118](#)
 - in models [II:555](#)
 - in observation graphs [I:444](#)
 - interpolate [I:346](#)
 - recoding [I:141](#)
 - relational comparisons involving [I:139](#)
 - test [I:140](#)
- Mixed frequency graph [I:452](#)
- Mixed line graph [I:484](#)
- MLE
 - See [Logl](#)
- Model consistent expectations [II:542](#)
- Models
 - add factors [II:511](#), [II:524](#), [II:537](#)

- adding equations [II:516](#)
- aliasing [II:513](#) , [II:537](#)
- binding variables [II:513](#)
- block structure [II:533](#)
- Broyden solution [II:760](#)
- Broyden solver [II:552](#)
- coefficient uncertainty [II:531](#) , [II:540](#) , [II:550](#)
- convergence test [II:555](#)
- creating [II:529](#)
- definition [II:419](#)
- demonstration [II:263](#)
- derivatives [II:554](#)
- diagnostic messages and iteration history [II:551](#)
- dynamic solution [II:546](#)
- dynamic solve [II:519](#)
- endogenous variables [II:511](#)
- equation view [II:531](#)
- estimating equations [II:515](#)
- excluding variables [II:536](#)
- exogenous variable [II:511](#)
- exogenous variable uncertainty [II:540](#) , [II:551](#)
- Fair-Taylor solution [II:541](#)
- fit option for solution [II:546](#)
- forecasting with [II:520](#)
- future values [II:540](#)
- Gauss-Seidel solution [II:759](#)
- Gauss-Seidel solve [II:552](#)
- handling of ARMA terms [II:546](#)
- identities [II:512](#)
- initialize excluded variables [II:553](#)
- inline equations [II:530](#)
- intercept shift add factor [II:538](#)
- linked equations [II:530](#)
- MA error terms [II:543](#)
- missing value handling [II:555](#)
- Newton solution [II:760](#)
- Newton's method [II:552](#)
- overriding variables [II:513](#) , [II:537](#) , [II:540](#)
- properties of equations [II:532](#)
- roundoff of solution [II:556](#)
- scenarios [II:263](#) , [II:527](#) , [II:535](#)
- scenarios (example) [II:263](#)
- simultaneous and recursive blocks [II:534](#)
- solution methods [II:552](#)
- solve (dynamic) [II:519](#)
- solve (static) [II:517](#)
- solving [II:539](#)

- solving to match target [II:556](#)
- starting values [II:555](#)
- static solution [II:546](#)
- static solve [II:517](#)
- stochastic equations [II:512](#)
- stochastic simulation [II:545](#)
- stochastic solution [II:547](#)
- text description of [II:534](#)
- text keywords [II:534](#)
- tracking variables [II:551](#)
- updating links [II:531](#)
- variable dependencies [II:533](#)
- variable shift add factor [II:538](#)
- variable view [II:533](#)

Moment condition [II:68](#)

Moment Selection Criteria [II:81](#)

Moody's Economy.com [I:304](#)

Moving statistics

- functions [I:137](#)

- geometric mean [I:149](#)

Multicollinearity [II:21](#)

- coefficient variance decomposition [II:144](#)

- test of [II:143](#) , [II:144](#)

Multiple processors [I:635](#)

Multivariate ARCH [II:422](#)

N

NA See NAs and Missing data.

Nadaraya-Watson [II:516](#)

Name

- object [I:75](#)

- reserved [I:76](#)

Name field in database query [I:287](#)

Naming objects

- spool [I:606](#)

NAs [I:139](#)

- forecasting [II:118](#)

- inequality comparison [I:139](#)

- See also Missing data

- test [I:140](#)

Near singular matrix [II:21](#)

- binary models [II:254](#)

- logl [II:359](#) , [II:366](#) , [II:368](#)

- nonlinear models [II:45](#) , [II:753](#)

- polynomial distributed lag [II:24](#)

- RESET test [II:177](#)

- var [II:476](#)

Nearest neighbor regression [I:517](#), [I:518](#)
 Negative binomial count model [II:289](#)
 Network proxy server [I:633](#)
 Newey-West automatic bandwidth
 cointegrating regression [II:231](#)
 GMM estimation [II:76](#)
 long-run covariance estimation [I:425](#), [II:781](#)
 system GMM [II:452](#)
 Newey-West consistent covariance
 cointegrating regression [II:231](#)
 GMM estimation [II:76](#)
 robust standard errors [II:34](#)
 system GMM [II:452](#)
 Newton's method [II:552](#), [II:760](#)
 Newton-Raphson [II:756](#)
 Noninvertible MA process [II:99](#), [II:104](#)
 Nonlinear coefficient restriction
 Wald test [II:151](#)
 Nonlinear least squares [II:40](#)
 convergence criterion [II:43](#)
 forecast standard errors [II:120](#)
 iteration option [II:43](#)
 specification [II:41](#)
 starting values [II:42](#)
 two stage [II:62](#)
 two stage with AR specification [II:63](#)
 weighted [II:45](#)
 weighted two stage [II:63](#), [II:74](#)
 with AR specification [II:44](#), [II:90](#)
 Nonnested tests [II:189](#)
 Nonparametric kernel
 technical details [II:776](#)
 Non-unique identifiers [I:237](#)
 Normality test [I:318](#), [I:330](#), [II:158](#), [II:206](#),
 [II:464](#)
 VAR [II:464](#)
 Normalize formula [I:144](#)
 N-step forecast test [II:180](#)
 N-step GMM
 single equation [II:71](#), [II:76](#)
 Null hypothesis [II:139](#)
 Number format
 See Display format
 Numbers
 relational comparison [I:134](#)
 N-way table [I:408](#)
 chi-square tests [I:406](#)

O

Object [I:67](#)
 allow multiple untitled [I:623](#)
 basics [I:68](#)
 closing untitled [I:623](#)
 copy [I:77](#)
 create [I:71](#)
 data [I:68](#), [I:81](#)
 delete [I:79](#)
 freeze [I:78](#)
 icon [I:69](#)
 label See Label object
 naming [I:76](#)
 open [I:72](#)
 print [I:79](#)
 procedure [I:69](#)
 sample [I:100](#)
 show [I:73](#)
 store [I:80](#)
 type [I:70](#)
 window [I:73](#)
 Objects menu [I:75](#)
 Observation equation [II:488](#), [II:494](#)
 Observation graphs [I:444](#), [I:480](#)
 missing values [I:444](#)
 Observation identifiers [I:254](#)
 Observation number [I:86](#)
 Observation scale [I:468](#)
 Observations, number of
 maximum [I:634](#)
 ODBC [I:40](#)
 OLS (ordinary least squares)
 See also Equation.
 adjusted R-squared [II:13](#)
 coefficient standard error [II:12](#)
 coefficient t-statistic [II:12](#)
 coefficients [II:11](#)
 standard error of regression [II:14](#)
 sum of squared residuals [II:14](#)
 system estimation [II:420](#), [II:447](#)
 Omitted variables test [II:153](#), [II:176](#)
 panel [II:668](#)
 One-step forecast test [II:180](#)
 One-step GMM
 single equation [II:71](#), [II:76](#)
 One-way frequency table [I:332](#)
 Open

- database [I:269](#)
 - multiple objects [I:72](#)
 - object [I:72](#)
 - options [I:265](#)
 - workfile [I:56](#)
 - Operator [I:131](#)
 - arithmetic [I:131](#)
 - conjunction (and, or) [I:134](#)
 - difference [I:136](#)
 - lag [I:135](#)
 - lead [I:135](#)
 - parentheses [I:132](#)
 - relational [I:134](#)
 - Optimization algorithms
 - BHHH [II:758](#)
 - first derivative methods [II:757](#)
 - Gauss-Newton [II:758](#)
 - Goldfeld-Quandt [II:757](#)
 - grid search [II:759](#)
 - Marquardt [II:758](#)
 - Newton-Raphson [II:756](#)
 - second derivative methods [II:756](#)
 - starting values [II:751](#)
 - step size [II:758](#)
 - Option settings
 - allow only one untitled [I:623](#)
 - backup workfiles [I:628](#)
 - date notation [I:624](#)
 - default fonts [I:624](#)
 - EViews sessions on open [I:624](#)
 - external program interface [I:632](#)
 - fonts [I:624](#)
 - frequency conversion [I:624](#)
 - keyboard focus [I:623](#)
 - network proxy server [I:633](#)
 - print setup [I:637](#)
 - program execution mode [I:631](#)
 - series auto label [I:625](#)
 - spreadsheet data display [I:627](#)
 - spreadsheet view defaults [I:626](#)
 - warn on close [I:623](#)
 - window appearance [I:621](#)
 - Or operator [I:94](#), [I:134](#)
 - Order condition
 - 2sls [II:57](#)
 - GMM [II:68](#)
 - Order of evaluation
 - logl [II:359](#)
 - Order of stacked data [II:575](#)
 - Ordered dependent variable [II:266](#)
 - error messages [II:270](#)
 - estimation [II:267](#)
 - expectation-prediction tables [II:270](#)
 - forecasting [II:272](#)
 - limit points [II:272](#)
 - log likelihood [II:267](#)
 - variable frequencies [II:270](#)
 - views [II:270](#)
 - Ordinary residual
 - binary models [II:261](#)
 - censored models [II:279](#)
 - count models [II:292](#)
 - truncated models [II:284](#)
 - Orientation [I:442](#)
 - Orthogonal regression [I:520](#)
 - Orthogonality condition [II:68](#), [II:451](#)
 - Outliers
 - detection of [II:182](#), [II:183](#)
 - Over identification [II:68](#)
 - Overdispersion [II:289](#), [II:297](#), [II:327](#)
 - specification test [II:292](#)
- P
- PACE [II:709](#)
 - details [II:740](#)
 - Pack database [I:293](#)
 - Packable space [II:270](#), [I:294](#)
 - Page
 - create new [I:57](#)
 - delete page [I:65](#)
 - rename [I:64](#)
 - reorder [I:65](#)
 - Page breaks [I:619](#)
 - Pairwise graphs [I:454](#)
 - Panel data [II:615](#)
 - analysis [II:635](#)
 - balanced [I:220](#)
 - cell identifier [II:621](#)
 - cointegration [II:640](#), [II:698](#)
 - convert to pool [I:251](#)
 - create workfile of [I:38](#)
 - cross-section identifiers [II:620](#)
 - cross-section summaries [II:629](#)
 - dated [I:219](#)
 - duplicate identifiers [I:218](#), [I:235](#)

- dynamic panel data [II:651](#)
- estimation See [Panel estimation](#).
- fixed effects test [II:672](#)
- frequency conversion [I:195](#)
- GMM estimation [II:651](#)
- graphs [II:635](#)
- group identifier [II:620](#)
- Hausman test [II:674](#)
- identifiers [I:216](#)
- instrumental variables estimation [II:650](#)
- irregular [I:220](#)
- lags [I:217](#), [II:623](#)
- lags and leads [II:623](#)
- least squares estimation [II:648](#)
- merging data into [II:634](#)
- nested [I:222](#)
- period summaries [II:629](#)
- pool comparison [II:565](#)
- regular [I:220](#)
- samples in panel workfiles [II:624](#)
- See also [Panel workfile](#).
- statistics [II:627](#)
- testing [II:668](#)
- time trend [II:627](#)
- trends [II:627](#)
- unbalanced [I:220](#)
- undated [I:219](#)
- unit root tests [II:391](#), [II:638](#)
- within-group identifier [II:622](#)
- workfile structure [I:216](#)
- [Panel estimation](#) [II:647](#)
 - examples [II:654](#)
 - GLS weights [II:649](#)
 - GMM [II:651](#)
 - GMM (example) [II:663](#)
 - GMM details [II:677](#)
 - least squares [II:648](#)
 - TSLs [II:650](#)
- [Panel unit root](#) See [Panel data - unit root tests](#).
- [Panel vs. pool](#) [II:565](#)
- [Panel workfile](#)
 - See also [Panel data](#).
 - create [II:615](#)
 - dated [I:230](#)
 - display [II:618](#)
 - nested [I:222](#)
 - structure [II:615](#), [II:619](#)
 - undated [I:235](#)
 - undated with ID [I:234](#)
- [Parallel analysis](#) [II:709](#)
- [Param \(command\)](#) [II:43](#), [II:428](#), [II:752](#)
- [Parameters](#)
 - logl [II:358](#)
- [PARCH](#) [II:210](#)
- [Park added variable test](#) [II:242](#)
- [Parks estimator](#) [II:607](#)
- [Partial analysis](#) [I:396](#)
- [Partial autocorrelation](#) [I:335](#), [II:94](#)
- [Partial covariance analysis](#) [I:396](#)
- [Parzen kernel](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:777](#)
- [Parzen-Cauchy kernel](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:777](#)
- [Parzen-Geometric kernel](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:777](#)
- [Parzen-Riesz kernel](#)
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:777](#)
- [Paste](#) [I:77](#)
 - data as new workfile [I:39](#)
 - existing series [I:105](#)
 - new series [I:104](#)
- [PcGive data](#) [I:304](#)
- [PDL \(polynomial distributed lag\)](#) [II:23](#), [II:120](#)
 - far end restriction [II:24](#)
 - forecast standard errors [II:120](#)
 - instrumental variables [II:25](#)
 - near end restriction [II:24](#)
 - specification [II:24](#)
- [Pearson covariance](#) [I:392](#)

Pedroni panel cointegration test [II:641](#) , [II:700](#)

Period

 summaries [II:629](#)

 SUR [II:608](#)

Phillips-Ouliaris cointegration test [II:694](#)

Phillips-Perron test [II:386](#)

Pie graph [I:491](#)

PNG [I:586](#)

Poisson count model [II:288](#)

Polynomial distributed lags, See PDL.

Pool [II:565](#)

 ? placeholder [II:570](#)

 and cross-section specific series [I:569](#)

 AR specification [II:588](#)

 balanced data [II:576](#) , [II:580](#)

 balanced sample [II:587](#)

 base name [II:569](#)

 coefficient test [II:600](#)

 cointegration [II:582](#)

 common coefficients [II:588](#)

 convergence criterion [II:591](#)

 convert to panel [I:257](#)

 copy [II:568](#)

 creating [II:571](#)

 cross-section [II:567](#)

 cross-section specific coefficients [II:588](#)

 defining [II:567](#)

 defining groups of identifiers [II:568](#)

 descriptive statistics [II:580](#)

 dummy variable [II:579](#)

 editing definitions [II:568](#)

 estimation [II:586](#)

 estimation details [II:601](#)

 export data [II:584](#)

 fixed effects [II:589](#) , [II:604](#)

 generate series [I:578](#)

 group [II:570](#)

 import [II:572](#)

 import data [II:572](#)

 import stacked data [II:576](#)

 instrumental variables [II:592](#) , [II:609](#)

 make group [II:583](#)

 make system [II:583](#)

 naming series [II:569](#)

 object [II:566](#)

 options [II:590](#)

 order [II:575](#)

 period-specific coefficients [II:588](#)

 pool series [II:570](#)

 procedures [II:600](#)

 random effects [II:589](#) , [II:605](#)

 residuals [II:601](#)

 restructure [II:574](#)

 series [II:570](#)

 setup [II:571](#)

 special group identity series [II:570](#)

 specification [II:567](#)

 stacked data [II:573](#)

 tests [II:600](#)

 unstacked data [II:572](#)

 workfile [II:565](#)

Pool data

 panel comparison [II:565](#)

Pool vs. panel [II:565](#)

Portmanteau test

 VAR [II:464](#)

PostScript [I:586](#)

 save graph as PostScript file [I:586](#)

Prais-Winsten [II:92](#)

Precedence of evaluation [I:132](#)

Predetermined variable [II:55](#)

Prediction table

 binary models [II:256](#)

 ordered models [II:270](#)

Prewhitening

 cointegrating regression [II:231](#)

 GMM estimation [II:76](#)

 long-run covariance estimation [II:783](#)

 robust standard errors [II:34](#)

 system GMM [II:430](#) , [II:453](#)

 technical details [II:783](#)

Principal components [I:409](#)

Principal factors [II:739](#)

Print

 graphs [I:585](#)

 mode [I:619](#)

 objects [I:79](#)

 settings [I:637](#)

 setup options [I:637](#)

 spool [I:619](#) , [I:638](#)

 tables [I:597](#)

 to a spool [I:602](#)

Probability response curve [II:262](#)

Probit models [II:249](#)

Procedures [I:69](#)

Processors

multiple [I:635](#)

Program

auto indent [I:631](#)backup files [I:631](#)execution option [I:631](#), [I:632](#), [I:633](#)syntax coloring [I:631](#)tab settings [I:631](#)Proxy server [I:633](#)P-value [II:139](#)for coefficient t-statistic [II:12](#)

Q

QML [II:289](#)QQ-plot [I:507](#), [I:508](#), [I:509](#)save data [I:374](#)

Q-statistic

Ljung-Box [I:335](#)residual serial correlation test [II:464](#)serial correlation test [II:87](#)

Quadratic

frequency conversion method [I:118](#)Quadratic hill-climbing [II:757](#)Quadratic spectral kernel [II:452](#)cointegrating regression [II:231](#)GMM estimation [II:76](#)long-run covariance estimation [I:425](#)robust standard errors [II:34](#)technical details [II:777](#)Qualitative dependent variable [II:247](#)Quandt breakpoint test [II:172](#)Quantile method [I:504](#)Quantile regression [II:331](#)

Quantiles

from series [I:339](#), [I:341](#)Quasi-generalized pseudomaximum likelihood [II:294](#)Quasi-likelihood ratio test [II:291](#), [II:295](#)Quasi-maximum likelihood [II:289](#)robust standard errors [II:297](#)Queries on database [I:283](#)advanced query [I:285](#)DRI [I:311](#)easy query [I:284](#)examples [I:290](#)logical expressions [I:285](#)wildcard characters [I:284](#)Quiet mode [I:632](#)

R

Ramsey RESET test [II:175](#)

Random effects

pool [II:589](#)pool descriptions [II:605](#)test for correlated effects (Hausman) [II:674](#)Random walk [II:379](#)Rank condition for identification [II:57](#)

Ranks

observations in series or vector [I:138](#)Ratio to moving-average [I:363](#)

RATS data

4.x native format [I:305](#)portable format [I:305](#)Read [II:572](#)Reading EViews data (in other applications) [I:112](#)Rebuild database [I:295](#)Recursive coefficient [II:181](#)save as series [I:181](#)

Recursive estimation

least squares [II:177](#)using state space [II:496](#)Recursive least squares [II:177](#)Recursive residual [II:177](#), [II:178](#)CUSUM [II:178](#)CUSUM of squares [I:179](#)n-step forecast test [II:180](#)one-step forecast test [II:180](#)save as series [I:181](#)Reduced covariance [II:718](#)Redundant variables test [II:154](#)panel [II:670](#)Registry [I:281](#)

Regression

adjusted R-squared [II:13](#)coefficient standard error [II:12](#)coefficients [II:11](#)collinearity [II:21](#)forecast [II:111](#)F-statistic [II:15](#)log likelihood [II:14](#)residuals from [II:20](#)

- See also [Equation](#).
- standard error of [II:14](#)
- sum of squared residuals [II:14](#)
- t-statistic for coefficient [II:12](#)
- Regression line
 - on graph [I:512](#)
- Regular data [I:213](#)
- Relational operators
 - and missing values [I:139](#)
- Remarks
 - field in database query [I:289](#)
- Removing data [I:244](#)
- Rename [I:76](#)
 - database [I:293](#)
 - objects in database [I:277](#)
 - page [I:64](#)
 - workfile page [I:64](#)
- Reorder
 - page [I:65](#)
- Repair database [I:294](#)
- Representations view
 - equation [II:17](#)
- Resample [I:344](#)
- Reserved names [I:76](#)
- RESET test [II:175](#)
- Reshaping a workfile [I:248](#)
- Residuals
 - binary models [II:261](#)
 - censored dependent variable models [II:278](#)
 - count models [II:291](#)
 - default series RESID [II:19](#)
 - display of in equation [II:19](#)
 - from estimated equation [II:20](#)
 - from two stage least squares [II:58](#)
 - generalized [II:261](#), [II:279](#), [II:285](#), [II:292](#)
 - make series or group containing [II:19](#)
 - of equation [II:18](#)
 - ordinary [II:261](#), [II:279](#), [II:284](#), [II:292](#)
 - plot [II:18](#)
 - plots of [II:182](#)
 - pool [II:601](#)
 - recursive [II:177](#), [II:178](#)
 - standardized [II:18](#), [II:261](#), [II:279](#), [II:284](#), [II:292](#)
 - studentized [II:183](#)
 - sum of squares [II:14](#)
 - symmetrically trimmed [II:281](#)
 - system [II:435](#)
 - tests of [II:157](#)
 - truncated dependent variable [II:284](#)
 - unconditional [II:86](#), [II:91](#)
- Resize
 - spools [I:609](#)
 - table columns and rows [I:592](#)
 - workfile [I:225](#), [I:238](#)
- Restricted estimation [II:8](#)
- Restricted log likelihood [II:252](#)
- Restricted VAR [II:472](#)
- Restructuring [II:574](#)
- Results
 - display or retrieve [II:16](#)
- Rich Text Format [I:597](#)
- Robust standard errors [II:32](#)
 - Bollerslev-Wooldridge for GARCH [II:202](#)
 - clustered [II:649](#)
 - GLM [II:297](#), [II:306](#)
 - GMM [II:72](#)
 - Huber-White (QML) [II:297](#), [II:306](#)
- Robustness iterations [I:514](#), [I:519](#)
- Root mean square error [II:121](#)
- Rotate
 - factors [II:712](#), [II:743](#)
 - graphs [I:442](#)
- Rotation of factors [II:712](#)
 - details [II:743](#)
- Row
 - functions [I:152](#)
 - height [I:592](#)
- R-squared
 - adjusted [II:13](#)
 - for regression [II:13](#)
 - from two stage least squares [II:59](#)
 - McFadden [II:252](#)
 - negative [II:204](#)
 - uncentered [II:159](#), [II:163](#)
 - with AR specification [II:92](#)
- RTF [I:597](#), [I:598](#)
 - create [I:638](#)
 - redirecting print to [I:638](#)
- S
- Sample
 - @all [I:93](#)
 - @first [I:93](#)

- adjustment in estimation [II:10](#)
- all observations [I:93](#)
- balanced [II:587](#)
- breaks [I:444](#)
- change [I:92](#)
- command [I:94](#)
- common [I:139](#)
- current [I:50](#)
- date pairs [I:92](#)
- first observation [I:93](#)
- if condition [I:93](#)
- individual [I:139](#)
- intraday data [I:95](#)
- last observation [I:93](#)
- range pairs [I:92](#)
- selection and missing values [I:94](#)
- specifying sample object [I:100](#)
- specifying samples in panel workfiles [II:624](#)
- used in estimation [II:9](#)
- using sample objects in expressions [I:100](#)
- with expressions [I:95](#)
- workfile [I:91](#)
- SAR specification [II:97](#)
- SARMA [II:97](#)
- SAS file [I:40](#)
- Save
 - backup workfile [I:54](#)
 - graphs [I:586](#)
 - options [I:265](#)
 - save as new workfile [I:54](#)
 - spool [I:620](#)
 - tables [I:598](#)
 - workfile [I:53](#)
 - workfile as foreign file [I:110](#)
 - workfile precision and compression [I:55](#)
- Scalar [I:154](#)
- Scale factor [II:278](#)
- Scaled coefficients [II:140](#)
- Scaling
 - factor analysis [II:711](#)
- Scatterplot [I:487](#)
 - categorical [I:535](#)
 - matrix of [I:456](#)
 - with confidence ellipse [I:521](#)
 - with kernel regression fit [I:515](#)
 - with nearest neighbor fit [I:517](#)
 - with orthogonal regression line [I:520](#)
 - with regression line [I:512](#)
- Scenarios [II:527](#)
 - simple example [II:263](#)
- Schwarz criterion [II:771](#)
 - for equation [II:15](#)
- Score coefficients [II:714](#)
- Score vector [II:262](#)
- Scores [II:713](#)
- Seasonal
 - ARMA terms [II:97](#)
 - difference [I:137](#), [II:96](#)
 - graphs [I:491](#)
- Seasonal adjustment [I:349](#)
 - additive [I:363](#)
 - Census X11 (historical) [I:358](#)
 - Census X12 [I:349](#)
 - multiplicative [I:363](#)
 - Tramo/Seats [I:358](#)
- Second derivative methods [II:756](#)
- Seemingly unrelated regression [II:421](#), [II:448](#)
- Select
 - all [I:72](#)
 - object [I:71](#)
- Sensitivity of binary prediction [II:257](#)
- Serial correlation
 - ARIMA models [II:93](#)
 - Durbin-Watson statistic [II:14](#), [II:86](#)
 - first order [II:86](#)
 - higher order [II:86](#)
 - nonlinear models [II:90](#)
 - tests [II:86](#), [II:159](#)
 - theory [II:85](#)
 - two stage regression [II:91](#)
- Series [I:315](#)
 - auto-series [I:145](#)
 - auto-updating [I:155](#)
 - auto-updating and databases [I:158](#)
 - auto-updating and forecasting [II:130](#)
 - binning [I:339](#)
 - classification [I:339](#)
 - create [I:82](#), [I:141](#)
 - cross-section specific [II:569](#)
 - delete observation [I:88](#)
 - description of [I:81](#)
 - descriptive statistics [I:316](#)
 - difference [I:136](#)
 - display format [I:83](#)
 - display type [I:83](#)

- dynamic assignment [I:143](#)
- edit in differences [I:381](#)
- edit mode default [I:627](#)
- editing [I:87](#)
- functions [I:133](#)
- generate by command [I:144](#)
- graph [I:316](#), [I:439](#)
- implicit assignment [I:143](#)
- in pool objects [II:570](#)
- insert observation [I:88](#)
- interpolate [I:346](#)
- lag [I:135](#)
- lead [I:135](#)
- pooled [II:570](#)
- procs [I:339](#)
- properties [I:338](#)
- ranking [I:138](#)
- resample [I:344](#)
- setting graph axis [I:463](#)
- smpl+/- [I:86](#)
- spreadsheet view [I:316](#)
- spreadsheet view defaults [I:626](#)
- using expressions in place of [I:145](#)
- Shade region of graph [I:564](#)
- Shadowing of object names [I:292](#)
- Sharing violation [I:270](#)
- Show object view [I:72](#)
- Siegel-Tukey test [I:329](#)
- Sign test [I:323](#)
- Signal equation [II:494](#)
- Signal variables
 - views [II:504](#)
- Silverman bandwidth [I:501](#)
- Simultaneous equations [See systems.](#)
- Singular matrix
 - error in binary estimation [II:254](#)
 - error in estimation [II:21](#), [II:45](#), [II:753](#)
 - error in logl [II:359](#), [II:366](#), [II:368](#)
 - error in PDL estimation [II:24](#)
 - error in RESET test [II:177](#)
 - error in VAR estimation [II:476](#)
- Skewness [I:317](#)
- SMA specification [II:97](#)
- Smoother
 - methods [I:364](#)
 - parameters [I:364](#)
 - state space [II:489](#)
- Smpl command [I:94](#)
- Smpl+/- [I:86](#)
- Solve
 - Broyden [II:552](#)
 - Gauss-Seidel [II:759](#)
 - Newton-Raphson [II:756](#)
- Sort
 - display [I:382](#)
 - observations in a graph [I:443](#), [I:565](#)
 - spreadsheet display [I:382](#)
 - valmaps [I:173](#)
 - workfile [I:265](#)
- Source
 - field in database query [I:289](#)
- Sparse label option [I:319](#), [I:405](#)
- Spearman rank correlation [I:392](#)
- Spearman rank-order
 - theory [I:400](#)
- Specification
 - by formula [II:7](#)
 - by list [II:6](#)
 - of equation [II:6](#)
 - of nonlinear equation [II:41](#)
 - of systems [II:424](#)
- Specification test
 - for binary models [II:265](#)
 - for overdispersion [II:292](#)
 - for tobit [II:281](#)
 - of equation [II:139](#)
 - RESET (Ramsey) [II:175](#)
 - White [II:163](#)
- Specificity of binary prediction [II:257](#)
- Spectrum estimation [II:388](#), [II:389](#)
- Spike graph [I:484](#)
- Spool [I:601](#)
 - add to [I:602](#)
 - appending [I:603](#)
 - comments [I:606](#)
 - copying to [I:603](#)
 - create [I:601](#)
 - customization [I:613](#)
 - delete objects [I:610](#)
 - display mode [I:615](#)
 - embedding [I:604](#)
 - extract [I:610](#)
 - flatten tree hierarchy [I:611](#)
 - hiding objects [I:607](#)

- indentation I:610
- management I:602
- naming objects I:606
- order I:610
- print I:638
- print size I:620
- print to I:602
- printing I:619
- properties I:613
- rearrange I:610
- redirecting print to I:638
- resize I:609
- saving I:620
- Spreadsheet
 - file export I:112
 - file import I:106
 - series I:316
 - sort display default I:627
 - sort display order I:382
 - view option I:626, I:627
- Spreadsheet view
 - alpha I:166
 - display type I:83
 - group I:380
- SPSS file I:40
- SSCP I:394
- Stability test II:169
 - Chow breakpoint II:170
 - Chow forecast II:174
 - RESET II:175
 - with unequal variance II:186
- Stacked data II:573
 - balanced II:576
 - descriptive statistics II:581
 - order II:575
- Stacking data I:257
- Standard deviation I:317
- Standard error
 - for estimated coefficient II:12
 - forecast II:120, II:133
 - of the regression II:14
 - See also Robust standard errors.
 - VAR II:468
- Standardized coefficients II:140
- Standardized residual II:18
 - binary models II:261
 - censored models II:279
 - count models II:292
 - truncated models II:284
- Start
 - field in database query I:288
- Starting values
 - (G)ARCH models II:201
 - binary models II:253
 - for ARMA estimation II:101
 - for coefficients II:43, II:751
 - for nonlinear least squares II:42
 - for systems II:428
 - logl II:362
 - param statement II:43, II:752
 - state space II:497
 - user supplied II:101
- Stata file I:40
- State equation II:488, II:492
- State space II:487
 - @mprior II:497
 - @vprior II:497
 - estimation II:491, II:501
 - filtering II:488
 - forecasting II:490
 - interpreting II:502
 - observation equation II:488
 - representation II:487
 - specification II:487, II:492
 - specification (automatic) II:500
 - starting values II:497
 - state equation II:488
 - views II:503
- State variables II:487
- State views II:505
- Static forecast II:125
- Static OLS II:220, II:221
- Stationary time series II:379
- Status line I:9
- Step size II:758
 - logl II:361
- Stepwise II:46
 - swapwise II:51
 - uni-directional II:50
- Stochastic equations
 - in model II:512
- Store I:80
 - as .DB? file I:273
 - from pool II:584

- in database [I:272](#)
 - merge objects [I:273](#)
 - Structural change [II:169](#)
 - See also [Breakpoint test](#).
 - Structural forecast [II:125](#)
 - Structural solution of models [II:546](#)
 - Structural VAR [II:471](#)
 - estimation [II:477](#)
 - factorization matrix [II:465](#)
 - identification [II:476](#)
 - long-run restrictions [II:474](#)
 - short-run restrictions [II:472](#)
 - Structuring a workflow [I:213](#)
 - Studentized residual [II:183](#)
 - Sum of squared residuals
 - for regression [II:14](#)
 - Summarizing data [I:383](#)
 - Summary statistics
 - for regression variables [II:13](#)
 - SUR [II:421](#) , [II:448](#)
 - Survivor function [I:505](#)
 - log [I:505](#)
 - save data [I:374](#)
 - Swapwise [II:51](#)
 - Symbol graph [I:480](#)
 - Symmetrically trimmed residuals [II:281](#)
 - Syntax coloring [I:631](#)
 - System [II:419](#)
 - ARCH [II:422](#)
 - covariance matrix [II:434](#)
 - create [II:422](#) , [II:423](#)
 - cross-equation weighting [II:420](#)
 - definition [II:419](#)
 - derivatives [II:434](#)
 - estimation [II:420](#) , [II:428](#)
 - estimation methods (technical) [II:446](#)
 - forecast [II:435](#)
 - full information maximum likelihood [II:422](#)
 - GMM [II:450](#)
 - gradients [II:434](#)
 - Instruments [II:425](#)
 - make system from group [I:430](#)
 - OLS [II:420](#) , [II:447](#)
 - options [II:431](#)
 - residuals [II:435](#)
 - specification [II:424](#)
 - specify from VAR [II:471](#)
 - SUR [II:421](#) , [II:448](#)
 - three stage least squares [II:421](#) , [II:450](#)
 - two stage least squares [II:421](#) , [II:449](#)
 - views [II:434](#)
 - weighted least squares [II:421](#) , [II:447](#)
 - System options [I:634](#)
- T
- Tab settings [I:631](#)
 - Table [I:589](#)
 - cell annotation [I:595](#)
 - cell format [I:593](#)
 - cell merging [I:595](#)
 - color [I:594](#)
 - column resize [I:592](#)
 - column width See [Column width](#).
 - comments [I:595](#)
 - copy [I:597](#)
 - copy to other windows programs [I:597](#)
 - customization [I:592](#)
 - edit [I:591](#)
 - editing [I:591](#)
 - font [I:594](#)
 - fonts [I:594](#)
 - formatting [I:593](#)
 - gridlines [I:592](#)
 - merging [I:595](#)
 - paste as unformatted text [I:597](#)
 - print [I:597](#)
 - row resize [I:592](#)
 - save to disk [I:598](#)
 - selecting cells [I:589](#)
 - title [I:592](#)
 - Tabs
 - See [Page](#)
 - Tabulation
 - n-way [I:404](#)
 - one-way [I:332](#)
 - TARCH [II:208](#)
 - Template [I:577](#)
 - Test
 - See also [Hypothesis tests](#), [Specification test](#)
 - and [Goodness of fit](#)
 - ARCH [II:162](#)
 - breakpoint [II:170](#) , [II:172](#)
 - coefficient [II:140](#)
 - Durbin-Wu-Hausman [II:79](#)

- Hansen instability [II:239](#)
- heteroskedasticity [II:161](#)
- Park added variable [II:242](#)
- pooled [II:600](#)
- RESET [II:175](#)
- residual [II:157](#)
- stability tests [II:169](#)
- variance ratio [II:402](#)
- White [II:163](#)
- Text [I:598](#)
- Text file
 - open as workfile [I:40](#)
- Theil inequality coefficient [II:122](#)
- Themes [I:621](#)
- Theoretical distribution graph [I:503](#)
 - save data [I:374](#)
- Three stage least squares [See 3sls \(Three Stage Least Squares\)](#)
- Threshold GARCH (TARCH) [II:208](#)
- Time series functions [I:135](#)
- Title bar [I:6](#), [I:50](#), [I:74](#)
- To (lag range) [II:7](#)
- Tobit [II:273](#)
- Toolbar [I:50](#), [I:74](#)
- Tracking model variables [II:551](#)
- Tramo/Seats [I:358](#)
- Transition equation [II:488](#)
- Transpose [I:380](#)
- Trend
 - panel data [II:627](#)
 - See also [@trend](#).
- Truncated dependent variable [II:283](#)
 - estimation [II:283](#)
 - fitted index [II:285](#)
 - forecasting [II:285](#)
 - log likelihood [II:283](#)
 - residuals [II:284](#)
- Truncation point [II:284](#)
- TSD data format [I:304](#)
- TSP portable data format [I:306](#)
- t-statistics
 - retrieve from equation [II:12](#)
- Tukey [I:504](#)
- Tukey-Hamming kernel
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:778](#)
- Tukey-Hanning kernel
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:778](#)
- Tukey-Parzen kernel
 - cointegrating regression [II:231](#)
 - GMM estimation [II:76](#)
 - long-run covariance estimation [I:425](#)
 - robust standard errors [II:34](#)
 - technical details [II:778](#)
- Type
 - field in database query [I:287](#)
- U
- Unconditional residual [II:91](#)
- Uni-directional [II:50](#)
- Unit root test [I:336](#), [II:379](#)
 - augmented Dickey-Fuller [II:384](#)
 - Dickey-Fuller [II:384](#)
 - Dickey-Fuller GLS detrended [II:385](#)
 - Elliot, Rothenberg, and Stock [II:387](#)
 - KPSS [II:387](#)
 - panel data [II:391](#), [II:638](#)
 - Phillips-Perron [II:386](#), [II:387](#)
 - pooled data [II:581](#)
 - trend assumption [II:385](#)
- Units
 - field in database query [I:289](#)
- Unstacked data [II:572](#)
- Unstacking data [I:251](#)
- Unstacking identifiers [I:253](#)
- Untitled [I:76](#)
- Update
 - automatic [I:155](#)
 - coefficient vector [II:19](#), [II:752](#)
 - from Database [I:80](#)
 - graphs [I:559](#)
 - group [I:380](#)
- Updating graphs [I:558](#)
- Urdua factorization matrix [II:465](#)
- User specified GMM weight matrix [II:76](#)
- User supplied starting values [II:101](#)

V

Valmap [I:169](#)

- cautions [I:180](#)
- find label for value [I:179](#)
- find numeric value for label [I:179](#)
- find string value for label [I:180](#)
- functions [I:179](#)
- properties [I:174](#)
- sorting [I:173](#)

Value map SeeValmap.

Van der Waerden [I:504](#)

Van der Waerden test [I:323](#), [I:328](#)

VAR

- AR roots [II:462](#)
- autocorrelation LM test [II:464](#)
- autocorrelation test [II:464](#)
- coefficients [II:480](#)
- cointegration [II:685](#)
- correlograms [II:464](#)
- decomposition [II:470](#)
- estimation [II:460](#)
- estimation output [II:461](#)
- factorization matrix in normality test [II:465](#)
- forecasting [II:480](#)
- Granger causality test [II:463](#)
- impulse response [II:467](#)
- Jarque-Bera normality test [II:464](#)
- lag exclusion test [II:463](#)
- lag length [II:463](#)
- lag length choice [II:463](#)
- lag structure [II:462](#)
- mathematical model [II:459](#)
- response standard errors [II:468](#)
- restrictions [II:472](#)
- See also impulse response, Structural VAR.

VARHAC [I:422](#)

- technical details [II:782](#)

Variance

- equality test [I:329](#)
- hypothesis test of [I:322](#)

Variance decomposition [II:144](#), [II:470](#)

Variance equation

See ARCH and GARCH.

Variance factor [II:297](#)

Variance inflation factor (VIF) [II:143](#)

Variance proportion [II:122](#)

Variance ratio test [II:402](#)

example [II:404](#)

technical details [II:408](#)

VEC [II:478](#)

estimating [II:478](#)

Vector autoregression

See VAR.

Vector error correction model

See VEC and VAR. [II:478](#)

Verbose model [I:632](#)

View

default [I:72](#)

Volatility [II:196](#)

W

Wald test [II:146](#)

- coefficient restriction [II:146](#)
- demonstration [I:23](#)
- formula [II:151](#)
- F-statistic [II:152](#)
- joint restriction [II:148](#)
- nonlinear restriction [II:151](#)
- structural change with unequal variance [II:186](#)

Warning on close option [I:623](#)

Watson test [I:330](#)

Weak instruments [II:64](#), [II:80](#)

Weighted least squares [II:36](#)

- cross-equation weighting [II:420](#)
- nonlinear [II:45](#)
- nonlinear two stage [II:63](#), [II:74](#)
- pool [II:589](#)
- system estimation [II:447](#)
- two stage in systems [II:421](#), [II:449](#)
- weight scaling [II:38](#)
- weight type [II:37](#)

Weighting matrix

- GMM [II:69](#), [II:76](#)
- heteroskedasticity and autocorrelation consistent (HAC) in system GMM [II:451](#)
- heteroskedasticity and autocorrelation consistent (HAC) robust standard errors [II:34](#)
- kernel options (system) [II:452](#)
- system GMM [II:451](#)
- White (cointegrating regression) [II:231](#)
- White (GMM) [II:76](#)
- White (robust standard errors) [II:33](#)
- White (system GMM) [II:451](#)

White heteroskedasticity consistent covariance

- matrix
 - cointegrating regression [II:231](#)
 - GMM [II:76](#)
 - robust standard errors [II:33](#)
 - system GMM [II:451](#)
 - White heteroskedasticity test [II:163](#)
 - VAR [II:466](#)
 - Whitening [I:424](#), [I:431](#)
 - Width of table column [I:592](#)
 - Wilcoxon test
 - rank sum [I:327](#)
 - signed ranks [I:323](#)
 - Wildcard characters [I:51](#)
 - in easy query [I:284](#)
 - Windmeijer standard errors [II:73](#)
 - Window
 - active [I:74](#)
 - database [I:269](#)
 - EViews main [I:6](#)
 - object [I:75](#)
 - Windows metafile [I:586](#)
 - Within deviations [II:627](#), [II:635](#)
 - Within factors [I:543](#)
 - identification [I:547](#)
 - WMF [I:586](#)
 - Work area [I:9](#)
 - Workfile
 - append to [I:241](#)
 - applying structure to [I:223](#)
 - automatic backup [I:628](#)
 - common structure errors [I:236](#)
 - contract [I:244](#)
 - copy from [I:244](#)
 - create [I:34](#)
 - description of [I:33](#)
 - directory [I:50](#)
 - export [I:265](#)
 - load existing from disk [I:56](#)
 - multi-page [I:56](#)
 - observation numbers [I:86](#)
 - panel [II:615](#)
 - pool [II:565](#), [II:574](#)
 - remove structure [I:238](#)
 - reshape [I:248](#)
 - resize [I:225](#), [I:238](#)
 - sample [I:91](#)
 - save [I:53](#)
 - sorting [I:265](#)
 - stacking [I:257](#)
 - statistics [I:53](#)
 - storage defaults [I:627](#)
 - storage precision and compression [I:628](#)
 - structure settings [I:224](#)
 - structuring [I:213](#)
 - summary view [I:53](#)
 - undated [I:215](#)
 - unstacking [I:251](#)
 - window [I:49](#)
 - workfiles
 - loading [I:105](#)
 - Write [II:584](#)
- X
- X11 (historical) [I:358](#)
 - limitations [I:358](#)
 - X11 using X12 [I:351](#)
 - X12 [I:349](#)
 - XY (area) graph [I:489](#)
 - XY (bar) graph [I:489](#)
 - XY (line) graph [I:488](#)
- Y
- Yates' continuity correction [I:327](#)

