

SERVICE HANDBOOK

SandBlaster[®]

**Self Cleaning Commercial Gas Water Heaters
with Flue Damper and Electronic Ignition**



MODELS COVERED

SBD71 120 Through SBD85 500

Part Number 317926-000
Printed in the U.S.A. - 0810

 **state**
COMMERCIAL
The Expert's Choice[®]

SBD TANK TYPE HEATERS SERVICE HANDBOOK

SBD HANDBOOK TABLE OF CONTENTS

	PAGE		PAGE
Introduction	1-2	Troubleshooting (continued)	
		Troubleshooting the Effikal	28-30
		Wire Harness Test	31
Installation	3	IID Module	32
Clearances	4	Pilot Spark	33
Air Requirements	5-8	Pilot Valve	34-35
Contaminated Air	9	Main Burner Test	36
Flammable	9	Flame Rectification	37
Gas Pressure	10	IID Module	38
Gas Valve	11	Main Gas Valve	39-40
Venting	12-15		
Sequence of Operation		Service Charts and General	
Mechanical	16	Questions and Answers	41-42
Electrical	17-18		
 		Parts List	43-50
Troubleshooting		Component Part Information	51
Transformer	19		
High Limit	20-21	Service Check List	52-53
Damper (on Standby)	22		
PC Board	22-23	Comments	54
Thermostat	24		
Effikal Damper	25		
Effikal Harness Test	26		
Normal Operation	26-27		

SBD SERVICE HANDBOOK INTRODUCTION

This service handbook is designed to aid in servicing and troubleshooting State SBD water heaters in the field. No duplication or reproduction of this book may be made without the express written authorization of the State Water Heater Company.

The following text and illustrations will provide you with a step by step procedure to verify proper installation, operation, and troubleshooting procedures. Additional quick reference data is included to assist you in servicing this product.

The information contained in this handbook is designed to answer common questions encountered in the operation of the SBD product line and is not meant to be all inclusive. If you are experiencing a problem not covered in this handbook, please contact the Technical Information Department at 1-800-365-0577 or your Local State Water Heater Sales Representative for further assistance. This handbook is intended for use by licensed plumbing professionals and reference should be made to the installation manual accompanying the product. This handbook contains supplemental information to the SBD installation and operation manual.

SBD TANK TYPE HEATERS SERVICE HANDBOOK

Qualifications: Installation or service of this water heater requires ability equivalent to that of a licensed tradesman in the field involved. Plumbing, air supply, venting, gas supply and electrical testing skills are required.



Tools Required:

- Phillips head screwdriver
- standard screwdrivers
- a 3/8 and 7/16 inch open end wrench
- set of marked drill bits
- an electrical multimeter tester capable of measuring continuity
- gas pressure gauge or manometer
- water pressure gauge
- thermometer
- 1/2 inch socket with extension for removal of the clean out cover,
- 1 1/16 inch socket with extension for anode removal.

CUSTOM COMMERCIAL STORAGE TANK MODEL NUMBER BREAKDOWN

Model Breakdown

SBD 85 500 P E A CGA D




**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

INSTALLATION

This portion of the handbook will review some often overlooked installation considerations, taking note of necessary installation requirements for the SBD 71120 through SBD 85500 model heaters. The installation manual covers most of these items in detail.

CLEARANCES FROM COMBUSTIBLES



Clearance to Combustibles Table


MODEL	A	B	C
120 - 200	1" (2.54CM)	1" (2.54CM)	1" (2.54CM)
250 - 305	2" (5.08CM)	2" (5.08CM)	2" (5.08CM)
365 - 400	3" (7.75CM)	3" (7.75CM)	3" (7.75CM)
500	5" (12.7CM)	5" (12.7CM)	5" (12.7CM)

A 24 inch clearance for all serviceable parts is recommended. Clearances may vary between SBD models – See instruction manual or the label on the heater, for clearances applicable to your specific model.

*20" (50.8CM) for 500 models.

SBD TANK TYPE HEATERS
SERVICE HANDBOOK

EXTERIOR CLEARANCE




"Copyright by the American Gas Association. Used by permission of the copyright holder".

This illustrates the exterior roof clearances for SBD units with natural draft venting. The vent shall extend at least 3 feet above the highest point where it passes through a roof of a building, and at least 2 feet higher than any portion of a building within a horizontal distance of 10 feet (for vents of 12" in diameter or less). (NFPA 54 ANSI Z 223.1 SEC 7.5.2a). (Sec 7.6.2a may allow reduction to 8 feet with a "Listed vent cap").

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**AIR FOR COMBUSTION
10 CUBIC FEET OF AIR PER 1,000 BTU**




Stoichiometric or theoretical complete combustion requires 10 cubic feet of air per 1000 BTUH input of the gas input. The National Fuel Gas Code also recommends an additional 2.5 cu.ft. of "excess" air. This 12.5 cu.ft minimum supply air per 1000 BTUH input applies to natural and propane gas models.

The National Fuel Gas Code also specifies minimum make-up air opening sizes for various building installations. (Ref: NFPA 54, ANSI Z223.1, sec 5.3)

SBD TANK TYPE HEATERS SERVICE HANDBOOK

MAKE-UP AIR DIRECT COMMUNICATION




A fresh supply of make-up air for combustion can be supplied to the heater through make-up air ducts which directly communicate with the out of doors. Two openings are required - one within 12 inches of the top of the enclosure and one within twelve inches of the bottom of the enclosure. Each opening shall have a free area of not less than 1 square inch per 4000 BTUH of the total input of all appliances within the enclosure.

The lower opening is primarily providing combustion air. The upper opening is providing vent dilution air and acts as a relief opening for flue gases should the vent become obstructed or a downdraft condition occur. Additionally, when the heater is installed in a confined space and communicating with the outdoor air, one permanent opening, commencing within 12 in. (30 cm) of the top of the enclosure, shall be permitted where the equipment has clearances of at least 1 in. (2.5 cm) from the sides and back and 6 in. (16 cm) from the front of the appliance. The opening shall directly communicate with the outdoors and shall communicate through a vertical or horizontal duct to the outdoors or spaces (crawl or attic) that freely communicate with the outdoors, and shall have a minimum free area of:

- a. 1 sq. in. per 3000 BTU per hr (7 cm² per kW) of the total input of all equipment located in the enclosure, and
- b. Not less than the sum of the areas of all vent connectors in the confined space.


SBD TANK TYPE HEATERS SERVICE HANDBOOK

MAKE-UP AIR VERTICAL DUCTS




Often it is more practical to install vertical make-up air ducts to the out doors. Again, two openings are required - one within 12 inches of the top of the enclosure and one within twelve inches of the bottom of the enclosure. Each opening shall have a free area of not less than 1 square inch per 4000 BTUH of the total input of all appliances within the enclosure.

MAKE-UP AIR HORIZONTAL DUCTS



When the heater is installed in an interior room with no roof access for vertical ducts, horizontal make-up air ducts should be installed. When using horizontal ducts, two openings are required - one within 12 inches of the top of the enclosure and one within twelve inches of the bottom of the enclosure. Each opening shall have a free area of not less than 1 square inch per 2000 BTUH of the total input of all appliances within the enclosure.


**INSUFFICIENT MAKE-UP AIR
BACKDRAFT**



Insufficient make-up air is a major cause of combustion problems. One common example is in a restaurant installation where exhaust vent equipment was not considered in sizing make-up air requirements. This may result in air being backdrafted by the restaurant exhaust equipment through the heater causing flue gas spillage, flame roll out, improper combustion, inconsistent pilot operation, and/or erratic heater shut down.

SBD TANK TYPE HEATERS SERVICE HANDBOOK

CONTAMINATED AIR



Along with adequate make-up air, the quality of the air is important. Contaminants in combustion air can lead to premature heater failure. Vapors from bleaches, soaps, waxes, salts, etc. are drawn into the combustion chamber with the make-up air and, once fired, mix with water vapor in the gases to form extremely corrosive hydrochloric or hydrofluoric acid and other corrosive byproducts.


AIR FOR COMBUSTION Flammable Items



Flammable items, pressurized containers or any other potentially hazardous articles must never be placed on or adjacent to the heater. Open containers of flammable material should not be stored or used in the same room with the heater.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

GAS PRESSURE REQUIREMENTS



	Natural Gas	Propane Gas
Maximum Supply Pressure	10.5" W.C.	13.8" W.C.
Minimum Supply Pressure	5.0" W.C.	11" W.C.
Manifold Pressure	4.0 " W.C.	10" W.C.

The supply gas pressure is normally measured at the dirt leg or at the gas pressure tapping on the gas supply shutoff valve. This reading must be measured with 'flowing' gas.

The manifold gas pressure is measured at the manifold pressure tap of the gas valve when the gas is flowing.

SBD TANK TYPE HEATERS SERVICE HANDBOOK

SBD GAS VALVE


The gas valves used on all SBD water heaters are 24 volt AC combination step opening gas valves. They incorporate the pilot valve, main valve, and gas pressure regulators into one body. The inlet view of the valve features a filter screen and the top knob. The top knob is a manual on/off gas control for both the pilot and main gas valves. When the top knob is placed on the black mark, gas is supplied only to the pilot valve.

On the top view, we see the pilot solenoid and pilot and main gas regulators. The top view also displays the "TH and "TR" terminals. The pilot gas regulator is found under its cover screw. It is factory preset at 3.5" W.C. but can be adjusted from 2.5 to 5 inches water column. The main gas regulator is found under its cover screw. It is factory preset to 3.5 inches W.C. and adjusts gas pressure output from 2.5 to 5 inches water column. The two electrical terminals are marked TH and TR. The TH terminal is the common between the pilot valve solenoid coil and the main valve solenoid coil. The other wire emerging from the pilot solenoid connects to the pilot valve electrical output on the IID (terminal PV). The TR terminal connects directly to the main valve electrical output from the IID module (terminal MV).


On the outlet view of the gas valve, we see the pilot gas connection port, manifold gas connection port, a limited bleed vent port, the manifold gas and pressure tap.

See step 18 for SBD-500 gas valve illustration


INLET VIEW



TOP VIEW



OUTLET VIEW



SBD TANK TYPE HEATERS SERVICE HANDBOOK


VENTING Atmospheric, Single, and Multiple Heaters

All SBD water heaters are classified by ANSI as category I (non-condensing, negative pressure venting) appliances. They are approved for type B vent.

For larger applications, SBD water heaters can be common vented together either in a tapered manifold or constant size manifold. (Follow National Fuel Gas Code requirements for sizing and installation.)

Combined Vents

When vents are combined, the area of the combined vent should be equal to area of the largest single vent, plus 50% of area of all others joining.



EXAMPLE: To combine two 6" vents with an 8" vent, the area of a combined vent should be one half area of two 6 inch vents (14 + 14) plus area of 8 inch vent (50) or 78 sq. inches. Referring to chart, 78 sq. inches require 10" diameter vent.

Vent Size	Area in Square Inches	Vent Size	Area in Square Inches
5"	20	10"	79
6"	28	12"	113
7"	38	14"	154
8"	50	16"	201
9"	64	18"	254

Nine Rules for Good Vents


1. The vent pipe should ALWAYS be the same size as the outlet of the draft diverter or factory supplied vent reducer.
 - Model SBD 120 are supplied with a 6" to 5" reducer.
 - Models SBD 250, 251 and 275 are supplied with a 8" to 6" reducer.




**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

Nine Rules for Good Vents (continued)


2. The diameter of a vent pipe should NEVER be reduced, no matter what the circumstances.





3. In some cases it may be necessary to run a vent larger than the draft diverter outlet.



4. Take the maximum vertical rise possible immediately above the draft diverter.




- 5.




SBD TANK TYPE HEATERS SERVICE HANDBOOK

Nine Rules for Good Vents (continued)


- 6. Horizontal pipe should be sloped upward at a minimum of $\frac{1}{4}$ " per foot.




- 7. Horizontal elements should be limited to 75% of the vertical rise of the vent above the connection.




- 8. Flue gases must be kept hot for proper venting.



The vent pipe should be extended to meet local codes




- 9. Obstructions can cause down drafts.




SBD TANK TYPE HEATERS SERVICE HANDBOOK

POWER VENT KITS FOR SIDEWALL VENTING




SBD water heaters can be used with power vent kits for sidewall venting. State offers power vent kits for use on installations with a maximum of 100 equivalent feet of vent piping. The power vent kits also use type B vent materials. When power venting, specific exterior clearances must be maintained, as outlined in the National Fuel Gas Code. (NFPA 54, ANSI A223.1, sec 7.8)



**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

SBD SEQUENCE OF OPERATION




SEQUENCE OF OPERATION

To understand SBD tank type water heaters, an examination of their sequence of operation is necessary.

When the thermostat calls for heat, the relay in the draft hood assembly activates the flue damper motor. The damper opens and power flows to the IID (Intermittent Ignition Device). This activates the IID module to open the pilot valve and begin sparking at the pilot burner assembly. Once the pilot flame is established and confirmed back to the IID, the sparking is stopped and the main gas valve is opened, allowing gas flow to the main burner. When the thermostat satisfies, main and pilot gas is shut off. Damper is returned to closed position.


**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**SBD ELECTRICAL SEQUENCE
100 – 109 Series**



SBD TANK TYPE HEATERS SERVICE HANDBOOK

SBD ELECTRICAL SEQUENCE OF OPERATION 115/60/12A



**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**


TROUBLESHOOTING SBD WATER HEATERS

To troubleshoot a SBD water heater check that:

- 120 VAC is supplied to the heater
- the tank is full of water
- gas is supplied to the unit

STEP 1

TEST THE TRANSFORMER




STEP 1 - TO TEST THE TRANSFORMER - Using a multimeter, test for 24 VAC between the secondary transformer terminals.

IF	THEN
The meter does not read 24 VAC:	<ul style="list-style-type: none">• Check that the 120 VAC is supplied from the On/Off Switch – if not, replace switch.• Check that the 120 VAC is supplied from transformer.
The meter reads 24 VAC:	<ul style="list-style-type: none">• Go to step 2.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 2

HIGH LIMIT, LEFT TERMINAL TEST




STEP 2. HIGH LIMIT, LEFT TERMINAL TEST. Test for 24 VAC between the left high limit terminal and ground.

IF	THEN
The meter does not read 24 VAC:	<ul style="list-style-type: none">• Check wiring between transformer and high limit.
The meter reads 24 VAC:	<ul style="list-style-type: none">• Go to Step 3.

Note: The high limit (Energy Cut Off) opens if the tank water temperature exceeds 205 degrees. The control is resettable (manually) when the tank water temperature drops below 185 degrees.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 3 TEST HIGH LIMIT RIGHT TERMINAL



STEP 3. TO TEST HIGH LIMIT RIGHT TERMINAL. Ensure that the jumper wire between the high limit and thermostat is connected, and the damper motor power line is connected. Test for 24 VAC between the high limit right terminal and ground.

IF	THEN
The meter does not read 24 VAC:	<ul style="list-style-type: none"> • Push the reset button and redo the test (storage water temperature below 185 degrees).
The meter reads 24 VAC:	<ul style="list-style-type: none"> • Go to step 4.



After Push in Reset - 24 VAC is now present

Reasons For Resetting		
Condition	Cause	Solution
High limit open	Never set on initial installation	Push high limit button
Excessive water temperature	Faulty thermostat	Replace dual control
Heater shut down before reaching thermostat setting	Faulty high limit	Replace dual control

Note: The right terminal of the high limit has a jumper wire connected to the left terminal of the thermostat. There is also a black wire connecting to the damper motor assembly. This black wire supplies power to the motor to close the damper during periods of standby.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 4	INSPECT THE DAMPER
---------------	---------------------------



STEP 4. INSPECT THE DAMPER. Lower the thermostat setting so the unit will not be calling for heat, then inspect the damper.

IF	THEN
If the damper is open:	<ul style="list-style-type: none"> Go to step 5.
If the damper is closed:	<ul style="list-style-type: none"> Go to step 7.

Note: If the water temperature in the tank is below 120 degrees F, temporarily disconnect the jumper wire between the high limit and thermostat to simulate a satisfied thermostat.

STEP 5	CHECK THE PC BOARD
---------------	---------------------------




STEP 5. CHECK THE PC BOARD. Test for 24 VAC between the black PC board wire connection and ground.

IF	THEN
24 VAC is not present:	<ul style="list-style-type: none"> Check the black wire connections between PC Board and high limit.
24 VAC is present:	<ul style="list-style-type: none"> Go to step 6.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 6

PC BOARD MOTOR TEST



STEP 6. PC BOARD/MOTOR TEST. Check for 24 VAC between the two motor lead terminals of the PC board. Disconnect the wires for this test.

IF	THEN
24 VAC is not present:	<ul style="list-style-type: none">• Replace the Damper Drive and go to step 7. The board and relay are one piece. Regardless of which part is defective, both parts should be changed.
Voltage is present:	<ul style="list-style-type: none">• This verifies that the motor is receiving power but not closing the damper.• Replace the Damper Drive and go to step 7.


Note: The service switch may be used to bypass the damper, while waiting for a replacement part.

WARNING - In the event of damper motor failure, verify that the damper is in the "open" position before utilizing the service switch

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 7

THERMOSTAT TEST



STEP 7. THERMOSTAT TEST. Set the thermostat to call for heat. Using your multimeter, test for 24 VAC between right terminal and ground.

IF	THEN
The meter does not read 24 VAC and the jumper wire between the high limit and the thermostat is in place:	<ul style="list-style-type: none">• Replace the thermostat
The meter reads 24 VAC:	<ul style="list-style-type: none">• Go to step 8.


Note: If the high limit to thermostat jumper wire was disconnected earlier to simulate a satisfied thermostat, reconnect the jumper to the terminals.

Note: A yellow wire from this thermostat terminal connects to the damper PC board.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

EFFIKAL DAMPER

The wiring colors from the damper PC Board are different colors than the wires on the heater wiring harness. The male/female plugs to connect the damper board to the heater harness join in only one way.




Effikal Control Cover (Photo of kit mounting)

Effikal Style

Adapter not necessary on production 110,111 Series

The heater harness wires still serve the same function:

- Black – 24V Constant if high limit closed
- Yellow – 24V To damper if the thermostat is closed
- Red – 24V From damper to IID if damper closes end switch
- White – Neutral (common)



**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**


HARNES CHART

Heater Harness	Function	Damper Harness
Black	24V Hot	1-Brown
Yellow	24V from Thermostat	2-Orange
Red	24V from damper	3-Yellow
White	24V common	4-Black

NORMAL OPERATION

Condition:

- Heater on standby
- Damper closed
- High Limit closed



Wires are from left to right:
Black • Yellow • Brown • Orange

STEP 8	TEST FOR 24VAC BETWEEN BLACK (COMMON) AND BROWN
---------------	--

STEP 8. TEST FOR 24VAC BETWEEN BLACK (COMMON) AND BROWN

IF	THEN
24VAC is present	Continue to Step 8A.
24VAC is not present	See Troubleshooting Step 9A

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

NORMAL OPERATION (continued)

Condition:

- Thermostat closed, damper in process of opening

STEP 8A	TEST FOR 24VAC BETWEEN BLACK AND ORANGE
----------------	--

IF	THEN
24VAC is present	Continue to Step 8B.
24VAC is not present	See Troubleshooting Step 9B.

Condition:

- Thermostat closed, damper fully open

STEP 8B	TEST FOR 24VAC BETWEEN BLACK AND YELLOW
----------------	--

IF	THEN
24VAC is present	Continue to Step 10A.
24VAC is not present	See Troubleshooting Step 9B.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**


TROUBLESHOOTING THE EFFIKAL DAMPER

Condition:

Thermostat closed, damper closed

Wires are from left to right:

Black • Yellow • Brown • Orange



STEP 9A

TEST BETWEEN BLACK (COMMON) AND BROWN ON THE DAMPER BOARD


IF	THEN
24VAC is present	This is correct
24VAC is not present	<ul style="list-style-type: none">• See Steps 1 thru 4 Check the harness plugs connecting heater and damper for looseness or damage.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

TROUBLESHOOTING THE EFFIKAL DAMPER (continued)

Condition:

Thermostat closed, damper open.



STEP 9B	A1 IS CORRECT, CHECK SERVICE SWITCH POSITION
----------------	---

IF	THEN
Switch is incorrect position	Replace damper board/motor assembly.
Switch is not in correct position	<ul style="list-style-type: none">• Adjust switch• Cycle thermostat to verify that damper operation is correct.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

TROUBLESHOOTING THE EFFIKAL DAMPER (continued)

Condition:

Thermostat closed, damper is open fully

STEP 10A

TEST FOR 24VAC BETWEEN BLACK AND YELLOW

IF	THEN
24VAC is present	This is correct – continue to Step 11
24VAC is not present	<ul style="list-style-type: none">• See Step 9B.• Check the harness plug connecting.• Check that cam on shaft rotates with shaft.• Replace the damper board.• Ensure that cam is secure against end switch.

Condition:

Damper rotates continuously

STEP 10B


ADJUST END SWITCH TO CAM CONTACT



IF	THEN
Damper stops in proper position	24 VAC should be open on a call for heat and close during standby/
Damper does not stop in proper position	<ul style="list-style-type: none">• Replace damper assembly.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 11	WIRE HARNESS TEST
----------------	--------------------------



STEP 11. WIRE HARNESS TEST. Test for 24 VAC between terminal 24V on the IID module, and 24V GND.


IF	THEN
24 VAC is not present:	<ul style="list-style-type: none"> Check the wiring harness.
24 VAC is present:	<ul style="list-style-type: none"> Go to step 12.

Note: This test may be easier to conduct by removing the red wire from the IID terminal. Test for 24 VAC between the red wire and ground. Reconnect the red wire to the 24V terminal after the test.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 12

IID MODULE TEST




STEP 12. IID MODULE TEST (Power to the Pilot Valve). Using a multimeter, test for 24 VAC between terminal PV and 24V (GND) on the IID during the 90 second trial for ignition.

IF	THEN
The meter does not read 24 VAC and the IID module is not between ignition trials:	<ul style="list-style-type: none"> • Replace the module.
The meter does read 24 VAC:	<ul style="list-style-type: none"> • Go to step 13

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 13

PILOT SPARK TEST




STEP 13. PILOT SPARK TEST. Visually check for spark at the pilot assembly.

Note: The pilot burner mounts on the left side of the main burner.

IF	THEN
The igniter is not sparking:	Check for: <ul style="list-style-type: none"> • A 7/64" spark gap • Spark cable continuity • Ground cable continuity
Sparking is present:	<ul style="list-style-type: none"> • Go to step 14.


Power To Module May Be Interrupted To Reset .



**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 14A

PILOT VALVE - OHM TEST




SBD 120 – 400 GAS VALVE

STEP 14A. PILOT VALVE - OHM TEST. If pilot assembly is sparking but no pilot flame is established, disconnect the pilot valve solenoid leads. Using a multimeter, (set to read ohms) test for 20* ohms resistance +/- 5 through the solenoid coil.

IF	THEN
The meter does not read 20 ohms plus or minus 5:	<ul style="list-style-type: none">• Replace gas valve
The meter does read 20 ohms plus or minus 5:	<ul style="list-style-type: none">• Gas valve should work. Also check that pilot gas is present and pilot tube or orifice are not blocked

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 14B **PILOT VALVE TEST – SBD 500 ONLY**



STEP 14B. PILOT VALVE TEST – SBD 500 ONLY. Testing the two coils of the Honeywell VR8404P 5004 gas valve used on the model SBD 500 only. Because of built in diodes, it is difficult to test for ohms resistance through these coils. The following is a DC amperage check of the main and pilot coils.

Condition:

- Tank calls for heat
- PV terminal of module has 24 Vac
- No Pilot flame

Test Procedure:

- Turn off power to heater
- Meter set to test for DC amperage (on meters, the black wire is in the “com” port, the red wire is in the “10A” port, the dial is set to 20M/10A in the DC AMP test area).
- Blue “PV” wire is disconnected from the ignition PV terminal.
- Install meter in series between gas valve and ignition module – 10A wire to blue gas valve lead, common wire to PV module terminal.
- Turn power on to heater, after module receives 24V

Test DC Amperage through Pilot coil of gas valve


IF	THEN
.75 to .85 DCA is not present:	• Replace the gas valve
.75 to .85 DCA is present	• Pilot should work if gas (not air) is present to pilot

Power off, reattach blue gas valve wire to PV terminal of module.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 15

MAIN BURNER TEST




STEP 15. MAIN BURNER TEST. Visually check for main burner.

IF	THEN
The main burner ignites:	<ul style="list-style-type: none">• Sequence is complete
The main burner does not ignite	<ul style="list-style-type: none">• Go to step 16

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 16

FLAME RECTIFICATION



STEP 16. FLAME RECTIFICATION

Note: Flame rectification means that an alternating current (AC) signal is changed to a direct current (DC) signal. The pilot flame is the 'switch' which connects the pilot hood to the igniter and ground. If the pilot hood and igniter sensor had the same surface area, the flame 'switch' would conduct an AC signal. Because the pilot surface is greater than the igniter surface, the signal becomes a DC current that the module can interpret. The pilot hood must be properly grounded and the pilot flame must remain in contact with both surfaces for the flame proving signal to remain constant.

If the signal is broken for just 8 tenths of a second, the heater will cycle off.


Sparking at the pilot will continue if an insufficient signal is received by the module.

Sparking at the pilot will stop almost immediately after the ignition module senses the pilot flame.

IF	THEN
Sparking continues after pilot is established:	<ul style="list-style-type: none">• Check wire connections• Check flame contact between hood and lighter• Clean pilot burner surfaces• Replace pilot assembly
Sparking stops:	<ul style="list-style-type: none">• Go to step 17.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 17	IID MODULE TEST
----------------	------------------------



Pilot is lit - Sparking has stopped.


STEP 17. IID MODULE TEST (Power to the Main Valve). Using a multimeter, test for 24 VAC between terminal MV on the IID and 24V (GND).

IF	THEN
24 VAC is not present:	<ul style="list-style-type: none"> Replace the IID module. Conduct Step 18 before applying power to replacement module.
24 VAC is present:	<ul style="list-style-type: none"> Go to step 18.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

STEP 18A

MAIN GAS VALVE CHECK



SBD 120 – 400 GAS VALVE


STEP 18A. MAIN GAS VALVE CHECK. Disconnect wires from gas valve TH and TR terminals. Using a multimeter, test for 68 ohms plus or minus 5 between TH and TR on the main valve coil.

IF	THEN
The meter reads '0' or infinity	<ul style="list-style-type: none">• Replace the gas valve
The meter reads 68* ohms plus or minus 5	<ul style="list-style-type: none">• The main burner will ignite

SBD TANK TYPE HEATERS SERVICE HANDBOOK

STEP 18B

MAIN GAS VALVE COIL CHECK



STEP 18B. MAIN GAS VALVE COIL CHECK – SBD 500 ONLY

Condition:

- Pilot lights
- Sparking stops
- No main burner ignition

Test Procedure:

- Power off
- Disconnect red, main valve wire from module MV terminal
- Meter set to test for DC amperage
- 10A wire to red gas valve wire, COM wire to MV terminal of ignition module
- Turn power on to heater
- After pilot lights and sparking stops

IF:	THEN:
.25 to .35 DC Amps is not present	<ul style="list-style-type: none"> • Replace the gas valve
.25 to .35DCA is present	<ul style="list-style-type: none"> • Main burner gas should ignite.

Be certain to correct you meter wire connections and setting before performing further tests.

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

GENERAL SERVICE CHART

CONDITION	CAUSE	SOLUTION
DAMPER OPENS NO POWER TO IID MODULE	. DAMPER NOT FULLY OPEN	.EFFIKAL – REPLACE DAMPER CONTROL ASSEMBLY . REPLACE DAMPER
	. DEFECTIVE PROTECTOR SWITCH	. REPLACE PC BOARD
PILOT LIGHTS, SPARKS CONTINUOUSLY	PILOT FLAME NOT PROVING	SEE FLAME RECTIFICATION - STEP 16
HEATER WILL NOT IGNITE	NOT PROVING PILOT FLAME EXISTANCE	INTERRUPT 120 VAC POWER . CHECK GROUND WIRE ATTACHMENT . CLEAN OR REPLACE PILOT ASSEMBLY
	PILOT GAS NOT COMPLETELY INTERRUPTED AT END OF HEATING CYCLE	. CHECK SUPPLY GAS PRESSURE . REPLACE GAS VALVE
WEEPING TEMPERATURE AND PRESSURE RELIEF VALVE	. THERMAL EXPANSION	ADD THERMAL EXPANSION TANK
	. FAULTY VALVE	REPLACE RELIEF VALVE
LARGE VOLUME WATER RELIEF FROM T&P VALVE	. EXCESSIVE WATER TEMPERATURE	. CHECK WIRING . REPLACE DUAL CONTROLLER
	. FAULTY RELIEF VALVE	REPLACE RELIEF VALVE
PREMATURE TANK LEAKAGE	CONDENSATION	. INCREASE STORED WATER TEMPERATURE AND CONFIRM PROPERLY SIZED APPLICATION
	CONTAMINATED AIR	. REMOVE CONTAMINANTS. . SUPPLY CLEAN COMBUSTION AIR.
	WATER HAMMER	. ADD WATER HAMMER ARRESTOR. . REDUCE WATER PRESSURE. . REMOVE UNNECESSARY CHECK VALVES.
	THERMAL EXPANSION	ADD THERMAL EXPANSION TANK.
	DEPLETED ANODES	SCHEDULE ANODE CHECKS - REPLACE AS NEEDED.
DAMPER WILL NOT OPEN	BINDING SHAFT	SUPPORT VENTING
	DAMPER MOTOR	EFFIKAL-REPLACE DAMPER CONTROL ASSEMBLY
NO SPARK AT PILOT - DAMPER FULLY OPEN	DAMPER ASSEMBLY	SEE STEP 10A Services Switch may bypass problem until replacement part is received. (EFFIKAL – REPLACE DAMPER CONTROL ASSEMBLY
	IID MODULE	REPLACE IID STEP 12
	SPARK CABLE	REPLACE CABLE STEP 13

SBD TANK TYPE HEATERS SERVICE HANDBOOK


GENERAL QUESTIONS AND ANSWERS

- Q: What is unique about the Canadian – SBC-CGA – models vs. U.S. SBD models?**
A: The Canadian models have different dimensions to meet Canadian code requirements.
- Q: How much electrical power is required for a SBD water heater?**
A: The SBD models draw approximately .7 Amps at 120VAC.
- Q: The units require "leg kits" to meet National Sanitation Foundation standards.**
- Q: When should SBDs be delimed? NOTE: The "Hydrocannon" should eliminate or greatly reduce the lime build up rate from the water heater.**
Many variables affect the liming up process including:
water temperature - The amount of lime precipitation during the same period of time will be nearly 2 times greater if water is stored at 140 degrees F than at 120 degrees F. A 180 degree setting will precipitate lime about seven times as fast as a 140 degree F setting.
volume of water - The more gallons flowing through the SBD, the more exposure to accumulation.
hardness – The harder the water the higher the possibility of lime build up. 1 to 3.5 grains per gallon is "soft", 3.5 to 7 grains per gallon is "moderate", 7 to 10.5 grains per gallon is "hard" and 10.5 + grains per gallon is "very hard". (An aspirin is about 5 grains. One grain is equal to 17.1 parts per million.)
A: Deliming should be done when a slight rumbling or popping sound is detected when the main burners are on.
- Q: What effect will lime build-up have on the SBD water heater?**
A: One eighth inch of scale build-up may reduce efficiency as much as 22%; a 1/4 inch build-up, as much as 38%.
A: Less efficient heat transfer means more bottom head expansion/contraction stress and premature leakage.
A: Heavy build-up on the bottom head and bottom portion of the flue pipes leads to more heat transfer at the top of the flues. This can lead to stacking or erratic thermostat operation.
A: The "Hydrocannon" greatly reduces the possibility of lime build-up.
- Q: Anode rods provide additional protection against corrosion. When should these be replaced?**
A: When large gouges or pits appear in the anodes, replace them. It is recommended that these be inspected every 6 months.


**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**SBD MODELS 120 THRU 500A
SERIES 110-111**


**PARTIAL REPLACEMENT
PARTS LIST
MODELS SBD 120 THRU 500A:
STANDARD AND ASME (A)
SERIES 110/111**




EFFIKAL DAMPER DRIVE ASSEMBLY



**GAS VALVES
HONEYWELL VALVE SBD 500A**



WHITE RODGERS VALVE SBC 120 - 400A



**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**SBD MODELS 120 THRU 500A (continued)
SERIES 110-111**

ITEM PARTS

- 1 Flue Baffle
- 3 Main Burner Orifice Bracket.....
- 4 Main Burner
- 5 Main Burner w/Pilot Bracket.....
- 6 Pilot Burner, Natural
- 7 Pilot Burner, LP

CLEANOUT ASSEMBLY

- 11 ...Gasket
- 12 ...Pressure Plate
- 13 ...Screws, Self Tapping.....
- 17 Control, Ignition Module.....
- 18 Control, Dual w/ECO
- 19 Cover, Cleanout.....
- 22a Drafthood.....
- 22b Damper Drive Assembly
- 22c Harness Adapter.....

LABELS

- 41 Manifold
- 42 Instruction Manual
- 43 Main Burner Orifice, Natural.....
- 44 Main Burner Orifice, LP
- 45 Anode Rod.....
- 47 Transformer
- 48 Pilot Tubing.....
- 49 Inlet Tube.....
- 51 Gas Valve Natural.....
- 52 Gas Valve LP.....
- 55 Switch Panel/Mounting Plate
- 56 Off/On Switch
- 57 Bushing.....
- 58 Jumper Wire
- 59 Control Box Panel.....
- 60 Cover - Burner
- 61 Hydro-Cannon
- 62 (1 1/2") galvanized pipe cap
- 63 (1 1/2") galvanized pipe plug.....
- 64 (1 1/2") galvanized pipe union....

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**SBD MODELS 120 THRU 500A (continued)
SERIES 110-111**

ITEM PARTS

- 1 Flue Baffle
- 3 Main Burner Orifice Bracket.....
- 4 Main Burner
- 5 Main Burner w/Pilot Bracket.....
- 6 Pilot Burner, Natural
- 7 Pilot Burner, LP

CLEANOUT ASSEMBLY

- 11 ...Gasket
- 12 ...Pressure Plate
- 13 ...Screws, Self Tapping.....
- 17 Control, Ignition Module.....
- 18 Control, Dual w/ECO
- 19 Cover, Cleanout.....
- 22a Drafthood.....
- 22b Damper Drive Assembly
- 22c Harness Adapter.....

LABELS

- 41 Manifold
- 42 Instruction Manual
- 43 Main Burner Orifice, Natural
- 44 Main Burner Orifice, LP
- 45 Anode Rod.....
- 47 Transformer
- 48 Pilot Tubing.....
- 49 Inlet Tube.....
- 51 Gas Valve Natural.....
- 52 Gas Valve LP.....
- 55 Switch Panel/Mounting Plate
- 56 Off/On Switch
- 57 Bushing.....
- 58 Jumper Wire
- 59 Control Box Panel.....
- 60 Cover - Burner
- 61 Hydro-Cannon
- 62 (1 1/2") galvanized pipe cap
- 63 (1 1/2") galvanized pipe plug.....
- 64 (1 1/2") galvanized pipe union.....

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**SBD MODELS 120 THRU 500A (continued)
SERIES 110-111**

ITEM PARTS DESCRIPTION

- 1 Flue Baffle.....
- 3 Main Burner Orifice Bracket.....
..... 098044(9)
- 4 Main Burner
- 5 Main Burner w/Pilot Bracket.....
- 6 Pilot Burner, Natural.....
- 4
- 7 Pilot Burner, LP.....

3

CLEANOUT ASSEMBLY

- 11 Gasket
- 12 Pressure Plate
- 13 Screws, Self Tapping
- 17 Control, Ignition Module
- 18 Control, Dual w/ECO.....
- 19 Cover, Cleanout.....
- 22a Drafthood.....
- 22b Damper Drive Assembly
- 22c Harness Adapter.....

LABELS

- 41 Manifold
- 42 Instruction Manual.....
- 43 Main Burner Orifice, NAT.....
- 28
- 44 Main Burner Orifice, LP.....
- 44
- 45 Anode Rod.....
- 42
- 47 Transformer
- 48 Pilot Tubing.....
- 49 Inlet Tube.....
- 51 Gas Valve Natural.....
- 0
- 52 Gas Valve LP.....
- 1
- 55 Switch Panel/Mounting Plate
- 56 Off/On Switch.....
- 57 Bushing.....
- 58 Jumper Wire
- 59 Control Box Panel.....
- 60 Cover - Burner
- 61 Hydro-Cannon.....
- 62 (1 1/2") galvanized pipe cap.....
- 63 (1 1/2") galvanized pipe plug.....
- 3
- 64 (1 1/2") galvanized pipe union.....

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**SBD MODELS 120 THRU 500A (continued)
SERIES 110-111**

ITEM PARTS DESCRIPTION

- 1 Flue Baffle
- 3 Main Burner Orifice Bracket
- 4 Main Burner
- 5 Main Burner w/Pilot Bracket
- 6 Pilot Burner, Natural
- 7 Pilot Burner, LP

CLEANOUT ASSEMBLY

- 11 Gasket
- 12 Pressure Plate
- 13 Screws, Self Tapping
- 17 Control, Ignition Module
- 18 Control, Dual w/ECO
- 19 Cover, Cleanout
- 22a Drafthood
- 22b Damper Drive Assembly
- 22c Harness Adapter

LABELS

- 41 Manifold
- 42 Instruction Manual
- 43 Main Burner Orifice, Natural
- 44 Main Burner Orifice, LP
- 45 Anode Rod
- 47 Transformer
- 48 Pilot Tubing
- 49 Inlet Tube
- 51 Gas Valve Natural
- 52 Gas Valve LP
- 55 Switch Panel/Mounting Plate
- 56 Off/On Switch
- 57 Bushing
- 58 Jumper Wire
- 59 Control Box Panel
- 60 Cover - Burner
- 61 Hydro-Cannon
- 62 (1 1/2") galvanized pipe cap
- 63 (1 1/2") galvanized pipe plug
- 64 (1 1/2") galvanized pipe union

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

SBD MODELS 120 THRU 500A (continued)

ITEM PARTS DESCRIPTION

- 1 Flue Baffle.....
- 3 Main Burner Orifice Bracket.....
- 4 Main Burner
- 5 Main Burner w/Pilot Bracket.....
- 6 Pilot Burner, Natural.....
- 7 Pilot Burner, LP.....

CLEANOUT ASSEMBLY

- 11 Gasket
- 12 Pressure Plate
- 13 Screws, Self Tapping
- 17 Control, Ignition Module
- 18 Control, Dual w/ECO.....
- 19 Cover, Cleanout
- 22a Drafthood
- 22b Damper Drive Assembly
- 22c Harness Adapter.....

LABELS

- 41 Manifold
- 42 Instruction Manual.....
- 43 Main Burner Orifice, Natural.....
- 44 Main Burner Orifice, LP.....
- 45 Anode Rod
- 47 Transformer
- 48 Pilot Tubing.....
- 49 Inlet Tube.....
- 51 Gas Valve Natural.....
- 52 Gas Valve LP.....
- 55 Switch Panel/Mounting Plate
- 56 Off/On Switch.....
- 57 Bushing.....
- 58 Jumper Wire.....
- 59 Control Box Panel.....
- 60 Cover - Burner
- 61 Hydro-Cannon.....
- 62 (1 1/2") galvanized pipe cap.....
- 63 (1 1/2") galvanized pipe plug.....
- 64 (1 1/2") galvanized pipe union.....

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

**SBD MODELS 120 THRU 500A (continued)
SERIES 110-111**

ITEM PARTS DESCRIPTION

- 1 Flue Baffle.....
- 3 Main Burner Orifice Bracket.....
- 4 Main Burner
- 5 Main Burner w/Pilot Bracket.....
- 6 Pilot Burner, Natural.....
- 7 Pilot Burner, LP.....

CLEANOUT ASSEMBLY

- 11 Gasket
- 12 Pressure Plate
- 13 Screws, Self Tapping
- 17 Control, Ignition Module.....
- 18 Control, Dual w/ECO.....
- 19 Cover, Cleanout.....
- 22a Drafthood
- 22b Damper Drive Assembly
- 22c Harness Adapter

LABELS

- 41 Manifold
- 42 Instruction Manual.....
- 43 Main Burner Orifice, Natural.....
- 44 Main Burner Orifice, LP.....
- 45 Anode Rod.....
- 47 Transformer
- 48 Pilot Tubing.....
- 49 Inlet Tube.....
- 51 Gas Valve Natural.....
- 52 Gas Valve LP.....
- 55 Switch Panel/Mounting Plate
- 56 Off/On Switch.....
- 57 Bushing.....
- 58 Jumper Wire.....
- 59 Control Box Panel.....
- 60 Cover - Burner.....
- 61 Hydro-Cannon.....
- 62 (1 1/2") galvanized pipe cap.....
- 63 (1 1/2") galvanized pipe plug.....
- 64 (1 1/2") galvanized pipe union.....

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

COMPONENT PART INFORMATION

	NAME	SPECIFICATIONS
DUAL CONTROLLER	THERMOST AT	120-180° RANGE, ± 4°, 5° DIFFERENTIAL, LIQUID FILLED, ANTI- STACKING
	HIGH LIMIT (ECO)	OPENS - 205° FIXED, MANUAL RESET BELOW 185°
GAS VALVE	NATURAL GAS	SBD 120-400;24VAC, 60hz, .6A,.7" to 3.5" W.C., STEP OPEN
		SBD 500; 24VAC, 60hz, Dual Gas Valve, STEP OPEN
	PROPANE GAS	SBD 120-400; 2.5 – 10" W.C. STEP OPEN
		SBD 500; 24VAC, 60hz, Dual Gas Valve, STEP OPEN
INTERMITENT IGNITION DEVICE CONTROL	NATURAL GAS AND PROPANE GAS	24 VAC, 50-60 HZ, .1A; .7 MICROAMP SIGNAL CONTINUOUS RETRIAL
DAMPER	COMPLETE ASSEMBLY	
	MOTOR	24 VAC, 60 HZ, 120 RPM, 5 WATT (NOT 110, 111 SERIES)
	P.C. BOARD W/RELAY	Service Switch (NOT 110, 111 SERIES)
TRANSFORMER		120 V PRIMARY, 24 VAC SECONDARY, 40 VA, 50-60 HZ, CLASS 2 "B"

**SBD TANK TYPE HEATERS
SERVICE HANDBOOK**

SBD SERVICE CHECKLIST

(This service checklist may be photo copied to assist with SBD service call.)

This checklist is intended to aid the Service Agent in determining that the State SBD Water Heater has been properly installed and is operating correctly. Because the circumstances of each installation may vary greatly, it is not intended to be an all-inclusive list of the problems that the Service Agent may encounter. Any item checked "no" on this list should be thoroughly investigated and corrective action taken, if required.

SERVICE AGENT _____ INSTALLATION DATE _____
MODEL NUMBER _____ SERVICE DATE _____
SERIAL NUMBER _____ LOCATION ADDRESS _____

GAS TYPE - CHECK ONE

NATURAL _____ PHONE() _____ - _____
PROPANE _____

- I. Check Clearances (circle answer)
- | | | |
|--------------------------------------|-----|----|
| A. Are exterior clearances adequate? | yes | no |
| B. Are interior clearances adequate? | yes | no |

Comments:

- II. Check Makeup Air Requirements
- | | | |
|--|-----|----|
| A. Is the quantity of make-up air adequate per the National Fuel Gas Code? | yes | no |
|--|-----|----|

Comments:

- | | | |
|--|-----|----|
| B. Is the quality of make-up air adequate? | yes | no |
|--|-----|----|

Comments:

- III. Gas Pressure (fill in blank)
- | |
|---|
| A. Supply gas pressure _____ inches of W.C. |
| B. Manifold gas pressure (main burner) _____ inches of W.C. |

Comments:

- IV. Venting (check)
- | | | |
|--|-----|----|
| A. Properly sized per the National Fuel Gas Code? | yes | no |
| B. Does the installation have mechanically assisted venting? | yes | no |

If so, is it operational?	yes	no
---------------------------	-----	----

Comments:

SBD TANK TYPE HEATERS SERVICE HANDBOOK

V. WATER PIPING

Is the system properly sized?	yes	no
Is the system properly installed?	yes	no
Are there any water leaks?	yes	no
Does the installation have a recirculating system?	yes	no
If so, is it operational?	yes	no

VI. PROPER SEQUENCE OF OPERATION

During standby does damper close on standby?	yes	no
During standby is pilot flame off?	yes	no
On a call for heat does thermostat close?	yes	no
On a call for heat does damper open completely?	yes	no
Does sparking begin at pilot?	yes	no
Is pilot flame established?	yes	no
If so, does sparking stop?	yes	no
Does main burner ignite?	yes	no
Does the thermostat satisfy?	yes	no
Does damper close?	yes	no

Comments:

VII. SAFETY

A. Gas

Does pilot flame prove before main burner ignites?	yes	no
Does damper blade fully open before ignition sequence occurs?	yes	no
Is burner cover plate in place?	yes	no
Is burner floor shield in place?	yes	no
Does IID lockout occur after 30 sec. trial for ignition? (Propane models only)	yes	no

B. Water Temperature

Is the thermostat adjusted to the lowest acceptable temperature?	yes	no
Does the installation have a mixing valve?	yes	no
If so, is it operational?	yes	no
What is the outlet temperature of the mixing valve? _____		
Is a properly rated temperature and pressure relief valve installed?	yes	no

C. Electrical

Is the 120 VAC electrical power supply properly wired?	yes	no
Are all the SBD control covers in place?	yes	no
Is the 120 VAC electrical power supply properly fused?	yes	no

D. Flammables

Are flammable materials located in the area of the water heater?	yes	no
Are flammable vapors located in the area of the water heater?	yes	no

(This service checklist may be photo copied to assist with SBD service call.)

COMMENTS

Author: Terry Mulder

Prepared by the State Water Heaters Training Department.
For additional technical information call 800-365-0577.



©Copyright 2007 State Industries, Inc.

State Water Heaters
500 Tennessee Waltz Parkway
Ashland City, TN 37015
800-365-8170
www.statewaterheaters.com